

StarPU Handbook

for StarPU 1.2.6

This manual documents the usage of StarPU version 1.2.6. Its contents was last updated on 21 September 2018.

Copyright © 2009–2018 Université de Bordeaux

Copyright © 2010-2018 CNRS

Copyright © 2011-2018 Inria

Permission is granted to copy, distribute and/or modify this document under the terms of the GNU Free Documentation License, Version 1.3 or any later version published by the Free Software Foundation; with no Invariant Sections, no Front-Cover Texts, and no Back-Cover Texts. A copy of the license is included in the section entitled “GNU Free Documentation License”.

Contents

1	Introduction	3
1.1	Motivation	3
1.2	StarPU in a Nutshell	3
1.2.1	Codelet and Tasks	4
1.2.2	StarPU Data Management Library	4
1.3	Application Taskification	4
1.4	Glossary	4
1.5	Research Papers	5
1.6	StarPU Applications	5
1.7	Further Reading	6
I	StarPU Basics	7
2	Building and Installing StarPU	9
2.1	Installing a Binary Package	9
2.2	Installing from Source	9
2.2.1	Optional Dependencies	9
2.2.2	Getting Sources	10
2.2.3	Configuring StarPU	10
2.2.4	Building StarPU	11
2.2.5	Installing StarPU	11
2.3	Setting up Your Own Code	11
2.3.1	Setting Flags for Compiling, Linking and Running Applications	11
2.3.2	Running a Basic StarPU Application	12
2.3.3	Running a Basic StarPU Application on Microsoft Visual C	12
2.3.4	Kernel Threads Started by StarPU	12
2.3.5	Enabling OpenCL	13
2.4	Benchmarking StarPU	13
2.4.1	Task Size Overhead	13
2.4.2	Data Transfer Latency	14
2.4.3	Matrix-Matrix Multiplication	14
2.4.4	Cholesky Factorization	14
2.4.5	LU Factorization	14
2.4.6	Simulated benchmarks	14

3 Basic Examples	15
3.1 Hello World Using The C Extension	15
3.2 Hello World Using StarPU's API	16
3.2.1 Required Headers	16
3.2.2 Defining A Codelet	16
3.2.3 Submitting A Task	17
3.2.4 Execution Of Hello World	17
3.2.5 Passing Arguments To The Codelet	17
3.2.6 Defining A Callback	18
3.2.7 Where To Execute A Codelet	19
3.3 Vector Scaling Using the C Extension	19
3.3.1 Adding an OpenCL Task Implementation	21
3.3.2 Adding a CUDA Task Implementation	22
3.4 Vector Scaling Using StarPU's API	22
3.4.1 Source Code of Vector Scaling	23
3.4.2 Execution of Vector Scaling	24
3.5 Vector Scaling on an Hybrid CPU/GPU Machine	24
3.5.1 Definition of the CUDA Kernel	24
3.5.2 Definition of the OpenCL Kernel	25
3.5.3 Definition of the Main Code	26
3.5.4 Execution of Hybrid Vector Scaling	27
 II StarPU Quick Programming Guide	 29
 4 Advanced Examples	 31

5	Check List When Performance Are Not There	33
5.1	Check Task Size	33
5.2	Configuration Which May Improve Performance	33
5.3	Data Related Features Which May Improve Performance	33
5.4	Task Related Features Which May Improve Performance	34
5.5	Scheduling Related Features Which May Improve Performance	34
5.6	CUDA-specific Optimizations	34
5.7	OpenCL-specific Optimizations	35
5.8	Detection Stuck Conditions	35
5.9	How to Limit Memory Used By StarPU And Cache Buffer Allocations	36
5.10	How To Reduce The Memory Footprint Of Internal Data Structures	36
5.11	How To Reuse Memory	37
5.12	Performance Model Calibration	37
5.13	Profiling	39
5.14	Overhead Profiling	40
III	StarPU Inside	41
6	Tasks In StarPU	43
6.1	Task Granularity	43
6.2	Task Submission	43
6.3	Task Priorities	43
6.4	Setting Many Data Handles For a Task	44
6.5	Setting a Variable Number Of Data Handles For a Task	44
6.6	Using Multiple Implementations Of A Codelet	44
6.7	Enabling Implementation According To Capabilities	45
6.8	Insert Task Utility	46
6.9	Getting Task Children	48
6.10	Parallel Tasks	48
6.10.1	Fork-mode Parallel Tasks	48
6.10.2	SPMD-mode Parallel Tasks	49
6.10.3	Parallel Tasks Performance	49
6.10.4	Combined Workers	50
6.10.5	Concurrent Parallel Tasks	50
6.10.6	Synchronization Tasks	50

7	Data Management	51
7.1	Data Interface	51
7.1.1	Variable Data Interface	51
7.1.2	Vector Data Interface	51
7.1.3	Matrix Data Interface	51
7.1.4	Block Data Interface	52
7.1.5	BCSR Data Interface	52
7.1.6	CSR Data Interface	53
7.2	Data Management	53
7.3	Data Prefetch	54
7.4	Partitioning Data	54
7.5	Asynchronous Partitioning	55
7.6	Manual Partitioning	56
7.7	Defining A New Data Filter	57
7.8	Data Reduction	57
7.9	Commute Data Access	58
7.10	Concurrent Data Accesses	59
7.11	Temporary Buffers	59
7.11.1	Temporary Data	59
7.11.2	Scratch Data	60
7.12	The Multiformat Interface	60
7.13	Defining A New Data Interface	61
7.14	Specifying A Target Node For Task Data	63
8	Scheduling	65
8.1	Task Scheduling Policies	65
8.2	Performance Model-Based Task Scheduling Policies	66
8.3	Task Distribution Vs Data Transfer	66
8.4	Energy-based Scheduling	67
8.5	Static Scheduling	67
8.6	Defining A New Scheduling Policy	68
8.7	Graph-based Scheduling	68
8.8	Debugging Scheduling	69

9 Scheduling Contexts	71
9.1 General Ideas	71
9.2 Creating A Context	71
9.3 Modifying A Context	72
9.4 Submitting Tasks To A Context	72
9.5 Deleting A Context	72
9.6 Emptying A Context	72
10 Scheduling Context Hypervisor	73
10.1 What Is The Hypervisor	73
10.2 Start the Hypervisor	73
10.3 Interrogate The Runtime	73
10.4 Trigger the Hypervisor	74
10.5 Resizing Strategies	74
10.6 Defining A New Hypervisor Policy	76
11 Modularized Scheduler	77
11.1 Introduction	77
11.2 Using Modularized Schedulers	78
11.2.1 Existing Modularized Schedulers	78
11.2.2 An Example : The Tree-Eager-Prefetching Strategy	78
11.2.3 Interface	79
11.3 Building a Modularized Scheduler	79
11.3.1 Pre-implemented Components	79
11.3.2 Progression And Validation Rules	79
11.3.3 Implementing a Modularized Scheduler	80
11.4 Writing a Scheduling Component	81
11.4.1 Generic Scheduling Component	81
11.4.2 Instantiation : Redefining the Interface	81
11.4.3 Detailed Progression and Validation Rules	81

12 Debugging Tools	83
12.1 TroubleShooting In General	83
12.2 Using The Gdb Debugger	84
12.3 Using Other Debugging Tools	84
12.4 Using The Temanejo Task Debugger	84
13 Online Performance Tools	87
13.1 On-line Performance Feedback	87
13.1.1 Enabling On-line Performance Monitoring	87
13.1.2 Per-task Feedback	87
13.1.3 Per-codelet Feedback	87
13.1.4 Per-worker Feedback	88
13.1.5 Bus-related Feedback	88
13.1.6 MPI-related Feedback	89
13.1.7 StarPU-Top Interface	89
13.2 Task And Worker Profiling	90
13.3 Performance Model Example	91
13.4 Data trace and tasks length	93
14 Offline Performance Tools	95
14.1 Off-line Performance Feedback	95
14.1.1 Generating Traces With FxT	95
14.1.2 Creating a Gantt Diagram	96
14.1.3 Creating a DAG With Graphviz	97
14.1.4 Getting Task Details	97
14.1.5 Monitoring Activity	98
14.1.6 Getting Modular Scheduler Animation	98
14.1.7 Limiting The Scope Of The Trace	98
14.2 Performance Of Codelets	99
14.3 Trace Statistics	104
14.4 Theoretical Lower Bound On Execution Time	106
14.5 Theoretical Lower Bound On Execution Time Example	106
14.6 Memory Feedback	107
14.7 Data Statistics	108

15 Frequently Asked Questions	109
15.1 How To Initialize A Computation Library Once For Each Worker?	109
15.2 Using The Driver API	110
15.3 On-GPU Rendering	110
15.4 Using StarPU With MKL 11 (Intel Composer XE 2013)	111
15.5 Thread Binding on NetBSD	111
15.6 StarPU permanently eats 100% of all CPUs	111
15.7 Interleaving StarPU and non-StarPU code	112
15.8 When running with CUDA or OpenCL devices, I am seeing less CPU cores	112
15.9 StarPU does not see my CUDA device	112
15.10 StarPU does not see my OpenCL device	113
15.11 I keep getting a "Incorrect performance model file" error	113
 IV StarPU Extensions	 115
16 Out Of Core	117
16.1 Introduction	117
16.2 Use a new disk memory	117
16.3 Data Registration	118
16.4 Using Wont Use	118
16.5 Examples: disk_copy	119
16.6 Examples: disk_compute	120
16.7 Performances	122
16.8 Disk functions	122
 17 MPI Support	 123
17.1 Example used in this documentation	123
17.2 About not using the MPI support	124
17.3 Simple Example	124
17.4 How to Initialize StarPU-MPI	125
17.5 Point To Point Communication	125
17.6 Exchanging User Defined Data Interface	126
17.7 MPI Insert Task Utility	128
17.8 Pruning MPI task insertion	130
17.9 Temporary Data	130
17.10 Per-node Data	131
17.11 MPI cache support	132
17.12 MPI Data migration	132
17.13 MPI Collective Operations	133

18 FFT Support	135
18.1 Compilation	135
19 MIC/SCC Support	137
19.1 Compilation	137
19.2 Porting Applications To MIC Xeon Phi / SCC	137
19.3 Launching Programs	138
20 C Extensions	139
20.1 Defining Tasks	139
20.2 Initialization, Termination, and Synchronization	142
20.3 Registered Data Buffers	142
20.4 Using C Extensions Conditionally	143
21 Native Fortran Support	145
21.1 Implementation Details and Specificities	145
21.1.1 Prerequisites	145
21.1.2 Configuration	145
21.1.3 Examples	145
21.1.4 Compiling a Native Fortran Application	146
21.2 Fortran Translation for Common StarPU API Idioms	146
21.3 Uses, Initialization and Shutdown	147
21.4 Fortran Flavor of StarPU's Variadic Insert_task	147
21.5 Functions and Subroutines Expecting Data Structures Arguments	148
21.6 Additional Notes about the Native Fortran Support	148
21.6.1 Using StarPU with Older Fortran Compilers	148
21.6.2 Valid API Mixes and Language Mixes	148
22 SOCL OpenCL Extensions	149

23 SimGrid Support	151
23.1 Preparing Your Application For Simulation	151
23.2 Calibration	152
23.3 Simulation	152
23.4 Simulation On Another Machine	153
23.5 Simulation Examples	153
23.6 Simulations On Fake Machines	153
23.7 Tweaking Simulation	153
23.8 MPI Applications	153
23.9 Debugging Applications	154
23.10 Memory Usage	154
24 OpenMP Runtime Support	155
24.1 Implementation Details and Specificities	155
24.1.1 Main Thread	155
24.1.2 Extended Task Semantics	155
24.2 Configuration	155
24.3 Uses, Initialization and Shutdown	156
24.4 Parallel Regions and Worksharing	156
24.4.1 Parallel Regions	156
24.4.2 Parallel For	157
24.4.3 Sections	157
24.4.4 Single	158
24.5 Tasks	158
24.5.1 Explicit Tasks	158
24.5.2 Data Dependencies	159
24.5.3 TaskWait and TaskGroup	159
24.6 Synchronization Support	160
24.6.1 Simple Locks	160
24.6.2 Nestable Locks	161
24.6.3 Critical Sections	161
24.6.4 Barriers	161

V StarPU Reference API	163
25 Execution Configuration Through Environment Variables	165
25.1 Configuring Workers	165
25.2 Configuring The Scheduling Engine	167
25.3 Extensions	168
25.4 Miscellaneous And Debug	169
25.5 Configuring The Hypervisor	172
26 Compilation Configuration	173
26.1 Common Configuration	173
26.2 Configuring Workers	174
26.3 Extension Configuration	175
26.4 Advanced Configuration	175
27 Module Index	177
27.1 Modules	177
28 Module Documentation a.k.a StarPU's API	179
28.1 Versioning	179
28.1.1 Detailed Description	179
28.1.2 Macro Definition Documentation	179
28.1.2.1 STARPU_MAJOR_VERSION	179
28.1.2.2 STARPU_MINOR_VERSION	179
28.1.2.3 STARPU_RELEASE_VERSION	180
28.1.3 Function Documentation	180
28.1.3.1 starpu_get_version()	180
28.2 Initialization and Termination	180
28.2.1 Detailed Description	180
28.2.2 Data Structure Documentation	180
28.2.2.1 struct starpu_driver	180
28.2.2.2 union starpu_driver.id	181

28.2.2.3	struct starpu_conf	181
28.2.3	Function Documentation	186
28.2.3.1	starpu_init()	186
28.2.3.2	starpu_initialize()	186
28.2.3.3	starpu_conf_init()	186
28.2.3.4	starpu_shutdown()	187
28.2.3.5	starpu_pause()	187
28.2.3.6	starpu_resume()	187
28.2.3.7	starpu_asynchronous_copy_disabled()	187
28.2.3.8	starpu_asynchronous_cuda_copy_disabled()	187
28.2.3.9	starpu_asynchronous_opengl_copy_disabled()	187
28.2.3.10	starpu_asynchronous_mic_copy_disabled()	188
28.2.3.11	starpu_topology_print()	188
28.3	Standard Memory Library	188
28.3.1	Detailed Description	188
28.3.2	Macro Definition Documentation	188
28.3.2.1	starpu_data_malloc_pinned_if_possible	189
28.3.2.2	starpu_data_free_pinned_if_possible	189
28.3.2.3	STARPU_MALLOC_PINNED	189
28.3.2.4	STARPU_MALLOC_COUNT	189
28.3.2.5	STARPU_MALLOC_NORECLAIM	189
28.3.2.6	STARPU_MALLOC_SIMULATION_FOLDED	190
28.3.2.7	STARPU_MEMORY_WAIT	190
28.3.2.8	STARPU_MEMORY_OVERFLOW	190
28.3.3	Function Documentation	190
28.3.3.1	starpu_malloc_flags()	190
28.3.3.2	starpu_malloc_set_align()	190
28.3.3.3	starpu_malloc()	191
28.3.3.4	starpu_free()	191
28.3.3.5	starpu_free_flags()	191

28.3.3.6	starpu_memory_pin()	191
28.3.3.7	starpu_memory_unpin()	191
28.3.3.8	starpu_memory_get_total()	192
28.3.3.9	starpu_memory_get_available()	192
28.3.3.10	starpu_memory_allocate()	192
28.3.3.11	starpu_memory_deallocate()	192
28.3.3.12	starpu_memory_wait_available()	193
28.4	Toolbox	193
28.4.1	Detailed Description	194
28.4.2	Macro Definition Documentation	194
28.4.2.1	STARPU_GNUC_PREREQ	194
28.4.2.2	STARPU_UNLIKELY	194
28.4.2.3	STARPU_LIKELY	194
28.4.2.4	STARPU_ATTRIBUTE_UNUSED	194
28.4.2.5	STARPU_ATTRIBUTE_INTERNAL	194
28.4.2.6	STARPU_ATTRIBUTE_MALLOC	195
28.4.2.7	STARPU_ATTRIBUTE_WARN_UNUSED_RESULT	195
28.4.2.8	STARPU_ATTRIBUTE_PURE	195
28.4.2.9	STARPU_ATTRIBUTE_ALIGNED	195
28.4.2.10	STARPU_WARN_UNUSED_RESULT	195
28.4.2.11	STARPU_POISON_PTR	195
28.4.2.12	STARPU_MIN	195
28.4.2.13	STARPU_MAX	196
28.4.2.14	STARPU_ASSERT	196
28.4.2.15	STARPU_ASSERT_MSG	196
28.4.2.16	STARPU_ABORT	196
28.4.2.17	STARPU_ABORT_MSG	196
28.4.2.18	STARPU_CHECK_RETURN_VALUE	196
28.4.2.19	STARPU_CHECK_RETURN_VALUE_IS	197
28.4.2.20	STARPU_RMB	197

28.4.2.21	STARPU_WMB	197
28.4.3	Function Documentation	197
28.4.3.1	starpu_get_env_number()	197
28.5	Threads	197
28.5.1	Detailed Description	199
28.5.2	Macro Definition Documentation	199
28.5.2.1	STARPU_PTHREAD_CREATE_ON	199
28.5.2.2	STARPU_PTHREAD_CREATE	199
28.5.2.3	STARPU_PTHREAD_MUTEX_INIT	200
28.5.2.4	STARPU_PTHREAD_MUTEX_DESTROY	200
28.5.2.5	STARPU_PTHREAD_MUTEX_LOCK	200
28.5.2.6	STARPU_PTHREAD_MUTEX_UNLOCK	200
28.5.2.7	STARPU_PTHREAD_KEY_CREATE	200
28.5.2.8	STARPU_PTHREAD_KEY_DELETE	200
28.5.2.9	STARPU_PTHREAD_SETSPECIFIC	201
28.5.2.10	STARPU_PTHREAD_GETSPECIFIC	201
28.5.2.11	STARPU_PTHREAD_RWLOCK_INIT	201
28.5.2.12	STARPU_PTHREAD_RWLOCK_RDLOCK	201
28.5.2.13	STARPU_PTHREAD_RWLOCK_WRLOCK	201
28.5.2.14	STARPU_PTHREAD_RWLOCK_UNLOCK	201
28.5.2.15	STARPU_PTHREAD_RWLOCK_DESTROY	201
28.5.2.16	STARPU_PTHREAD_COND_INIT	202
28.5.2.17	STARPU_PTHREAD_COND_DESTROY	202
28.5.2.18	STARPU_PTHREAD_COND_SIGNAL	202
28.5.2.19	STARPU_PTHREAD_COND_BROADCAST	202
28.5.2.20	STARPU_PTHREAD_COND_WAIT	202
28.5.2.21	STARPU_PTHREAD_BARRIER_INIT	202
28.5.2.22	STARPU_PTHREAD_BARRIER_DESTROY	203
28.5.2.23	STARPU_PTHREAD_BARRIER_WAIT	203
28.5.2.24	STARPU_PTHREAD_MUTEX_INITIALIZER	203

28.5.2.25	STARPU_PTHREAD_COND_INITIALIZER	203
28.5.3	Function Documentation	203
28.5.3.1	starpu_thread_create()	203
28.5.3.2	starpu_thread_join()	203
28.5.3.3	starpu_thread_exit()	204
28.5.3.4	starpu_thread_attr_init()	204
28.5.3.5	starpu_thread_attr_destroy()	204
28.5.3.6	starpu_thread_attr_setdetachstate()	204
28.5.3.7	starpu_thread_mutex_init()	204
28.5.3.8	starpu_thread_mutex_destroy()	205
28.5.3.9	starpu_thread_mutex_lock()	205
28.5.3.10	starpu_thread_mutex_unlock()	205
28.5.3.11	starpu_thread_mutex_trylock()	205
28.5.3.12	starpu_thread_mutexattr_gettype()	205
28.5.3.13	starpu_thread_mutexattr_settype()	206
28.5.3.14	starpu_thread_mutexattr_destroy()	206
28.5.3.15	starpu_thread_mutexattr_init()	206
28.5.3.16	starpu_thread_key_create()	206
28.5.3.17	starpu_thread_key_delete()	206
28.5.3.18	starpu_thread_setspecific()	206
28.5.3.19	starpu_thread_getspecific()	207
28.5.3.20	starpu_thread_cond_init()	207
28.5.3.21	starpu_thread_cond_signal()	207
28.5.3.22	starpu_thread_cond_broadcast()	207
28.5.3.23	starpu_thread_cond_wait()	207
28.5.3.24	starpu_thread_cond_timedwait()	208
28.5.3.25	starpu_thread_cond_destroy()	208
28.5.3.26	starpu_thread_rwlock_init()	208
28.5.3.27	starpu_thread_rwlock_destroy()	208
28.5.3.28	starpu_thread_rwlock_rdlock()	208

28.5.3.29	starpu_thread_rwlock_tryrdlock()	208
28.5.3.30	starpu_thread_rwlock_wrlock()	209
28.5.3.31	starpu_thread_rwlock_trywrlock()	209
28.5.3.32	starpu_thread_rwlock_unlock()	209
28.5.3.33	starpu_thread_barrier_init()	209
28.5.3.34	starpu_thread_barrier_destroy()	209
28.5.3.35	starpu_thread_barrier_wait()	209
28.5.3.36	starpu_thread_spin_init()	210
28.5.3.37	starpu_thread_spin_destroy()	210
28.5.3.38	starpu_thread_spin_lock()	210
28.5.3.39	starpu_thread_spin_trylock()	210
28.5.3.40	starpu_thread_spin_unlock()	210
28.5.3.41	starpu_sleep()	210
28.6	Bitmap	210
28.6.1	Detailed Description	211
28.6.2	Function Documentation	211
28.6.2.1	starpu_bitmap_create()	211
28.6.2.2	starpu_bitmap_destroy()	211
28.6.2.3	starpu_bitmap_set()	211
28.6.2.4	starpu_bitmap_unset()	212
28.6.2.5	starpu_bitmap_unset_all()	212
28.6.2.6	starpu_bitmap_get()	212
28.6.2.7	starpu_bitmap_unset_and()	212
28.6.2.8	starpu_bitmap_or()	212
28.6.2.9	starpu_bitmap_and_get()	212
28.6.2.10	starpu_bitmap_cardinal()	213
28.6.2.11	starpu_bitmap_first()	213
28.6.2.12	starpu_bitmap_last()	213
28.6.2.13	starpu_bitmap_next()	213
28.6.2.14	starpu_bitmap_has_next()	213

28.7 Workers' Properties	213
28.7.1 Detailed Description	214
28.7.2 Data Structure Documentation	214
28.7.2.1 struct starpu_worker_collection	214
28.7.2.2 struct starpu_sched_ctx_iterator	216
28.7.3 Macro Definition Documentation	217
28.7.3.1 STARPU_NMAXWORKERS	217
28.7.3.2 STARPU_MAXCPUS	217
28.7.3.3 STARPU_MAXNODES	217
28.7.3.4 starpu_worker_get_id_check	217
28.7.4 Enumeration Type Documentation	217
28.7.4.1 starpu_node_kind	217
28.7.4.2 starpu_worker_archtype	218
28.7.4.3 starpu_worker_collection_type	218
28.7.5 Function Documentation	218
28.7.5.1 starpu_worker_get_count()	218
28.7.5.2 starpu_worker_get_count_by_type()	218
28.7.5.3 starpu_cpu_worker_get_count()	219
28.7.5.4 starpu_cuda_worker_get_count()	219
28.7.5.5 starpu_mic_worker_get_count()	219
28.7.5.6 starpu_mic_device_get_count()	219
28.7.5.7 starpu_scc_worker_get_count()	219
28.7.5.8 starpu_opencl_worker_get_count()	219
28.7.5.9 starpu_worker_get_id()	220
28.7.5.10 starpu_worker_get_ids_by_type()	220
28.7.5.11 starpu_worker_get_by_type()	220
28.7.5.12 starpu_worker_get_by_devid()	220
28.7.5.13 starpu_worker_get_devid()	220
28.7.5.14 starpu_worker_get_type()	221
28.7.5.15 starpu_worker_get_name()	221

28.7.5.16 starpu_worker_get_memory_node()	221
28.7.5.17 starpu_node_get_kind()	221
28.7.5.18 starpu_worker_get_type_as_string()	221
28.8 Data Management	221
28.8.1 Detailed Description	223
28.8.2 Macro Definition Documentation	223
28.8.2.1 STARPU_ACQUIRE_NO_NODE	223
28.8.2.2 STARPU_ACQUIRE_ALL_NODES	223
28.8.2.3 STARPU_DATA_ACQUIRE_CB	224
28.8.3 Typedef Documentation	224
28.8.3.1 starpu_data_handle_t	224
28.8.3.2 starpu_arbiter_t	224
28.8.4 Enumeration Type Documentation	224
28.8.4.1 starpu_data_access_mode	224
28.8.5 Function Documentation	225
28.8.5.1 starpu_data_register()	225
28.8.5.2 starpu_data_ptr_register()	225
28.8.5.3 starpu_data_register_same()	226
28.8.5.4 starpu_data_unregister()	226
28.8.5.5 starpu_data_unregister_no_coherency()	226
28.8.5.6 starpu_data_unregister_submit()	226
28.8.5.7 starpu_data_invalidate()	226
28.8.5.8 starpu_data_invalidate_submit()	226
28.8.5.9 starpu_data_set_wt_mask()	227
28.8.5.10 starpu_data_set_name()	227
28.8.5.11 starpu_data_set_coordinates_array()	227
28.8.5.12 starpu_data_set_coordinates()	227
28.8.5.13 starpu_data_fetch_on_node()	227
28.8.5.14 starpu_data_prefetch_on_node()	228
28.8.5.15 starpu_data_idle_prefetch_on_node()	228

28.8.5.16 starpu_data_wont_use()	228
28.8.5.17 starpu_data_lookup()	228
28.8.5.18 starpu_data_request_allocation()	228
28.8.5.19 starpu_data_query_status()	229
28.8.5.20 starpu_data_advise_as_important()	229
28.8.5.21 starpu_data_set_reduction_methods()	229
28.8.5.22 starpu_data_get_interface_ops()	229
28.8.5.23 starpu_data_set_user_data()	229
28.8.5.24 starpu_data_get_user_data()	230
28.8.5.25 starpu_data_acquire()	230
28.8.5.26 starpu_data_acquire_cb()	230
28.8.5.27 starpu_data_acquire_cb_sequential_consistency()	230
28.8.5.28 starpu_data_acquire_try()	231
28.8.5.29 starpu_data_acquire_on_node()	231
28.8.5.30 starpu_data_acquire_on_node_cb()	231
28.8.5.31 starpu_data_acquire_on_node_cb_sequential_consistency()	231
28.8.5.32 starpu_data_acquire_on_node_cb_sequential_consistency_sync_jobids()	232
28.8.5.33 starpu_data_acquire_on_node_try()	232
28.8.5.34 starpu_data_release()	232
28.8.5.35 starpu_data_release_on_node()	232
28.8.5.36 starpu_arbiter_create()	232
28.8.5.37 starpu_data_assign_arbiter()	233
28.8.5.38 starpu_arbiter_destroy()	233
28.9 Data Interfaces	233
28.9.1 Detailed Description	237
28.9.2 Data Structure Documentation	237
28.9.2.1 struct starpu_data_interface_ops	237
28.9.2.2 struct starpu_data_copy_methods	240
28.9.2.3 struct starpu_variable_interface	245
28.9.2.4 struct starpu_vector_interface	245

28.9.2.5	struct starpu_matrix_interface	245
28.9.2.6	struct starpu_block_interface	246
28.9.2.7	struct starpu_bcsr_interface	246
28.9.2.8	struct starpu_csr_interface	247
28.9.2.9	struct starpu_coo_interface	247
28.9.3	Macro Definition Documentation	247
28.9.3.1	STARPU_VARIABLE_GET_PTR	247
28.9.3.2	STARPU_VARIABLE_GET_ELEMSIZE	247
28.9.3.3	STARPU_VARIABLE_GET_DEV_HANDLE	248
28.9.3.4	STARPU_VARIABLE_GET_OFFSET	248
28.9.3.5	STARPU_VECTOR_GET_PTR	248
28.9.3.6	STARPU_VECTOR_GET_DEV_HANDLE	248
28.9.3.7	STARPU_VECTOR_GET_OFFSET	248
28.9.3.8	STARPU_VECTOR_GET_NX	248
28.9.3.9	STARPU_VECTOR_GET_ELEMSIZE	249
28.9.3.10	STARPU_VECTOR_GET_SLICE_BASE	249
28.9.3.11	STARPU_MATRIX_GET_PTR	249
28.9.3.12	STARPU_MATRIX_GET_DEV_HANDLE	249
28.9.3.13	STARPU_MATRIX_GET_OFFSET	249
28.9.3.14	STARPU_MATRIX_GET_NX	249
28.9.3.15	STARPU_MATRIX_GET_NY	250
28.9.3.16	STARPU_MATRIX_GET_LD	250
28.9.3.17	STARPU_MATRIX_GET_ELEMSIZE	250
28.9.3.18	STARPU_BLOCK_GET_PTR	250
28.9.3.19	STARPU_BLOCK_GET_DEV_HANDLE	250
28.9.3.20	STARPU_BLOCK_GET_OFFSET	250
28.9.3.21	STARPU_BLOCK_GET_NX	250
28.9.3.22	STARPU_BLOCK_GET_NY	251
28.9.3.23	STARPU_BLOCK_GET_NZ	251
28.9.3.24	STARPU_BLOCK_GET_LDY	251

28.9.3.25 STARPU_BLOCK_GET_LDZ	251
28.9.3.26 STARPU_BLOCK_GET_ELEMSIZE	251
28.9.3.27 STARPU_BCSR_GET_NNZ	251
28.9.3.28 STARPU_BCSR_GET_NZVAL	251
28.9.3.29 STARPU_BCSR_GET_NZVAL_DEV_HANDLE	252
28.9.3.30 STARPU_BCSR_GET_COLIND	252
28.9.3.31 STARPU_BCSR_GET_COLIND_DEV_HANDLE	252
28.9.3.32 STARPU_BCSR_GET_ROWPTR	252
28.9.3.33 STARPU_BCSR_GET_ROWPTR_DEV_HANDLE	252
28.9.3.34 STARPU_BCSR_GET_OFFSET	252
28.9.3.35 STARPU_CSR_GET_NNZ	253
28.9.3.36 STARPU_CSR_GET_NROW	253
28.9.3.37 STARPU_CSR_GET_NZVAL	253
28.9.3.38 STARPU_CSR_GET_NZVAL_DEV_HANDLE	253
28.9.3.39 STARPU_CSR_GET_COLIND	253
28.9.3.40 STARPU_CSR_GET_COLIND_DEV_HANDLE	253
28.9.3.41 STARPU_CSR_GET_ROWPTR	253
28.9.3.42 STARPU_CSR_GET_ROWPTR_DEV_HANDLE	254
28.9.3.43 STARPU_CSR_GET_OFFSET	254
28.9.3.44 STARPU_CSR_GET_FIRSTENTRY	254
28.9.3.45 STARPU_CSR_GET_ELEMSIZE	254
28.9.3.46 STARPU_COO_GET_COLUMNS	254
28.9.3.47 STARPU_COO_GET_COLUMNS_DEV_HANDLE	254
28.9.3.48 STARPU_COO_GET_ROWS	254
28.9.3.49 STARPU_COO_GET_ROWS_DEV_HANDLE	255
28.9.3.50 STARPU_COO_GET_VALUES	255
28.9.3.51 STARPU_COO_GET_VALUES_DEV_HANDLE	255
28.9.3.52 STARPU_COO_GET_OFFSET	255
28.9.3.53 STARPU_COO_GET_NX	255
28.9.3.54 STARPU_COO_GET_NY	255

28.9.3.55	STARPU_COO_GET_NVALUES	255
28.9.3.56	STARPU_COO_GET_ELEMSIZE	256
28.9.4	Enumeration Type Documentation	256
28.9.4.1	starpu_data_interface_id	256
28.9.5	Function Documentation	256
28.9.5.1	starpu_void_data_register()	256
28.9.5.2	starpu_variable_data_register()	257
28.9.5.3	starpu_variable_ptr_register()	257
28.9.5.4	starpu_vector_data_register()	257
28.9.5.5	starpu_vector_ptr_register()	258
28.9.5.6	starpu_matrix_data_register()	258
28.9.5.7	starpu_matrix_ptr_register()	258
28.9.5.8	starpu_block_data_register()	259
28.9.5.9	starpu_block_ptr_register()	259
28.9.5.10	starpu_bcsr_data_register()	259
28.9.5.11	starpu_csr_data_register()	260
28.9.5.12	starpu_coo_data_register()	261
28.9.5.13	starpu_data_get_interface_on_node()	261
28.9.5.14	starpu_data_handle_to_pointer()	261
28.9.5.15	starpu_data_pointer_is_inside()	261
28.9.5.16	starpu_data_get_local_ptr()	262
28.9.5.17	starpu_data_get_interface_id()	262
28.9.5.18	starpu_data_get_size()	262
28.9.5.19	starpu_data_pack()	262
28.9.5.20	starpu_data_unpack()	262
28.9.5.21	starpu_variable_get_elemsize()	262
28.9.5.22	starpu_variable_get_local_ptr()	263
28.9.5.23	starpu_vector_get_nx()	263
28.9.5.24	starpu_vector_get_elemsize()	263
28.9.5.25	starpu_vector_get_local_ptr()	263

28.9.5.26 starpu_matrix_get_nx()	263
28.9.5.27 starpu_matrix_get_ny()	263
28.9.5.28 starpu_matrix_get_local_ld()	263
28.9.5.29 starpu_matrix_get_local_ptr()	264
28.9.5.30 starpu_matrix_get_elemsize()	264
28.9.5.31 starpu_block_get_nx()	264
28.9.5.32 starpu_block_get_ny()	264
28.9.5.33 starpu_block_get_nz()	264
28.9.5.34 starpu_block_get_local_ldy()	264
28.9.5.35 starpu_block_get_local_ldz()	264
28.9.5.36 starpu_block_get_local_ptr()	265
28.9.5.37 starpu_block_get_elemsize()	265
28.9.5.38 starpu_bcsr_get_nnz()	265
28.9.5.39 starpu_bcsr_get_nrow()	265
28.9.5.40 starpu_bcsr_get_firstentry()	265
28.9.5.41 starpu_bcsr_get_local_nzval()	265
28.9.5.42 starpu_bcsr_get_local_colind()	265
28.9.5.43 starpu_bcsr_get_local_rowptr()	266
28.9.5.44 starpu_bcsr_get_r()	266
28.9.5.45 starpu_bcsr_get_c()	266
28.9.5.46 starpu_bcsr_get_elemsize()	266
28.9.5.47 starpu_csr_get_nnz()	266
28.9.5.48 starpu_csr_get_nrow()	266
28.9.5.49 starpu_csr_get_firstentry()	266
28.9.5.50 starpu_csr_get_local_nzval()	267
28.9.5.51 starpu_csr_get_local_colind()	267
28.9.5.52 starpu_csr_get_local_rowptr()	267
28.9.5.53 starpu_csr_get_elemsize()	267
28.9.5.54 starpu_malloc_on_node_flags()	267
28.9.5.55 starpu_free_on_node_flags()	267

28.9.5.56 starpu_malloc_on_node()	268
28.9.5.57 starpu_free_on_node()	268
28.9.5.58 starpu_malloc_on_node_set_default_flags()	268
28.9.5.59 starpu_interface_copy()	268
28.9.5.60 starpu_hash_crc32c_be_n()	268
28.9.5.61 starpu_hash_crc32c_be()	269
28.9.5.62 starpu_hash_crc32c_string()	269
28.9.5.63 starpu_data_interface_get_next_id()	269
28.10 Data Partition	269
28.10.1 Detailed Description	271
28.10.2 Data Structure Documentation	271
28.10.2.1 struct starpu_data_filter	271
28.10.3 Function Documentation	273
28.10.3.1 starpu_data_partition()	273
28.10.3.2 starpu_data_unpartition()	273
28.10.3.3 starpu_data_get_nb_children()	274
28.10.3.4 starpu_data_get_child()	274
28.10.3.5 starpu_data_get_sub_data()	274
28.10.3.6 starpu_data_vget_sub_data()	274
28.10.3.7 starpu_data_map_filters()	274
28.10.3.8 starpu_data_vmap_filters()	275
28.10.3.9 starpu_data_partition_plan()	275
28.10.3.10 starpu_data_partition_submit()	275
28.10.3.11 starpu_data_partition_readonly_submit()	276
28.10.3.12 starpu_data_partition_readwrite_upgrade_submit()	276
28.10.3.13 starpu_data_unpartition_submit()	276
28.10.3.14 starpu_data_unpartition_readonly_submit()	277
28.10.3.15 starpu_data_partition_clean()	277
28.10.3.16 starpu_vector_filter_block()	277
28.10.3.17 starpu_vector_filter_block_shadow()	277

28.10.3.18	starpu_vector_filter_list_long()	278
28.10.3.19	starpu_vector_filter_list()	278
28.10.3.20	starpu_vector_filter_divide_in_2()	278
28.10.3.21	starpu_matrix_filter_block()	278
28.10.3.22	starpu_matrix_filter_block_shadow()	279
28.10.3.23	starpu_matrix_filter_vertical_block()	279
28.10.3.24	starpu_matrix_filter_vertical_block_shadow()	279
28.10.3.25	starpu_block_filter_block()	279
28.10.3.26	starpu_block_filter_block_shadow()	280
28.10.3.27	starpu_block_filter_vertical_block()	280
28.10.3.28	starpu_block_filter_vertical_block_shadow()	280
28.10.3.29	starpu_block_filter_depth_block()	280
28.10.3.30	starpu_block_filter_depth_block_shadow()	281
28.10.3.31	starpu_bcsr_filter_canonical_block()	281
28.10.3.32	starpu_csr_filter_vertical_block()	281
28.11	Out Of Core	281
28.11.1	Detailed Description	282
28.11.2	Data Structure Documentation	282
28.11.2.1	struct starpu_disk_ops	282
28.11.3	Macro Definition Documentation	285
28.11.3.1	STARPU_DISK_SIZE_MIN	285
28.11.4	Function Documentation	285
28.11.4.1	starpu_disk_register()	285
28.11.4.2	starpu_disk_open()	285
28.11.4.3	starpu_disk_close()	286
28.11.5	Variable Documentation	286
28.11.5.1	starpu_disk_swap_node	286
28.11.5.2	starpu_disk_stdio_ops	286
28.11.5.3	starpu_disk_unistd_ops	286
28.11.5.4	starpu_disk_unistd_o_direct_ops	286

28.11.5.5 starpu_disk_leveldb_ops	286
28.12 Multiformat Data Interface	287
28.12.1 Detailed Description	287
28.12.2 Data Structure Documentation	287
28.12.2.1 struct starpu_multiformat_data_interface_ops	287
28.12.2.2 struct starpu_multiformat_interface	287
28.12.3 Macro Definition Documentation	288
28.12.3.1 STARPU_MULTIFORMAT_GET_CPU_PTR	288
28.12.3.2 STARPU_MULTIFORMAT_GET_CUDA_PTR	288
28.12.3.3 STARPU_MULTIFORMAT_GET_OPENCL_PTR	288
28.12.3.4 STARPU_MULTIFORMAT_GET_MIC_PTR	288
28.12.3.5 STARPU_MULTIFORMAT_GET_NX	289
28.12.4 Function Documentation	289
28.12.4.1 starpu_multiformat_data_register()	289
28.13 Codelet And Tasks	289
28.13.1 Detailed Description	291
28.13.2 Data Structure Documentation	291
28.13.2.1 struct starpu_codelet	291
28.13.2.2 struct starpu_data_descr	296
28.13.2.3 struct starpu_task	296
28.13.3 Macro Definition Documentation	304
28.13.3.1 STARPU_NOWHERE	304
28.13.3.2 STARPU_CPU	304
28.13.3.3 STARPU_CUDA	304
28.13.3.4 STARPU_OPENCL	305
28.13.3.5 STARPU_MIC	305
28.13.3.6 STARPU_SCC	305
28.13.3.7 STARPU_MAIN_RAM	305
28.13.3.8 STARPU_MULTIPLE_CPU_IMPLEMENTATIONS	305
28.13.3.9 STARPU_MULTIPLE_CUDA_IMPLEMENTATIONS	305

28.13.3.10	STARPU_MULTIPLE_OPENCL_IMPLEMENTATIONS	306
28.13.3.11	STARPU_NMAXBUFS	306
28.13.3.12	STARPU_VARIABLE_NBUFFERS	306
28.13.3.13	STARPU_TASK_INITIALIZER	306
28.13.3.14	STARPU_TASK_GET_NBUFFERS	306
28.13.3.15	STARPU_TASK_GET_HANDLE	306
28.13.3.16	STARPU_TASK_SET_HANDLE	307
28.13.3.17	STARPU_CODELET_GET_MODE	307
28.13.3.18	STARPU_CODELET_SET_MODE	307
28.13.3.19	STARPU_TASK_GET_MODE	307
28.13.3.20	STARPU_TASK_SET_MODE	307
28.13.3.21	STARPU_CODELET_GET_NODE	308
28.13.3.22	STARPU_CODELET_SET_NODE	308
28.13.3.23	STARPU_TASK_INVALID	308
28.13.4	Typedef Documentation	308
28.13.4.1	starpu_cpu_func_t	308
28.13.4.2	starpu_cuda_func_t	308
28.13.4.3	starpu_openc1_func_t	308
28.13.4.4	starpu_mic_func_t	309
28.13.4.5	starpu_scc_func_t	309
28.13.4.6	starpu_mic_kernel_t	309
28.13.4.7	starpu_scc_kernel_t	309
28.13.5	Enumeration Type Documentation	309
28.13.5.1	starpu_codelet_type	309
28.13.5.2	starpu_task_status	310
28.13.6	Function Documentation	310
28.13.6.1	starpu_codelet_init()	310
28.13.6.2	starpu_task_init()	310
28.13.6.3	starpu_task_create()	310
28.13.6.4	starpu_task_dup()	311

28.13.6.5 starpu_task_clean()	311
28.13.6.6 starpu_task_destroy()	311
28.13.6.7 starpu_task_wait()	311
28.13.6.8 starpu_task_submit()	311
28.13.6.9 starpu_task_submit_to_ctx()	312
28.13.6.10 starpu_task_wait_for_all()	312
28.13.6.11 starpu_task_wait_for_all_in_ctx()	312
28.13.6.12 starpu_task_wait_for_n_submitted()	312
28.13.6.13 starpu_task_wait_for_n_submitted_in_ctx()	312
28.13.6.14 starpu_task_nready()	312
28.13.6.15 starpu_task_nsubmitted()	313
28.13.6.16 starpu_task_get_current()	313
28.13.6.17 starpu_task_get_name()	313
28.13.6.18 starpu_task_get_model_name()	313
28.13.6.19 starpu_codelet_display_stats()	313
28.13.6.20 starpu_task_wait_for_no_ready()	313
28.13.6.21 starpu_task_set_implementation()	314
28.13.6.22 starpu_task_get_implementation()	314
28.13.6.23 starpu_iteration_push()	314
28.13.6.24 starpu_iteration_pop()	314
28.13.6.25 starpu_create_sync_task()	314
28.14 Insert_Task	315
28.14.1 Detailed Description	315
28.14.2 Macro Definition Documentation	315
28.14.2.1 STARPU_VALUE	315
28.14.2.2 STARPU_CL_ARGS	316
28.14.2.3 STARPU_CALLBACK	316
28.14.2.4 STARPU_CALLBACK_WITH_ARG	316
28.14.2.5 STARPU_CALLBACK_ARG	316
28.14.2.6 STARPU_PRIORITY	316

28.14.2.7	STARPU_DATA_ARRAY	316
28.14.2.8	STARPU_DATA_MODE_ARRAY	316
28.14.2.9	STARPU_EXECUTE_ON_WORKER	317
28.14.2.10	STARPU_WORKER_ORDER	317
28.14.2.11	STARPU_TAG	317
28.14.2.12	STARPU_TAG_ONLY	317
28.14.2.13	STARPU_NAME	317
28.14.2.14	STARPU_FLOPS	317
28.14.2.15	STARPU_SCHED_CTX	317
28.14.2.16	STARPU_TASK_COLOR	318
28.14.3	Function Documentation	318
28.14.3.1	starpu_insert_task()	318
28.14.3.2	starpu_task_insert()	318
28.14.3.3	starpu_task_insert_data_make_room()	319
28.14.3.4	starpu_task_insert_data_process_arg()	319
28.14.3.5	starpu_task_insert_data_process_array_arg()	319
28.14.3.6	starpu_task_insert_data_process_mode_array_arg()	319
28.14.3.7	starpu_codelet_pack_args()	320
28.14.3.8	starpu_codelet_pack_arg_init()	320
28.14.3.9	starpu_codelet_pack_arg_fini()	320
28.14.3.10	starpu_codelet_unpack_args()	320
28.14.3.11	starpu_codelet_unpack_args_and_copyleft()	320
28.14.3.12	starpu_task_build()	321
28.15	Explicit Dependencies	321
28.15.1	Detailed Description	321
28.15.2	Typedef Documentation	321
28.15.2.1	starpu_tag_t	321
28.15.3	Function Documentation	322
28.15.3.1	starpu_task_declare_deps_array()	322
28.15.3.2	starpu_task_get_task_succs()	322

28.15.3.3 starpu_task_get_task_scheduled_succs()	322
28.15.3.4 starpu_tag_declare_deps()	323
28.15.3.5 starpu_tag_declare_deps_array()	323
28.15.3.6 starpu_tag_wait()	323
28.15.3.7 starpu_tag_wait_array()	324
28.15.3.8 starpu_tag_restart()	324
28.15.3.9 starpu_tag_remove()	324
28.15.3.10 starpu_tag_notify_from_apps()	324
28.16 Implicit Data Dependencies	324
28.16.1 Detailed Description	325
28.16.2 Function Documentation	325
28.16.2.1 starpu_data_set_default_sequential_consistency_flag()	325
28.16.2.2 starpu_data_get_default_sequential_consistency_flag()	325
28.16.2.3 starpu_data_set_sequential_consistency_flag()	325
28.16.2.4 starpu_data_get_sequential_consistency_flag()	326
28.17 Performance Model	326
28.17.1 Detailed Description	327
28.17.2 Data Structure Documentation	327
28.17.2.1 struct starpu_perfmodel_device	327
28.17.2.2 struct starpu_perfmodel_arch	327
28.17.2.3 struct starpu_perfmodel	327
28.17.2.4 struct starpu_perfmodel_regression_model	329
28.17.2.5 struct starpu_perfmodel_per_arch	329
28.17.2.6 struct starpu_perfmodel_history_list	330
28.17.2.7 struct starpu_perfmodel_history_entry	330
28.17.3 Enumeration Type Documentation	330
28.17.3.1 starpu_perfmodel_type	331
28.17.4 Function Documentation	331
28.17.4.1 starpu_perfmodel_init()	331
28.17.4.2 starpu_perfmodel_free_sampling_directories()	331

28.17.4.3 starpu_perfmodel_load_file()	331
28.17.4.4 starpu_perfmodel_load_symbol()	332
28.17.4.5 starpu_perfmodel_unload_model()	332
28.17.4.6 starpu_perfmodel_debugfilepath()	332
28.17.4.7 starpu_perfmodel_get_archtype_name()	332
28.17.4.8 starpu_perfmodel_get_arch_name()	332
28.17.4.9 starpu_worker_get_perf_archtype()	332
28.17.4.10 starpu_perfmodel_initialize()	333
28.17.4.11 starpu_perfmodel_list()	333
28.17.4.12 starpu_perfmodel_directory()	333
28.17.4.13 starpu_perfmodel_print()	333
28.17.4.14 starpu_perfmodel_print_all()	333
28.17.4.15 starpu_perfmodel_print_estimations()	333
28.17.4.16 starpu_bus_print_bandwidth()	334
28.17.4.17 starpu_bus_print_affinity()	334
28.17.4.18 starpu_bus_print_filenames()	334
28.17.4.19 starpu_perfmodel_update_history()	334
28.17.4.20 starpu_transfer_bandwidth()	334
28.17.4.21 starpu_transfer_latency()	334
28.17.4.22 starpu_transfer_predict()	335
28.17.4.23 starpu_perfmodel_history_based_expected_perf()	335
28.18 Profiling	335
28.18.1 Detailed Description	336
28.18.2 Data Structure Documentation	336
28.18.2.1 struct starpu_profiling_task_info	336
28.18.2.2 struct starpu_profiling_worker_info	337
28.18.2.3 struct starpu_profiling_bus_info	337
28.18.3 Macro Definition Documentation	338
28.18.3.1 STARPU_PROFILING_DISABLE	338
28.18.3.2 STARPU_PROFILING_ENABLE	338

28.18.4 Function Documentation	338
28.18.4.1 starpu_profiling_status_set()	338
28.18.4.2 starpu_profiling_status_get()	338
28.18.4.3 starpu_profiling_init()	339
28.18.4.4 starpu_profiling_set_id()	339
28.18.4.5 starpu_profiling_worker_get_info()	339
28.18.4.6 starpu_bus_get_profiling_info()	339
28.18.4.7 starpu_bus_get_count()	339
28.18.4.8 starpu_bus_get_id()	339
28.18.4.9 starpu_bus_get_src()	340
28.18.4.10 starpu_bus_get_dst()	340
28.18.4.11 starpu_timing_timespec_delay_us()	340
28.18.4.12 starpu_timing_timespec_to_us()	340
28.18.4.13 starpu_profiling_bus_helper_display_summary()	340
28.18.4.14 starpu_profiling_worker_helper_display_summary()	340
28.18.4.15 starpu_data_display_memory_stats()	341
28.19 Theoretical Lower Bound on Execution Time	341
28.19.1 Detailed Description	341
28.19.2 Function Documentation	341
28.19.2.1 starpu_bound_start()	341
28.19.2.2 starpu_bound_stop()	341
28.19.2.3 starpu_bound_print_dot()	342
28.19.2.4 starpu_bound_compute()	342
28.19.2.5 starpu_bound_print_lp()	342
28.19.2.6 starpu_bound_print_mps()	342
28.19.2.7 starpu_bound_print()	342
28.20 CUDA Extensions	342
28.20.1 Detailed Description	343
28.20.2 Macro Definition Documentation	343
28.20.2.1 STARPU_USE_CUDA	343

28.20.2.2 STARPU_MAXCUDADEVs	343
28.20.2.3 STARPU_CUDA_REPORT_ERROR	343
28.20.2.4 STARPU_CUBLAS_REPORT_ERROR	343
28.20.3 Function Documentation	344
28.20.3.1 starpu_cuda_get_local_stream()	344
28.20.3.2 starpu_cuda_get_device_properties()	344
28.20.3.3 starpu_cuda_report_error()	344
28.20.3.4 starpu_cuda_copy_async_sync()	344
28.20.3.5 starpu_cuda_set_device()	345
28.20.3.6 starpu_cublas_init()	345
28.20.3.7 starpu_cublas_shutdown()	345
28.20.3.8 starpu_cublas_report_error()	345
28.21 OpenCL Extensions	345
28.21.1 Detailed Description	347
28.21.2 Data Structure Documentation	347
28.21.2.1 struct starpu_opencil_program	347
28.21.3 Macro Definition Documentation	347
28.21.3.1 STARPU_USE_OPENCL	347
28.21.3.2 STARPU_MAXOPENCLDEVs	347
28.21.3.3 STARPU_OPENCL_DATADIR	348
28.21.3.4 STARPU_OPENCL_DISPLAY_ERROR	348
28.21.3.5 STARPU_OPENCL_REPORT_ERROR	348
28.21.3.6 STARPU_OPENCL_REPORT_ERROR_WITH_MSG	348
28.21.4 Function Documentation	348
28.21.4.1 starpu_opencil_get_context()	348
28.21.4.2 starpu_opencil_get_device()	349
28.21.4.3 starpu_opencil_get_queue()	349
28.21.4.4 starpu_opencil_get_current_context()	349
28.21.4.5 starpu_opencil_get_current_queue()	349
28.21.4.6 starpu_opencil_set_kernel_args()	349

28.21.4.7 starpu_opencil_load_opencil_from_file()	350
28.21.4.8 starpu_opencil_load_opencil_from_string()	350
28.21.4.9 starpu_opencil_unload_opencil()	350
28.21.4.10 starpu_opencil_load_program_source()	350
28.21.4.11 starpu_opencil_load_program_source_malloc()	350
28.21.4.12 starpu_opencil_compile_opencil_from_file()	351
28.21.4.13 starpu_opencil_compile_opencil_from_string()	351
28.21.4.14 starpu_opencil_load_binary_opencil()	351
28.21.4.15 starpu_opencil_load_kernel()	351
28.21.4.16 starpu_opencil_release_kernel()	351
28.21.4.17 starpu_opencil_collect_stats()	352
28.21.4.18 starpu_opencil_error_string()	352
28.21.4.19 starpu_opencil_display_error()	352
28.21.4.20 starpu_opencil_report_error()	352
28.21.4.21 starpu_opencil_allocate_memory()	352
28.21.4.22 starpu_opencil_copy_ram_to_opencil()	353
28.21.4.23 starpu_opencil_copy_opencil_to_ram()	353
28.21.4.24 starpu_opencil_copy_opencil_to_opencil()	353
28.21.4.25 starpu_opencil_copy_async_sync()	354
28.22 OpenMP Runtime Support	354
28.22.1 Detailed Description	356
28.22.2 Data Structure Documentation	357
28.22.2.1 struct starpu_omp_lock_t	357
28.22.2.2 struct starpu_omp_nest_lock_t	357
28.22.2.3 struct starpu_omp_parallel_region_attr	357
28.22.2.4 struct starpu_omp_task_region_attr	358
28.22.3 Macro Definition Documentation	359
28.22.3.1 STARPU_OPENMP	359
28.22.4 Enumeration Type Documentation	359
28.22.4.1 starpu_omp_sched_value	359

28.22.4.2 starpu_omp_proc_bind_value	359
28.22.5 Function Documentation	360
28.22.5.1 starpu_omp_init()	360
28.22.5.2 starpu_omp_shutdown()	360
28.22.5.3 starpu_omp_parallel_region()	360
28.22.5.4 starpu_omp_master()	360
28.22.5.5 starpu_omp_master_inline()	361
28.22.5.6 starpu_omp_barrier()	361
28.22.5.7 starpu_omp_critical()	361
28.22.5.8 starpu_omp_critical_inline_begin()	361
28.22.5.9 starpu_omp_critical_inline_end()	362
28.22.5.10 starpu_omp_single()	362
28.22.5.11 starpu_omp_single_inline()	362
28.22.5.12 starpu_omp_single_copyprivate()	362
28.22.5.13 starpu_omp_single_copyprivate_inline_begin()	363
28.22.5.14 starpu_omp_single_copyprivate_inline_end()	363
28.22.5.15 starpu_omp_for()	363
28.22.5.16 starpu_omp_for_inline_first()	364
28.22.5.17 starpu_omp_for_inline_next()	364
28.22.5.18 starpu_omp_for_alt()	365
28.22.5.19 starpu_omp_for_inline_first_alt()	365
28.22.5.20 starpu_omp_for_inline_next_alt()	366
28.22.5.21 starpu_omp_ordered()	366
28.22.5.22 starpu_omp_ordered_inline_begin()	366
28.22.5.23 starpu_omp_ordered_inline_end()	366
28.22.5.24 starpu_omp_sections()	367
28.22.5.25 starpu_omp_sections_combined()	367
28.22.5.26 starpu_omp_task_region()	367
28.22.5.27 starpu_omp_taskwait()	368
28.22.5.28 starpu_omp_taskgroup()	368

28.22.5.29	starpu_omp_taskgroup_inline_begin()	368
28.22.5.30	starpu_omp_taskgroup_inline_end()	369
28.22.5.31	starpu_omp_set_num_threads()	369
28.22.5.32	starpu_omp_get_num_threads()	369
28.22.5.33	starpu_omp_get_thread_num()	370
28.22.5.34	starpu_omp_get_max_threads()	370
28.22.5.35	starpu_omp_get_num_procs()	370
28.22.5.36	starpu_omp_in_parallel()	371
28.22.5.37	starpu_omp_set_dynamic()	371
28.22.5.38	starpu_omp_get_dynamic()	371
28.22.5.39	starpu_omp_set_nested()	372
28.22.5.40	starpu_omp_get_nested()	372
28.22.5.41	starpu_omp_get_cancellation()	372
28.22.5.42	starpu_omp_set_schedule()	373
28.22.5.43	starpu_omp_get_schedule()	373
28.22.5.44	starpu_omp_get_thread_limit()	373
28.22.5.45	starpu_omp_set_max_active_levels()	374
28.22.5.46	starpu_omp_get_max_active_levels()	374
28.22.5.47	starpu_omp_get_level()	374
28.22.5.48	starpu_omp_get_ancestor_thread_num()	375
28.22.5.49	starpu_omp_get_team_size()	375
28.22.5.50	starpu_omp_get_active_level()	375
28.22.5.51	starpu_omp_in_final()	376
28.22.5.52	starpu_omp_get_proc_bind()	376
28.22.5.53	starpu_omp_set_default_device()	376
28.22.5.54	starpu_omp_get_default_device()	377
28.22.5.55	starpu_omp_get_num_devices()	377
28.22.5.56	starpu_omp_get_num_teams()	377
28.22.5.57	starpu_omp_get_team_num()	378
28.22.5.58	starpu_omp_is_initial_device()	378

28.22.5.59	starpu_omp_init_lock()	378
28.22.5.60	starpu_omp_destroy_lock()	379
28.22.5.61	starpu_omp_set_lock()	379
28.22.5.62	starpu_omp_unset_lock()	379
28.22.5.63	starpu_omp_test_lock()	380
28.22.5.64	starpu_omp_init_nest_lock()	380
28.22.5.65	starpu_omp_destroy_nest_lock()	380
28.22.5.66	starpu_omp_set_nest_lock()	381
28.22.5.67	starpu_omp_unset_nest_lock()	381
28.22.5.68	starpu_omp_test_nest_lock()	381
28.22.5.69	starpu_omp_atomic_fallback_inline_begin()	382
28.22.5.70	starpu_omp_atomic_fallback_inline_end()	382
28.22.5.71	starpu_omp_get_wtime()	382
28.22.5.72	starpu_omp_get_wtick()	383
28.22.5.73	starpu_omp_vector_annotate()	383
28.23	MIC Extensions	383
28.23.1	Detailed Description	384
28.23.2	Macro Definition Documentation	384
28.23.2.1	STARPU_USE_MIC	384
28.23.2.2	STARPU_MAXMICDEVS	384
28.23.3	Typedef Documentation	384
28.23.3.1	starpu_mic_func_symbol_t	384
28.23.4	Function Documentation	384
28.23.4.1	starpu_mic_register_kernel()	384
28.23.4.2	starpu_mic_get_kernel()	385
28.24	SCC Extensions	385
28.24.1	Detailed Description	385
28.24.2	Macro Definition Documentation	385
28.24.2.1	STARPU_USE_SCC	385
28.24.2.2	STARPU_MAXSCCDEVS	385

28.24.3 Typedef Documentation	386
28.24.3.1 starpu_scc_func_symbol_t	386
28.24.4 Function Documentation	386
28.24.4.1 starpu_scc_register_kernel()	386
28.24.4.2 starpu_scc_get_kernel()	386
28.25 Miscellaneous Helpers	386
28.25.1 Detailed Description	387
28.25.2 Function Documentation	387
28.25.2.1 starpu_data_cpy()	387
28.25.2.2 starpu_execute_on_each_worker()	387
28.25.2.3 starpu_execute_on_each_worker_ex()	387
28.25.2.4 starpu_execute_on_specific_workers()	388
28.25.2.5 starpu_timing_now()	388
28.26 FxT Support	388
28.26.1 Detailed Description	388
28.26.2 Data Structure Documentation	388
28.26.2.1 struct starpu_fxt_codelet_event	388
28.26.2.2 struct starpu_fxt_options	389
28.26.3 Function Documentation	390
28.26.3.1 starpu_fxt_options_init()	390
28.26.3.2 starpu_fxt_generate_trace()	390
28.26.3.3 starpu_fxt_start_profiling()	390
28.26.3.4 starpu_fxt_stop_profiling()	390
28.26.3.5 starpu_fxt_autostart_profiling()	390
28.26.3.6 starpu_fxt_write_data_trace()	390
28.26.3.7 starpu_fxt_trace_user_event()	391
28.26.3.8 starpu_fxt_trace_user_event_string()	391
28.27 FFT Support	391
28.27.1 Detailed Description	391
28.27.2 Function Documentation	391

28.27.2.1 starpufft_malloc()	391
28.27.2.2 starpufft_free()	392
28.27.2.3 starpufft_plan_dft_1d()	392
28.27.2.4 starpufft_plan_dft_2d()	392
28.27.2.5 starpufft_start()	392
28.27.2.6 starpufft_start_handle()	392
28.27.2.7 starpufft_execute()	393
28.27.2.8 starpufft_execute_handle()	393
28.27.2.9 starpufft_cleanup()	393
28.27.2.10 starpufft_destroy_plan()	393
28.28 MPI Support	393
28.28.1 Detailed Description	395
28.28.2 Macro Definition Documentation	395
28.28.2.1 STARPU_USE_MPI	396
28.28.2.2 STARPU_MPI_TAG_UB	396
28.28.2.3 starpu_mpi_data_register	396
28.28.2.4 starpu_data_set_tag	396
28.28.2.5 starpu_mpi_data_set_rank	396
28.28.2.6 starpu_data_set_rank	396
28.28.2.7 starpu_data_get_rank	397
28.28.2.8 starpu_data_get_tag	397
28.28.2.9 STARPU_MPI_PER_NODE	397
28.28.2.10 STARPU_EXECUTE_ON_NODE	397
28.28.2.11 STARPU_EXECUTE_ON_DATA	397
28.28.2.12 STARPU_NODE_SELECTION_POLICY	397
28.28.3 Function Documentation	397
28.28.3.1 starpu_mpi_init_comm()	398
28.28.3.2 starpu_mpi_init()	398
28.28.3.3 starpu_mpi_initialize()	398
28.28.3.4 starpu_mpi_initialize_extended()	398

28.28.3.5	starpu_mpi_shutdown()	398
28.28.3.6	starpu_mpi_comm_amounts_retrieve()	399
28.28.3.7	starpu_mpi_comm_size()	399
28.28.3.8	starpu_mpi_comm_rank()	399
28.28.3.9	starpu_mpi_world_rank()	399
28.28.3.10	starpu_mpi_world_size()	399
28.28.3.11	starpu_mpi_send()	399
28.28.3.12	starpu_mpi_recv()	400
28.28.3.13	starpu_mpi_isend()	400
28.28.3.14	starpu_mpi_irecv()	400
28.28.3.15	starpu_mpi_isend_detached()	400
28.28.3.16	starpu_mpi_irecv_detached()	401
28.28.3.17	starpu_mpi_irecv_detached_sequential_consistency()	401
28.28.3.18	starpu_mpi_issend()	401
28.28.3.19	starpu_mpi_issend_detached()	402
28.28.3.20	starpu_mpi_wait()	402
28.28.3.21	starpu_mpi_test()	402
28.28.3.22	starpu_mpi_barrier()	402
28.28.3.23	starpu_mpi_wait_for_all()	402
28.28.3.24	starpu_mpi_isend_detached_unlock_tag()	403
28.28.3.25	starpu_mpi_irecv_detached_unlock_tag()	403
28.28.3.26	starpu_mpi_isend_array_detached_unlock_tag()	403
28.28.3.27	starpu_mpi_irecv_array_detached_unlock_tag()	403
28.28.3.28	starpu_mpi_get_communication_tag()	404
28.28.3.29	starpu_mpi_set_communication_tag()	404
28.28.3.30	starpu_mpi_datatype_register()	404
28.28.3.31	starpu_mpi_datatype_unregister()	404
28.28.3.32	starpu_mpi_comm_get_attr()	404
28.28.3.33	starpu_mpi_cache_is_enabled()	404
28.28.3.34	starpu_mpi_cache_set()	405

28.28.3.35	starpu_mpi_cache_flush()	405
28.28.3.36	starpu_mpi_cache_flush_all_data()	405
28.28.3.37	starpu_mpi_cached_receive()	405
28.28.3.38	starpu_mpi_cached_send()	405
28.28.3.39	starpu_mpi_data_register_comm()	405
28.28.3.40	starpu_mpi_data_set_tag()	406
28.28.3.41	starpu_mpi_data_set_rank_comm()	406
28.28.3.42	starpu_mpi_data_get_rank()	406
28.28.3.43	starpu_mpi_data_get_tag()	406
28.28.3.44	starpu_mpi_data_migrate()	406
28.28.3.45	starpu_mpi_insert_task()	407
28.28.3.46	starpu_mpi_task_insert()	407
28.28.3.47	starpu_mpi_task_build()	407
28.28.3.48	starpu_mpi_task_post_build()	408
28.28.3.49	starpu_mpi_get_data_on_node()	408
28.28.3.50	starpu_mpi_get_data_on_node_detached()	408
28.28.3.51	starpu_mpi_get_data_on_all_nodes_detached()	408
28.28.3.52	starpu_mpi_node_selection_get_current_policy()	408
28.28.3.53	starpu_mpi_node_selection_set_current_policy()	409
28.28.3.54	starpu_mpi_node_selection_register_policy()	409
28.28.3.55	starpu_mpi_node_selection_unregister_policy()	409
28.28.3.56	starpu_mpi_redux_data()	409
28.28.3.57	starpu_mpi_scatter_detached()	410
28.28.3.58	starpu_mpi_gather_detached()	410
28.29	Task Bundles	410
28.29.1	Detailed Description	411
28.29.2	Typedef Documentation	411
28.29.2.1	starpu_task_bundle_t	411
28.29.3	Function Documentation	411
28.29.3.1	starpu_task_bundle_create()	411

28.29.3.2 starpu_task_bundle_insert()	411
28.29.3.3 starpu_task_bundle_remove()	411
28.29.3.4 starpu_task_bundle_close()	412
28.29.3.5 starpu_task_bundle_expected_length()	412
28.29.3.6 starpu_task_bundle_expected_energy()	412
28.29.3.7 starpu_task_bundle_expected_data_transfer_time()	412
28.30 Task Lists	412
28.30.1 Detailed Description	413
28.30.2 Data Structure Documentation	413
28.30.2.1 struct starpu_task_list	413
28.30.3 Function Documentation	413
28.30.3.1 starpu_task_list_init()	413
28.30.3.2 starpu_task_list_push_front()	413
28.30.3.3 starpu_task_list_push_back()	413
28.30.3.4 starpu_task_list_front()	413
28.30.3.5 starpu_task_list_back()	414
28.30.3.6 starpu_task_list_empty()	414
28.30.3.7 starpu_task_list_erase()	414
28.30.3.8 starpu_task_list_pop_front()	414
28.30.3.9 starpu_task_list_pop_back()	414
28.30.3.10 starpu_task_list_begin()	414
28.30.3.11 starpu_task_list_next()	414
28.30.3.12 starpu_task_list_ismember()	415
28.31 Parallel Tasks	415
28.31.1 Detailed Description	415
28.31.2 Function Documentation	415
28.31.2.1 starpu_combined_worker_get_size()	415
28.31.2.2 starpu_combined_worker_get_rank()	415
28.31.2.3 starpu_combined_worker_get_count()	416
28.31.2.4 starpu_combined_worker_get_id()	416

28.31.2.5 starpu_combined_worker_assign_workerid()	416
28.31.2.6 starpu_combined_worker_get_description()	416
28.31.2.7 starpu_combined_worker_can_execute_task()	416
28.31.2.8 starpu_parallel_task_barrier_init()	416
28.31.2.9 starpu_parallel_task_barrier_init_n()	417
28.32 Running Drivers	417
28.32.1 Detailed Description	417
28.32.2 Function Documentation	417
28.32.2.1 starpu_driver_run()	417
28.32.2.2 starpu_driver_init()	417
28.32.2.3 starpu_driver_run_once()	417
28.32.2.4 starpu_driver_deinit()	418
28.32.2.5 starpu_drivers_request_termination()	418
28.33 Expert Mode	418
28.33.1 Detailed Description	418
28.33.2 Function Documentation	418
28.33.2.1 starpu_wake_all_blocked_workers()	418
28.33.2.2 starpu_progression_hook_register()	418
28.33.2.3 starpu_progression_hook_deregister()	419
28.34 StarPU-Top Interface	419
28.34.1 Detailed Description	420
28.34.2 Data Structure Documentation	420
28.34.2.1 struct starpu_top_data	420
28.34.2.2 struct starpu_top_param	420
28.34.3 Enumeration Type Documentation	422
28.34.3.1 starpu_top_data_type	422
28.34.3.2 starpu_top_param_type	422
28.34.3.3 starpu_top_message_type	423
28.34.4 Function Documentation	423
28.34.4.1 starpu_top_add_data_boolean()	423

28.34.4.2 starpu_top_add_data_integer()	423
28.34.4.3 starpu_top_add_data_float()	424
28.34.4.4 starpu_top_register_parameter_boolean()	424
28.34.4.5 starpu_top_register_parameter_float()	424
28.34.4.6 starpu_top_register_parameter_integer()	424
28.34.4.7 starpu_top_register_parameter_enum()	425
28.34.4.8 starpu_top_init_and_wait()	425
28.34.4.9 starpu_top_update_parameter()	425
28.34.4.10 starpu_top_update_data_boolean()	425
28.34.4.11 starpu_top_update_data_integer()	425
28.34.4.12 starpu_top_update_data_float()	425
28.34.4.13 starpu_top_task_prevision()	426
28.34.4.14 starpu_top_debug_log()	426
28.34.4.15 starpu_top_debug_lock()	426
28.35 Scheduling Contexts	426
28.35.1 Detailed Description	428
28.35.2 Data Structure Documentation	428
28.35.2.1 struct starpu_sched_ctx_performance_counters	428
28.35.3 Macro Definition Documentation	429
28.35.3.1 STARPU_SCHED_CTX_POLICY_NAME	429
28.35.3.2 STARPU_SCHED_CTX_POLICY_STRUCT	429
28.35.3.3 STARPU_SCHED_CTX_POLICY_MIN_PRIO	430
28.35.3.4 STARPU_SCHED_CTX_POLICY_MAX_PRIO	430
28.35.3.5 STARPU_MIN_PRIO	430
28.35.3.6 STARPU_MAX_PRIO	430
28.35.3.7 STARPU_DEFAULT_PRIO	430
28.35.4 Function Documentation	430
28.35.4.1 starpu_sched_ctx_create()	430
28.35.4.2 starpu_sched_ctx_create_inside_interval()	431
28.35.4.3 starpu_sched_ctx_register_close_callback()	431

28.35.4.4 starpu_sched_ctx_add_workers()	431
28.35.4.5 starpu_sched_ctx_remove_workers()	431
28.35.4.6 starpu_sched_ctx_display_workers()	431
28.35.4.7 starpu_sched_ctx_delete()	432
28.35.4.8 starpu_sched_ctx_set_inheritor()	432
28.35.4.9 starpu_sched_ctx_set_context()	432
28.35.4.10 starpu_sched_ctx_get_context()	432
28.35.4.11 starpu_sched_ctx_stop_task_submission()	432
28.35.4.12 starpu_sched_ctx_finished_submit()	432
28.35.4.13 starpu_sched_ctx_get_workers_list()	433
28.35.4.14 starpu_sched_ctx_get_workers_list_raw()	433
28.35.4.15 starpu_sched_ctx_get_nworkers()	433
28.35.4.16 starpu_sched_ctx_get_nshared_workers()	433
28.35.4.17 starpu_sched_ctx_contains_worker()	433
28.35.4.18 starpu_sched_ctx_worker_get_id()	433
28.35.4.19 starpu_sched_ctx_overlapping_ctxs_on_worker()	434
28.35.4.20 starpu_sched_ctx_set_min_priority()	434
28.35.4.21 starpu_sched_ctx_set_max_priority()	434
28.35.4.22 starpu_sched_ctx_get_min_priority()	434
28.35.4.23 starpu_sched_ctx_get_max_priority()	434
28.35.4.24 starpu_sched_ctx_min_priority_is_set()	434
28.35.4.25 starpu_sched_ctx_max_priority_is_set()	435
28.35.4.26 starpu_sched_ctx_create_worker_collection()	435
28.35.4.27 starpu_sched_ctx_delete_worker_collection()	435
28.35.4.28 starpu_sched_ctx_get_worker_collection()	435
28.35.4.29 starpu_sched_ctx_set_perf_counters()	435
28.35.4.30 starpu_sched_ctx_call_pushed_task_cb()	435
28.35.4.31 starpu_sched_ctx_notify_hypervisor_exists()	436
28.35.4.32 starpu_sched_ctx_check_if_hypervisor_exists()	436
28.35.4.33 starpu_sched_ctx_set_policy_data()	436

28.35.4.34	starpu_sched_ctx_get_policy_data()	436
28.35.4.35	starpu_sched_ctx_exec_parallel_code()	436
28.35.4.36	starpu_sched_ctx_get_nready_tasks()	436
28.35.4.37	starpu_sched_ctx_get_nready_flops()	437
28.36	Scheduling Policy	437
28.36.1	Detailed Description	438
28.36.2	Data Structure Documentation	438
28.36.2.1	struct starpu_sched_policy	438
28.36.3	Macro Definition Documentation	441
28.36.3.1	STARPU_NMAX_SCHED_CTXS	441
28.36.3.2	STARPU_MAXIMPLEMENTATIONS	441
28.36.4	Function Documentation	441
28.36.4.1	starpu_sched_get_predefined_policies()	441
28.36.4.2	starpu_worker_get_sched_condition()	441
28.36.4.3	starpu_wake_worker()	441
28.36.4.4	starpu_sched_set_min_priority()	442
28.36.4.5	starpu_sched_set_max_priority()	442
28.36.4.6	starpu_sched_get_min_priority()	442
28.36.4.7	starpu_sched_get_max_priority()	442
28.36.4.8	starpu_push_local_task()	442
28.36.4.9	starpu_push_task_end()	442
28.36.4.10	starpu_worker_can_execute_task()	443
28.36.4.11	starpu_worker_can_execute_task_impl()	443
28.36.4.12	starpu_worker_can_execute_task_first_impl()	443
28.36.4.13	starpu_task_footprint()	443
28.36.4.14	starpu_task_data_footprint()	443
28.36.4.15	starpu_task_expected_length()	444
28.36.4.16	starpu_worker_get_relative_speedup()	444
28.36.4.17	starpu_task_expected_data_transfer_time()	444
28.36.4.18	starpu_data_expected_transfer_time()	444

28.36.4.1	starpu_task_expected_energy()	444
28.36.4.20	starpu_task_expected_conversion_time()	444
28.36.4.21	starpu_get_prefetch_flag()	445
28.36.4.22	starpu_prefetch_task_input_on_node()	445
28.36.4.23	starpu_idle_prefetch_task_input_on_node()	445
28.36.4.24	starpu_sched_ctx_worker_shares_tasks_lists()	445
28.37	Tree	445
28.37.1	Detailed Description	446
28.37.2	Data Structure Documentation	446
28.37.2.1	struct starpu_tree	446
28.37.3	Function Documentation	447
28.37.3.1	starpu_tree_reset_visited()	447
28.37.3.2	starpu_tree_insert()	447
28.37.3.3	starpu_tree_get()	447
28.37.3.4	starpu_tree_get_neighbour()	447
28.37.3.5	starpu_tree_free()	448
28.38	Scheduling Context Hypervisor - Regular usage	448
28.38.1	Detailed Description	448
28.38.2	Macro Definition Documentation	448
28.38.2.1	SC_HYPERVISOR_MAX_IDLE	449
28.38.2.2	SC_HYPERVISOR_PRIORITY	449
28.38.2.3	SC_HYPERVISOR_MIN_WORKERS	449
28.38.2.4	SC_HYPERVISOR_MAX_WORKERS	449
28.38.2.5	SC_HYPERVISOR_GRANULARITY	449
28.38.2.6	SC_HYPERVISOR_FIXED_WORKERS	449
28.38.2.7	SC_HYPERVISOR_MIN_TASKS	450
28.38.2.8	SC_HYPERVISOR_NEW_WORKERS_MAX_IDLE	450
28.38.2.9	SC_HYPERVISOR_TIME_TO_APPLY	450
28.38.2.10	SC_HYPERVISOR_ISPEED_W_SAMPLE	450
28.38.2.11	SC_HYPERVISOR_ISPEED_CTX_SAMPLE	450

28.38.2.12	SC_HYPERVISOR_NULL	450
28.38.3	Function Documentation	450
28.38.3.1	sc_hypervisor_init()	451
28.38.3.2	sc_hypervisor_shutdown()	451
28.38.3.3	sc_hypervisor_register_ctx()	451
28.38.3.4	sc_hypervisor_unregister_ctx()	451
28.38.3.5	sc_hypervisor_resize_ctxs()	451
28.38.3.6	sc_hypervisor_stop_resize()	452
28.38.3.7	sc_hypervisor_start_resize()	452
28.38.3.8	sc_hypervisor_get_policy()	452
28.38.3.9	sc_hypervisor_add_workers_to_sched_ctx()	452
28.38.3.10	sc_hypervisor_remove_workers_from_sched_ctx()	452
28.38.3.11	sc_hypervisor_move_workers()	452
28.38.3.12	sc_hypervisor_size_ctxs()	453
28.38.3.13	sc_hypervisor_set_type_of_task()	453
28.38.3.14	sc_hypervisor_update_diff_total_flops()	453
28.38.3.15	sc_hypervisor_update_diff_elapsed_flops()	453
28.38.3.16	sc_hypervisor_ctl()	453
28.39	Scheduling Context Hypervisor - Building a new resizing policy	454
28.39.1	Detailed Description	454
28.39.2	Data Structure Documentation	454
28.39.2.1	struct sc_hypervisor_policy	454
28.39.2.2	struct sc_hypervisor_policy_config	456
28.39.2.3	struct sc_hypervisor_wrapper	457
28.39.2.4	struct sc_hypervisor_resize_ack	458
28.39.2.5	struct sc_hypervisor_policy_task_pool	458
28.39.3	Macro Definition Documentation	458
28.39.3.1	STARPU_HYPERVISOR_TAG	459
28.39.4	Function Documentation	459
28.39.4.1	sc_hypervisor_post_resize_request()	459

28.39.4.2 <code>sc_hypervisor_get_size_req()</code>	459
28.39.4.3 <code>sc_hypervisor_save_size_req()</code>	459
28.39.4.4 <code>sc_hypervisor_free_size_req()</code>	459
28.39.4.5 <code>sc_hypervisor_can_resize()</code>	460
28.39.4.6 <code>sc_hypervisor_get_config()</code>	460
28.39.4.7 <code>sc_hypervisor_set_config()</code>	460
28.39.4.8 <code>sc_hypervisor_get_sched_ctxs()</code>	460
28.39.4.9 <code>sc_hypervisor_get_nsched_ctxs()</code>	460
28.39.4.10 <code>sc_hypervisor_get_wrapper()</code>	460
28.39.4.11 <code>sc_hypervisor_get_elapsed_flops_per_sched_ctx()</code>	460
28.40 Modularized Scheduler Interface	461
28.40.1 Detailed Description	463
28.40.2 Data Structure Documentation	463
28.40.2.1 <code>struct starpu_sched_component</code>	463
28.40.2.2 <code>struct starpu_sched_tree</code>	467
28.40.2.3 <code>struct starpu_sched_component_fifo_data</code>	467
28.40.2.4 <code>struct starpu_sched_component_prio_data</code>	468
28.40.2.5 <code>struct starpu_sched_component_mct_data</code>	468
28.40.2.6 <code>struct starpu_sched_component_perfmodel_select_data</code>	468
28.40.2.7 <code>struct starpu_sched_component_composed_recipe</code>	468
28.40.2.8 <code>struct starpu_sched_component_specs</code>	468
28.40.3 Macro Definition Documentation	468
28.40.3.1 <code>STARPU_SCHED_COMPONENT_IS_HOMOGENEOUS</code>	469
28.40.3.2 <code>STARPU_SCHED_COMPONENT_IS_SINGLE_MEMORY_NODE</code>	469
28.40.4 Enumeration Type Documentation	469
28.40.4.1 <code>starpu_sched_component_properties</code>	469
28.40.5 Function Documentation	469
28.40.5.1 <code>starpu_sched_tree_create()</code>	469
28.40.5.2 <code>starpu_sched_tree_destroy()</code>	469
28.40.5.3 <code>starpu_sched_tree_update_workers()</code>	470

28.40.5.4	starpu_sched_tree_update_workers_in_ctx()	470
28.40.5.5	starpu_sched_tree_push_task()	470
28.40.5.6	starpu_sched_tree_pop_task()	470
28.40.5.7	starpu_sched_tree_add_workers()	470
28.40.5.8	starpu_sched_tree_remove_workers()	470
28.40.5.9	starpu_sched_component_connect()	471
28.40.5.10	starpu_sched_component_create()	471
28.40.5.11	starpu_sched_component_destroy()	471
28.40.5.12	starpu_sched_component_destroy_rec()	471
28.40.5.13	starpu_sched_component_can_execute_task()	471
28.40.5.14	starpu_sched_component_execute_preds()	472
28.40.5.15	starpu_sched_component_transfer_length()	472
28.40.5.16	starpu_sched_component_worker_get()	472
28.40.5.17	starpu_sched_component_worker_get_workerid()	472
28.40.5.18	starpu_sched_component_is_worker()	472
28.40.5.19	starpu_sched_component_is_simple_worker()	472
28.40.5.20	starpu_sched_component_is_combined_worker()	473
28.40.5.21	starpu_sched_component_worker_pre_exec_hook()	473
28.40.5.22	starpu_sched_component_worker_post_exec_hook()	473
28.40.5.23	starpu_sched_component_estimated_load()	473
28.40.5.24	starpu_sched_component_estimated_end_min()	473
28.40.5.25	starpu_sched_component_estimated_end_average()	473
28.40.5.26	starpu_sched_component_fifo_create()	474
28.40.5.27	starpu_sched_component_is_fifo()	474
28.40.5.28	starpu_sched_component_prio_create()	474
28.40.5.29	starpu_sched_component_is_prio()	474
28.40.5.30	starpu_sched_tree_work_stealing_push_task()	474
28.40.5.31	starpu_sched_component_is_work_stealing()	474
28.40.5.32	starpu_sched_component_is_random()	475
28.40.5.33	starpu_sched_component_is_eager()	475

28.40.5.34	starpu_sched_component_is_eager_calibration()	475
28.40.5.35	starpu_sched_component_mct_create()	475
28.40.5.36	starpu_sched_component_is_mct()	475
28.40.5.37	starpu_sched_component_heft_create()	475
28.40.5.38	starpu_sched_component_is_heft()	476
28.40.5.39	starpu_sched_component_perfmodel_select_create()	476
28.40.5.40	starpu_sched_component_is_perfmodel_select()	476
28.40.5.41	starpu_sched_component_composed_recipe_create()	476
28.40.5.42	starpu_sched_component_composed_recipe_create_singleton()	476
28.40.5.43	starpu_sched_component_composed_recipe_add()	476
28.40.5.44	starpu_sched_component_composed_recipe_destroy()	477
28.40.5.45	starpu_sched_component_composed_component_create()	477
28.40.5.46	starpu_sched_component_make_scheduler()	477
28.40.5.47	starpu_sched_component_push_task()	477
28.40.5.48	starpu_sched_component_pull_task()	477
29	File Index	479
29.1	File List	479
30	File Documentation	481
30.1	starpu.h File Reference	481
30.2	starpu_bitmap.h File Reference	482
30.3	starpu_bound.h File Reference	482
30.4	starpu_config.h File Reference	483
30.5	starpu_cublas.h File Reference	485
30.6	starpu_cuda.h File Reference	485
30.7	starpu_data.h File Reference	485
30.8	starpu_data_filters.h File Reference	487
30.9	starpu_data_interfaces.h File Reference	489
30.10	starpu_deprecated_api.h File Reference	494
30.11	starpu_disk.h File Reference	494

30.12starpu_driver.h File Reference	494
30.13starpu_expert.h File Reference	495
30.14starpu_fxt.h File Reference	495
30.15starpu_hash.h File Reference	496
30.16starpu_mic.h File Reference	496
30.17starpu_opencl.h File Reference	496
30.18starpu_openmp.h File Reference	498
30.19starpu_perfmodel.h File Reference	500
30.20starpu_profiling.h File Reference	502
30.21starpu_rand.h File Reference	503
30.22starpu_scc.h File Reference	503
30.23starpu_sched_ctx.h File Reference	503
30.24starpu_sched_ctx_hypervisor.h File Reference	505
30.25starpu_scheduler.h File Reference	505
30.26starpu_sink.h File Reference	506
30.27starpu_stdlib.h File Reference	507
30.28starpu_task.h File Reference	507
30.28.1 Macro Definition Documentation	509
30.28.1.1 STARPU_CODELET_SIMGRID_EXECUTE	509
30.28.1.2 STARPU_CUDA_ASYNC	510
30.28.1.3 STARPU_OPENCL_ASYNC	510
30.29starpu_task_bundle.h File Reference	510
30.30starpu_task_list.h File Reference	510
30.31starpu_task_util.h File Reference	511
30.31.1 Data Structure Documentation	512
30.31.1.1 struct starpu_codelet_pack_arg_data	512
30.32starpu_thread.h File Reference	512
30.32.1 Data Structure Documentation	514
30.32.1.1 struct starpu_pthread_barrier_t	514
30.32.1.2 struct starpu_pthread_spinlock_t	514

30.33starpu_thread_util.h File Reference	514
30.34starpu_top.h File Reference	515
30.35starpu_tree.h File Reference	516
30.36starpu_util.h File Reference	517
30.37starpu_worker.h File Reference	518
30.38starpu_mpi.h File Reference	519
30.39starpufft.h File Reference	522
30.40sc_hypervisor.h File Reference	523
30.41sc_hypervisor_config.h File Reference	524
30.42sc_hypervisor_ip.h File Reference	525
30.43sc_hypervisor_monitoring.h File Reference	525
30.44sc_hypervisor_policy.h File Reference	526
30.44.1 Data Structure Documentation	527
30.44.1.1 struct types_of_workers	527
31 Deprecated List	529
VI Appendix	531
32 Full Source Code for the 'Scaling a Vector' Example	533
32.1 Main Application	533
32.2 CPU Kernel	534
32.3 CUDA Kernel	535
32.4 OpenCL Kernel	535
32.4.1 Invoking the Kernel	535
32.4.2 Source of the Kernel	536
33 GNU Free Documentation License	537
33.1 ADDENDUM: How to use this License for your documents	541
VII Index	543
Index	545

Chapter 1

Introduction

1.1 Motivation

The use of specialized hardware such as accelerators or coprocessors offers an interesting approach to overcome the physical limits encountered by processor architects. As a result, many machines are now equipped with one or several accelerators (e.g. a GPU), in addition to the usual processor(s). While a lot of efforts have been devoted to offload computation onto such accelerators, very little attention has been paid to portability concerns on the one hand, and to the possibility of having heterogeneous accelerators and processors to interact on the other hand.

StarPU is a runtime system that offers support for heterogeneous multicore architectures, it not only offers a unified view of the computational resources (i.e. CPUs and accelerators at the same time), but it also takes care of efficiently mapping and executing tasks onto an heterogeneous machine while transparently handling low-level issues such as data transfers in a portable fashion.

1.2 StarPU in a Nutshell

StarPU is a software tool aiming to allow programmers to exploit the computing power of the available CPUs and GPUs, while relieving them from the need to specially adapt their programs to the target machine and processing units.

At the core of StarPU is its runtime support library, which is responsible for scheduling application-provided tasks on heterogeneous CPU/GPU machines. In addition, StarPU comes with programming language support, in the form of extensions to languages of the C family ([C Extensions](#)), as well as an OpenCL front-end ([SOCL OpenCL Extensions](#)).

StarPU's runtime and programming language extensions support a task-based programming model. Applications submit computational tasks, with CPU and/or GPU implementations, and StarPU schedules these tasks and associated data transfers on available CPUs and GPUs. The data that a task manipulates are automatically transferred among accelerators and the main memory, so that programmers are freed from the scheduling issues and technical details associated with these transfers.

StarPU takes particular care of scheduling tasks efficiently, using well-known algorithms from the literature ([Task Scheduling Policies](#)). In addition, it allows scheduling experts, such as compiler or computational library developers, to implement custom scheduling policies in a portable fashion ([Defining A New Scheduling Policy](#)).

The remainder of this section describes the main concepts used in StarPU.

1.2.1 Codelet and Tasks

One of the StarPU primary data structures is the **codelet**. A codelet describes a computational kernel that can possibly be implemented on multiple architectures such as a CPU, a CUDA device or an OpenCL device.

Another important data structure is the **task**. Executing a StarPU task consists in applying a codelet on a data set, on one of the architectures on which the codelet is implemented. A task thus describes the codelet that it uses, but also which data are accessed, and how they are accessed during the computation (read and/or write). StarPU tasks are asynchronous: submitting a task to StarPU is a non-blocking operation. The task structure can also specify a **callback** function that is called once StarPU has properly executed the task. It also contains optional fields that the application may use to give hints to the scheduler (such as priority levels).

By default, task dependencies are inferred from data dependency (sequential coherency) by StarPU. The application can however disable sequential coherency for some data, and dependencies can be specifically expressed. A task may be identified by a unique 64-bit number chosen by the application which we refer as a **tag**. Task dependencies can be enforced either by the means of callback functions, by submitting other tasks, or by expressing dependencies between tags (which can thus correspond to tasks that have not yet been submitted).

1.2.2 StarPU Data Management Library

Because StarPU schedules tasks at runtime, data transfers have to be done automatically and “just-in-time” between processing units, relieving application programmers from explicit data transfers. Moreover, to avoid unnecessary transfers, StarPU keeps data where it was last needed, even if was modified there, and it allows multiple copies of the same data to reside at the same time on several processing units as long as it is not modified.

1.3 Application Taskification

TODO

1.4 Glossary

A **codelet** records pointers to various implementations of the same theoretical function.

A **memory node** can be either the main RAM, GPU-embedded memory or a disk memory.

A **bus** is a link between memory nodes.

A **data handle** keeps track of replicates of the same data (**registered** by the application) over various memory nodes. The data management library manages to keep them coherent.

The **home** memory node of a data handle is the memory node from which the data was registered (usually the main memory node).

A **task** represents a scheduled execution of a codelet on some data handles.

A **tag** is a rendez-vous point. Tasks typically have their own tag, and can depend on other tags. The value is chosen by the application.

A **worker** execute tasks. There is typically one per CPU computation core and one per accelerator (for which a whole CPU core is dedicated).

A **driver** drives a given kind of workers. There are currently CPU, CUDA, and OpenCL drivers. They usually start several workers to actually drive them.

A **performance model** is a (dynamic or static) model of the performance of a given codelet. Codelets can have execution time performance model as well as energy consumption performance models.

A data **interface** describes the layout of the data: for a vector, a pointer for the start, the number of elements and the size of elements ; for a matrix, a pointer for the start, the number of elements per row, the offset between rows, and the size of each element ; etc. To access their data, codelet functions are given interfaces for the local memory node replicates of the data handles of the scheduled task.

Partitioning data means dividing the data of a given data handle (called **father**) into a series of **children** data handles which designate various portions of the former.

A **filter** is the function which computes children data handles from a father data handle, and thus describes how the partitioning should be done (horizontal, vertical, etc.)

Acquiring a data handle can be done from the main application, to safely access the data of a data handle from its home node, without having to unregister it.

1.5 Research Papers

Research papers about StarPU can be found at <http://starpu.gforge.inria.fr/publications/>.

A good overview is available in the research report at <http://hal.archives-ouvertes.fr/inria-00467677>.

1.6 StarPU Applications

You can first have a look at the chapters [Basic Examples](#) and [Advanced Examples](#). A tutorial is also installed in the directory `share/doc/starpu/tutorial/`.

Many examples are also available in the StarPU sources in the directory `examples/`. Simple examples include:

incrementer/ Trivial incrementation test.

basic_examples/ Simple documented Hello world and vector/scalar product (as shown in [Basic Examples](#)), matrix product examples (as shown in [Performance Model Example](#)), an example using the blocked matrix data interface, an example using the variable data interface, and an example using different formats on CPUs and GPUs.

matvecmult/ OpenCL example from NVidia, adapted to StarPU.

axpy/ AXPY CUBLAS operation adapted to StarPU.

native_fortran/ Example of using StarPU's native Fortran support.

fortran90/ Example of Fortran 90 bindings, using C marshalling wrappers.

fortran/ Example of Fortran 77 bindings, using C marshalling wrappers.

More advanced examples include:

filters/ Examples using filters, as shown in [Partitioning Data](#).

lu/ LU matrix factorization, see for instance `xlu_implicit.c`

cholesky/ Cholesky matrix factorization, see for instance `cholesky_implicit.c`.

1.7 Further Reading

The documentation chapters include

- Part 1: StarPU Basics
 - [Building and Installing StarPU](#)
 - [Basic Examples](#)
- Part 2: StarPU Quick Programming Guide
 - [Advanced Examples](#)
 - [Check List When Performance Are Not There](#)
- Part 3: StarPU Inside
 - [Tasks In StarPU](#)
 - [Data Management](#)
 - [Scheduling](#)
 - [Scheduling Contexts](#)
 - [Scheduling Context Hypervisor](#)
 - [Modularized Schedulers](#)
 - [Debugging Tools](#)
 - [Online Performance Tools](#)
 - [Offline Performance Tools](#)
 - [Frequently Asked Questions](#)
- Part 4: StarPU Extensions
 - [Out Of Core](#)
 - [MPI Support](#)
 - [FFT Support](#)
 - [MIC Xeon Phi / SCC Support](#)
 - [C Extensions](#)
 - [The StarPU Native Fortran Support](#)
 - [SOCL OpenCL Extensions](#)
 - [SimGrid Support](#)
 - [The StarPU OpenMP Runtime Support \(SORS\)](#)
- Part 5: StarPU Reference API
 - [Execution Configuration Through Environment Variables](#)
 - [Compilation Configuration](#)
 - [ModuleDocumentation](#)
 - [FileDocumentation](#)
 - [Deprecated List](#)
- Part: Appendix
 - [Full source code for the 'Scaling a Vector' example](#)
 - [The GNU Free Documentation License](#)

Make sure to have had a look at those too!

Part I

StarPU Basics

Chapter 2

Building and Installing StarPU

2.1 Installing a Binary Package

One of the StarPU developers being a Debian Developer, the packages are well integrated and very uptodate. To see which packages are available, simply type:

```
$ apt-cache search starpu
```

To install what you need, type for example:

```
$ sudo apt-get install libstarpu-1.2 libstarpu-dev
```

2.2 Installing from Source

StarPU can be built and installed by the standard means of the GNU autotools. The following chapter is intended to briefly remind how these tools can be used to install StarPU.

2.2.1 Optional Dependencies

The `hwloc` (<http://www.open-mpi.org/software/hwloc>) topology discovery library is not mandatory to use StarPU but strongly recommended. It allows for topology aware scheduling, which improves performance. `libhwloc` is available in major free operating system distributions, and for most operating systems.

If `libhwloc` is installed in a standard location, no option is required, it will be detected automatically, otherwise `--with-hwloc=<directory>` should be used to specify its location.

If `libhwloc` is not available on your system, the option `--without-hwloc` should be explicitly given when calling the `configure` script.

2.2.2 Getting Sources

StarPU's sources can be obtained from the download page of the StarPU website (<http://starpu.gforge.inria.fr/files/>).

All releases and the development tree of StarPU are freely available on Inria's gforge under the LGPL license. Some releases are available under the BSD license.

The latest release can be downloaded from the Inria's gforge (http://gforge.inria.fr/frs/?group_id=1570) or directly from the StarPU download page (<http://starpu.gforge.inria.fr/files/>).

The latest nightly snapshot can be downloaded from the StarPU gforge website (<http://starpu.gforge.inria.fr/testing/>).

```
$ wget http://starpu.gforge.inria.fr/testing/starpu-nightly-latest.tar.gz
```

And finally, current development version is also accessible via git. It should only be used if you need the very latest changes (i.e. less than a day old!).

```
$ git clone https://scm.gforge.inria.fr/anonscm/git/starpu/starpu.git
```

2.2.3 Configuring StarPU

Running `autogen.sh` is not necessary when using the tarball releases of StarPU. However when using the source code from the git repository, you first need to generate the configure scripts and the Makefiles. This requires the availability of `autoconf` and `automake` ≥ 2.60 .

```
$ ./autogen.sh
```

You then need to configure StarPU. Details about options that are useful to give to `./configure` are given in [Compilation Configuration](#).

```
$ ./configure
```

If `configure` does not detect some software or produces errors, please make sure to post the contents of the file `config.log` when reporting the issue.

By default, the files produced during the compilation are placed in the source directory. As the compilation generates a lot of files, it is advised to put them all in a separate directory. It is then easier to cleanup, and this allows to compile several configurations out of the same source tree. To do so, simply enter the directory where you want the compilation to produce its files, and invoke the `configure` script located in the StarPU source directory.

```
$ mkdir build
$ cd build
$ ../configure
```

By default, StarPU will be installed in `/usr/local/bin`, `/usr/local/lib`, etc. You can specify an installation prefix other than `/usr/local` using the option `-prefix`, for instance:

```
$ ../configure --prefix=$HOME/starpu
```


2.2.4 Building StarPU

```
$ make
```

Once everything is built, you may want to test the result. An extensive set of regression tests is provided with StarPU. Running the tests is done by calling `make check`. These tests are run every night and the result from the main profile is publicly available (<http://starpu.gforge.inria.fr/testing/>).

```
$ make check
```

2.2.5 Installing StarPU

In order to install StarPU at the location which was specified during configuration:

```
$ make install
```

Libtool interface versioning information are included in libraries names (`libstarpu-1.2.so`, `libstarpumpi-1.2.so` and `libstarpufft-1.2.so`).

2.3 Setting up Your Own Code

2.3.1 Setting Flags for Compiling, Linking and Running Applications

StarPU provides a `pkg-config` executable to obtain relevant compiler and linker flags. As compiling and linking an application against StarPU may require to use specific flags or libraries (for instance CUDA or `libspe2`).

If StarPU was not installed at some standard location, the path of StarPU's library must be specified in the environment variable `PKG_CONFIG_PATH` to allow `pkg-config` to find it. For example if StarPU was installed in `$STARPU_PATH`:

```
$ PKG_CONFIG_PATH=$PKG_CONFIG_PATH:$STARPU_PATH/lib/pkgconfig
```

The flags required to compile or link against StarPU are then accessible with the following commands:

```
$ pkg-config --cflags starpu-1.2 # options for the compiler
$ pkg-config --libs starpu-1.2   # options for the linker
```

Note that it is still possible to use the API provided in the version 1.0 of StarPU by calling `pkg-config` with the `starpu-1.0` package. Similar packages are provided for `starpumpi-1.0` and `starpufft-1.0`. It is also possible to use the API provided in the version 0.9 of StarPU by calling `pkg-config` with the `libstarpu` package. Similar packages are provided for `libstarpumpi` and `libstarpufft`.

Make sure that `pkg-config --libs starpu-1.2` actually produces some output before going further: `PKG_CONFIG_PATH` has to point to the place where `starpu-1.2.pc` was installed during `make install`.

Also pass the option `-static` if the application is to be linked statically.

It is also necessary to set the environment variable `LD_LIBRARY_PATH` to locate dynamic libraries at runtime.

```
$ LD_LIBRARY_PATH=$STARPU_PATH/lib:$LD_LIBRARY_PATH
```

When using a Makefile, the following lines can be added to set the options for the compiler and the linker:

```
CFLAGS      += $(shell pkg-config --cflags starpu-1.2)
LDFLAGS     += $(shell pkg-config --libs starpu-1.2)
```

2.3.2 Running a Basic StarPU Application

Basic examples using StarPU are built in the directory `examples/basic_examples/` (and installed in `$STARPU_PATH/lib/starpu/examples/`). You can for example run the example `vector_scal`.

```
$ ./examples/basic_examples/vector_scal
BEFORE: First element was 1.000000
AFTER: First element is 3.140000
```

When StarPU is used for the first time, the directory `$STARPU_HOME/.starpu/` is created, performance models will be stored in this directory ([STARPU_HOME](#)).

Please note that buses are benchmarked when StarPU is launched for the first time. This may take a few minutes, or less if `libhwloc` is installed. This step is done only once per user and per machine.

2.3.3 Running a Basic StarPU Application on Microsoft Visual C

Batch files are provided to run StarPU applications under Microsoft Visual C. They are installed in `$STARPU_PATH/bin/msvc`.

To execute a StarPU application, you first need to set the environment variable [STARPU_PATH](#).

```
c:\....> cd c:\cygwin\home\ci\starpu\
c:\....> set STARPU_PATH=c:\cygwin\home\ci\starpu\
c:\....> cd bin\msvc
c:\....> starpu_open.bat starpu_simple.c
```

The batch script will run Microsoft Visual C with a basic project file to run the given application.

The batch script `starpu_clean.bat` can be used to delete all compilation generated files.

The batch script `starpu_exec.bat` can be used to compile and execute a StarPU application from the command prompt.

```
c:\....> cd c:\cygwin\home\ci\starpu\
c:\....> set STARPU_PATH=c:\cygwin\home\ci\starpu\
c:\....> cd bin\msvc
c:\....> starpu_exec.bat ..\..\..\examples\basic_examples\hello_world.c
```

```
MSVC StarPU Execution
...
/out:hello_world.exe
...
Hello world (params = {1, 2.00000})
Callback function got argument 0000042
c:\....>
```

2.3.4 Kernel Threads Started by StarPU

StarPU automatically binds one thread per CPU core. It does not use SMT/hyperthreading because kernels are usually already optimized for using a full core, and using hyperthreading would make kernel calibration rather random.

Since driving GPUs is a CPU-consuming task, StarPU dedicates one core per GPU.

While StarPU tasks are executing, the application is not supposed to do computations in the threads it starts itself, tasks should be used instead.

TODO: add a StarPU function to bind an application thread (e.g. the main thread) to a dedicated core (and thus disable the corresponding StarPU CPU worker).

2.3.5 Enabling OpenCL

When both CUDA and OpenCL drivers are enabled, StarPU will launch an OpenCL worker for NVIDIA GPUs only if CUDA is not already running on them. This design choice was necessary as OpenCL and CUDA can not run at the same time on the same NVIDIA GPU, as there is currently no interoperability between them.

To enable OpenCL, you need either to disable CUDA when configuring StarPU:

```
$ ./configure --disable-cuda
```

or when running applications:

```
$ STARPU_NCUDA=0 ./application
```

OpenCL will automatically be started on any device not yet used by CUDA. So on a machine running 4 GPUS, it is therefore possible to enable CUDA on 2 devices, and OpenCL on the 2 other devices by doing so:


```
$ STARPU_NCUDA=2 ./application
```

2.4 Benchmarking StarPU

Some interesting benchmarks are installed among examples in `$STARPU_PATH/lib/starpu/examples/`. Make sure to try various schedulers, for instance `STARPU_SCHED=dmda`.

2.4.1 Task Size Overhead

This benchmark gives a glimpse into how long a task should be (in μ s) for StarPU overhead to be low enough to keep efficiency. Running `tasks_size_overhead.sh` generates a plot of the speedup of tasks of various sizes, depending on the number of CPUs being used.



2.4.2 Data Transfer Latency

`local_pingpong` performs a ping-pong between the first two CUDA nodes, and prints the measured latency.

2.4.3 Matrix-Matrix Multiplication

`sgemm` and `dgemm` perform a blocked matrix-matrix multiplication using BLAS and cuBLAS. They output the obtained GFlops.

2.4.4 Cholesky Factorization

`cholesky_*` perform a Cholesky factorization (single precision). They use different dependency primitives.

2.4.5 LU Factorization

`lu_*` perform an LU factorization. They use different dependency primitives.

2.4.6 Simulated benchmarks

It can also be convenient to try simulated benchmarks, if you want to give a try at CPU-GPU scheduling without actually having a GPU at hand. This can be done by using the `simgrid` version of StarPU: first install the `simgrid` simulator from <http://simgrid.gforge.inria.fr/> (we tested with `simgrid` 3.11, 3.12 and 3.13, other versions may have compatibility issues), then configure StarPU with `--enable-simgrid` and rebuild and install it, and then you can simulate the performance for a few virtualized systems shipped along StarPU: `attila`, `mirage`, `idgraf`, and `sirocco`.

For instance:

```
$ export STARPU_PERF_MODEL_DIR=$STARPU_PATH/share/starpu/perfmodels/sampling
$ export STARPU_HOSTNAME=attila
$ $STARPU_PATH/lib/starpu/examples/cholesky_implicit -size $((960*20)) -nblocks 20
```

Will show the performance of the cholesky factorization with the `attila` system. It will be interesting to try with different matrix sizes and schedulers.

Performance models are available for `cholesky_*`, `lu_*`, `*gemm`, with block sizes 320, 640, or 960 (plus 1440 for `sirocco`), and for stencil with block size 128x128x128, 192x192x192, and 256x256x256.

Chapter 3

Basic Examples

3.1 Hello World Using The C Extension

This section shows how to implement a simple program that submits a task to StarPU using the StarPU C extension ([C Extensions](#)). The complete example, and additional examples, is available in the directory `gcc-plugin/examples` of the StarPU distribution. A similar example showing how to directly use the StarPU's API is shown in [Hello World Using StarPU's API](#).

GCC from version 4.5 permit to use the StarPU GCC plug-in ([C Extensions](#)). This makes writing a task both simpler and less error-prone. In a nutshell, all it takes is to declare a task, declare and define its implementations (for CPU, OpenCL, and/or CUDA), and invoke the task like a regular C function. The example below defines `my_task` which has a single implementation for CPU:

```
#include <stdio.h>

/* Task declaration. */
static void my_task (int x) __attribute__ ((task));

/* Definition of the CPU implementation of 'my_task'. */
static void my_task (int x)
{
    printf ("Hello, world! With x = %d\n", x);
}

int main ()
{
    /* Initialize StarPU. */
    #pragma starpu initialize

    /* Do an asynchronous call to 'my_task'. */
    my_task (42);

    /* Wait for the call to complete. */
    #pragma starpu wait

    /* Terminate. */
    #pragma starpu shutdown

    return 0;
}
```

The code can then be compiled and linked with GCC and the flag `-fplugin`:

```
$ gcc `pkg-config starpu-1.2 --cflags` hello-starpu.c \
    -fplugin=`pkg-config starpu-1.2 --variable=gccplugin` \
    `pkg-config starpu-1.2 --libs`
```

The code can also be compiled without the StarPU C extension and will behave as a normal sequential code.

```
$ gcc hello-starpup.c
hello-starpup.c:33:1: warning: 'task' attribute directive ignored [-Wattributes]
$ ./a.out
Hello, world! With x = 42
```

As can be seen above, the C extensions allows programmers to use StarPU tasks by essentially annotating “regular” C code.

3.2 Hello World Using StarPU's API

This section shows how to achieve the same result as in the previous section using StarPU's standard C API.

3.2.1 Required Headers

The header [starpup.h](#) should be included in any code using StarPU.

```
#include <starpup.h>
```

3.2.2 Defining A Codelet

A codelet is a structure that represents a computational kernel. Such a codelet may contain an implementation of the same kernel on different architectures (e.g. CUDA, x86, ...). For compatibility, make sure that the whole structure is properly initialized to zero, either by using the function [starpup_codelet_init\(\)](#), or by letting the compiler implicitly do it as exemplified below.

The field [starpup_codelet::nbuffers](#) specifies the number of data buffers that are manipulated by the codelet: here the codelet does not access or modify any data that is controlled by our data management library.

We create a codelet which may only be executed on CPUs. When a CPU core will execute a codelet, it will call the function `cpu_func`, which *must* have the following prototype:

```
void (*cpu_func)(void *buffers[], void *cl_arg);
```

In this example, we can ignore the first argument of this function which gives a description of the input and output buffers (e.g. the size and the location of the matrices) since there is none. We also ignore the second argument which is a pointer to optional arguments for the codelet.

```
void cpu_func(void *buffers[], void *cl_arg)
{
    printf("Hello world\n");
}

struct starpup_codelet cl =
{
    .cpu_funcs = { cpu_func },
    .nbuffers = 0
};
```

3.2.3 Submitting A Task

Before submitting any tasks to StarPU, `starpu_init()` must be called. The `NULL` argument specifies that we use the default configuration. Tasks can then be submitted until the termination of StarPU – done by a call to `starpu_shutdown()`.

In the example below, a task structure is allocated by a call to `starpu_task_create()`. This function allocates and fills the task structure with its default settings, it does not submit the task to StarPU.

The field `starpu_task::cl` is a pointer to the codelet which the task will execute: in other words, the codelet structure describes which computational kernel should be offloaded on the different architectures, and the task structure is a wrapper containing a codelet and the piece of data on which the codelet should operate.

If the field `starpu_task::synchronous` is non-zero, task submission will be synchronous: the function `starpu_task_submit()` will not return until the task has been executed. Note that the function `starpu_shutdown()` does not guarantee that asynchronous tasks have been executed before it returns, `starpu_task_wait_for_all()` can be used to this effect, or data can be unregistered (`starpu_data_unregister()`), which will implicitly wait for all the tasks scheduled to work on it, unless explicitly disabled thanks to `starpu_data_set_default_sequential_consistency_flag()` or `starpu_data_set_sequential_consistency_flag()`.

```
int main(int argc, char **argv)
{
    /* initialize StarPU */
    starpu_init(NULL);

    struct starpu_task *task = starpu_task_create();

    task->cl = &cl; /* Pointer to the codelet defined above */

    /* starpu_task_submit will be a blocking call. If unset,
    starpu_task_wait() needs to be called after submitting the task. */
    task->synchronous = 1;

    /* submit the task to StarPU */
    starpu_task_submit(task);

    /* terminate StarPU */
    starpu_shutdown();

    return 0;
}
```

3.2.4 Execution Of Hello World

```
$ make hello_world
cc $(pkg-config --cflags starpu-1.2) hello_world.c -o hello_world $(pkg-config --libs starpu-1.2)
$ ./hello_world
Hello world
```

3.2.5 Passing Arguments To The Codelet

The optional field `starpu_task::cl_arg` field is a pointer to a buffer (of size `starpu_task::cl_arg_size`) with some parameters for the kernel described by the codelet. For instance, if a codelet implements a computational kernel that multiplies its input vector by a constant, the constant could be specified by the means of this buffer, instead of registering it as a StarPU data. It must however be noted that StarPU avoids making copy whenever possible and rather passes the pointer as such, so the buffer which is pointed at must be kept allocated until the task terminates, and if several tasks are submitted with various parameters, each of them must be given a pointer to their own buffer.

```

struct params
{
    int i;
    float f;
};

void cpu_func(void *buffers[], void *cl_arg)
{
    struct params *params = cl_arg;

    printf("Hello world (params = {%i, %f} )\n", params->i, params->f);
}

```

As said before, the field `starpu_codelet::nbuffers` specifies the number of data buffers which are manipulated by the codelet. It does not count the argument — the parameter `cl_arg` of the function `cpu_func` — since it is not managed by our data management library, but just contains trivial parameters.

Be aware that this may be a pointer to a *copy* of the actual buffer, and not the pointer given by the programmer: if the codelet modifies this buffer, there is no guarantee that the initial buffer will be modified as well: this for instance implies that the buffer cannot be used as a synchronization medium. If synchronization is needed, data has to be registered to StarPU, see [Vector Scaling Using StarPU's API](#).

```

int main(int argc, char **argv)
{
    /* initialize StarPU */
    starpu_init(NULL);

    struct starpu_task *task = starpu_task_create();

    task->cl = &cl; /* Pointer to the codelet defined above */

    struct params params = { 1, 2.0f };
    task->cl_arg = &params;
    task->cl_arg_size = sizeof(params);

    /* starpu_task_submit will be a blocking call */
    task->synchronous = 1;

    /* submit the task to StarPU */
    starpu_task_submit(task);

    /* terminate StarPU */
    starpu_shutdown();

    return 0;
}

$ make hello_world
cc $(pkg-config --cflags starpu-1.2) hello_world.c -o hello_world $(pkg-config --libs starpu-1.2)
$ ./hello_world
Hello world (params = {1, 2.000000} )

```

3.2.6 Defining A Callback

Once a task has been executed, an optional callback function `starpu_task::callback_func` is called when defined. While the computational kernel could be offloaded on various architectures, the callback function is always executed on a CPU. The pointer `starpu_task::callback_arg` is passed as an argument of the callback function. The prototype of a callback function must be:

```

void (*callback_function)(void *);

void callback_func(void *callback_arg)
{
    printf("Callback function (arg %x)\n", callback_arg);
}

int main(int argc, char **argv)
{

```



```

/* initialize StarPU */
starpu_init(NULL);

struct starpu_task *task = starpu_task_create();

task->cl = &cl; /* Pointer to the codelet defined above */

task->callback_func = callback_func;
task->callback_arg = 0x42;

/* starpu_task_submit will be a blocking call */
task->synchronous = 1;

/* submit the task to StarPU */
starpu_task_submit(task);

/* terminate StarPU */
starpu_shutdown();

return 0;
}

$ make hello_world
cc $(pkg-config --cflags starpu-1.2) hello_world.c -o hello_world $(pkg-config --libs starpu-1.2)
$ ./hello_world
Hello world
Callback function (arg 42)

```

3.2.7 Where To Execute A Codelet

```

struct starpu_codelet cl =
{
    .where = STARPU_CPU,
    .cpu_funcs = { cpu_func },
    .cpu_funcs_name = { "cpu_func" },
    .nbuffers = 0
};

```

We create a codelet which may only be executed on the CPUs. The optional field `starpu_codelet::where` is a bitmask which defines where the codelet may be executed. Here, the value `STARPU_CPU` means that only CPUs can execute this codelet. When the optional field `starpu_codelet::where` is unset, its value is automatically set based on the availability of the different fields `XXX_funcs`.

TODO: explain `starpu_codelet::cpu_funcs_name`

3.3 Vector Scaling Using the C Extension

The previous example has shown how to submit tasks. In this section, we show how StarPU tasks can manipulate data.

We will first show how to use the C language extensions provided by the GCC plug-in ([C Extensions](#)). The complete example, and additional examples, is available in the directory `gcc-plugin/examples` of the StarPU distribution. These extensions map directly to StarPU's main concepts: tasks, task implementations for CPU, OpenCL, or CUDA, and registered data buffers. The standard C version that uses StarPU's standard C programming interface is given in [Vector Scaling Using StarPU's API](#).

First of all, the vector-scaling task and its simple CPU implementation has to be defined:

```

/* Declare the 'vector_scal' task. */
static void vector_scal (unsigned size, float vector[size],
                        float factor)
    __attribute__ ((task));

/* Define the standard CPU implementation. */
static void
vector_scal (unsigned size, float vector[size], float factor)
{
    unsigned i;
    for (i = 0; i < size; i++)
        vector[i] *= factor;
}

```

Next, the body of the program, which uses the task defined above, can be implemented:

```

int main (void)
{
    #pragma starpu initialize

    #define NX      0x100000
    #define FACTOR 3.14

    {
        float vector[NX]
            __attribute__ ((heap_allocated, registered));

        size_t i;
        for (i = 0; i < NX; i++)
            vector[i] = (float) i;

        vector_scal (NX, vector, FACTOR);
    }

    #pragma starpu wait
    /* VECTOR is automatically freed here. */

    #pragma starpu shutdown

    return valid ? EXIT_SUCCESS : EXIT_FAILURE;
}

```

The function `main` above does several things:

- It initializes StarPU.
- It allocates `vector` in the heap; it will automatically be freed when its scope is left. Alternatively, good old `malloc` and `free` could have been used, but they are more error-prone and require more typing.
- It registers the memory pointed to by `vector`. Eventually, when OpenCL or CUDA task implementations are added, this will allow StarPU to transfer the memory region between GPUs and the main memory. Removing this `pragma` is an error.
- It invokes the task `vector_scal`. The invocation looks the same as a standard C function call. However, it is an asynchronous invocation, meaning that the actual call is performed in parallel with the caller's continuation.
- It waits for the termination of the asynchronous call `vector_scal`.
- Finally, StarPU is shut down.

The program can be compiled and linked with GCC and the flag `-fplugin`:

```

$ gcc `pkg-config starpu-1.2 --cflags` vector_scal.c \
    -fplugin=`pkg-config starpu-1.2 --variable=gccplugin` \
    `pkg-config starpu-1.2 --libs`

```

And voilà!

3.3.1 Adding an OpenCL Task Implementation

Now, this is all fine and great, but you certainly want to take advantage of these newfangled GPUs that your lab just bought, don't you?

So, let's add an OpenCL implementation of the task `vector_scal`. We assume that the OpenCL kernel is available in a file, `vector_scal_opengl_kernel.cl`, not shown here. The OpenCL task implementation is similar to the one used with the standard C API ([Definition of the OpenCL Kernel](#)). It is declared and defined in our C file like this:

```
/* The OpenCL programs, loaded from 'main' (see below). */
static struct starpu_opengl_program cl_programs;

static void vector_scal_opengl (unsigned size, float vector[size],
                               float factor)
    __attribute__((task_implementation ("opengl", vector_scal)));

static void
vector_scal_opengl (unsigned size, float vector[size], float factor)
{
    int id, devid, err;
    cl_kernel kernel;
    cl_command_queue queue;
    cl_event event;

    /* VECTOR is GPU memory pointer, not a main memory pointer. */
    cl_mem val = (cl_mem) vector;

    id = starpu_worker_get_id ();
    devid = starpu_worker_get_devid (id);

    /* Prepare to invoke the kernel. In the future, this will be largely automated. */
    err = starpu_opengl_load_kernel (&kernel, &queue, &cl_programs,
                                     "vector_mult_opengl", devid);
    if (err != CL_SUCCESS)
        STARPU_OPENGL_REPORT_ERROR (err);

    err = clSetKernelArg (kernel, 0, sizeof (size), &size);
    err |= clSetKernelArg (kernel, 1, sizeof (val), &val);
    err |= clSetKernelArg (kernel, 2, sizeof (factor), &factor);
    if (err)
        STARPU_OPENGL_REPORT_ERROR (err);

    size_t global = 1, local = 1;
    err = clEnqueueNDRangeKernel (queue, kernel, 1, NULL, &global,
                                   &local, 0, NULL, &event);
    if (err != CL_SUCCESS)
        STARPU_OPENGL_REPORT_ERROR (err);

    clFinish (queue);
    starpu_opengl_collect_stats (event);
    clReleaseEvent (event);

    /* Done with KERNEL. */
    starpu_opengl_release_kernel (kernel);
}
```

The OpenCL kernel itself must be loaded from `main`, sometime after the `pragma initialize`:

```
starpu_opengl_load_opengl_from_file ("vector_scal_opengl_kernel.cl",
                                     &cl_programs, "");
```

And that's it. The task `vector_scal` now has an additional implementation, for OpenCL, which StarPU's scheduler may choose to use at runtime. Unfortunately, the `vector_scal_opengl` above still has to go through the common OpenCL boilerplate; in the future, additional extensions will automate most of it.

3.3.2 Adding a CUDA Task Implementation

Adding a CUDA implementation of the task is very similar, except that the implementation itself is typically written in CUDA, and compiled with `nvcc`. Thus, the C file only needs to contain an external declaration for the task implementation:

```
extern void vector_scal_cuda (unsigned size, float vector[size],
                             float factor)
__attribute__((task_implementation ("cuda", vector_scal)));
```

The actual implementation of the CUDA task goes into a separate compilation unit, in a `.cu` file. It is very close to the implementation when using StarPU's standard C API ([Definition of the CUDA Kernel](#)).

```
/* CUDA implementation of the 'vector_scal' task, to be compiled with 'nvcc'. */

#include <starpu.h>
#include <stdlib.h>

static __global__ void
vector_mult_cuda (unsigned n, float *val, float factor)
{
    unsigned i = blockIdx.x * blockDim.x + threadIdx.x;

    if (i < n)
        val[i] *= factor;
}

/* Definition of the task implementation declared in the C file. */
extern "C" void
vector_scal_cuda (size_t size, float vector[], float factor)
{
    unsigned threads_per_block = 64;
    unsigned nblocks = (size + threads_per_block - 1) / threads_per_block;

    vector_mult_cuda <<< nblocks, threads_per_block, 0,
        starpu_cuda_get_local_stream () >>> (size, vector, factor);

    cudaStreamSynchronize (starpu_cuda_get_local_stream ());
}
```

The complete source code, in the directory `gcc-plugin/examples/vector_scal` of the StarPU distribution, also shows how an SSE-specialized CPU task implementation can be added.

For more details on the C extensions provided by StarPU's GCC plug-in, see [C Extensions](#).

3.4 Vector Scaling Using StarPU's API

This section shows how to achieve the same result as explained in the previous section using StarPU's standard C API.

The full source code for this example is given in [Full source code for the 'Scaling a Vector' example](#).

3.4.1 Source Code of Vector Scaling

Programmers can describe the data layout of their application so that StarPU is responsible for enforcing data coherency and availability across the machine. Instead of handling complex (and non-portable) mechanisms to perform data movements, programmers only declare which piece of data is accessed and/or modified by a task, and StarPU makes sure that when a computational kernel starts somewhere (e.g. on a GPU), its data are available locally.

Before submitting those tasks, the programmer first needs to declare the different pieces of data to StarPU using the functions `starpu_*_data_register`. To ease the development of applications for StarPU, it is possible to describe multiple types of data layout. A type of data layout is called an **interface**. There are different predefined interfaces available in StarPU: here we will consider the **vector interface**.

The following lines show how to declare an array of `NX` elements of type `float` using the vector interface:

```
float vector[NX];

starpu_data_handle_t vector_handle;
starpu_vector_data_register(&vector_handle, STARPU_MAIN_RAM, (
    uintptr_t)vector, NX,
    sizeof(vector[0]));
```

The first argument, called the **data handle**, is an opaque pointer which designates the array within StarPU. This is also the structure which is used to describe which data is used by a task. The second argument is the node number where the data originally resides. Here it is `STARPU_MAIN_RAM` since the array `vector` is in the main memory. Then comes the pointer `vector` where the data can be found in main memory, the number of elements in the vector and the size of each element. The following shows how to construct a StarPU task that will manipulate the vector and a constant factor.

```
float factor = 3.14;
struct starpu_task *task = starpu_task_create();

task->cl = &cl; /* Pointer to the codelet defined below */
task->handles[0] = vector_handle; /* First parameter of the codelet */
task->cl_arg = &factor;
task->cl_arg_size = sizeof(factor);
task->synchronous = 1;

starpu_task_submit(task);
```

Since the factor is a mere constant float value parameter, it does not need a preliminary registration, and can just be passed through the pointer `starpu_task::cl_arg` like in the previous example. The vector parameter is described by its handle. `starpu_task::handles` should be set with the handles of the data, the access modes for the data are defined in the field `starpu_codelet::modes` (`STARPU_R` for read-only, `STARPU_W` for write-only and `STARPU_RW` for read and write access).

The definition of the codelet can be written as follows:

```
void scal_cpu_func(void *buffers[], void *cl_arg)
{
    unsigned i;
    float *factor = cl_arg;

    /* length of the vector */
    unsigned n = STARPU_VECTOR_GET_NX(buffers[0]);
    /* CPU copy of the vector pointer */
    float *val = (float *)STARPU_VECTOR_GET_PTR(buffers[0]);

    for (i = 0; i < n; i++)
        val[i] *= *factor;
}

struct starpu_codelet cl =
{
    .cpu_funcs = { scal_cpu_func },
    .cpu_funcs_name = { "scal_cpu_func" },
    .nbuffers = 1,
    .modes = { STARPU_RW }
};
```

The first argument is an array that gives a description of all the buffers passed in the array `starpu_task::handles`. The size of this array is given by the field `starpu_codelet::nbuffers`. For the sake of genericity, this array contains pointers to the different interfaces describing each buffer. In the case of the **vector interface**, the location of the vector (resp. its length) is accessible in the `starpu_vector_interface::ptr` (resp. `starpu_vector_interface::nx`) of this interface. Since the vector is accessed in a read-write fashion, any modification will automatically affect future accesses to this vector made by other tasks.

The second argument of the function `scal_cpu_func` contains a pointer to the parameters of the codelet (given in `starpu_task::cl_arg`), so that we read the constant factor from this pointer.

3.4.2 Execution of Vector Scaling

```
$ make vector_scal
cc $(pkg-config --cflags starpu-1.2) vector_scal.c -o vector_scal $(pkg-config --libs starpu-1.2)
$ ./vector_scal
0.000000 3.000000 6.000000 9.000000 12.000000
```

3.5 Vector Scaling on an Hybrid CPU/GPU Machine

Contrary to the previous examples, the task submitted in this example may not only be executed by the CPUs, but also by a CUDA device.

3.5.1 Definition of the CUDA Kernel

The CUDA implementation can be written as follows. It needs to be compiled with a CUDA compiler such as `nvcc`, the NVIDIA CUDA compiler driver. It must be noted that the vector pointer returned by `STARPU_VECTOR_GET_PTR` is here a pointer in GPU memory, so that it can be passed as such to the kernel call `vector_mult_cuda`.

```
#include <starpu.h>

static __global__ void vector_mult_cuda(unsigned n, float *val,
                                       float factor)
{
    unsigned i = blockIdx.x*blockDim.x + threadIdx.x;
    if (i < n)
        val[i] *= factor;
}

extern "C" void scal_cuda_func(void *buffers[], void *_args)
{
    float *factor = (float *)_args;

    /* length of the vector */
    unsigned n = STARPU_VECTOR_GET_NX(buffers[0]);
    /* local copy of the vector pointer */
    float *val = (float *)STARPU_VECTOR_GET_PTR(buffers[0]);
    unsigned threads_per_block = 64;
    unsigned nblocks = (n + threads_per_block - 1) / threads_per_block;

    vector_mult_cuda<<<nblocks, threads_per_block, 0, starpu_cuda_get_local_stream()>>>
        (n, val, *factor);

    cudaStreamSynchronize(starpu_cuda_get_local_stream());
}
```

3.5.2 Definition of the OpenCL Kernel

The OpenCL implementation can be written as follows. StarPU provides tools to compile a OpenCL kernel stored in a file.

```
__kernel void vector_mult_opengl(int nx, __global float* val, float factor)
{
    const int i = get_global_id(0);
    if (i < nx) {
        val[i] *= factor;
    }
}
```

Contrary to CUDA and CPU, [STARPU_VECTOR_GET_DEV_HANDLE](#) has to be used, which returns a `cl_mem` (which is not a device pointer, but an OpenCL handle), which can be passed as such to the OpenCL kernel. The difference is important when using partitioning, see [Partitioning Data](#).

```
#include <starpu.h>

extern struct starpu_opengl_program programs;

void scal_opengl_func(void *buffers[], void *_args)
{
    float *factor = _args;
    int id, devid, err;
    cl_kernel kernel;
    cl_command_queue queue;
    cl_event event;

    /* length of the vector */
    unsigned n = STARPU_VECTOR_GET_NX(buffers[0]);
    /* OpenCL copy of the vector pointer */
    cl_mem val = (cl_mem)STARPU_VECTOR_GET_DEV_HANDLE(buffers[0]);

    { /* OpenCL specific code */
        id = starpu_worker_get_id();
        devid = starpu_worker_get_devid(id);

        err = starpu_opengl_load_kernel(&kernel, &queue,
                                        &programs,
                                        "vector_mult_opengl", /* Name of the codelet */
                                        devid);
        if (err != CL_SUCCESS) STARPU_OPENCL_REPORT_ERROR(err);

        err = clSetKernelArg(kernel, 0, sizeof(n), &n);
        err |= clSetKernelArg(kernel, 1, sizeof(val), &val);
        err |= clSetKernelArg(kernel, 2, sizeof(*factor), factor);
        if (err) STARPU_OPENCL_REPORT_ERROR(err);
    }

    { /* OpenCL specific code */
        size_t global=n;
        size_t local;
        size_t s;
        cl_device_id device;

        starpu_opengl_get_device(devid, &device);
        err = clGetKernelWorkGroupInfo (kernel, device, CL_KERNEL_WORK_GROUP_SIZE,
                                        sizeof(local), &local, &s);
        if (err != CL_SUCCESS) STARPU_OPENCL_REPORT_ERROR(err);
        if (local > global) local=global;

        err = clEnqueueNDRangeKernel(queue, kernel, 1, NULL, &global, &local, 0,
                                     NULL, &event);
        if (err != CL_SUCCESS) STARPU_OPENCL_REPORT_ERROR(err);
    }

    { /* OpenCL specific code */
        clFinish(queue);
        starpu_opengl_collect_stats(event);
        clReleaseEvent(event);

        starpu_opengl_release_kernel(kernel);
    }
}
```

3.5.3 Definition of the Main Code

The CPU implementation is the same as in the previous section.

Here is the source of the main application. You can notice that the fields `starpu_codelet::cuda_funcs` and `starpu_codelet::openc1_funcs` are set to define the pointers to the CUDA and OpenCL implementations of the task.

```

/*
 * This example demonstrates how to use StarPU to scale an array by a factor.
 * It shows how to manipulate data with StarPU's data management library.
 * 1- how to declare a piece of data to StarPU (starpu_vector_data_register)
 * 2- how to describe which data are accessed by a task (task->handles[0])
 * 3- how a kernel can manipulate the data (buffers[0].vector.ptr)
 */
#include <starpu.h>

#define    NX    2048

extern void scal_cpu_func(void *buffers[], void *_args);
extern void scal_sse_func(void *buffers[], void *_args);
extern void scal_cuda_func(void *buffers[], void *_args);
extern void scal_openc1_func(void *buffers[], void *_args);

static struct starpu_codelet cl = {
    .where = STARPU_CPU | STARPU_CUDA | STARPU_OPENCL,
    /* CPU implementation of the codelet */
    .cpu_funcs = { scal_cpu_func, scal_sse_func },
    .cpu_funcs_name = { "scal_cpu_func", "scal_sse_func" },
#ifdef STARPU_USE_CUDA
    /* CUDA implementation of the codelet */
    .cuda_funcs = { scal_cuda_func },
#endif
#ifdef STARPU_USE_OPENCL
    /* OpenCL implementation of the codelet */
    .openc1_funcs = { scal_openc1_func },
#endif
    .nbuffers = 1,
    .modes = { STARPU_RW }
};

#ifdef STARPU_USE_OPENCL
struct starpu_openc1_program programs;
#endif

int main(int argc, char **argv)
{
    /* We consider a vector of float that is initialized just as any of C
     * data */
    float vector[NX];
    unsigned i;
    for (i = 0; i < NX; i++)
        vector[i] = 1.0f;

    fprintf(stderr, "BEFORE: First element was %f\n", vector[0]);

    /* Initialize StarPU with default configuration */
    starpu_init(NULL);

#ifdef STARPU_USE_OPENCL
    starpu_openc1_load_openc1_from_file(
        "examples/basic_examples/vector_scal_openc1_kernel.cl", &programs, NULL);
#endif

    /* Tell StarPU to associate the "vector" vector with the "vector_handle"
     * identifier. When a task needs to access a piece of data, it should
     * refer to the handle that is associated to it.
     * In the case of the "vector" data interface:
     * - the first argument of the registration method is a pointer to the
     *   handle that should describe the data
     * - the second argument is the memory node where the data (ie. "vector")
     *   resides initially: STARPU_MAIN_RAM stands for an address in main memory, as
     *   opposed to an adress on a GPU for instance.
     * - the third argument is the adress of the vector in RAM
     * - the fourth argument is the number of elements in the vector
     * - the fifth argument is the size of each element.
     */
    starpu_data_handle_t vector_handle;
    starpu_vector_data_register(&vector_handle, STARPU_MAIN_RAM,
        (uintptr_t)vector,
                               NX, sizeof(vector[0]));

    float factor = 3.14;

```



```

/* create a synchronous task: any call to starpu_task_submit will block
 * until it is terminated */
struct starpu_task *task = starpu_task_create();
task->synchronous = 1;

task->cl = &cl;

/* the codelet manipulates one buffer in RW mode */
task->handles[0] = vector_handle;

/* an argument is passed to the codelet, beware that this is a
 * READ-ONLY buffer and that the codelet may be given a pointer to a
 * COPY of the argument */
task->cl_arg = &factor;
task->cl_arg_size = sizeof(factor);

/* execute the task on any eligible computational ressource */
starpu_task_submit(task);

/* StarPU does not need to manipulate the array anymore so we can stop
 * monitoring it */
starpu_data_unregister(vector_handle);

#ifdef STARPU_USE_OPENCL
starpu_opengl_unload_opengl(&programs);
#endif

/* terminate StarPU, no task can be submitted after */
starpu_shutdown();

fprintf(stderr, "AFTER First element is %f\n", vector[0]);

return 0;
}

```

3.5.4 Execution of Hybrid Vector Scaling

The Makefile given at the beginning of the section must be extended to give the rules to compile the CUDA source code. Note that the source file of the OpenCL kernel does not need to be compiled now, it will be compiled at run-time when calling the function `starpu_opengl_load_opengl_from_file()`.

```

CFLAGS += $(shell pkg-config --cflags starpu-1.2)
LDLAGS += $(shell pkg-config --libs starpu-1.2)
CC      = gcc

vector_scal: vector_scal.o vector_scal_cpu.o vector_scal_cuda.o vector_scal_opengl.o

%.o: %.cu
    nvcc $(CFLAGS) $< -c $@

clean:
    rm -f vector_scal *.o

$ make

```

and to execute it, with the default configuration:

```

$ ./vector_scal
0.000000 3.000000 6.000000 9.000000 12.000000

```

or for example, by disabling CPU devices:

```

$ STARPU_NCPU=0 ./vector_scal
0.000000 3.000000 6.000000 9.000000 12.000000

```

or by disabling CUDA devices (which may permit to enable the use of OpenCL, see [Enabling OpenCL](#)) :

```

$ STARPU_NCUDA=0 ./vector_scal
0.000000 3.000000 6.000000 9.000000 12.000000

```


Part II

StarPU Quick Programming Guide

Chapter 4

Advanced Examples

TODO

Chapter 5

Check List When Performance Are Not There

TODO: improve!

To achieve good performance, we give below a list of features which should be checked.

For a start, you can use [Offline Performance Tools](#) to get a Gantt chart which will show roughly where time is spent, and focus correspondingly.

5.1 Check Task Size

Make sure that your tasks are not too small, because the StarPU runtime overhead is not completely zero. You can run the `tasks_size_overhead.sh` script to get an idea of the scalability of tasks depending on their duration (in μ s), on your own system.

Typically, 10 μ s-ish tasks are definitely too small, the CUDA overhead itself is much bigger than this.

1ms-ish tasks may be a good start, but will not necessarily scale to many dozens of cores, so it's better to try to get 10ms-ish tasks.

Tasks durations can easily be observed when performance models are defined (see [Performance Model Example](#)) by using the `starpu_perfmodel_plot` or `starpu_perfmodel_display` tool (see [Performance Of Codelets](#))

When using parallel tasks, the problem is even worse since StarPU has to synchronize the execution of tasks.

5.2 Configuration Which May Improve Performance

The `--enable-fast` configuration option disables all assertions. This makes StarPU more performant for really small tasks by disabling all sanity checks. Only use this for measurements and production, not for development, since this will drop all basic checks.

5.3 Data Related Features Which May Improve Performance

link to [Data Management](#)

link to [Data Prefetch](#)

5.4 Task Related Features Which May Improve Performance

link to [Task Granularity](#)

link to [Task Submission](#)

link to [Task Priorities](#)

5.5 Scheduling Related Features Which May Improve Performance

link to [Task Scheduling Policies](#)

link to [Task Distribution Vs Data Transfer](#)

link to [Energy-based Scheduling](#)

link to [Static Scheduling](#)

5.6 CUDA-specific Optimizations

Due to CUDA limitations, StarPU will have a hard time overlapping its own communications and the codelet computations if the application does not use a dedicated CUDA stream for its computations instead of the default stream, which synchronizes all operations of the GPU. StarPU provides one by the use of [starpu_cuda_get_local_stream\(\)](#) which can be used by all CUDA codelet operations to avoid this issue. For instance:

```
func <<<grid,block,0,starpu_cuda_get_local_stream()>>> (foo, bar);
cudaStreamSynchronize(starpu_cuda_get_local_stream());
```

Unfortunately, some CUDA libraries do not have stream variants of kernels. This will lower the potential for overlapping.

Calling [starpu_cublas_init\(\)](#) makes StarPU already do appropriate calls for the CUBLAS library. Some libraries like Magma may however change the current stream of CUBLAS v1, one then has to call `cublasSetKernelStream(starpu_cuda_get_local_stream())` at the beginning of the codelet to make sure that CUBLAS is really using the proper stream. When using CUBLAS v2, [starpu_cublas_get_local_handle\(\)](#) can be called to queue CUBLAS kernels with the proper configuration.

Similarly, calling [starpu_cusparse_init\(\)](#) makes StarPU create CUSPARSE handles on each CUDA device, [starpu_cusparse_get_local_handle\(\)](#) can then be used to queue CUSPARSE kernels with the proper configuration.

If the kernel can be made to only use this local stream or other self-allocated streams, i.e. the whole kernel submission can be made asynchronous, then one should enable asynchronous execution of the kernel. This means setting the flag [STARPU_CUDA_ASYNC](#) in the corresponding field [starpu_codelet::cuda_flags](#), and dropping the `cudaStreamSynchronize()` call at the end of the `cuda_func` function, so that it returns immediately after having queued the kernel to the local stream. That way, StarPU will be able to submit and complete data transfers while kernels are executing, instead of only at each kernel submission. The kernel just has to make sure that StarPU can use the local stream to synchronize with the kernel startup and completion.

If the kernel uses its own non-default stream, one can synchronize this stream with the StarPU-provided stream this way:


```

cudaEvent_t event;
call_kernel_with_its_own_stream()
cudaEventCreateWithFlags(&event, cudaEventDisableTiming);
cudaEventRecord(event, get_kernel_stream());
cudaStreamWaitEvent(starpu_cuda_get_local_stream(), event, 0);
cudaEventDestroy(event);

```

This code makes the StarPU-provided stream wait for a new event, which will be triggered by the completion of the kernel.

Using the flag `STARPU_CUDA_ASYNC` also permits to enable concurrent kernel execution, on cards which support it (Kepler and later, notably). This is enabled by setting the environment variable `STARPU_NWORKER_PER_CUDA` to the number of kernels to execute concurrently. This is useful when kernels are small and do not feed the whole GPU with threads to run.

Concerning memory allocation, you should really not use `cudaMalloc/cudaFree` within the kernel, since `cudaFree` introduces a awfully lot of synchronizations within CUDA itself. You should instead add a parameter to the codelet with the `STARPU_SCRATCH` mode access. You can then pass to the task a handle registered with the desired size but with the `NULL` pointer, that handle can even be the shared between tasks, StarPU will allocate per-task data on the fly before task execution, and reuse the allocated data between tasks.

See `examples/pi/pi_redux.c` for an example of use.

5.7 OpenCL-specific Optimizations

If the kernel can be made to only use the StarPU-provided command queue or other self-allocated queues, i.e. the whole kernel submission can be made asynchronous, then one should enable asynchronous execution of the kernel. This means setting the flag `STARPU_OPENCL_ASYNC` in the corresponding field `starpu_codelet::opencl_flags` and dropping the `clFinish()` and `starpu_openccl_collect_stats()` calls at the end of the kernel, so that it returns immediately after having queued the kernel to the provided queue. That way, StarPU will be able to submit and complete data transfers while kernels are executing, instead of only at each kernel submission. The kernel just has to make sure that StarPU can use the command queue it has provided to synchronize with the kernel startup and completion.

5.8 Detection Stuck Conditions

It may happen that for some reason, StarPU does not make progress for a long period of time. Reason are sometimes due to contention inside StarPU, but sometimes this is due to external reasons, such as stuck MPI driver, or CUDA driver, etc.

```
export STARPU_WATCHDOG_TIMEOUT=10000 (STARPU_WATCHDOG_TIMEOUT)
```

allows to make StarPU print an error message whenever StarPU does not terminate any task for 10ms, but lets the application continue normally. In addition to that,

```
export STARPU_WATCHDOG_CRASH=1 (STARPU_WATCHDOG_CRASH)
```

raises `SIGABRT` in this condition, thus allowing to catch the situation in `gdb`. It can also be useful to type `handle SIGABRT nopass` in `gdb` to be able to let the process continue, after inspecting the state of the process.

5.9 How to Limit Memory Used By StarPU And Cache Buffer Allocations

By default, StarPU makes sure to use at most 90% of the memory of GPU devices, moving data in and out of the device as appropriate and with prefetch and writeback optimizations. Concerning the main memory, by default it will not limit its consumption, since by default it has nowhere to push the data to when memory gets tight. This also means that by default StarPU will not cache buffer allocations in main memory, since it does not know how much of the system memory it can afford.

In the case of GPUs, the `STARPU_LIMIT_CUDA_MEM`, `STARPU_LIMIT_CUDA_devid_MEM`, `STARPU_LIMIT_OPENCL_MEM`, and `STARPU_LIMIT_OPENCL_devid_MEM` environment variables can be used to control how much (in MiB) of the GPU device memory should be used at most by StarPU (their default values are 90% of the available memory).

In the case of the main memory, the `STARPU_LIMIT_CPU_MEM` environment variable can be used to specify how much (in MiB) of the main memory should be used at most by StarPU for buffer allocations. This way, StarPU will be able to cache buffer allocations (which can be a real benefit if a lot of buffers are involved, or if allocation fragmentation can become a problem), and when using `Out Of Core`, StarPU will know when it should evict data out to the disk.

It should be noted that by default only buffer allocations automatically done by StarPU are accounted here, i.e. allocations performed through `starpu_malloc_on_node()` which are used by the data interfaces (matrix, vector, etc.). This does not include allocations performed by the application through e.g. `malloc()`. It does not include allocations performed through `starpu_malloc()` either, only allocations performed explicitly with the `STARPU_MALLOC_COUNT` flag, i.e. by calling

```
starpu_malloc_flags (STARPU_MALLOC_COUNT)
```

are taken into account. If the application wants to make StarPU aware of its own allocations, so that StarPU knows precisely how much data is allocated, and thus when to evict allocation caches or data out to the disk, `starpu_memory_allocate()` can be used to specify an amount of memory to be accounted for. `starpu_memory_deallocate()` can be used to account freed memory back. Those can for instance be used by data interfaces with dynamic data buffers: instead of using `starpu_malloc_on_node()`, they would dynamically allocate data with `malloc/realloc`, and notify starpu of the delta thanks to `starpu_memory_allocate()` and `starpu_memory_deallocate()` calls.

`starpu_memory_get_total()` and `starpu_memory_get_available()` can be used to get an estimation of how much memory is available. `starpu_memory_wait_available()` can also be used to block until an amount of memory becomes available, but it may be preferable to call

```
starpu_memory_allocate (STARPU_MEMORY_WAIT)
```

to reserve this amount immediately.

5.10 How To Reduce The Memory Footprint Of Internal Data Structures

It is possible to reduce the memory footprint of the task and data internal structures of StarPU by describing the shape of your machine and/or your application at the configure step.

To reduce the memory footprint of the data internal structures of StarPU, one can set the `--enable-maxcpus`, `--enable-maxcudadev`, `--enable-maxopencldev` and `--enable-maxnodes` configure parameters to give StarPU the architecture of the machine it will run on, thus tuning the size of the structures to the machine.

To reduce the memory footprint of the task internal structures of StarPU, one can set the `--enable-maxbuffers` configure parameter to give StarPU the maximum number of buffers that a task can use during an execution. For

example, in the Cholesky factorization (dense linear algebra application), the GEMM task uses up to 3 buffers, so it is possible to set the maximum number of task buffers to 3 to run a Cholesky factorization on StarPU.

The size of the various structures of StarPU can be printed by `tests/microbenchs/display_structures_size`.

It is also often useless to submit **all** the tasks at the same time. One can make the `starpu_task_submit()` function block when a reasonable given number of tasks have been submitted, by setting the `STARPU_LIMIT_MIN_SUBMITTED_TASKS` and `STARPU_LIMIT_MAX_SUBMITTED_TASKS` environment variables, for instance:

```
export STARPU_LIMIT_MAX_SUBMITTED_TASKS=10000

export STARPU_LIMIT_MIN_SUBMITTED_TASKS=9000
```

To make StarPU block submission when 10000 tasks are submitted, and unblock submission when only 9000 tasks are still submitted, i.e. 1000 tasks have completed among the 10000 which were submitted when submission was blocked. Of course this may reduce parallelism if the threshold is set too low. The precise balance depends on the application task graph.

An idea of how much memory is used for tasks and data handles can be obtained by setting the `STARPU_MAX_MEMORY_USE` environment variable to 1.

5.11 How To Reuse Memory

When your application needs to allocate more data than the available amount of memory usable by StarPU (given by `starpu_memory_get_available()`), the allocation cache system can reuse data buffers used by previously executed tasks. For this system to work with MPI tasks, you need to submit tasks progressively instead of as soon as possible, because in the case of MPI receives, the allocation cache check for reusing data buffers will be done at submission time, not at execution time.

You have two options to control the task submission flow. The first one is by controlling the number of submitted tasks during the whole execution. This can be done whether by setting the environment variables `STARPU_LIMIT_MAX_SUBMITTED_TASKS` and `STARPU_LIMIT_MIN_SUBMITTED_TASKS` to tell StarPU when to stop submitting tasks and when to wake up and submit tasks again, or by explicitly calling `starpu_task_wait_for_n_submitted()` in your application code for finest grain control (for example, between two iterations of a submission loop).

The second option is to control the memory size of the allocation cache. This can be done in the application by using jointly `starpu_memory_get_available()` and `starpu_memory_wait_available()` to submit tasks only when there is enough memory space to allocate the data needed by the task, i.e when enough data are available for reuse in the allocation cache.

5.12 Performance Model Calibration

Most schedulers are based on an estimation of codelet duration on each kind of processing unit. For this to be possible, the application programmer needs to configure a performance model for the codelets of the application (see [Performance Model Example](#) for instance). History-based performance models use on-line calibration. StarPU will automatically calibrate codelets which have never been calibrated yet, and save the result in `$STARPU_HOME/.starpu/sampling/codelets`. The models are indexed by machine name.

By default, StarPU stores separate performance models according to the hostname of the system. To avoid having to calibrate performance models for each node of a homogeneous cluster for instance, the model can be shared by using `export STARPU_HOSTNAME=some_global_name (STARPU_HOSTNAME)`, where `some_global_name` is the name of the cluster for instance, which thus overrides the hostname of the system.

By default, StarPU stores separate performance models for each GPU. To avoid having to calibrate performance models for each GPU of a homogeneous set of GPU devices for instance, the model can be shared by setting `export STARPU_PERF_MODEL_HOMOGENEOUS_CUDA=1`, `export STARPU_PERF_MODEL_HOMOGENEOUS_OPENCL=1`, `export STARPU_PERF_MODEL_HOMOGENEOUS_MIC=1`, or `export STARPU_PERF_MODEL_HOMOGENEOUS_SCC=1` (depending on your GPU device type).


To force continuing calibration, use `export STARPU_CALIBRATE=1` ([STARPU_CALIBRATE](#)). This may be necessary if your application has not-so-stable performance. StarPU will force calibration (and thus ignore the current result) until 10 (`_STARPU_CALIBRATION_MINIMUM`) measurements have been made on each architecture, to avoid badly scheduling tasks just because the first measurements were not so good. Details on the current performance model status can be obtained from the tool `starpu_perfmodel_display`: the `-l` option lists the available performance models, and the `-s` option permits to choose the performance model to be displayed. The result looks like:

```
$ starpu_perfmodel_display -s starpu_sl_u_model_11
performance model for cpu_impl_0
# hash      size      flops      mean      dev      n
914f3bef    1048576  0.000000e+00 2.503577e+04 1.982465e+02 8
3e921964    65536   0.000000e+00 5.527003e+02 1.848114e+01 7
e5a07e31    4096    0.000000e+00 1.717457e+01 5.190038e+00 14
...
```

Which shows that for the LU 11 kernel with a 1MiB matrix, the average execution time on CPUs was about 25ms, with a 0.2ms standard deviation, over 8 samples. It is a good idea to check this before doing actual performance measurements.

A graph can be drawn by using the tool `starpu_perfmodel_plot`:

```
$ starpu_perfmodel_plot -s starpu_sl_u_model_11
4096 16384 65536 262144 1048576 4194304
$ gnuplot starpu_starp_u_model_11.gp
$ gv starpu_starp_u_model_11.eps
```



If a kernel source code was modified (e.g. performance improvement), the calibration information is stale and should be dropped, to re-calibrate from start. This can be done by using `export STARPU_CALIBRATE=2` ([STARPU_CALIBRATE](#)).

Note: history-based performance models get calibrated only if a performance-model-based scheduler is chosen.

The history-based performance models can also be explicitly filled by the application without execution, if e.g. the application already has a series of measurements. This can be done by using [starpu_perfmodel_update_history\(\)](#), for instance:

```
static struct starpu_perfmodel perf_model = {
    .type = STARPU_HISTORY_BASED,
    .symbol = "my_perfmodel",
};

struct starpu_codelet cl = {
    .cuda_funcs = { cuda_func1, cuda_func2 },
    .nbuffers = 1,
    .modes = {STARPU_W},
    .model = &perf_model
};

void feed(void) {
    struct my_measure *measure;
    struct starpu_task task;
    starpu_task_init(&task);

    task.cl = &cl;

    for (measure = &measures[0]; measure < measures[last]; measure++) {
        starpu_data_handle_t handle;
        starpu_vector_data_register(&handle, -1, 0, measure->size, sizeof(float)
    );
        task.handles[0] = handle;
        starpu_perfmodel_update_history(&perf_model, &task,
                                      STARPU_CUDA_DEFAULT + measure->cuda_dev, 0,
                                      measure->implementation, measure->time);

        starpu_task_clean(&task);
        starpu_data_unregister(handle);
    }
}
```

Measurement has to be provided in milliseconds for the completion time models, and in Joules for the energy consumption models.

5.13 Profiling

A quick view of how many tasks each worker has executed can be obtained by setting `export STARPU_WORKER_STATS=1` ([STARPU_WORKER_STATS](#)). This is a convenient way to check that execution did happen on accelerators, without penalizing performance with the profiling overhead.

A quick view of how much data transfers have been issued can be obtained by setting `export STARPU_BUS_STATS=1` ([STARPU_BUS_STATS](#)).

More detailed profiling information can be enabled by using `export STARPU_PROFILING=1` ([STARPU_PROFILING](#)) or by calling [starpu_profiling_status_set\(\)](#) from the source code. Statistics on the execution can then be obtained by using `export STARPU_BUS_STATS=1` and `export STARPU_WORKER_STATS=1`. More details on performance feedback are provided in the next chapter.

5.14 Overhead Profiling

[Offline Performance Tools](#) can already provide an idea of to what extent and which part of StarPU bring overhead on the execution time. To get a more precise analysis of the parts of StarPU which bring most overhead, `gprof` can be used.

First, recompile and reinstall StarPU with `gprof` support:

```
./configure --enable-perf-debug --disable-shared --disable-build-tests --disable-build-examples
```

Make sure not to leave a dynamic version of StarPU in the target path: remove any remaining `libstarpu-*.so`

Then relink your application with the static StarPU library, make sure that running `ldd` on your application does not mention any `libstarpu` (i.e. it's really statically-linked).

```
gcc test.c -o test $(pkg-config --cflags starpu-1.3) $(pkg-config --libs starpu-1.3)
```

Now you can run your application, and a `gmon.out` file should appear in the current directory, you can process it by running `gprof` on your application:

```
gprof ./test
```

This will dump an analysis of the time spent in StarPU functions.

Part III

StarPU Inside

Chapter 6

Tasks In StarPU

6.1 Task Granularity

Like any other runtime, StarPU has some overhead to manage tasks. Since it does smart scheduling and data management, this overhead is not always neglectable. The order of magnitude of the overhead is typically a couple of microseconds, which is actually quite smaller than the CUDA overhead itself. The amount of work that a task should do should thus be somewhat bigger, to make sure that the overhead becomes neglectible. The offline performance feedback can provide a measure of task length, which should thus be checked if bad performance are observed. To get a grasp at the scalability possibility according to task size, one can run `tests/microbenchs/tasks_size_overhead.sh` which draws curves of the speedup of independent tasks of very small sizes.

The choice of scheduler also has impact over the overhead: for instance, the scheduler `dmda` takes time to make a decision, while `eager` does not. `tasks_size_overhead.sh` can again be used to get a grasp at how much impact that has on the target machine.

6.2 Task Submission

To let StarPU make online optimizations, tasks should be submitted asynchronously as much as possible. Ideally, all the tasks should be submitted, and mere calls to `starpu_task_wait_for_all()` or `starpu_data_unregister()` be done to wait for termination. StarPU will then be able to rework the whole schedule, overlap computation with communication, manage accelerator local memory usage, etc.

6.3 Task Priorities

By default, StarPU will consider the tasks in the order they are submitted by the application. If the application programmer knows that some tasks should be performed in priority (for instance because their output is needed by many other tasks and may thus be a bottleneck if not executed early enough), the field `starpu_task::priority` should be set to transmit the priority information to StarPU.

6.4 Setting Many Data Handles For a Task

The maximum number of data a task can manage is fixed by the environment variable `STARPU_NMAXBUFS` which has a default value which can be changed through the configure option `--enable-maxbuffers`.

However, it is possible to define tasks managing more data by using the field `starpu_task::dyn_handles` when defining a task and the field `starpu_codelet::dyn_modes` when defining the corresponding codelet.

```
enum starpu_data_access_mode modes[STARPU_NMAXBUFS+1] = {
    STARPU_R, STARPU_R, ...
};

struct starpu_codelet dummy_big_cl =
{
    .cuda_funcs = { dummy_big_kernel },
    .opencl_funcs = { dummy_big_kernel },
    .cpu_funcs = { dummy_big_kernel },
    .cpu_funcs_name = { "dummy_big_kernel" },
    .nbuffers = STARPU_NMAXBUFS+1,
    .dyn_modes = modes
};

task = starpu_task_create();
task->cl = &dummy_big_cl;
task->dyn_handles = malloc(task->cl->nbuffers * sizeof(starpu_data_handle_t));
for(i=0 ; i<task->cl->nbuffers ; i++)
{
    task->dyn_handles[i] = handle;
}
starpu_task_submit(task);

starpu_data_handle_t *handles = malloc(dummy_big_cl.nbuffers * sizeof(
    starpu_data_handle_t));
for(i=0 ; i<dummy_big_cl.nbuffers ; i++)
{
    handles[i] = handle;
}
starpu_task_insert(&dummy_big_cl,
    STARPU_VALUE, &dummy_big_cl.nbuffers, sizeof(dummy_big_cl.nbuffers
    ),
    STARPU_DATA_ARRAY, handles, dummy_big_cl.nbuffers,
    0);
```

The whole code for this complex data interface is available in the directory `examples/basic_↵`
`examples/dynamic_handles.c`.

6.5 Setting a Variable Number Of Data Handles For a Task

Normally, the number of data handles given to a task is fixed in the `starpu_codelet::nbuffers` codelet field. This field can however be set to `STARPU_VARIABLE_NBUFFERS`, in which case the `starpu_task::nbuffers` task field must be set, and the `starpu_task::modes` field (or `starpu_task::dyn_modes` field, see [Setting Many Data Handles For a Task](#)) should be used to specify the modes for the handles.

6.6 Using Multiple Implementations Of A Codelet

One may want to write multiple implementations of a codelet for a single type of device and let StarPU choose which one to run. As an example, we will show how to use SSE to scale a vector. The codelet can be written as follows:

```
#include <xmmintrin.h>

void scal_sse_func(void *buffers[], void *cl_arg)
{
    float *vector = (float *) STARPU_VECTOR_GET_PTR(buffers[0]);
    unsigned int n = STARPU_VECTOR_GET_NX(buffers[0]);
    unsigned int n_iterations = n/4;
    if (n % 4 != 0)
        n_iterations++;

    __m128 *VECTOR = (__m128*) vector;
    __m128 factor __attribute__((aligned(16)));
    factor = _mm_set1_ps(*(float *) cl_arg);

    unsigned int i;
    for (i = 0; i < n_iterations; i++)
        VECTOR[i] = _mm_mul_ps(factor, VECTOR[i]);
}

struct starpu_codelet cl = {
    .cpu_funcs = { scal_cpu_func, scal_sse_func },
    .cpu_funcs_name = { "scal_cpu_func", "scal_sse_func" },
    .nbuffers = 1,
    .modes = { STARPU_RW }
};
```

Schedulers which are multi-implementation aware (only `dmda` and `pheft` for now) will use the performance models of all the implementations it was given, and pick the one which seems to be the fastest.

6.7 Enabling Implementation According To Capabilities

Some implementations may not run on some devices. For instance, some CUDA devices do not support double floating point precision, and thus the kernel execution would just fail; or the device may not have enough shared memory for the implementation being used. The field `starpu_codelet::can_execute` permits to express this. For instance:

```
static int can_execute(unsigned workerid, struct starpu_task *task, unsigned nimpl)
{
    const struct cudaDeviceProp *props;
    if (starpu_worker_get_type(workerid) == STARPU_CPU_WORKER)
        return 1;
    /* Cuda device */
    props = starpu_cuda_get_device_properties(workerid);
    if (props->major >= 2 || props->minor >= 3)
        /* At least compute capability 1.3, supports doubles */
        return 1;
    /* Old card, does not support doubles */
    return 0;
}

struct starpu_codelet cl = {
    .can_execute = can_execute,
    .cpu_funcs = { cpu_func },
    .cpu_funcs_name = { "cpu_func" },
    .cuda_funcs = { gpu_func },
    .nbuffers = 1,
    .modes = { STARPU_RW }
};
```

This can be essential e.g. when running on a machine which mixes various models of CUDA devices, to take benefit from the new models without crashing on old models.

Note: the function `starpu_codelet::can_execute` is called by the scheduler each time it tries to match a task with a worker, and should thus be very fast. The function `starpu_cuda_get_device_properties()` provides a quick access to CUDA properties of CUDA devices to achieve such efficiency.

Another example is to compile CUDA code for various compute capabilities, resulting with two CUDA functions, e.g. `scal_gpu_13` for compute capability 1.3, and `scal_gpu_20` for compute capability 2.0. Both functions can be provided to StarPU by using `starpu_codelet::cuda_funcs`, and `starpu_codelet::can_execute` can then be used to rule out the `scal_gpu_20` variant on a CUDA device which will not be able to execute it:

```

static int can_execute(unsigned workerid, struct starpu_task *task, unsigned nimpl)
{
    const struct cudaDeviceProp *props;
    if (starpu_worker_get_type(workerid) == STARPU_CPU_WORKER)
        return 1;
    /* Cuda device */
    if (nimpl == 0)
        /* Trying to execute the 1.3 capability variant, we assume it is ok in all cases. */
        return 1;
    /* Trying to execute the 2.0 capability variant, check that the card can do it. */
    props = starpu_cuda_get_device_properties(workerid);
    if (props->major >= 2 || props->minor >= 0)
        /* At least compute capability 2.0, can run it */
        return 1;
    /* Old card, does not support 2.0, will not be able to execute the 2.0 variant. */
    return 0;
}

struct starpu_codelet cl = {
    .can_execute = can_execute,
    .cpu_funcs = { cpu_func },
    .cpu_funcs_name = { "cpu_func" },
    .cuda_funcs = { scal_gpu_13, scal_gpu_20 },
    .nbuffers = 1,
    .modes = { STARPU_RW }
};

```

Another example is having specialized implementations for some given common sizes, for instance here we have a specialized implementation for 1024x1024 matrices:

```

static int can_execute(unsigned workerid, struct starpu_task *task, unsigned nimpl)
{
    const struct cudaDeviceProp *props;
    if (starpu_worker_get_type(workerid) == STARPU_CPU_WORKER)
        return 1;
    /* Cuda device */
    switch (nimpl)
    {
        case 0:
            /* Trying to execute the generic capability variant. */
            return 1;
        case 1:
            {
                /* Trying to execute the size == 1024 specific variant. */
                struct starpu_matrix_interface *interface = starpu_data_get_interface_on_node
                    (task->handles[0]);
                return STARPU_MATRIX_GET_NX(interface) == 1024 && STARPU_MATRIX_GET_NY
                    (interface) == 1024;
            }
    }
}

struct starpu_codelet cl = {
    .can_execute = can_execute,
    .cpu_funcs = { cpu_func },
    .cpu_funcs_name = { "cpu_func" },
    .cuda_funcs = { potrf_gpu_generic, potrf_gpu_1024 },
    .nbuffers = 1,
    .modes = { STARPU_RW }
};

```

Note: the most generic variant should be provided first, as some schedulers are not able to try the different variants.

6.8 Insert Task Utility

StarPU provides the wrapper function `starpu_task_insert()` to ease the creation and submission of tasks.

Here the implementation of the codelet:

```

void func_cpu(void *descr[], void *_args)
{
    int *x0 = (int *)STARPU_VARIABLE_GET_PTR(descr[0]);
    float *x1 = (float *)STARPU_VARIABLE_GET_PTR(descr[1]);
    int ifactor;
    float ffactor;

    starpu_codelet_unpack_args(_args, &ifactor, &ffactor);
    *x0 = *x0 * ifactor;
    *x1 = *x1 * ffactor;
}

struct starpu_codelet mycodelet = {
    .cpu_funcs = { func_cpu },
    .cpu_funcs_name = { "func_cpu" },
    .nbuffers = 2,
    .modes = { STARPU_RW, STARPU_RW }
};

```

And the call to the function `starpu_task_insert()`:

```

starpu_task_insert(&mycodelet,
    STARPU_VALUE, &ifactor, sizeof(ifactor),
    STARPU_VALUE, &ffactor, sizeof(ffactor),
    STARPU_RW, data_handles[0],
    STARPU_RW, data_handles[1],
    0);

```

The call to `starpu_task_insert()` is equivalent to the following code:

```

struct starpu_task *task = starpu_task_create();
task->cl = &mycodelet;
task->handles[0] = data_handles[0];
task->handles[1] = data_handles[1];
char *arg_buffer;
size_t arg_buffer_size;
starpu_codelet_pack_args(&arg_buffer, &arg_buffer_size,
    STARPU_VALUE, &ifactor, sizeof(ifactor),
    STARPU_VALUE, &ffactor, sizeof(ffactor),
    0);
task->cl_arg = arg_buffer;
task->cl_arg_size = arg_buffer_size;
int ret = starpu_task_submit(task);

```

Here a similar call using `STARPU_DATA_ARRAY`.

```

starpu_task_insert(&mycodelet,
    STARPU_DATA_ARRAY, data_handles, 2,
    STARPU_VALUE, &ifactor, sizeof(ifactor),
    STARPU_VALUE, &ffactor, sizeof(ffactor),
    0);

```

If some part of the task insertion depends on the value of some computation, the macro `STARPU_DATA_ACQUIRE_CB` can be very convenient. For instance, assuming that the index variable `i` was registered as handle `A_handle[i]`:

```

/* Compute which portion we will work on, e.g. pivot */
starpu_task_insert(&which_index, STARPU_W, i_handle, 0);

/* And submit the corresponding task */
STARPU_DATA_ACQUIRE_CB(i_handle, STARPU_R,
    starpu_task_insert(&work,
        STARPU_RW, A_handle[i],
        0));

```

The macro `STARPU_DATA_ACQUIRE_CB` submits an asynchronous request for acquiring data `i` for the main application, and will execute the code given as third parameter when it is acquired. In other words, as soon as the value of `i` computed by the codelet `which_index` can be read, the portion of code passed as third parameter of `STARPU_DATA_ACQUIRE_CB` will be executed, and is allowed to read from `i` to use it e.g. as an index. Note that this macro is only available when compiling StarPU with the compiler `gcc`.

There is several ways of calling the function `starpu_codelet_unpack_args()`.

```

void func_cpu(void *descr[], void *_args)
{
    int ifactor;
    float ffactor;

    starpu_codelet_unpack_args(_args, &ifactor, &ffactor);
}

void func_cpu(void *descr[], void *_args)
{
    int ifactor;
    float ffactor;

    starpu_codelet_unpack_args(_args, &ifactor, 0);
    starpu_codelet_unpack_args(_args, &ifactor, &ffactor);
}

void func_cpu(void *descr[], void *_args)
{
    int ifactor;
    float ffactor;
    char buffer[100];

    starpu_codelet_unpack_args_and_copyleft(_args, buffer, 100,
&ifactor, 0);
    starpu_codelet_unpack_args(buffer, &ffactor);
}

```

6.9 Getting Task Children

It may be interesting to get the list of tasks which depend on a given task, notably when using implicit dependencies, since this list is computed by StarPU. [starpu_task_get_task_succs\(\)](#) provides it. For instance:

```

struct starpu_task *tasks[4];
ret = starpu_task_get_task_succs(task, sizeof(tasks)/sizeof(*tasks), tasks);

```

6.10 Parallel Tasks

StarPU can leverage existing parallel computation libraries by the means of parallel tasks. A parallel task is a task which gets worked on by a set of CPUs (called a parallel or combined worker) at the same time, by using an existing parallel CPU implementation of the computation to be achieved. This can also be useful to improve the load balance between slow CPUs and fast GPUs: since CPUs work collectively on a single task, the completion time of tasks on CPUs become comparable to the completion time on GPUs, thus relieving from granularity discrepancy concerns. `hwloc` support needs to be enabled to get good performance, otherwise StarPU will not know how to better group cores.

Two modes of execution exist to accomodate with existing usages.

6.10.1 Fork-mode Parallel Tasks

In the Fork mode, StarPU will call the codelet function on one of the CPUs of the combined worker. The codelet function can use [starpu_combined_worker_get_size\(\)](#) to get the number of threads it is allowed to start to achieve the computation. The CPU binding mask for the whole set of CPUs is already enforced, so that threads created by the function will inherit the mask, and thus execute where StarPU expected, the OS being in charge of choosing how to schedule threads on the corresponding CPUs. The application can also choose to bind threads by hand, using e.g. `sched_getaffinity` to know the CPU binding mask that StarPU chose.

For instance, using OpenMP (full source is available in `examples/openmp/vector_scal.c`):

```

void scal_cpu_func(void *buffers[], void *_args)
{
    unsigned i;
    float *factor = _args;
    struct starpu_vector_interface *vector = buffers[0];
    unsigned n = STARPU_VECTOR_GET_NX(vector);
    float *val = (float *)STARPU_VECTOR_GET_PTR(vector);

#pragma omp parallel for num_threads(starpu_combined_worker_get_size())
    for (i = 0; i < n; i++)
        val[i] *= *factor;
}

static struct starpu_codelet cl =
{
    .modes = { STARPU_RW },
    .where = STARPU_CPU,
    .type = STARPU_FORKJOIN,
    .max_parallelism = INT_MAX,
    .cpu_funcs = { scal_cpu_func },
    .cpu_funcs_name = { "scal_cpu_func" },
    .nbuffers = 1,
};

```

Other examples include for instance calling a BLAS parallel CPU implementation (see `examples/mult/xgemv.c`).

6.10.2 SPMD-mode Parallel Tasks

In the SPMD mode, StarPU will call the codelet function on each CPU of the combined worker. The codelet function can use `starpu_combined_worker_get_size()` to get the total number of CPUs involved in the combined worker, and thus the number of calls that are made in parallel to the function, and `starpu_combined_worker_get_rank()` to get the rank of the current CPU within the combined worker. For instance:

```

static void func(void *buffers[], void *_args)
{
    unsigned i;
    float *factor = _args;
    struct starpu_vector_interface *vector = buffers[0];
    unsigned n = STARPU_VECTOR_GET_NX(vector);
    float *val = (float *)STARPU_VECTOR_GET_PTR(vector);

    /* Compute slice to compute */
    unsigned m = starpu_combined_worker_get_size();
    unsigned j = starpu_combined_worker_get_rank();
    unsigned slice = (n+m-1)/m;

    for (i = j * slice; i < (j+1) * slice && i < n; i++)
        val[i] *= *factor;
}

static struct starpu_codelet cl =
{
    .modes = { STARPU_RW },
    .type = STARPU_SPMD,
    .max_parallelism = INT_MAX,
    .cpu_funcs = { func },
    .cpu_funcs_name = { "func" },
    .nbuffers = 1,
};

```

Of course, this trivial example will not really benefit from parallel task execution, and was only meant to be simple to understand. The benefit comes when the computation to be done is so that threads have to e.g. exchange intermediate results, or write to the data in a complex but safe way in the same buffer.

6.10.3 Parallel Tasks Performance

To benefit from parallel tasks, a parallel-task-aware StarPU scheduler has to be used. When exposed to codelets with a flag `STARPU_FORKJOIN` or `STARPU_SPMD`, the schedulers `pheft` (parallel-heft) and `peager` (parallel eager) will indeed also try to execute tasks with several CPUs. It will automatically try the various available combined worker sizes (making several measurements for each worker size) and thus be able to avoid choosing a large combined worker if the codelet does not actually scale so much.

6.10.4 Combined Workers

By default, StarPU creates combined workers according to the architecture structure as detected by `hwloc`. It means that for each object of the `hwloc` topology (NUMA node, socket, cache, ...) a combined worker will be created. If some nodes of the hierarchy have a big arity (e.g. many cores in a socket without a hierarchy of shared caches), StarPU will create combined workers of intermediate sizes. The variable `STARPU_SYNTHESIZE_ARYTY_COMBINED_WORKER` permits to tune the maximum arity between levels of combined workers.

The combined workers actually produced can be seen in the output of the tool `starpu_machine_display` (the environment variable `STARPU_SCHED` has to be set to a combined worker-aware scheduler such as `pheft` or `peager`).

6.10.5 Concurrent Parallel Tasks

Unfortunately, many environments and librairies do not support concurrent calls.

For instance, most OpenMP implementations (including the main ones) do not support concurrent `pragma omp parallel` statements without nesting them in another `pragma omp parallel` statement, but StarPU does not yet support creating its CPU workers by using such `pragma`.

Other parallel libraries are also not safe when being invoked concurrently from different threads, due to the use of global variables in their sequential sections for instance.

The solution is then to use only one combined worker at a time. This can be done by setting the field `starpu_conf::single_combined_worker` to 1, or setting the environment variable `STARPU_SINGLE_COMBINED_WORKER` to 1. StarPU will then run only one parallel task at a time (but other CPU and GPU tasks are not affected and can be run concurrently). The parallel task scheduler will however still try varying combined worker sizes to look for the most efficient ones.

6.10.6 Synchronization Tasks

For the application conveniency, it may be useful to define tasks which do not actually make any computation, but wear for instance dependencies between other tasks or tags, or to be submitted in callbacks, etc.

The obvious way is of course to make kernel functions empty, but such task will thus have to wait for a worker to become ready, transfer data, etc.

A much lighter way to define a synchronization task is to set its `starpu_task::cl` field to `NULL`. The task will thus be a mere synchronization point, without any data access or execution content: as soon as its dependencies become available, it will terminate, call the callbacks, and release dependencies.

An intermediate solution is to define a codelet with its `starpu_codelet::where` field set to `STARPU_NOWHERE`, for instance:

```
struct starpu_codelet cl = {
    .where = STARPU_NOWHERE,
    .nbuffers = 1,
    .modes = { STARPU_R },
}

task = starpu_task_create();
task->cl = &cl;
task->handles[0] = handle;
starpu_task_submit(task);
```

will create a task which simply waits for the value of `handle` to be available for read. This task can then be depended on, etc.

Chapter 7

Data Management

TODO: intro qui parle de coherency entre autres

7.1 Data Interface

StarPU provides several data interfaces for programmers to describe the data layout of their application. There are predefined interfaces already available in StarPU. Users can define new data interfaces as explained in [Defining A New Data Interface](#). All functions provided by StarPU are documented in [Data Interfaces](#). You will find a short list below.

7.1.1 Variable Data Interface

A variable is a given size byte element, typically a scalar. Here an example of how to register a variable data to StarPU by using [starpu_variable_data_register\(\)](#).

```
float var = 42.0;
starpu_data_handle_t var_handle;
starpu_variable_data_register(&var_handle, STARPU_MAIN_RAM, (
    uintptr_t)&var, sizeof(var));
```

7.1.2 Vector Data Interface

A vector is a fixed number of elements of a given size. Here an example of how to register a vector data to StarPU by using [starpu_vector_data_register\(\)](#).

```
float vector[NX];
starpu_data_handle_t vector_handle;
starpu_vector_data_register(&vector_handle, STARPU_MAIN_RAM, (
    uintptr_t)vector, NX, sizeof(vector[0]));
```

7.1.3 Matrix Data Interface

To register 2-D matrices with a potential padding, one can use the matrix data interface. Here an example of how to register a matrix data to StarPU by using [starpu_matrix_data_register\(\)](#).

```
float *matrix;
starpu_data_handle_t matrix_handle;
matrix = (float*)malloc(width * height * sizeof(float));
starpu_matrix_data_register(&matrix_handle, STARPU_MAIN_RAM, (
    uintptr_t)matrix, width, width, height, sizeof(float));
```

7.1.4 Block Data Interface

To register 3-D blocks with potential paddings on Y and Z dimensions, one can use the block data interface. Here an example of how to register a block data to StarPU by using `starpu_block_data_register()`.

```
float *block;
starpu_data_handle_t block_handle;
block = (float*)malloc(nx*ny*nz*sizeof(float));
starpu_block_data_register(&block_handle, STARPU_MAIN_RAM, (
    uintptr_t)block, nx, nx*ny, nx, ny, nz, sizeof(float));
```

7.1.5 BCSR Data Interface

BCSR (Blocked Compressed Sparse Row Representation) sparse matrix data can be registered to StarPU using the bcsr data interface. Here an example on how to do so by using `starpu_bcsr_data_register()`.

```
/*
 * We use the following matrix:
 *
 * +-----+
 * | 0  1  0  0 |
 * | 2  3  0  0 |
 * | 4  5  8  9 |
 * | 6  7 10 11 |
 * +-----+
 *
 * nzval  = [0, 1, 2, 3] ++ [4, 5, 6, 7] ++ [8, 9, 10, 11]
 * colind = [0, 0, 1]
 * rowptr = [0, 1, 3]
 * r = c = 2
 */

/* Size of the blocks */
int R = 2;
int C = 2;

int NROWS = 2;
int NNZ_BLOCKS = 3; /* out of 4 */
int NZVAL_SIZE = (R*C*NNZ_BLOCKS);

int nzval[NZVAL_SIZE] =
{
    0, 1, 2, 3, /* First block */
    4, 5, 6, 7, /* Second block */
    8, 9, 10, 11 /* Third block */
};
uint32_t colind[NNZ_BLOCKS] =
{
    0, /* block-column index for first block in nzval */
    0, /* block-column index for second block in nzval */
    1  /* block-column index for third block in nzval */
};
uint32_t rowptr[NROWS+1] =
{
    0, /* block-index in nzval of the first block of the first row. */
    1, /* block-index in nzval of the first block of the second row. */
    NNZ_BLOCKS /* number of blocks, to allow an easier element's access for the kernels */
};

starpu_data_handle_t bcsr_handle;
starpu_bcsr_data_register(&bcsr_handle,
    STARPU_MAIN_RAM,
    NNZ_BLOCKS,
    NROWS,
    (uintptr_t) nzval,
    colind,
    rowptr,
    0, /* firstentry */
    R,
    C,
    sizeof(nzval[0]));
```

StarPU provides an example on how to deal with such matrices in `examples/spmv`.

7.1.6 CSR Data Interface

TODO

7.2 Data Management

When the application allocates data, whenever possible it should use the `starpu_malloc()` function, which will ask CUDA or OpenCL to make the allocation itself and pin the corresponding allocated memory, or to use the `starpu_memory_pin()` function to pin memory allocated by other ways, such as local arrays. This is needed to permit asynchronous data transfer, i.e. permit data transfer to overlap with computations. Otherwise, the trace will show that the `DriverCopyAsync` state takes a lot of time, this is because CUDA or OpenCL then reverts to synchronous transfers.

By default, StarPU leaves replicates of data wherever they were used, in case they will be re-used by other tasks, thus saving the data transfer time. When some task modifies some data, all the other replicates are invalidated, and only the processing unit which ran this task will have a valid replicate of the data. If the application knows that this data will not be re-used by further tasks, it should advise StarPU to immediately replicate it to a desired list of memory nodes (given through a bitmask). This can be understood like the write-through mode of CPU caches.

```
starpu_data_set_wt_mask(img_handle, 1<<0);
```

will for instance request to always automatically transfer a replicate into the main memory (node 0), as bit 0 of the write-through bitmask is being set.

```
starpu_data_set_wt_mask(img_handle, ~0U);
```

will request to always automatically broadcast the updated data to all memory nodes.

Setting the write-through mask to `~0U` can also be useful to make sure all memory nodes always have a copy of the data, so that it is never evicted when memory gets scarce.

Implicit data dependency computation can become expensive if a lot of tasks access the same piece of data. If no dependency is required on some piece of data (e.g. because it is only accessed in read-only mode, or because write accesses are actually commutative), use the function `starpu_data_set_sequential_consistency_flag()` to disable implicit dependencies on this data.

In the same vein, accumulation of results in the same data can become a bottleneck. The use of the mode `STARPU_REDUX` permits to optimize such accumulation (see [Data Reduction](#)). To a lesser extent, the use of the flag `STARPU_COMMUTE` keeps the bottleneck (see [Commute Data Access](#)), but at least permits the accumulation to happen in any order.

Applications often need a data just for temporary results. In such a case, registration can be made without an initial value, for instance this produces a vector data:

```
starpu_vector_data_register(&handle, -1, 0, n, sizeof(float));
```

StarPU will then allocate the actual buffer only when it is actually needed, e.g. directly on the GPU without allocating in main memory.

In the same vein, once the temporary results are not useful any more, the data should be thrown away. If the handle is not to be reused, it can be unregistered:

```
starpu_data_unregister_submit(handle);
```

actual unregistration will be done after all tasks working on the handle terminate.

If the handle is to be reused, instead of unregistering it, it can simply be invalidated:

```
starpu_data_invalidate_submit(handle);
```

the buffers containing the current value will then be freed, and reallocated only when another task writes some value to the handle.

7.3 Data Prefetch

The scheduling policies `heft`, `dmda` and `pheft` perform data prefetch (see [STARPU_PREFETCH](#)): as soon as a scheduling decision is taken for a task, requests are issued to transfer its required data to the target processing unit, if needed, so that when the processing unit actually starts the task, its data will hopefully be already available and it will not have to wait for the transfer to finish.

The application may want to perform some manual prefetching, for several reasons such as excluding initial data transfers from performance measurements, or setting up an initial statically-computed data distribution on the machine before submitting tasks, which will thus guide StarPU toward an initial task distribution (since StarPU will try to avoid further transfers).

This can be achieved by giving the function [starpu_data_prefetch_on_node\(\)](#) the handle and the desired target memory node. The [starpu_data_idle_prefetch_on_node\(\)](#) variant can be used to issue the transfer only when the bus is idle.

Conversely, one can advise StarPU that some data will not be useful in the close future by calling [starpu_data_wont_use\(\)](#). StarPU will then write its value back to its home node, and evict it from GPUs when room is needed.

7.4 Partitioning Data

An existing piece of data can be partitioned in sub parts to be used by different tasks, for instance:

```
#define NX 1048576
#define PARTS 16
int vector[NX];
starpu_data_handle_t handle;

/* Declare data to StarPU */
starpu_vector_data_register(&handle, STARPU_MAIN_RAM, (uintptr_t)
    vector,
    NX, sizeof(vector[0]));

/* Partition the vector in PARTS sub-vectors */
struct starpu_data_filter f =
{
    .filter_func = starpu_vector_filter_block,
    .nchildren = PARTS
};
starpu_data_partition(handle, &f);
```

The task submission then uses the function [starpu_data_get_sub_data\(\)](#) to retrieve the sub-handles to be passed as tasks parameters.

```
/* Submit a task on each sub-vector */
for (i=0; i<starpu_data_get_nb_children(handle); i++) {
    /* Get subdata number i (there is only 1 dimension) */
    starpu_data_handle_t sub_handle = starpu_data_get_sub_data(
        handle, 1, i);
    struct starpu_task *task = starpu_task_create();

    task->handles[0] = sub_handle;
    task->cl = &cl;
    task->synchronous = 1;
    task->cl_arg = &factor;
    task->cl_arg_size = sizeof(factor);

    starpu_task_submit(task);
}
```

Partitioning can be applied several times, see `examples/basic_examples/mult.c` and `examples/filters/`.

Wherever the whole piece of data is already available, the partitioning will be done in-place, i.e. without allocating new buffers but just using pointers inside the existing copy. This is particularly important to be aware of when using OpenCL, where the kernel parameters are not pointers, but `cl_mem` handles. The kernel thus needs to be also passed the offset within the OpenCL buffer:

```
void openc1_func(void *buffers[], void *cl_arg)
{
    cl_mem vector = (cl_mem) STARPU_VECTOR_GET_DEV_HANDLE(buffers[0]);
    unsigned offset = STARPU_BLOCK_GET_OFFSET(buffers[0]);

    ...
    clSetKernelArg(kernel, 0, sizeof(vector), &vector);
    clSetKernelArg(kernel, 1, sizeof(offset), &offset);
    ...
}
```

And the kernel has to shift from the pointer passed by the OpenCL driver:

```
__kernel void openc1_kernel(__global int *vector, unsigned offset)
{
    block = (__global void *)block + offset;
    ...
}
```

StarPU provides various interfaces and filters for matrices, vectors, etc., but applications can also write their own data interfaces and filters, see `examples/interface` and `examples/filters/custom_mf` for an example, and see [Defining A New Data Interface](#) and [Defining A New Data Filter](#) for documentation.

7.5 Asynchronous Partitioning

The partitioning functions described in the previous section are synchronous: `starpu_data_partition()` and `starpu_data_unpartition()` both wait for all the tasks currently working on the data. This can be a bottleneck for the application.

An asynchronous API also exists, it works only on handles with sequential consistency. The principle is to first plan the partitioning, which returns data handles of the partition, which are not functional yet. Along other task submission, one can submit the actual partitioning, and then use the handles of the partition. Before using the handle of the whole data, one has to submit the unpartitioning. `fmultiple_submit` is a complete example using this technique.

In short, we first register a matrix and plan the partitioning:

```
starpu_matrix_data_register(&handle, STARPU_MAIN_RAM, (uintptr_t)
    matrix, NX, NX, NY, sizeof(matrix[0]));
struct starpu_data_filter f_vert =
{
    .filter_func = starpu_matrix_filter_block,
    .nchildren = PARTS
};
starpu_data_partition_plan(handle, &f_vert, vert_handle);
```

`starpu_data_partition_plan()` returns the handles for the partition in `vert_handle`.

One can submit tasks working on the main handle, but not yet on the `vert_handle` handles. Now we submit the partitioning:

```
starpu_data_partition_submit(handle, PARTS, vert_handle);
```

And now we can submit tasks working on `vert_handle` handles (and not on the main handle any more). Eventually we want to work on the main handle again, so we submit the unpartitioning:

```
starpu_data_unpartition_submit(handle, PARTS, vert_handle, -1);
```

And now we can submit tasks working on the main handle again.

All this code is asynchronous, just submitting which tasks, partitioning and unpartitioning should be done at runtime.

Planning several partitioning of the same data is also possible, one just has to submit unpartitioning (to get back to the initial handle) before submitting another partitioning.

It is also possible to activate several partitioning at the same time, in read-only mode, by using `starpu_data_partition_readonly_submit()`. A complete example is available in `examples/filters/fmultiple_submit_readonly.c`.

7.6 Manual Partitioning

One can also handle partitioning by hand, by registering several views on the same piece of data. The idea is then to manage the coherency of the various views through the common buffer in the main memory. `fmultiple_manual` is a complete example using this technique.

In short, we first register the same matrix several times:

```
starpu_matrix_data_register(&handle, STARPU_MAIN_RAM, (uintptr_t)
    matrix, NX, NX, NY, sizeof(matrix[0]));

for (i = 0; i < PARTS; i++)
    starpu_matrix_data_register(&vert_handle[i], STARPU_MAIN_RAM
        , (uintptr_t)&matrix[0][i*(NX/PARTS)], NX, NX/PARTS, NY, sizeof(matrix[0][0]));
```

Since StarPU is not aware that the two handles are actually pointing to the same data, we have a danger of inadvertently submitting tasks to both views, which will bring a mess since StarPU will not guarantee any coherency between the two views. To make sure we don't do this, we invalidate the view that we will not use:

```
for (i = 0; i < PARTS; i++)
    starpu_data_invalidate(vert_handle[i]);
```

Then we can safely work on `handle`.

When we want to switch to the vertical slice view, all we need to do is bring coherency between them by running an empty task on the home node of the data:

```
void empty(void *buffers[] STARPU_ATTRIBUTE_UNUSED, void *cl_arg
    STARPU_ATTRIBUTE_UNUSED)
{ }

struct starpu_codelet cl_switch =
{
    .cpu_funcs = {empty},
    .nbuffers = STARPU_VARIABLE_NBUFFERS,
};

ret = starpu_task_insert(&cl_switch, STARPU_RW, handle,
    STARPU_W, vert_handle[0],
    STARPU_W, vert_handle[1],
    0);
```

The execution of the `switch` task will get back the matrix data into the main memory, and thus the vertical slices will get the updated value there.

Again, we prefer to make sure that we don't accidentally access the matrix through the whole-matrix handle:

```
starpu_data_invalidate_submit(handle);
```

And now we can start using vertical slices, etc.

7.7 Defining A New Data Filter

StarPU provides a series of predefined filters in `API_Data_Partition`, but additional filters can be defined by the application. The principle is that the filter function just fills the memory location of the *i*-th subpart of a data. Examples are provided in `src/datawizard/interfaces/*_filters.c`, and see [starpu_data_filter::filter_func](#) for the details.

7.8 Data Reduction

In various cases, some piece of data is used to accumulate intermediate results. For instances, the dot product of a vector, maximum/minimum finding, the histogram of a photograph, etc. When these results are produced along the whole machine, it would not be efficient to accumulate them in only one place, incurring data transmission each and access concurrency.

StarPU provides a mode `STARPU_REDUX`, which permits to optimize this case: it will allocate a buffer on each memory node, and accumulate intermediate results there. When the data is eventually accessed in the normal mode `STARPU_R`, StarPU will collect the intermediate results in just one buffer.

For this to work, the user has to use the function [starpu_data_set_reduction_methods\(\)](#) to declare how to initialize these buffers, and how to assemble partial results.

For instance, `cg` uses that to optimize its dot product: it first defines the codelets for initialization and reduction:

```
struct starpu_codelet bzero_variable_cl =
{
    .cpu_funcs = { bzero_variable_cpu },
    .cpu_funcs_name = { "bzero_variable_cpu" },
    .cuda_funcs = { bzero_variable_cuda },
    .nbuffers = 1,
}

static void accumulate_variable_cpu(void *descr[], void *cl_arg)
{
    double *v_dst = (double *)STARPU_VARIABLE_GET_PTR(descr[0]);
    double *v_src = (double *)STARPU_VARIABLE_GET_PTR(descr[1]);
    *v_dst = *v_dst + *v_src;
}

static void accumulate_variable_cuda(void *descr[], void *cl_arg)
{
    double *v_dst = (double *)STARPU_VARIABLE_GET_PTR(descr[0]);
    double *v_src = (double *)STARPU_VARIABLE_GET_PTR(descr[1]);
    cublasaxpy(1, (double)1.0, v_src, 1, v_dst, 1);
    cudaStreamSynchronize(starpu_cuda_get_local_stream());
}

struct starpu_codelet accumulate_variable_cl =
{
    .cpu_funcs = { accumulate_variable_cpu },
    .cpu_funcs_name = { "accumulate_variable_cpu" },
    .cuda_funcs = { accumulate_variable_cuda },
    .nbuffers = 1,
}
```

and attaches them as reduction methods for its handle `dtq`:

```
starpu_variable_data_register(&dtq_handle, -1, NULL, sizeof(type));
starpu_data_set_reduction_methods(dtq_handle,
    &accumulate_variable_cl, &bzero_variable_cl);
```

and `dtq_handle` can now be used in mode `STARPU_REDUX` for the dot products with partitioned vectors:

```
for (b = 0; b < nblocks; b++)
    starpu_task_insert(&dot_kernel_cl,
        STARPU_REDUX, dtq_handle,
        STARPU_R, starpu_data_get_sub_data(v1, 1, b),
        STARPU_R, starpu_data_get_sub_data(v2, 1, b),
        0);
```

During registration, we have here provided `NULL`, i.e. there is no initial value to be taken into account during reduction. StarPU will thus only take into account the contributions from the tasks `dot_kernel_cl`. Also, it will not allocate any memory for `dtq_handle` before tasks `dot_kernel_cl` are ready to run.

If another dot product has to be performed, one could unregister `dtq_handle`, and re-register it. But one can also call `starpu_data_invalidate_submit()` with the parameter `dtq_handle`, which will clear all data from the handle, thus resetting it back to the initial status `register(NULL)`.

The example `cg` also uses reduction for the blocked `gemv` kernel, leading to yet more relaxed dependencies and more parallelism.

`STARPU_REDUX` can also be passed to `starpu_mpi_task_insert()` in the MPI case. This will however not produce any MPI communication, but just pass `STARPU_REDUX` to the underlying `starpu_task_insert()`. It is up to the application to call `starpu_mpi_redux_data()`, which posts tasks which will reduce the partial results among MPI nodes into the MPI node which owns the data. For instance, some hypothetical application which collects partial results into data `res`, then uses it for other computation, before looping again with a new reduction:

```
for (i = 0; i < 100; i++) {
    starpu_mpi_task_insert(MPI_COMM_WORLD, &init_res, STARPU_W, res, 0);
    starpu_mpi_task_insert(MPI_COMM_WORLD, &work, STARPU_RW, A,
        STARPU_R, B, STARPU_REDUX, res, 0);
    starpu_mpi_redux_data(MPI_COMM_WORLD, res);
    starpu_mpi_task_insert(MPI_COMM_WORLD, &work2, STARPU_RW, B, STARPU_R,
        res, 0);
}
```

7.9 Commute Data Access

By default, the implicit dependencies computed from data access use the sequential semantic. Notably, write accesses are always serialized in the order of submission. In some applicative cases, the write contributions can actually be performed in any order without affecting the eventual result. In this case it is useful to drop the strictly sequential semantic, to improve parallelism by allowing StarPU to reorder the write accesses. This can be done by using the `STARPU_COMMUTE` data access flag. Accesses without this flag will however properly be serialized against accesses with this flag. For instance:

```
starpu_task_insert(&c11,
    STARPU_R, h,
    STARPU_RW, handle,
    0);
starpu_task_insert(&c12,
    STARPU_R, handle1,
    STARPU_RW|STARPU_COMMUTE, handle,
    0);
starpu_task_insert(&c12,
    STARPU_R, handle2,
    STARPU_RW|STARPU_COMMUTE, handle,
    0);
starpu_task_insert(&c13,
    STARPU_R, g,
    STARPU_RW, handle,
    0);
```

The two tasks running `c12` will be able to commute: depending on whether the value of `handle1` or `handle2` becomes available first, the corresponding task running `c12` will start first. The task running `c11` will however always be run before them, and the task running `c13` will always be run after them.

If a lot of tasks use the commute access on the same set of data and a lot of them are ready at the same time, it may become interesting to use an arbiter, see [Concurrent Data Accesses](#).

7.10 Concurrent Data Accesses

When several tasks are ready and will work on several data, StarPU is faced with the classical Dining Philosophers problem, and has to determine the order in which it will run the tasks.

Data accesses usually use sequential ordering, so data accesses are usually already serialized, and thus by default StarPU uses the Dijkstra solution which scales very well in terms of overhead: tasks will just acquire data one by one by data handle pointer value order.

When sequential ordering is disabled or the `STARPU_COMMUTE` flag is used, there may be a lot of concurrent accesses to the same data, and the Dijkstra solution gets only poor parallelism, typically in some pathological cases which do happen in various applications. In this case, one can use a data access arbiter, which implements the classical centralized solution for the Dining Philosophers problem. This is more expensive in terms of overhead since it is centralized, but it opportunisticly gets a lot of parallelism. The centralization can also be avoided by using several arbiters, thus separating sets of data for which arbitration will be done. If a task accesses data from different arbiters, it will acquire them arbiter by arbiter, in arbiter pointer value order.

See the `tests/datawizard/test_arbiter.cpp` example.

Arbiters however do not support the `STARPU_REDUX` flag yet.

7.11 Temporary Buffers

There are two kinds of temporary buffers: temporary data which just pass results from a task to another, and scratch data which are needed only internally by tasks.

7.11.1 Temporary Data

Data can sometimes be entirely produced by a task, and entirely consumed by another task, without the need for other parts of the application to access it. In such case, registration can be done without prior allocation, by using the special memory node number `-1`, and passing a zero pointer. StarPU will actually allocate memory only when the task creating the content gets scheduled, and destroy it on unregistration.

In addition to this, it can be tedious for the application to have to unregister the data, since it will not use its content anyway. The unregistration can be done lazily by using the function `starpu_data_unregister_submit()`, which will record that no more tasks accessing the handle will be submitted, so that it can be freed as soon as the last task accessing it is over.

The following code exemplifies both points: it registers the temporary data, submits three tasks accessing it, and records the data for automatic unregistration.

```
starpu_vector_data_register(&handle, -1, 0, n, sizeof(float));
starpu_task_insert(&produce_data, STARPU_W, handle, 0);
starpu_task_insert(&compute_data, STARPU_RW, handle, 0);
starpu_task_insert(&summarize_data, STARPU_R, handle, STARPU_W,
    result_handle, 0);
starpu_data_unregister_submit(handle);
```

The application may also want to see the temporary data initialized on the fly before being used by the task. This can be done by using `starpu_data_set_reduction_methods()` to set an initialization codelet (no redux codelet is needed).

7.11.2 Scratch Data

Some kernels sometimes need temporary data to achieve the computations, i.e. a workspace. The application could allocate it at the start of the codelet function, and free it at the end, but this would be costly. It could also allocate one buffer per worker (similarly to [How To Initialize A Computation Library Once For Each Worker?](#)), but this would make them systematic and permanent. A more optimized way is to use the data access mode `STARPU_SCRATCH`, as exemplified below, which provides per-worker buffers without content consistency. The buffer is registered only once, using memory node `-1`, i.e. the application didn't allocate memory for it, and StarPU will allocate it on demand at task execution.

```
starpu_vector_data_register(&workspace, -1, 0, sizeof(float));
for (i = 0; i < N; i++)
    starpu_task_insert(&compute, STARPU_R, input[i],
                      STARPU_SCRATCH, workspace, STARPU_W, output[i], 0);
```

StarPU will make sure that the buffer is allocated before executing the task, and make this allocation per-worker: for CPU workers, notably, each worker has its own buffer. This means that each task submitted above will actually have its own workspace, which will actually be the same for all tasks running one after the other on the same worker. Also, if for instance memory becomes scarce, StarPU will notice that it can free such buffers easily, since the content does not matter.

The example `examples/pi` uses scratches for some temporary buffer.

7.12 The Multiformat Interface

It may be interesting to represent the same piece of data using two different data structures: one only used on CPUs, and one only used on GPUs. This can be done by using the multiformat interface. StarPU will be able to convert data from one data structure to the other when needed. Note that the scheduler `dmda` is the only one optimized for this interface. The user must provide StarPU with conversion codelets:

```
#define NX 1024
struct point array_of_structs[NX];
starpu_data_handle_t handle;

/*
 * The conversion of a piece of data is itself a task, though it is created,
 * submitted and destroyed by StarPU internals and not by the user. Therefore,
 * we have to define two codelets.
 * Note that for now the conversion from the CPU format to the GPU format has to
 * be executed on the GPU, and the conversion from the GPU to the CPU has to be
 * executed on the CPU.
 */
#ifdef STARPU_USE_OPENCL
void cpu_to_opengl_opengl_func(void *buffers[], void *args);
struct starpu_codelet cpu_to_opengl_cl = {
    .where = STARPU_OPENGL,
    .opengl_funcs = { cpu_to_opengl_opengl_func },
    .nbuffers = 1,
    .modes = { STARPU_RW }
};

void opengl_to_cpu_func(void *buffers[], void *args);
struct starpu_codelet opengl_to_cpu_cl = {
    .where = STARPU_CPU,
    .cpu_funcs = { opengl_to_cpu_func },
    .cpu_funcs_name = { "opengl_to_cpu_func" },
    .nbuffers = 1,
    .modes = { STARPU_RW }
};
#endif

struct starpu_multiformat_data_interface_ops format_ops = {
#ifdef STARPU_USE_OPENCL
    .opengl_elsize = 2 * sizeof(float),
    .cpu_to_opengl_cl = &cpu_to_opengl_cl,
    .opengl_to_cpu_cl = &opengl_to_cpu_cl,
#endif
    .cpu_elsize = 2 * sizeof(float),
    ...
};

starpu_multiformat_data_register(handle, STARPU_MAIN_RAM, &
    array_of_structs, NX, &format_ops);
```

Kernels can be written almost as for any other interface. Note that `STARPU_MULTIFORMAT_GET_CPU_PTR` shall only be used for CPU kernels. CUDA kernels must use `STARPU_MULTIFORMAT_GET_CUDA_PTR`, and OpenCL kernels must use `STARPU_MULTIFORMAT_GET_OPENCL_PTR`. `STARPU_MULTIFORMAT_GET_NX` may be used in any kind of kernel.

```
static void
multiformat_scal_cpu_func(void *buffers[], void *args)
{
    struct point *aos;
    unsigned int n;

    aos = STARPU_MULTIFORMAT_GET_CPU_PTR(buffers[0]);
    n = STARPU_MULTIFORMAT_GET_NX(buffers[0]);
    ...
}

extern "C" void multiformat_scal_cuda_func(void *buffers[], void *_args)
{
    unsigned int n;
    struct struct_of_arrays *soa;

    soa = (struct struct_of_arrays *) STARPU_MULTIFORMAT_GET_CUDA_PTR(
        buffers[0]);
    n = STARPU_MULTIFORMAT_GET_NX(buffers[0]);
    ...
}
```

A full example may be found in `examples/basic_examples/multiformat.c`.

7.13 Defining A New Data Interface

Let's define a new data interface to manage complex numbers.

```
/* interface for complex numbers */
struct starpu_complex_interface
{
    double *real;
    double *imaginary;
    int nx;
};
```

Registering such a data to StarPU is easily done using the function `starpu_data_register()`. The last parameter of the function, `interface_complex_ops`, will be described below.

```
void starpu_complex_data_register(starpu_data_handle_t *handle,
    unsigned home_node, double *real, double *imaginary, int nx)
{
    struct starpu_complex_interface complex =
    {
        .real = real,
        .imaginary = imaginary,
        .nx = nx
    };

    if (interface_complex_ops.interfaceid == STARPU_UNKNOWN_INTERFACE_ID)
    {
        interface_complex_ops.interfaceid = starpu_data_interface_get_next_id(
        );
    }

    starpu_data_register(handleptr, home_node, &complex, &interface_complex_ops);
}
```

Different operations need to be defined for a data interface through the type `starpu_data_interface_ops`. We only define here the basic operations needed to run simple applications. The source code for the different functions can be found in the file `examples/interface/complex_interface.c`, the details of the hooks to be provided are documented `starpu_data_interface_ops`.

```
static struct starpu_data_interface_ops interface_complex_ops =
{
    .register_data_handle = complex_register_data_handle,
    .allocate_data_on_node = complex_allocate_data_on_node,
    .copy_methods = &complex_copy_methods,
    .get_size = complex_get_size,
    .footprint = complex_footprint,
    .interfaceid = STARPU_UNKNOWN_INTERFACE_ID,
    .interface_size = sizeof(struct starpu_complex_interface),
};
```

Functions need to be defined to access the different fields of the complex interface from a StarPU data handle.

```
double *starpu_complex_get_real(starpu_data_handle_t handle)
{
    struct starpu_complex_interface *complex_interface =
        (struct starpu_complex_interface *) starpu_data_get_interface_on_node
        (handle, STARPU_MAIN_RAM);
    return complex_interface->real;
}

double *starpu_complex_get_imaginary(starpu_data_handle_t handle);
int starpu_complex_get_nx(starpu_data_handle_t handle);
```

Similar functions need to be defined to access the different fields of the complex interface from a `void *` pointer to be used within codelet implementations.

```
#define STARPU_COMPLEX_GET_REAL(interface) \
    (((struct starpu_complex_interface *) (interface))->real)
#define STARPU_COMPLEX_GET_IMAGINARY(interface) \
    (((struct starpu_complex_interface *) (interface))->imaginary)
#define STARPU_COMPLEX_GET_NX(interface) \
    (((struct starpu_complex_interface *) (interface))->nx)
```

Complex data interfaces can then be registered to StarPU.

```
double real = 45.0;
double imaginary = 12.0;
starpu_complex_data_register(&handle1, STARPU_MAIN_RAM, &real, &imaginary, 1);
starpu_task_insert(&cl_display, STARPU_R, handle1, 0);
```

and used by codelets.

```
void display_complex_codelet(void *descr[], __attribute__((unused)) void *_args)
{
    int nx = STARPU_COMPLEX_GET_NX(descr[0]);
    double *real = STARPU_COMPLEX_GET_REAL(descr[0]);
    double *imaginary = STARPU_COMPLEX_GET_IMAGINARY(descr[0]);
    int i;

    for(i=0 ; i<nx ; i++)
    {
        fprintf(stderr, "Complex[%d] = %3.2f + %3.2f i\n", i, real[i], imaginary[i]);
    }
}
```

The whole code for this complex data interface is available in the directory `examples/interface/`.

7.14 Specifying A Target Node For Task Data

When executing a task on a GPU for instance, StarPU would normally copy all the needed data for the tasks on the embedded memory of the GPU. It may however happen that the task kernel would rather have some of the datas kept in the main memory instead of copied in the GPU, a pivoting vector for instance. This can be achieved by setting the `starpu_codelet::specific_nodes` flag to 1, and then fill the `starpu_codelet::nodes` array (or `starpu_codelet::dyn_nodes` when `starpu_codelet::nbuffers` is greater than `STARPU_NMAXBUFS`) with the node numbers where data should be copied to, or -1 to let StarPU copy it to the memory node where the task will be executed. For instance, with the following codelet:

```
struct starpu_codelet cl =
{
    .cuda_funcs = { kernel },
    .nbuffers = 2,
    .modes = { STARPU_RW, STARPU_RW },
    .specific_nodes = 1,
    .nodes = { STARPU_MAIN_RAM, -1 },
};
```

the first data of the task will be kept in the main memory, while the second data will be copied to the CUDA GPU as usual. A working example is available in `tests/datawizard/specific_node.c`

Chapter 8

Scheduling

8.1 Task Scheduling Policies

The basics of the scheduling policy are the following:

- The scheduler gets to schedule tasks (`push` operation) when they become ready to be executed, i.e. they are not waiting for some tags, data dependencies or task dependencies.
- Workers pull tasks (`pop` operation) one by one from the scheduler.

This means scheduling policies usually contain at least one queue of tasks to store them between the time when they become available, and the time when a worker gets to grab them.

By default, StarPU uses the simple greedy scheduler `eager`. This is because it provides correct load balance even if the application codelets do not have performance models. Other non-modelling scheduling policies can be selected among the list below, thanks to the environment variable `STARPU_SCHED`. For instance `export STARPU_SCHED=dmda`. Use `help` to get the list of available schedulers.

Non Performance Modelling Policies:

The **eager** scheduler uses a central task queue, from which all workers draw tasks to work on concurrently. This however does not permit to prefetch data since the scheduling decision is taken late. If a task has a non-0 priority, it is put at the front of the queue.

The **random** scheduler uses a queue per worker, and distributes tasks randomly according to assumed worker overall performance.

The **ws** (work stealing) scheduler uses a queue per worker, and schedules a task on the worker which released it by default. When a worker becomes idle, it steals a task from the most loaded worker.

The **lws** (locality work stealing) scheduler uses a queue per worker, and schedules a task on the worker which released it by default. When a worker becomes idle, it steals a task from neighbour workers. It also takes into account priorities.

The **prio** scheduler also uses a central task queue, but sorts tasks by priority specified by the programmer (between -5 and 5).

8.2 Performance Model-Based Task Scheduling Policies

If (**and only if**) your application **codelets have performance models** ([Performance Model Example](#)), you should change the scheduler thanks to the environment variable `STARPU_SCHED`, to select one of the policies below, in order to take advantage of StarPU's performance modelling. For instance `export STARPU_SCHED=dmda`. Use `help` to get the list of available schedulers.

Note: Depending on the performance model type chosen, some preliminary calibration runs may be needed for the model to converge. If the calibration has not been done, or is insufficient yet, or if no performance model is specified for a codelet, every task built from this codelet will be scheduled using an **eager** fallback policy.

Troubleshooting: Configuring and recompiling StarPU using the `-enable-verbose` configure flag displays some statistics at the end of execution about the percentage of tasks which have been scheduled by a DM* family policy using performance model hints. A low or zero percentage may be the sign that performance models are not converging or that codelets do not have performance models enabled.

Performance Modelling Policies:

The **dm** (deque model) scheduler takes task execution performance models into account to perform a HEFT-similar scheduling strategy: it schedules tasks where their termination time will be minimal. The difference with HEFT is that **dm** schedules tasks as soon as they become available, and thus in the order they become available, without taking priorities into account.

The **dmda** (deque model data aware) scheduler is similar to dm, but it also takes into account data transfer time.

The **dmdar** (deque model data aware ready) scheduler is similar to dmda, but it also privileges tasks whose data buffers are already available on the target device.

The **dmdas** (deque model data aware sorted) scheduler is similar to dmdar, except that it sorts tasks by priority order, which allows to become even closer to HEFT by respecting priorities after having made the scheduling decision (but it still schedules tasks in the order they become available).

The **dmdasd** (deque model data aware sorted decision) scheduler is similar to dmdas, except that when scheduling a task, it takes into account its priority when computing the minimum completion time, since this task may get executed before others, and thus the latter should be ignored.

The **heft** (heterogeneous earliest finish time) scheduler is a deprecated alias for **dmda**.

The **pheft** (parallel HEFT) scheduler is similar to dmda, it also supports parallel tasks (still experimental). Should not be used when several contexts using it are being executed simultaneously.

The **peager** (parallel eager) scheduler is similar to eager, it also supports parallel tasks (still experimental). Should not be used when several contexts using it are being executed simultaneously.

TODO: describe modular schedulers

8.3 Task Distribution Vs Data Transfer

Distributing tasks to balance the load induces data transfer penalty. StarPU thus needs to find a balance between both. The target function that the scheduler dmda of StarPU tries to minimize is $\alpha * T_{\text{execution}} + \beta * T_{\text{data_transfer}}$, where $T_{\text{execution}}$ is the estimated execution time of the codelet (usually accurate), and $T_{\text{data_transfer}}$ is the estimated data transfer time. The latter is estimated based on bus calibration before execution start, i.e. with an idle machine, thus without contention. You can force bus re-calibration by running the tool `starpu_calibrate_bus`. The beta parameter defaults to 1, but it can be worth trying to tweak it by using `export STARPU_SCHED_BETA=2` ([STARPU_SCHED_BETA](#)) for instance, since during real application execution, contention makes transfer times bigger. This is of course imprecise, but in practice, a rough estimation already gives the good results that a precise estimation would give.

8.4 Energy-based Scheduling

If the application can provide some energy consumption performance model (through the field `starpu_codelet::energy_model`), StarPU will take it into account when distributing tasks. The target function that the scheduler dmda minimizes becomes $\alpha * T_{\text{execution}} + \beta * T_{\text{data_transfer}} + \gamma * \text{Consumption}$, where `Consumption` is the estimated task consumption in Joules. To tune this parameter, use `export STARPU_SCHED_GAMMA=3000` (`STARPU_SCHED_GAMMA`) for instance, to express that each Joule (i.e kW during 1000us) is worth 3000us execution time penalty. Setting `alpha` and `beta` to zero permits to only take into account energy consumption.

This is however not sufficient to correctly optimize energy: the scheduler would simply tend to run all computations on the most energy-conservative processing unit. To account for the consumption of the whole machine (including idle processing units), the idle power of the machine should be given by setting `export STARPU_IDLE_POWER=200` (`STARPU_IDLE_POWER`) for 200W, for instance. This value can often be obtained from the machine power supplier.

The energy actually consumed by the total execution can be displayed by setting `export STARPU_PROFILING=1 STARPU_WORKER_STATS=1`.

On-line task consumption measurement is currently only supported through the `CL_PROFILING_POWER_CONSUMED` OpenCL extension, implemented in the Movisim simulator. Applications can however provide explicit measurements by using the function `starpu_perfmodel_update_history()` (exemplified in [Performance Model Example](#) with the `energy_model` performance model). Fine-grain measurement is often not feasible with the feedback provided by the hardware, so the user can for instance run a given task a thousand times, measure the global consumption for that series of tasks, divide it by a thousand, repeat for varying kinds of tasks and task sizes, and eventually feed StarPU with these manual measurements through `starpu_perfmodel_update_history()`. For instance, for CUDA devices, `nvidia-smi -q -d POWER` can be used to get the current consumption in Watt. Multiplying this value by the average duration of a single task gives the consumption of the task in Joules, which can be given to `starpu_perfmodel_update_history()`.

8.5 Static Scheduling

In some cases, one may want to force some scheduling, for instance force a given set of tasks to GPU0, another set to GPU1, etc. while letting some other tasks be scheduled on any other device. This can indeed be useful to guide StarPU into some work distribution, while still letting some degree of dynamism. For instance, to force execution of a task on CUDA0:

```
task->execute_on_a_specific_worker = 1;
task->workerid = starpu_worker_get_by_type(STARPU_CUDA_WORKER, 0);
```

One can also specify the order in which tasks must be executed by setting the `starpu_task::workerorder` field. If this field is set to a non-zero value, it provides the per-worker consecutive order in which tasks will be executed, starting from 1. For a given of such task, the worker will thus not execute it before all the tasks with smaller order value have been executed, notably in case those tasks are not available yet due to some dependencies. This eventually gives total control of task scheduling, and StarPU will only serve as a "self-timed" task runtime. Of course, the provided order has to be runnable, i.e. a task should not depend on another task bound to the same worker with a bigger order.

Note however that using scheduling contexts while statically scheduling tasks on workers could be tricky. Be careful to schedule the tasks exactly on the workers of the corresponding contexts, otherwise the workers' corresponding scheduling structures may not be allocated or the execution of the application may deadlock. Moreover, the hypervisor should not be used when statically scheduling tasks.

8.6 Defining A New Scheduling Policy

A full example showing how to define a new scheduling policy is available in the StarPU sources in the directory `examples/scheduler/`.

The scheduler has to provide methods:

```
static struct starpu_sched_policy dummy_sched_policy = {
    .init_sched = init_dummy_sched,
    .deinit_sched = deinit_dummy_sched,
    .add_workers = dummy_sched_add_workers,
    .remove_workers = dummy_sched_remove_workers,
    .push_task = push_task_dummy,
    .pop_task = pop_task_dummy,
    .policy_name = "dummy",
    .policy_description = "dummy scheduling strategy"
};
```

The idea is that when a task becomes ready for execution, the `starpu_sched_policy::push_task` method is called. When a worker is idle, the `starpu_sched_policy::pop_task` method is called to get a task. It is up to the scheduler to implement what is between. A simple eager scheduler is for instance to make `starpu_sched_policy::push_task` push the task to a global list, and make `starpu_sched_policy::pop_task` pop from this list.

The `starpu_sched_policy` section provides the exact rules that govern the methods of the policy.

Make sure to have a look at the [Scheduling Policy](#) section, which provides a list of the available functions for writing advanced schedulers, such as `starpu_task_expected_length()`, `starpu_task_expected_data_transfer_time()`, `starpu_task_expected_energy()`, etc. Other useful functions include `starpu_transfer_bandwidth()`, `starpu_transfer_latency()`, `starpu_transfer_predict()`, ...

Usual functions can also be used on tasks, for instance one can do

```
size = 0;
write = 0;
if (task->cl)
    for (i = 0; i < STARPU_TASK_GET_NBUFFERS(task); i++)
    {
        starpu_data_handle_t data = STARPU_TASK_GET_HANDLE(task,
            i);
        size_t datasize = starpu_data_get_size(data);
        size += datasize;
        if (STARPU_TASK_GET_MODE(task, i) & STARPU_W)
            write += datasize;
    }
```

And various queues can be used in schedulers. A variety of examples of schedulers can be read in `src/sched_policies`, for instance `random_policy.c`, `eager_central_policy.c`, `work_stealing_policy.c`.

8.7 Graph-based Scheduling

For performance reasons, most of the schedulers shipped with StarPU use simple list-scheduling heuristics, assuming that the application has already set priorities. This is why they do their scheduling between when tasks become available for execution and when a worker becomes idle, without looking at the task graph.

Other heuristics can however look at the task graph. Recording the task graph is expensive, so it is not available by default, the scheduling heuristic has to set `_starpu_graph_record` to 1 from the initialization function, to make it available. Then the `_starpu_graph*` functions can be used.

`src/sched_policies/graph_test_policy.c` is an example of simple greedy policy which automatically computes priorities by bottom-up rank.

The idea is that while the application submits tasks, they are only pushed to a bag of tasks. When the application is finished with submitting tasks, it calls `starpu_do_schedule()` (or `starpu_task_wait_for_all()`, which calls `starpu_do_schedule()`), and the `starpu_sched_policy::do_schedule` method of the scheduler is called. This method calls `_starpu_graph_compute_depths` to compute the bottom-up ranks, and then uses these rank to set priorities over tasks.

It then has two priority queues, one for CPUs, and one for GPUs, and uses a dumb heuristic based on the duration of the task over CPUs and GPUs to decide between the two queues. CPU workers can then pop from the CPU priority queue, and GPU workers from the GPU priority queue.

8.8 Debugging Scheduling

All the [Online Performance Tools](#) and [Offline Performance Tools](#) can be used to get information about how well the execution proceeded, and thus the overall quality of the execution.

Precise debugging can also be performed by using the `STARPU_TASK_BREAK_ON_PUSH`, `STARPU_TASK_BREAK_ON_SCHED`, `STARPU_TASK_BREAK_ON_POP`, and `STARPU_TASK_BREAK_ON_EXEC` environment variables. By setting the `job_id` of a task in these environment variables, StarPU will raise `SIGTRAP` when the task is being scheduled, pushed, or popped by the scheduler. This means that when one notices that a task is being scheduled in a seemingly odd way, one can just reexecute the application in a debugger, with some of those variables set, and the execution will stop exactly at the scheduling points of this task, thus allowing to inspect the scheduler state, etc.

Chapter 9

Scheduling Contexts

TODO: improve!

9.1 General Ideas

Scheduling contexts represent abstracts sets of workers that allow the programmers to control the distribution of computational resources (i.e. CPUs and GPUs) to concurrent parallel kernels. The main goal is to minimize interferences between the execution of multiple parallel kernels, by partitioning the underlying pool of workers using contexts.

9.2 Creating A Context

By default, the application submits tasks to an initial context, which disposes of all the computation resources available to StarPU (all the workers). If the application programmer plans to launch several parallel kernels simultaneously, by default these kernels will be executed within this initial context, using a single scheduler policy(see [Task Scheduling Policies](#)). Meanwhile, if the application programmer is aware of the demands of these kernels and of the specificity of the machine used to execute them, the workers can be divided between several contexts. These scheduling contexts will isolate the execution of each kernel and they will permit the use of a scheduling policy proper to each one of them.

Scheduling Contexts may be created in two ways: either the programmers indicates the set of workers corresponding to each context (providing he knows the identifiers of the workers running within StarPU), or the programmer does not provide any worker list and leaves the Hypervisor assign workers to each context according to their needs ([Scheduling Context Hypervisor](#))

Both cases require a call to the function `starpu_sched_ctx_create()`, which requires as input the worker list (the exact list or a NULL pointer) and the scheduling policy. The latter one can be a character list corresponding to the name of a StarPU predefined policy or the pointer to a custom policy. The function returns an identifier of the context created which you will use to indicate the context you want to submit the tasks to.

```
/* the list of resources the context will manage */
int workerids[3] = {1, 3, 10};

/* indicate the scheduling policy to be used within the context, the list of
workers assigned to it, the number of workers, the name of the context */
int id_ctx = starpu_sched_ctx_create("dmda", workerids, 3, "my_ctx");

/* let StarPU know that the following tasks will be submitted to this context */
starpu_sched_ctx_set_task_context(id);

/* submit the task to StarPU */
starpu_task_submit(task);
```

Note: Parallel greedy and parallel heft scheduling policies do not support the existence of several disjoint contexts on the machine. Combined workers are constructed depending on the entire topology of the machine, not only the one belonging to a context.

9.3 Modifying A Context

A scheduling context can be modified dynamically. The application may change its requirements during the execution and the programmer can add additional workers to a context or remove if no longer needed. In the following example we have two scheduling contexts `sched_ctx1` and `sched_ctx2`. After executing a part of the tasks some of the workers of `sched_ctx1` will be moved to context `sched_ctx2`.

```
/* the list of ressources that context 1 will give away */
int workerids[3] = {1, 3, 10};

/* add the workers to context 1 */
starpu_sched_ctx_add_workers(workerids, 3, sched_ctx2);

/* remove the workers from context 2 */
starpu_sched_ctx_remove_workers(workerids, 3, sched_ctx1);
```

9.4 Submitting Tasks To A Context

The application may submit tasks to several contexts either simultaneously or sequentially. If several threads of submission are used the function `starpu_sched_ctx_set_context()` may be called just before `starpu_task_submit()`. Thus StarPU considers that the current thread will submit tasks to the corresponding context.

When the application may not assign a thread of submission to each context, the id of the context must be indicated by using the function `starpu_task_submit_to_ctx()` or the field `STARPU_SCHED_CTX` for `starpu_task_insert()`.

9.5 Deleting A Context

When a context is no longer needed it must be deleted. The application can indicate which context should keep the resources of a deleted one. All the tasks of the context should be executed before doing this. Thus, the programmer may use either a barrier and then delete the context directly, or just indicate that other tasks will not be submitted later on to the context (such that when the last task is executed its workers will be moved to the inheritor) and delete the context at the end of the execution (when a barrier will be used eventually).

```
/* when the context 2 is deleted context 1 inherits its resources */
starpu_sched_ctx_set_inheritor(sched_ctx2, sched_ctx1);

/* submit tasks to context 2 */
for (i = 0; i < ntasks; i++)
    starpu_task_submit_to_ctx(task[i], sched_ctx2);

/* indicate that context 2 finished submitting and that */
/* as soon as the last task of context 2 finished executing */
/* its workers can be moved to the inheritor context */
starpu_sched_ctx_finished_submit(sched_ctx2);

/* wait for the tasks of both contexts to finish */
starpu_task_wait_for_all();

/* delete context 2 */
starpu_sched_ctx_delete(sched_ctx2);

/* delete context 1 */
starpu_sched_ctx_delete(sched_ctx1);
```

9.6 Emptying A Context

A context may have no resources at the beginning or at a certain moment of the execution. Task can still be submitted to these contexts and they will be executed as soon as the contexts will have resources. A list of tasks pending to be executed is kept and when workers are added to the contexts these tasks start being submitted. However, if resources are never allocated to the context the program will not terminate. If these tasks have low priority the programmer can forbid the application to submit them by calling the function `starpu_sched_ctx_stop_task_submission()`.

Chapter 10

Scheduling Context Hypervisor

10.1 What Is The Hypervisor

StarPU proposes a platform to construct Scheduling Contexts, to delete and modify them dynamically. A parallel kernel, can thus be isolated into a scheduling context and interferences between several parallel kernels are avoided. If users know exactly how many workers each scheduling context needs, they can assign them to the contexts at their creation time or modify them during the execution of the program.

The Scheduling Context Hypervisor Plugin is available for users who do not dispose of a regular parallelism, who cannot know in advance the exact size of the context and need to resize the contexts according to the behavior of the parallel kernels.

The Hypervisor receives information from StarPU concerning the execution of the tasks, the efficiency of the resources, etc. and it decides accordingly when and how the contexts can be resized. Basic strategies of resizing scheduling contexts already exist but a platform for implementing additional custom ones is available.

10.2 Start the Hypervisor

The Hypervisor must be initialized once at the beginning of the application. At this point a resizing policy should be indicated. This strategy depends on the information the application is able to provide to the hypervisor as well as on the accuracy needed for the resizing procedure. For example, the application may be able to provide an estimation of the workload of the contexts. In this situation the hypervisor may decide what resources the contexts need. However, if no information is provided the hypervisor evaluates the behavior of the resources and of the application and makes a guess about the future. The hypervisor resizes only the registered contexts.

10.3 Interrogate The Runtime

The runtime provides the hypervisor with information concerning the behavior of the resources and the application. This is done by using the `performance_counters` which represent callbacks indicating when the resources are idle or not efficient, when the application submits tasks or when it becomes to slow.

10.4 Trigger the Hypervisor

The resizing is triggered either when the application requires it (`sc_hypervisor_resize_ctxs()`) or when the initial distribution of resources alters the performance of the application (the application is too slow or the resource is idle for too long time). If the environment variable `SC_HYPERVISOR_TRIGGER_RESIZE` is set to `speed` the monitored speed of the contexts is compared to a theoretical value computed with a linear program, and the resizing is triggered whenever the two values do not correspond. Otherwise, if the environment variable is set to `idle` the hypervisor triggers the resizing algorithm whenever the workers are idle for a period longer than the threshold indicated by the programmer. When this happens different resizing strategies are applied that target minimizing the total execution of the application, the instant speed or the idle time of the resources.

10.5 Resizing Strategies

The plugin proposes several strategies for resizing the scheduling context.

The **Application driven** strategy uses users's input concerning the moment when they want to resize the contexts. Thus, users tag the task that should trigger the resizing process. One can set directly the field `starpu_task->hypervisor_tag` or use the macro `STARPU_HYPERVISOR_TAG` in the function `starpu_task_insert()`.

```
task.hypervisor_tag = 2;
```

or

```
starpu_task_insert(&codelet,
    ...,
    STARPU_HYPERVISOR_TAG, 2,
    0);
```

Then users have to indicate that when a task with the specified tag is executed the contexts should resize.

```
sc_hypervisor_resize(sched_ctx, 2);
```

Users can use the same tag to change the resizing configuration of the contexts if they consider it necessary.

```
sc_hypervisor_ctl(sched_ctx,
    SC_HYPERVISOR_MIN_WORKERS, 6,
    SC_HYPERVISOR_MAX_WORKERS, 12,
    SC_HYPERVISOR_TIME_TO_APPLY, 2,
    NULL);
```

The **Idleness** based strategy moves workers unused in a certain context to another one needing them. (see [Scheduling Context Hypervisor - Regular usage](#))

```
int workerids[3] = {1, 3, 10};
int workerids2[9] = {0, 2, 4, 5, 6, 7, 8, 9, 11};
sc_hypervisor_ctl(sched_ctx_id,
    SC_HYPERVISOR_MAX_IDLE, workerids, 3, 10000.0,
    SC_HYPERVISOR_MAX_IDLE, workerids2, 9, 50000.0,
    NULL);
```


The **Gflops rate** based strategy resizes the scheduling contexts such that they all finish at the same time. The speed of each of them is computed and once one of them is significantly slower the resizing process is triggered. In order to do these computations users have to input the total number of instructions needed to be executed by the parallel kernels and the number of instruction to be executed by each task.

The number of flops to be executed by a context are passed as parameter when they are registered to the hypervisor,

```
sc_hypervisor_register_ctx(sched_ctx_id, flops)
```

and the one to be executed by each task are passed when the task is submitted. The corresponding field is `starpu->_task::flops` and the corresponding macro in the function `starpu_task_insert()` is `STARPU_FLOPS` (**Caution:** but take care of passing a double, not an integer, otherwise parameter passing will be bogus). When the task is executed the resizing process is triggered.

```
task.flops = 100;
```

or

```
starpu_task_insert(&codelet,
    ...,
    STARPU_FLOPS, (double) 100,
    0);
```

The **Fleft** strategy uses a linear program to predict the best distribution of resources such that the application finishes in a minimum amount of time. As for the **Gflops rate** strategy the programmers has to indicate the total number of flops to be executed when registering the context. This number of flops may be updated dynamically during the execution of the application whenever this information is not very accurate from the beginning. The function `sc_hypervisor_update_diff_total_flops()` is called in order to add or to remove a difference to the flops left to be executed. Tasks are provided also the number of flops corresponding to each one of them. During the execution of the application the hypervisor monitors the consumed flops and recomputes the time left and the number of resources to use. The speed of each type of resource is (re)evaluated and inserter in the linear program in order to better adapt to the needs of the application.

The **Tleft** strategy uses a linear program too, that considers all the types of tasks and the number of each of them and it tries to allocates resources such that the application finishes in a minimum amount of time. A previous calibration of StarPU would be useful in order to have good predictions of the execution time of each type of task.

The types of tasks may be determines directly by the hypervisor when they are submitted. However there are applications that do not expose all the graph of tasks from the beginning. In this case in order to let the hypervisor know about all the tasks the function `sc_hypervisor_set_type_of_task()` will just inform the hypervisor about future tasks without submitting them right away.

The **Ispeed** strategy divides the execution of the application in several frames. For each frame the hypervisor computes the speed of the contexts and tries making them run at the same speed. The strategy requires less contribution from users as the hypervisor requires only the size of the frame in terms of flops.

```
int workerids[3] = {1, 3, 10};
int workerids2[9] = {0, 2, 4, 5, 6, 7, 8, 9, 11};
sc_hypervisor_ctl(sched_ctx_id,
    SC_HYPERVERISOR_ISPEED_W_SAMPLE, workerids, 3, 2000000000.0,
    SC_HYPERVERISOR_ISPEED_W_SAMPLE, workerids2, 9, 200000000000.0
    ,
    SC_HYPERVERISOR_ISPEED_CTX_SAMPLE, 60000000000.0,
    NULL);
```

The **Throughput** strategy focuses on maximizing the throughput of the resources and resizes the contexts such that the machine is running at its maximum efficiency (maximum instant speed of the workers).

10.6 Defining A New Hypervisor Policy

While Scheduling Context Hypervisor Plugin comes with a variety of resizing policies (see [Resizing Strategies](#)), it may sometimes be desirable to implement custom policies to address specific problems. The API described below allows users to write their own resizing policy.

Here an example of how to define a new policy


```
struct sc_hypervisor_policy dummy_policy =
{
    .handle_poped_task = dummy_handle_poped_task,
    .handle_pushed_task = dummy_handle_pushed_task,
    .handle_idle_cycle = dummy_handle_idle_cycle,
    .handle_idle_end = dummy_handle_idle_end,
    .handle_post_exec_hook = dummy_handle_post_exec_hook,
    .custom = 1,
    .name = "dummy"
};
```

Chapter 11

Modularized Scheduler

11.1 Introduction

StarPU's Modularized Schedulers are made of individual Scheduling Components Modularizedly assembled as a Scheduling Tree. Each Scheduling Component has an unique purpose, such as prioritizing tasks or mapping tasks over resources. A typical Scheduling Tree is shown below.



When a task is pushed by StarPU in a Modularized Scheduler, the task moves from a Scheduling Component to an other, following the hierarchy of the Scheduling Tree, and is stored in one of the Scheduling Components of the strategy. When a worker wants to pop a task from the Modularized Scheduler, the corresponding Worker Component of the Scheduling Tree tries to pull a task from its parents, following the hierarchy, and gives it to the worker if it succeeded to get one.

11.2.3 Interface

Each Scheduling Component must follow the following pre-defined Interface to be able to interact with other Scheduling Components.

- **Push (Caller_Component, Child_Component, Task)**
The calling Scheduling Component transfers a task to its Child Component. When the Push function returns, the task no longer belongs to the calling Component. The Modularized Schedulers' model relies on this function to perform prefetching. See [starpu_sched_component::push_task](#) for more details
- **Pull (Caller_Component, Parent_Component) -> Task**
The calling Scheduling Component requests a task from its Parent Component. When the Pull function ends, the returned task belongs to the calling Component. See [starpu_sched_component::pull_task](#) for more details
- **Can_Push (Caller_Component, Parent_Component)**
The calling Scheduling Component notifies its Parent Component that it is ready to accept new tasks. See [starpu_sched_component::can_push](#) for more details
- **Can_Pull (Caller_Component, Child_Component)**
The calling Scheduling Component notifies its Child Component that it is ready to give new tasks. See [starpu_sched_component::can_pull](#) for more details

11.3 Building a Modularized Scheduler

11.3.1 Pre-implemented Components

StarPU is currently shipped with the following four Scheduling Components :

- **Flow-control Components : Fifo, Prio**
Components which store tasks. They can also prioritize them if they have a defined priority. It is possible to define a threshold for those Components following two criterias : the number of tasks stored in the Component, or the sum of the expected length of all tasks stored in the Component.
- **Resource-Mapping Components : Mct, Heft, Eager, Random, Work-Stealing**
"Core" of the Scheduling Strategy, those Components are the ones who make scheduling choices.
- **Worker Components : Worker**
Each Worker Component modelize a concrete worker.
- **Special-Purpose Components : Perfmodel_Select, Best_Implementation**
Components dedicated to original purposes. The Perfmodel_Select Component decides which Resource-Mapping Component should be used to schedule a task. The Best_Implementation Component chooses which implementation of a task should be used on the choosen resource.

11.3.2 Progression And Validation Rules

Some rules must be followed to ensure the correctness of a Modularized Scheduler :

- At least one Flow-control Component without threshold per Worker Component is needed in a Modularized Scheduler, to store incoming tasks from StarPU and to give tasks to Worker Components who asks for it. It is possible to use one Flow-control Component per Worker Component, or one for all Worker Components, depending on how the Scheduling Tree is defined.
- At least one Resource-Mapping Component is needed in a Modularized Scheduler. Resource-Mapping Components are the only ones who can make scheduling choices, and so the only ones who can have several child.

11.3.3 Implementing a Modularized Scheduler

The following code shows how the Tree-Eager-Prefetching Scheduler shown in Section [An Example : The Tree-Eager-Prefetching Strategy](#) is implemented :

```
#define _STARPU_SCHED_NTASKS_THRESHOLD_DEFAULT 2
#define _STARPU_SCHED_EXP_LEN_THRESHOLD_DEFAULT 1000000000.0

static void initialize_eager_prefetching_center_policy(unsigned sched_ctx_id)
{
    unsigned ntasks_threshold = _STARPU_SCHED_NTASKS_THRESHOLD_DEFAULT;
    double exp_len_threshold = _STARPU_SCHED_EXP_LEN_THRESHOLD_DEFAULT;

    [...]

    starpu_sched_ctx_create_worker_collection
        (sched_ctx_id, STARPU_WORKER_LIST);

    /* Create the Scheduling Tree */
    struct starpu_sched_tree * t =
        starpu_sched_tree_create(sched_ctx_id);

    /* The Root Component is a Flow-control Fifo Component */
    t->root = starpu_sched_component_fifo_create(NULL);

    /* The Resource-mapping Component of the strategy is an Eager Component
    */
    struct starpu_sched_component * eager_component =
        starpu_sched_component_eager_create(NULL);

    /* Create links between Components : the Eager Component is the child
    * of the Root Component */
    t->root->add_child
        (t->root, eager_component);
    eager_component->add_father
        (eager_component, t->root);

    /* A task threshold is set for the Flow-control Components which will
    * be connected to Worker Components. By doing so, this Modularized
    * Scheduler will be able to perform some prefetching on the resources
    */
    struct starpu_sched_component_fifo_data fifo_data =
    {
        .ntasks_threshold = ntasks_threshold,
        .exp_len_threshold = exp_len_threshold,
    };

    unsigned i;
    for(i = 0;
        i < starpu_worker_get_count() +
        starpu_combined_worker_get_count();
        i++)
    {
        /* Each Worker Component has a Flow-control Fifo Component as
        * father */
        struct starpu_sched_component * worker_component =
            starpu_sched_component_worker_get(i);
        struct starpu_sched_component * fifo_component =
            starpu_sched_component_fifo_create(&fifo_data);
        fifo_component->add_child
            (fifo_component, worker_component);
        worker_component->add_father
            (worker_component, fifo_component);

        /* Each Flow-control Fifo Component associated to a Worker
        * Component is linked to the Eager Component as one of its
        * children */
        eager_component->add_child
            (eager_component, fifo_component);
        fifo_component->add_father
            (fifo_component, eager_component);
    }

    starpu_sched_tree_update_workers(t);
    starpu_sched_ctx_set_policy_data
        (sched_ctx_id, (void*)t);
}

/* Properly destroy the Scheduling Tree and all its Components */
static void deinitialize_eager_prefetching_center_policy(unsigned sched_ctx_id)
{
    struct starpu_sched_tree * tree =
        (struct starpu_sched_tree*)starpu_sched_ctx_get_policy_data
```

```

        (sched_ctx_id);
    starpu_sched_tree_destroy(tree);
    starpu_sched_ctx_delete_worker_collection
        (sched_ctx_id);
}

/* Initializing the starpu_sched_policy struct associated to the Modularized
 * Scheduler : only the init_sched and deinit_sched needs to be defined to
 * implement a Modularized Scheduler */
struct starpu_sched_policy _starpu_sched_tree_eager_prefetching_policy =
{
    .init_sched = initialize_eager_prefetching_center_policy,
    .deinit_sched = deinitialize_eager_prefetching_center_policy,
    .add_workers = starpu_sched_tree_add_workers,
    .remove_workers = starpu_sched_tree_remove_workers,
    .push_task = starpu_sched_tree_push_task,
    .pop_task = starpu_sched_tree_pop_task,
    .pre_exec_hook = starpu_sched_component_worker_pre_exec_hook,
    .post_exec_hook = starpu_sched_component_worker_post_exec_hook,
    .pop_every_task = NULL,
    .policy_name = "tree-eager-prefetching",
    .policy_description = "eager with prefetching tree policy"
};

```

11.4 Writing a Scheduling Component

11.4.1 Generic Scheduling Component

Each Scheduling Component is instantiated from a Generic Scheduling Component, which implements a generic version of the Interface. The generic implementation of Pull, Can_Pull and Can_Push functions are recursive calls to their parents (respectively to their children). However, as a Generic Scheduling Component do not know how much children it will have when it will be instantiated, it does not implement the Push function.


11.4.2 Instantiation : Redefining the Interface

A Scheduling Component must implement all the functions of the Interface. It is so necessary to implement a Push function to instantiate a Scheduling Component. The implemented Push function is the "fingerprint" of a Scheduling Component. Depending on how functionalities or properties the programmer wants to give to the Scheduling Component he is implementing, it is possible to reimplement all the functions of the Interface. For example, a Flow-control Component reimplements the Pull and the Can_Push functions of the Interface, allowing him to catch the generic recursive calls of these functions. The Pull function of a Flow-control Component can, for example, pop a task from the local storage queue of the Component, and give it to the calling Component which asks for it.

11.4.3 Detailed Progression and Validation Rules

- A Reservoir is a Scheduling Component which redefines a Push and a Pull function, in order to store tasks into it. A Reservoir delimit Scheduling Areas in the Scheduling Tree.
- A Pump is the engine source of the Scheduler : it pushes/pulls tasks to/from a Scheduling Component to an other. Native Pumps of a Scheduling Tree are located at the root of the Tree (incoming Push calls from StarPU), and at the leafs of the Tree (Pop calls coming from StarPU Workers). Pre-implemented Scheduling Components currently shipped with Pumps are Flow-Control Components and the Resource-Mapping Component Heft, within their defined Can_Push functions.
- A correct Scheduling Tree requires a Pump per Scheduling Area and per Execution Flow.

The Tree-Eager-Prefetching Scheduler shown in Section [An Example : The Tree-Eager-Prefetching Strategy](#) follows the previous assumptions :



Chapter 12

Debugging Tools

StarPU provides several tools to help debugging applications. Execution traces can be generated and displayed graphically, see [Generating Traces With FxT](#).

12.1 TroubleShooting In General

Generally-speaking, if you have troubles, pass `--enable-debug` to `./configure` to enable some checks which impact performance, but will catch common issues, possibly earlier than the actual problem you are observing, which may just be a consequence of a bug that happened earlier. Also, make sure not to have the `--enable-fast` option which drops very useful catchup assertions. If your program is valgrind-safe, you can use it, see [Using Other Debugging Tools](#).

Depending on your toolchain, it might happen that you get undefined reference to `'__stack_chk_guard'` errors. In that case, use the `-disable-fstack-protector-all` option to avoid the issue.

Then, if your program crashes with an assertion error, a segfault, etc. you can send us the result of

```
thread apply all bt
```

run in `gdb` at the point of the crash.

In case your program just hangs, but it may also be useful in case of a crash too, it helps to source `gdbinit` as described in the next section to be able to run and send us the output of the following commands:

```
starpu-workers
starpu-tasks
starpu-print-requests
starpu-print-prequests
starpu-print-frrequests
starpu-print-irrequests
```

To give us an idea of what is happening within StarPU. If the outputs are not too long, you can even run

```
starpu-all-tasks
starpu-print-all-tasks
starpu-print-datas-summary
starpu-print-datas
```

12.2 Using The Gdb Debugger

Some `gdb` helpers are provided to show the whole StarPU state:

```
(gdb) source tools/gdbinit
(gdb) help starpu
```

For instance,

- one can print all tasks with `starpu-print-all-tasks`,
- print all datas with `starpu-print-datas`,
- print all pending data transfers with `starpu-print-prequests`, `starpu-print-requests`, `starpu-print-frequests`, `starpu-print-irequests`,
- print pending MPI requests with `starpu-mpi-print-detached-requests`

Some functions can only work if `--enable-debug` was passed to `./configure` (because they impact performance)

12.3 Using Other Debugging Tools


Valgrind can be used on StarPU: `valgrind.h` just needs to be found at `./configure` time, to tell valgrind about some known false positives and disable host memory pinning. Other known false positives can be suppressed by giving the suppression files in `tools/valgrind/*.suppr` to valgrind's `-suppressions` option.

The environment variable `STARPU_DISABLE_KERNELS` can also be set to 1 to make StarPU does everything (schedule tasks, transfer memory, etc.) except actually calling the application-provided kernel functions, i.e. the computation will not happen. This permits to quickly check that the task scheme is working properly.

12.4 Using The Temanejo Task Debugger

StarPU can connect to Temanejo `>= 1.0rc2` (see <http://www.hlrs.de/temanejo>), to permit nice visual task debugging. To do so, build Temanejo's `libayudame.so`, install `Ayudame.h` to e.g. `/usr/local/include`, apply the `tools/patch-ayudame` to it to fix C build, re-`./configure`, make sure that it found it, rebuild StarPU. Run the Temanejo GUI, give it the path to your application, any options you want to pass it, the path to `libayudame.so`.

It permits to visualize the task graph, add breakpoints, continue execution task-by-task, and run `gdb` on a given task, etc.



Make sure to specify at least the same number of CPUs in the dialog box as your machine has, otherwise an error will happen during execution. Future versions of Temanejo should be able to tell StarPU the number of CPUs to use.

Tag numbers have to be below 4000000000000000000ULL to be usable for Temanejo (so as to distinguish them from tasks).

Chapter 13

Online Performance Tools

13.1 On-line Performance Feedback

13.1.1 Enabling On-line Performance Monitoring

In order to enable online performance monitoring, the application can call `starpu_profiling_status_set()` with the parameter `STARPU_PROFILING_ENABLE`. It is possible to detect whether monitoring is already enabled or not by calling `starpu_profiling_status_get()`. Enabling monitoring also reinitialize all previously collected feedback. The environment variable `STARPU_PROFILING` can also be set to 1 to achieve the same effect. The function `starpu_profiling_init()` can also be called during the execution to reinitialize performance counters and to start the profiling if the environment variable `STARPU_PROFILING` is set to 1.

Likewise, performance monitoring is stopped by calling `starpu_profiling_status_set()` with the parameter `STARPU_PROFILING_DISABLE`. Note that this does not reset the performance counters so that the application may consult them later on.

More details about the performance monitoring API are available in [Profiling](#).

13.1.2 Per-task Feedback

If profiling is enabled, a pointer to a structure `starpu_profiling_task_info` is put in the field `starpu_task::profiling_info` when a task terminates. This structure is automatically destroyed when the task structure is destroyed, either automatically or by calling `starpu_task_destroy()`.

The structure `starpu_profiling_task_info` indicates the date when the task was submitted (`starpu_profiling_task_info::submit_time`), started (`starpu_profiling_task_info::start_time`), and terminated (`starpu_profiling_task_info::end_time`), relative to the initialization of StarPU with `starpu_init()`. It also specifies the identifier of the worker that has executed the task (`starpu_profiling_task_info::workerid`). These date are stored as `timespec` structures which the user may convert into micro-seconds using the helper function `starpu_timing_timespec_to_us()`.

It is worth noting that the application may directly access this structure from the callback executed at the end of the task. The structure `starpu_task` associated to the callback currently being executed is indeed accessible with the function `starpu_task_get_current()`.

13.1.3 Per-codelet Feedback

The field `starpu_codelet::per_worker_stats` is an array of counters. The `i`-th entry of the array is incremented every time a task implementing the codelet is executed on the `i`-th worker. This array is not reinitialized when profiling is enabled or disabled.

13.1.4 Per-worker Feedback

The second argument returned by the function `starpu_profiling_worker_get_info()` is a structure `starpu_profiling_worker_info` that gives statistics about the specified worker. This structure specifies when StarPU started collecting profiling information for that worker (`starpu_profiling_worker_info::start_time`), the duration of the profiling measurement interval (`starpu_profiling_worker_info::total_time`), the time spent executing kernels (`starpu_profiling_worker_info::executing_time`), the time spent sleeping because there is no task to execute at all (`starpu_profiling_worker_info::sleeping_time`), and the number of tasks that were executed while profiling was enabled. These values give an estimation of the proportion of time spent do real work, and the time spent either sleeping because there are not enough executable tasks or simply wasted in pure StarPU overhead.

Calling `starpu_profiling_worker_get_info()` resets the profiling information associated to a worker.

To easily display all this information, the environment variable `STARPU_WORKER_STATS` can be set to 1 (in addition to setting `STARPU_PROFILING` to 1). A summary will then be displayed at program termination:

```
Worker stats:
CUDA 0.0 (4.7 GiB)
480 task(s)
total: 1574.82 ms executing: 1510.72 ms sleeping: 0.00 ms overhead 64.10 ms
325.217970 GFlop/s

CPU 0
22 task(s)
total: 1574.82 ms executing: 1364.81 ms sleeping: 0.00 ms overhead 210.01 ms
7.512057 GFlop/s

CPU 1
14 task(s)
total: 1574.82 ms executing: 1500.13 ms sleeping: 0.00 ms overhead 74.69 ms
6.675853 GFlop/s

CPU 2
14 task(s)
total: 1574.82 ms executing: 1553.12 ms sleeping: 0.00 ms overhead 21.70 ms
7.152886 GFlop/s
```

The number of GFlops is available because the `starpu_task::flops` field of the tasks were filled (or `STARPU_FLOPS` used in `starpu_task_insert()`).

When an FxT trace is generated (see [Generating Traces With FxT](#)), it is also possible to use the tool `starpu_workers_activity` (see [Monitoring Activity](#)) to generate a graphic showing the evolution of these values during the time, for the different workers.

13.1.5 Bus-related Feedback

The bus speed measured by StarPU can be displayed by using the tool `starpu_machine_display`, for instance:

```
StarPU has found:
  3 CUDA devices
      CUDA 0 (Tesla C2050 02:00.0)
      CUDA 1 (Tesla C2050 03:00.0)
      CUDA 2 (Tesla C2050 84:00.0)
```

from	to RAM	to CUDA 0	to CUDA 1	to CUDA 2
RAM	0.000000	5176.530428	5176.492994	5191.710722
CUDA 0	4523.732446	0.000000	2414.074751	2417.379201
CUDA 1	4523.718152	2414.078822	0.000000	2417.375119
CUDA 2	4534.229519	2417.069025	2417.060863	0.000000

Statistics about the data transfers which were performed and temporal average of bandwidth usage can be obtained by setting the environment variable `STARPU_BUS_STATS` to 1; a summary will then be displayed at program termination:

```
Data transfer stats:
RAM 0 -> CUDA 0 319.92 MB 213.10 MB/s (transfers : 91 - avg 3.52 MB)
CUDA 0 -> RAM 0 214.45 MB 142.85 MB/s (transfers : 61 - avg 3.52 MB)
RAM 0 -> CUDA 1 302.34 MB 201.39 MB/s (transfers : 86 - avg 3.52 MB)
CUDA 1 -> RAM 0 133.59 MB 88.99 MB/s (transfers : 38 - avg 3.52 MB)
CUDA 0 -> CUDA 1 144.14 MB 96.01 MB/s (transfers : 41 - avg 3.52 MB)
CUDA 1 -> CUDA 0 130.08 MB 86.64 MB/s (transfers : 37 - avg 3.52 MB)
RAM 0 -> CUDA 2 312.89 MB 208.42 MB/s (transfers : 89 - avg 3.52 MB)
CUDA 2 -> RAM 0 133.59 MB 88.99 MB/s (transfers : 38 - avg 3.52 MB)
CUDA 0 -> CUDA 2 151.17 MB 100.69 MB/s (transfers : 43 - avg 3.52 MB)
CUDA 2 -> CUDA 0 105.47 MB 70.25 MB/s (transfers : 30 - avg 3.52 MB)
CUDA 1 -> CUDA 2 175.78 MB 117.09 MB/s (transfers : 50 - avg 3.52 MB)
CUDA 2 -> CUDA 1 203.91 MB 135.82 MB/s (transfers : 58 - avg 3.52 MB)
Total transfers: 2.27 GB
```

13.1.6 MPI-related Feedback

Statistics about the data transfers which were performed over MPI can be obtained by setting the environment variable `STARPU_COMM_STATS` to 1; a summary will then be displayed at program termination:

```
[starpu_comm_stats][0] TOTAL: 4.000000 GB 4.000000 GB
[starpu_comm_stats][0->1] 4.000000 GB 4.000000 GB
[starpu_comm_stats][1] TOTAL: 8.000000 GB 8.000000 GB
[starpu_comm_stats][1->0] 8.000000 GB 8.000000 GB
```

13.1.7 StarPU-Top Interface

StarPU-Top is an interface which remotely displays the on-line state of a StarPU application and permits the user to change parameters on the fly.

Variables to be monitored can be registered by calling the functions `starpu_top_add_data_boolean()`, `starpu_top_add_data_integer()`, `starpu_top_add_data_float()`, e.g.:

```
starpu_top_data *data = starpu_top_add_data_integer("mynum", 0, 100, 1);
```

The application should then call `starpu_top_init_and_wait()` to give its name and wait for StarPU-Top to get a start request from the user. The name is used by StarPU-Top to quickly reload a previously-saved layout of parameter display.

```
starpu_top_init_and_wait("the application");
```

The new values can then be provided thanks to `starpu_top_update_data_boolean()`, `starpu_top_update_data_integer()`, `starpu_top_update_data_float()`, e.g.:

```
starpu_top_update_data_integer(data, mynum);
```

Updateable parameters can be registered thanks to `starpu_top_register_parameter_boolean()`, `starpu_top_register_parameter_integer()`, `starpu_top_register_parameter_float()`, e.g.:

```
float alpha;
starpu_top_register_parameter_float("alpha", &alpha, 0, 10, modif_hook);
```

`modif_hook` is a function which will be called when the parameter is being modified, it can for instance print the new value:

```
void modif_hook(struct starpu_top_param *d) {
    fprintf(stderr, "%s has been modified: %f\n", d->name, alpha);
}
```

Task schedulers should notify StarPU-Top when it has decided when a task will be scheduled, so that it can show it in its Gantt chart, for instance:

```
starpu_top_task_prevision(task, workerid, begin, end);
```

Starting StarPU-Top (StarPU-Top is started via the binary `starpu_top`) and the application can be done in two ways:

- The application is started by hand on some machine (and thus already waiting for the start event). In the Preference dialog of StarPU-Top, the SSH checkbox should be unchecked, and the hostname and port (default is 2011) on which the application is already running should be specified. Clicking on the connection button will thus connect to the already-running application.
- StarPU-Top is started first, and clicking on the connection button will start the application itself (possibly on a remote machine). The SSH checkbox should be checked, and a command line provided, e.g.:

```
$ ssh myserver STARPU_SCHED=dmda ./application
```

If port 2011 of the remote machine can not be accessed directly, an ssh port bridge should be added:

```
$ ssh -L 2011:localhost:2011 myserver STARPU_SCHED=dmda ./application
```

and "localhost" should be used as IP Address to connect to.

13.2 Task And Worker Profiling

A full example showing how to use the profiling API is available in the StarPU sources in the directory `examples/profiling/`.

```
struct starpu_task *task = starpu_task_create();
task->cl = &cl;
task->synchronous = 1;
/* We will destroy the task structure by hand so that we can
 * query the profiling info before the task is destroyed. */
task->destroy = 0;

/* Submit and wait for completion (since synchronous was set to 1) */
starpu_task_submit(task);

/* The task is finished, get profiling information */
struct starpu_profiling_task_info *info = task->profiling_info;

/* How much time did it take before the task started ? */
double delay += starpu_timing_timespec_delay_us(&info->submit_time
, &info->start_time);

/* How long was the task execution ? */
double length += starpu_timing_timespec_delay_us(&info->start_time
, &info->end_time);

/* We no longer need the task structure */
starpu_task_destroy(task);
```



```

/* Display the occupancy of all workers during the test */
int worker;
for (worker = 0; worker < starpu_worker_get_count(); worker++)
{
    struct starpu_profiling_worker_info worker_info;
    int ret = starpu_profiling_worker_get_info(worker, &worker_info);
    STARPU_ASSERT(!ret);

    double total_time = starpu_timing_timespec_to_us(&worker_info
        .total_time);
    double executing_time = starpu_timing_timespec_to_us(&
        worker_info.executing_time);
    double sleeping_time = starpu_timing_timespec_to_us(&
        worker_info.sleeping_time);
    double overhead_time = total_time - executing_time - sleeping_time;

    float executing_ratio = 100.0*executing_time/total_time;
    float sleeping_ratio = 100.0*sleeping_time/total_time;
    float overhead_ratio = 100.0 - executing_ratio - sleeping_ratio;

    char workername[128];
    starpu_worker_get_name(worker, workername, 128);
    fprintf(stderr, "Worker %s:\n", workername);
    fprintf(stderr, "\tttotal time: %.2lf ms\n", total_time*1e-3);
    fprintf(stderr, "\texec time: %.2lf ms (%.2f %%)\n",
        executing_time*1e-3, executing_ratio);
    fprintf(stderr, "\tblocked time: %.2lf ms (%.2f %%)\n",
        sleeping_time*1e-3, sleeping_ratio);
    fprintf(stderr, "\toverhead time: %.2lf ms (%.2f %%)\n",
        overhead_time*1e-3, overhead_ratio);
}

```

13.3 Performance Model Example

To achieve good scheduling, StarPU scheduling policies need to be able to estimate in advance the duration of a task. This is done by giving to codelets a performance model, by defining a structure `starpu_perfmodel` and providing its address in the field `starpu_codelet::model`. The fields `starpu_perfmodel::symbol` and `starpu_perfmodel::type` are mandatory, to give a name to the model, and the type of the model, since there are several kinds of performance models. For compatibility, make sure to initialize the whole structure to zero, either by using explicit `memset()`, or by letting the compiler implicitly do it as exemplified below.

- Measured at runtime (model type `STARPU_HISTORY_BASED`). This assumes that for a given set of data input/output sizes, the performance will always be about the same. This is very true for regular kernels on GPUs for instance (<0.1% error), and just a bit less true on CPUs (~1% error). This also assumes that there are few different sets of data input/output sizes. StarPU will then keep record of the average time of previous executions on the various processing units, and use it as an estimation. History is done per task size, by using a hash of the input and output sizes as an index. It will also save it in `$STARPU_HOME/.starpu/sampling/codelets` for further executions, and can be observed by using the tool `starpu_perfmodel_display`, or drawn by using the tool `starpu_perfmodel_plot` ([Performance Model Calibration](#)). The models are indexed by machine name. To share the models between machines (e.g. for a homogeneous cluster), use `export STARPU_HOSTNAME=some_global_name`. Measurements are only done when using a task scheduler which makes use of it, such as `dmda`. Measurements can also be provided explicitly by the application, by using the function `starpu_perfmodel_update_history()`.

The following is a small code example.

If e.g. the code is recompiled with other compilation options, or several variants of the code are used, the `symbol` string should be changed to reflect that, in order to recalibrate a new model from zero. The `symbol` string can even be constructed dynamically at execution time, as long as this is done before submitting any task using it.

```

static struct starpu_perfmodel mult_perf_model = {
    .type = STARPU_HISTORY_BASED,
    .symbol = "mult_perf_model"
};

struct starpu_codelet cl = {

```

```

.cpu_funcs = { cpu_mult },
.cpu_funcs_name = { "cpu_mult" },
.nbuffers = 3,
.modes = { STARPU_R, STARPU_R, STARPU_W },
/* for the scheduling policy to be able to use performance models */
.model = &mult_perf_model
};

```

- Measured at runtime and refined by regression (model types [STARPU_REGRESSION_BASED](#) and [STARPU_NL_REGRESSION_BASED](#)). This still assumes performance regularity, but works with various data input sizes, by applying regression over observed execution times. [STARPU_REGRESSION_BASED](#) uses an $a \cdot n^b$ regression form, [STARPU_NL_REGRESSION_BASED](#) uses an $a \cdot n^b + c$ (more precise than [STARPU_REGRESSION_BASED](#), but costs a lot more to compute).

For instance, `tests/perfmodels/regression_based.c` uses a regression-based performance model for the function `memset()`.

Of course, the application has to issue tasks with varying size so that the regression can be computed. StarPU will not trust the regression unless there is at least 10% difference between the minimum and maximum observed input size. It can be useful to set the environment variable [STARPU_CALIBRATE](#) to 1 and run the application on varying input sizes with [STARPU_SCHED](#) set to `dmda` scheduler, so as to feed the performance model for a variety of inputs. The application can also provide the measurements explicitly by using the function `starpu_perfmodel_update_history()`. The tools `starpu_perfmodel_display` and `starpu_perfmodel_plot` can be used to observe how much the performance model is calibrated ([Performance Model Calibration](#)); when their output look good, [STARPU_CALIBRATE](#) can be reset to 0 to let StarPU use the resulting performance model without recording new measures, and [STARPU_SCHED](#) can be set to `dmda` to benefit from the performance models. If the data input sizes vary a lot, it is really important to set [STARPU_CALIBRATE](#) to 0, otherwise StarPU will continue adding the measures, and result with a very big performance model, which will take time a lot of time to load and save.

For non-linear regression, since computing it is quite expensive, it is only done at termination of the application. This means that the first execution of the application will use only history-based performance model to perform scheduling, without using regression.

- Provided as an estimation from the application itself (model type [STARPU_COMMON](#) and field `starpu_perfmodel::cost_function`), see for instance `examples/common/blas_model.h` and `examples/common/blas_model.c`.
- Provided explicitly by the application (model type [STARPU_PER_ARCH](#)): either field `starpu_perfmodel::arch_cost_function`, or the fields `.per_arch[arch][nimpl].cost_function` have to be filled with pointers to functions which return the expected duration of the task in micro-seconds, one per architecture, see for instance `tests/datawizard/locality.c`

For [STARPU_HISTORY_BASED](#), [STARPU_REGRESSION_BASED](#), and [STARPU_NL_REGRESSION_BASED](#), the dimensions of task data (both input and output) are used as an index by default. [STARPU_HISTORY_BASED](#) uses a CRC hash of the dimensions as an index to distinguish histories, and [STARPU_REGRESSION_BASED](#) and [STARPU_NL_REGRESSION_BASED](#) use the total size as an index for the regression.

The `starpu_perfmodel::size_base` and `starpu_perfmodel::footprint` fields however permit the application to override that, when for instance some of the data do not matter for task cost (e.g. mere reference table), or when using sparse structures (in which case it is the number of non-zeros which matter), or when there is some hidden parameter such as the number of iterations, or when the application actually has a very good idea of the complexity of the algorithm, and just not the speed of the processor, etc. The example in the directory `examples/pi` uses this to include the number of iterations in the base size. `starpu_perfmodel::size_base` should be used when the variance of the actual performance is known (i.e. bigger returned value is longer execution time), and thus particularly useful for [STARPU_REGRESSION_BASED](#) or [STARPU_NL_REGRESSION_BASED](#). `starpu_perfmodel::footprint` can be used when the variance of the actual performance is unknown (irregular performance behavior, etc.), and thus only useful for [STARPU_HISTORY_BASED](#). `starpu_task_data_footprint()` can be used as a base and combined with other parameters through `starpu_hash_crc32c_be()` for instance.

StarPU will automatically determine when the performance model is calibrated, or rather, it will assume the performance model is calibrated until the application submits a task for which the performance can not be predicted.

For `STARPU_HISTORY_BASED`, StarPU will require 10 (`STARPU_CALIBRATE_MINIMUM`) measurements for a given size before estimating that an average can be taken as estimation for further executions with the same size. For `STARPU_REGRESSION_BASED` and `STARPU_NL_REGRESSION_BASED`, StarPU will require 10 (`STARPU_CALIBRATE_MINIMUM`) measurements, and that the minimum measured data size is smaller than 90% of the maximum measured data size (i.e. the measurement interval is large enough for a regression to have a meaning). Calibration can also be forced by setting the `STARPU_CALIBRATE` environment variable to 1, or even reset by setting it to 2.

How to use schedulers which can benefit from such performance model is explained in [Task Scheduling Policies](#).

The same can be done for task energy consumption estimation, by setting the field `starpu_codelet::energy_model` the same way as the field `starpu_codelet::model`. Note: for now, the application has to give to the energy consumption performance model a name which is different from the execution time performance model.


The application can request time estimations from the StarPU performance models by filling a task structure as usual without actually submitting it. The data handles can be created by calling any of the functions `starpu_*_data_register` with a NULL pointer and -1 node and the desired data sizes, and need to be unregistered as usual. The functions `starpu_task_expected_length()` and `starpu_task_expected_energy()` can then be called to get an estimation of the task cost on a given arch. `starpu_task_footprint()` can also be used to get the footprint used for indexing history-based performance models. `starpu_task_destroy()` needs to be called to destroy the dummy task afterwards. See `tests/perfmodels/regression_based.c` for an example.

13.4 Data trace and tasks length

It is possible to get statistics about tasks length and data size by using :

```
$ starpu_fxt_data_trace filename [codelet1 codelet2 ... codeletn]
```

Where filename is the FxT trace file and codeletX the names of the codelets you want to profile (if no names are specified, `starpu_fxt_data_trace` will profile them all). This will create a file, `data_trace.gp` which can be executed to get a `.eps` image of these results. On the image, each point represents a task, and each color corresponds to a codelet.



Chapter 14

Offline Performance Tools

To get an idea of what is happening, a lot of performance feedback is available, detailed in this chapter. The various informations should be checked for.

- What does the Gantt diagram look like? (see [Creating a Gantt Diagram](#))
 - If it's mostly green (tasks running in the initial context) or context specific color prevailing, then the machine is properly utilized, and perhaps the codelets are just slow. Check their performance, see [Performance Of Codelets](#).
 - If it's mostly purple (FetchingInput), tasks keep waiting for data transfers, do you perhaps have far more communication than computation? Did you properly use CUDA streams to make sure communication can be overlapped? Did you use data-locality aware schedulers to avoid transfers as much as possible?
 - If it's mostly red (Blocked), tasks keep waiting for dependencies, do you have enough parallelism? It might be a good idea to check what the DAG looks like (see [Creating a DAG With Graphviz](#)).
 - If only some workers are completely red (Blocked), for some reason the scheduler didn't assign tasks to them. Perhaps the performance model is bogus, check it (see [Performance Of Codelets](#)). Do all your codelets have a performance model? When some of them don't, the schedulers switches to a greedy algorithm which thus performs badly.

You can also use the Temanejo task debugger (see [Using The Temanejo Task Debugger](#)) to visualize the task graph more easily.

14.1 Off-line Performance Feedback

14.1.1 Generating Traces With FxT

StarPU can use the FxT library (see <https://savannah.nongnu.org/projects/fkt/>) to generate traces with a limited runtime overhead.

You can either get a tarball:

```
$ wget http://download.savannah.gnu.org/releases/fkt/fxt-0.2.11.tar.gz
```

or use the FxT library from CVS (autotools are required):

```
$ cvs -d :pserver:anonymous@cvs.sv.gnu.org:/sources/fkt co FxT
$ ./bootstrap
```

Compiling and installing the FxT library in the `$FXTDIR` path is done following the standard procedure:

```
$ ./configure --prefix=$FXTDIR
$ make
$ make install
```

In order to have StarPU to generate traces, StarPU should be configured with the option `--with-fxt` :

```
$ ./configure --with-fxt=$FXTDIR
```

Or you can simply point the `PKG_CONFIG_PATH` to `$FXTDIR/lib/pkgconfig` and pass `--with-fxt` to `./configure`

When FxT is enabled, a trace is generated when StarPU is terminated by calling `starpu_shutdown()`. The trace is a binary file whose name has the form `prof_file_XXX_YYY` where `XXX` is the user name, and `YYY` is the pid of the process that used StarPU. This file is saved in the `/tmp/` directory by default, or by the directory specified by the environment variable `STARPU_FXT_PREFIX`.

The additional configure option `--enable-fxt-lock` can be used to generate trace events which describes the locks behaviour during the execution. It is however very heavy and should not be used unless debugging StarPU's internal locking.

The environment variable `STARPU_FXT_TRACE` can be set to 0 to disable the generation of the `prof_file_XXX_YYY` file.

14.1.2 Creating a Gantt Diagram

When the FxT trace file `prof_file_something` has been generated, it is possible to generate a trace in the Paje format by calling:

```
$ starpu_fxt_tool -i /tmp/prof_file_something
```

Or alternatively, setting the environment variable `STARPU_GENERATE_TRACE` to 1 before application execution will make StarPU do it automatically at application shutdown.

This will create a file `paje.trace` in the current directory that can be inspected with the ViTE (<http://vite.gforge.inria.fr/>) trace visualizing open-source tool. It is possible to open the file `paje.trace` with ViTE by using the following command:

```
$ vite paje.trace
```

To get names of tasks instead of "unknown", fill the optional `starpu_codelet::name`, or use a performance model for them.

One can also introduce user-defined events in the diagram thanks to the `starpu_fxt_trace_user_event_string()` function.

In the MPI execution case, `STARPU_GENERATE_TRACE` will not work as expected (each node will try to generate `paje.trace`, thus mixing outputs...), you have to collect the trace files from the MPI nodes, and specify them all on the command `starpu_fxt_tool`, for instance:

```
$ starpu_fxt_tool -i /tmp/prof_file_something*
```

By default, all tasks are displayed using a green color. To display tasks with varying colors, pass option `-c` to `starpu_fxt_tool`.

By default, the trace contains all informations. To reduce the trace size, various `-no-foo` options can be passed to `starpu_fxt_tool`, see `starpu_fxt_tool -help`.

To identify tasks precisely, the application can set the `starpu_task::tag_id` field of the task (or use `STARPU_TAG_ONLY` when using `starpu_task_insert()`), and the value of the tag will show up in the trace.

It can also set the `starpu_task::name` field of the task (or use `STARPU_NAME`) when using `starpu_task_insert()`, to replace in traces the name of the codelet with an arbitrarily chosen name.

It can also set the iteration number, by just calling `starpu_iteration_push()` at the beginning of submission loops and `starpu_iteration_pop()` at the end of submission loops. These iteration numbers will show up in traces for all tasks submitted from there.

Coordinates can also be given to data with the `starpu_data_set_coordinates()` or `starpu_data_set_coordinates_array()` function. In the trace, tasks will then be assigned the coordinates of the first data they write to.

Traces can also be inspected by hand by using the tool `fxt_print`, for instance:

```
$ fxt_print -o -f /tmp/prof_file_something
```

Timings are in nanoseconds (while timings as seen in ViTE are in milliseconds).

14.1.3 Creating a DAG With Graphviz

When the FxT trace file `prof_file_something` has been generated, it is possible to generate a task graph in the DOT format by calling:

```
$ starpu_fxt_tool -i /tmp/prof_file_something
```

This will create a `dag.dot` file in the current directory. This file is a task graph described using the DOT language. It is possible to get a graphical output of the graph by using the graphviz library:

```
$ dot -Tpdf dag.dot -o output.pdf
```

14.1.4 Getting Task Details

When the FxT trace file `prof_file_something` has been generated, details on the executed tasks can be retrieved by calling:

```
$ starpu_fxt_tool -i /tmp/prof_file_something
```

This will create a `tasks.rec` file in the current directory. This file is in the recutils format, i.e. `Field: value` lines, and empty lines to separate each task. This can be used as a convenient input for various ad-hoc analysis tools. By default it only contains information about the actual execution. Performance models can be obtained by running `starpu_tasks_rec_complete` on it:

```
$ starpu_tasks_rec_complete tasks.rec tasks2.rec
```

which will add `EstimatedTime` lines which contain the performance model-estimated time (in μ s) for each worker starting from 0. Since it needs the performance models, it needs to be run the same way as the application execution, or at least with `STARPU_HOSTNAME` set to the hostname of the machine used for execution, to get the performance models of that machine.

14.1.5 Monitoring Activity

When the FxT trace file `prof_file_something` has been generated, it is possible to generate an activity trace by calling:

```
$ starpu_fxt_tool -i /tmp/prof_file_something
```

This will create a file `activity.data` in the current directory. A profile of the application showing the activity of StarPU during the execution of the program can be generated:

```
$ starpu_workers_activity activity.data
```

This will create a file named `activity.eps` in the current directory. This picture is composed of two parts. The first part shows the activity of the different workers. The green sections indicate which proportion of the time was spent executed kernels on the processing unit. The red sections indicate the proportion of time spent in StartPU: an important overhead may indicate that the granularity may be too low, and that bigger tasks may be appropriate to use the processing unit more efficiently. The black sections indicate that the processing unit was blocked because there was no task to process: this may indicate a lack of parallelism which may be alleviated by creating more tasks when it is possible.

The second part of the picture `activity.eps` is a graph showing the evolution of the number of tasks available in the system during the execution. Ready tasks are shown in black, and tasks that are submitted but not schedulable yet are shown in grey.

14.1.6 Getting Modular Scheduler Animation

When using modular schedulers (i.e. schedulers which use a modular architecture, and whose name start with "modular-"), the command

```
$ starpu_fxt_tool -i /tmp/prof_file_something
```

will also produce a `trace.html` file which can be viewed in a javascript-enabled web browser. It shows the flow of tasks between the components of the modular scheduler.

14.1.7 Limiting The Scope Of The Trace

For computing statistics, it is useful to limit the trace to a given portion of the time of the whole execution. This can be achieved by calling

```
starpu_fxt_autostart_profiling(0)
```

before calling `starpu_init()`, to prevent tracing from starting immediately. Then

```
starpu_fxt_start_profiling();
```

and

```
starpu_fxt_stop_profiling();
```

can be used around the portion of code to be traced. This will show up as marks in the trace, and states of workers will only show up for that portion.

14.2 Performance Of Codelets

The performance model of codelets (see [Performance Model Example](#)) can be examined by using the tool `starpu_perfmodel_display`:

```
$ starpu_perfmodel_display -l
file: <malloc_pinned.hannibal>
file: <starpu_slu_lu_model_21.hannibal>
file: <starpu_slu_lu_model_11.hannibal>
file: <starpu_slu_lu_model_22.hannibal>
file: <starpu_slu_lu_model_12.hannibal>
```

Here, the codelets of the example `lu` are available. We can examine the performance of the kernel 22 (in micro-seconds), which is history-based:

```
$ starpu_perfmodel_display -s starpu_slu_lu_model_22
performance model for cpu
# hash      size      mean      dev      n
57618ab0    19660800  2.851069e+05  1.829369e+04  109
performance model for cuda_0
# hash      size      mean      dev      n
57618ab0    19660800  1.164144e+04  1.556094e+01  315
performance model for cuda_1
# hash      size      mean      dev      n
57618ab0    19660800  1.164271e+04  1.330628e+01  360
performance model for cuda_2
# hash      size      mean      dev      n
57618ab0    19660800  1.166730e+04  3.390395e+02  456
```


We can see that for the given size, over a sample of a few hundreds of execution, the GPUs are about 20 times faster than the CPUs (numbers are in us). The standard deviation is extremely low for the GPUs, and less than 10% for CPUs.

This tool can also be used for regression-based performance models. It will then display the regression formula, and in the case of non-linear regression, the same performance log as for history-based performance models:

```
$ starpu_perfmodel_display -s non_linear_memset_regression_based
performance model for cpu_impl_0
Regression : #sample = 1400
Linear: y = alpha size ^ beta
alpha = 1.335973e-03
beta = 8.024020e-01
Non-Linear: y = a size ^b + c
a = 5.429195e-04
b = 8.654899e-01
c = 9.009313e-01
# hash size mean stddev n
a3d3725e 4096      4.763200e+00  7.650928e-01  100
870a30aa 8192      1.827970e+00  2.037181e-01  100
48e988e9 16384     2.652800e+00  1.876459e-01  100
961e65d2 32768     4.255530e+00  3.518025e-01  100
...
```

The same can also be achieved by using StarPU's library API, see [Performance Model](#) and notably the function `starpu_perfmodel_load_symbol()`. The source code of the tool `starpu_perfmodel_display` can be a useful example.


The tool `starpu_perfmodel_plot` can be used to draw performance models. It writes a `.gp` file in the current directory, to be run with the tool `gnuplot`, which shows the corresponding curve.



When the field `starpu_task::flops` is set (or `STARPU_FLOPS` is passed to `starpu_task_insert()`), `starpu_perfmodel_plot` can directly draw a GFlops curve, by simply adding the `-f` option:

```
$ starpu_perfmodel_plot -f -s chol_model_11
```


This will however disable displaying the regression model, for which we can not compute GFlops.



When the FxT trace file `prof_file_something` has been generated, it is possible to get a profiling of each codelet by calling:

```
$ starpu_fxt_tool -i /tmp/prof_file_something
$ starpu_codelet_profile distrib.data codelet_name
```


This will create profiling data files, and a `distrib.data.gp` file in the current directory, which draws the distribution of codelet time over the application execution, according to data input size.



This is also available in the tool `starpu_perfmodel_plot`, by passing it the fxt trace:

```
$ starpu_perfmodel_plot -s non_linear_memset_regression_based -i /tmp/prof_file_foo_0
```

It will produce a `.gp` file which contains both the performance model curves, and the profiling measurements.




If you have the statistical tool R installed, you can additionally use

```
$ starpu_codelet_histo_profile distrib.data
```

Which will create one .pdf file per codelet and per input size, showing a histogram of the codelet execution time distribution.

Histogram of $\text{val}[\text{val} > \text{quantile}(\text{val}, 0.01) \ \& \ \text{val} < \text{quantile}(\text{val}, 0.99)]$



14.3 Trace Statistics

More than just codelet performance, it is interesting to get statistics over all kinds of StarPU states (allocations, data transfers, etc.). This is particularly useful to check what may have gone wrong in the accuracy of the simgrid simulation.

This requires the R statistical tool, with the `plyr`, `ggplot2` and `data.table` packages. If your system distribution does not have packages for these, one can fetch them from CRAN:

```
$ R
> install.packages("plyr")
> install.packages("ggplot2")
> install.packages("data.table")
> install.packages("knitr")
```

The `pj_dump` tool from `pajeng` is also needed (see <https://github.com/schnorr/pajeng>)


One can then get textual or `.csv` statistics over the trace states:

```
$ starpu_paje_state_stats -v native.trace simgrid.trace
"Value"          "Events_native.csv" "Duration_native.csv" "Events_simgrid.csv" "Duration_simgrid.csv"
"Callback"       220                0.075978             220                0
"chol_model_11"  10                565.176              10                572.8695
"chol_model_21"  45                9184.828             45                9170.719
"chol_model_22" 165                64712.07             165               64299.203
$ starpu_paje_state_stats native.trace simgrid.trace
```

And one can plot histograms of execution times, of several states for instance:

```
$ starpu_paje_draw_histogram -n chol_model_11,chol_model_21,chol_model_22 native.trace simgrid.trace
```

and see the resulting pdf file:



A quick statistical report can be generated by using:

```
$ starpu_paje_summary native.trace simgrid.trace
```

it includes gantt charts, execution summaries, as well as state duration charts and time distribution histograms.

Other external Paje analysis tools can be used on these traces, one just needs to sort the traces by timestamp order (which not guaranteed to make recording more efficient):

```
$ starpu_paje_sort paje.trace
```

14.4 Theoretical Lower Bound On Execution Time

StarPU can record a trace of what tasks are needed to complete the application, and then, by using a linear system, provide a theoretical lower bound of the execution time (i.e. with an ideal scheduling).

The computed bound is not really correct when not taking into account dependencies, but for an application which have enough parallelism, it is very near to the bound computed with dependencies enabled (which takes a huge lot more time to compute), and thus provides a good-enough estimation of the ideal execution time.

[Theoretical Lower Bound On Execution Time Example](#) provides an example on how to use this.

14.5 Theoretical Lower Bound On Execution Time Example

For kernels with history-based performance models (and provided that they are completely calibrated), StarPU can very easily provide a theoretical lower bound for the execution time of a whole set of tasks. See for instance `examples/lu/lu_example.c`: before submitting tasks, call the function `starpu_bound_start()`, and after complete execution, call `starpu_bound_stop()`. `starpu_bound_print_lp()` or `starpu_bound_print_mps()` can then be used to output a Linear Programming problem corresponding to the schedule of your tasks. Run it through `lp_solve` or any other linear programming solver, and that will give you a lower bound for the total execution time of your tasks. If StarPU was compiled with the library `glpk` installed, `starpu_bound_compute()` can be used to solve it immediately and get the optimized minimum, in ms. Its parameter `integer` allows to decide whether integer resolution should be computed and returned

The `deps` parameter tells StarPU whether to take tasks, implicit data, and tag dependencies into account. Tags released in a callback or similar are not taken into account, only tags associated with a task are. It must be understood that the linear programming problem size is quadratic with the number of tasks and thus the time to solve it will be very long, it could be minutes for just a few dozen tasks. You should probably use `lp_solve -timeout 1 test.pl -wmps test.mps` to convert the problem to MPS format and then use a better solver, `glpsol` might be better than `lp_solve` for instance (the `-pcost` option may be useful), but sometimes doesn't manage to converge. `cbc` might look slower, but it is parallel. For `lp_solve`, be sure to try at least all the `-B` options. For instance, we often just use `lp_solve -cc -B1 -Bb -Bg -Bp -Bf -Br -BG -Bd -Bs -BB -Bo -Bc -Bi`, and the `-gr` option can also be quite useful. The resulting schedule can be observed by using the tool `starpu_lp2paje`, which converts it into the Paje format.

Data transfer time can only be taken into account when `deps` is set. Only data transfers inferred from implicit data dependencies between tasks are taken into account. Other data transfers are assumed to be completely overlapped.

Setting `deps` to 0 will only take into account the actual computations on processing units. It however still properly takes into account the varying performances of kernels and processing units, which is quite more accurate than just comparing StarPU performances with the fastest of the kernels being used.

The `prio` parameter tells StarPU whether to simulate taking into account the priorities as the StarPU scheduler would, i.e. schedule prioritized tasks before less prioritized tasks, to check to which extend this results to a less optimal solution. This increases even more computation time.

14.6 Memory Feedback

It is possible to enable memory statistics. To do so, you need to pass the option `--enable-memory-stats` when running `configure`. It is then possible to call the function `starpu_data_display_memory_stats()` to display statistics about the current data handles registered within StarPU.

Moreover, statistics will be displayed at the end of the execution on data handles which have not been cleared out. This can be disabled by setting the environment variable `STARPU_MEMORY_STATS` to 0.

For example, if you do not unregister data at the end of the complex example, you will get something similar to:

```
$ STARPU_MEMORY_STATS=0 ./examples/interface/complex
Complex[0] = 45.00 + 12.00 i
Complex[0] = 78.00 + 78.00 i
Complex[0] = 45.00 + 12.00 i
Complex[0] = 45.00 + 12.00 i
```

```
$ STARPU_MEMORY_STATS=1 ./examples/interface/complex
Complex[0] = 45.00 + 12.00 i
Complex[0] = 78.00 + 78.00 i
Complex[0] = 45.00 + 12.00 i
Complex[0] = 45.00 + 12.00 i
```

```
#-----
Memory stats:
#-----
Data on Node #3
#-----
Data : 0x553ff40
Size : 16

#--
Data access stats
/!\ Work Underway
Node #0
Direct access : 4
Loaded (Owner) : 0
Loaded (Shared) : 0
Invalidated (was Owner) : 0

Node #3
Direct access : 0
Loaded (Owner) : 0
Loaded (Shared) : 1
Invalidated (was Owner) : 0

#-----
Data : 0x5544710
Size : 16

#--
Data access stats
/!\ Work Underway
Node #0
Direct access : 2
Loaded (Owner) : 0
Loaded (Shared) : 1
Invalidated (was Owner) : 1

Node #3
Direct access : 0
Loaded (Owner) : 1
Loaded (Shared) : 0
Invalidated (was Owner) : 0
```

14.7 Data Statistics

Different data statistics can be displayed at the end of the execution of the application. To enable them, you need to pass the option `--enable-stats` when calling `configure`. When calling `starpu_shutdown()` various statistics will be displayed, execution, MSI cache statistics, allocation cache statistics, and data transfer statistics. The display can be disabled by setting the environment variable `STARPU_STATS` to 0.

```
$ ./examples/cholesky/cholesky_tag
Computation took (in ms)
518.16
Synthetic GFlops : 44.21
#-----
MSI cache stats :
TOTAL MSI stats hit 1622 (66.23 %) miss 827 (33.77 %)
...
```

```
$ STARPU_STATS=0 ./examples/cholesky/cholesky_tag
Computation took (in ms)
518.16
Synthetic GFlops : 44.21
```

Chapter 15

Frequently Asked Questions

15.1 How To Initialize A Computation Library Once For Each Worker?

Some libraries need to be initialized once for each concurrent instance that may run on the machine. For instance, a C++ computation class which is not thread-safe by itself, but for which several instantiated objects of that class can be used concurrently. This can be used in StarPU by initializing one such object per worker. For instance, the `libstarpuffft` example does the following to be able to use FFTW on CPUs.

Some global array stores the instantiated objects:

```
fftw_plan plan_cpu[STARPU_NMAXWORKERS];
```

At initialisation time of `libstarpup`, the objects are initialized:

```
int workerid;
for (workerid = 0; workerid < starpu_worker_get_count(); workerid++) {
    switch (starpu_worker_get_type(workerid)) {
        case STARPU_CPU_WORKER:
            plan_cpu[workerid] = fftw_plan(...);
            break;
    }
}
```

And in the codelet body, they are used:

```
static void fft(void *descr[], void *_args)
{
    int workerid = starpu_worker_get_id();
    fftw_plan plan = plan_cpu[workerid];
    ...

    fftw_execute(plan, ...);
}
```

This however is not sufficient for FFT on CUDA: initialization has to be done from the workers themselves. This can be done thanks to `starpu_execute_on_each_worker()`. For instance `libstarpuffft` does the following.

```
static void fft_plan_gpu(void *args)
{
    plan plan = args;
    int n2 = plan->n2[0];
    int workerid = starpu_worker_get_id();

    cufftPlan1d(&plan->plans[workerid].plan_cuda, n, _CUFFT_C2C, 1);
    cufftSetStream(plan->plans[workerid].plan_cuda, starpu_cuda_get_local_stream());
}
void starpufft_plan(void)
{
    starpu_execute_on_each_worker(fft_plan_gpu, plan, STARPU_CUDA);
}
```

15.2 Using The Driver API

Running Drivers

```
int ret;
struct starpu_driver = {
    .type = STARPU_CUDA_WORKER,
    .id.cuda_id = 0
};
ret = starpu_driver_init(&d);
if (ret != 0)
    error();
while (some_condition) {
    ret = starpu_driver_run_once(&d);
    if (ret != 0)
        error();
}
ret = starpu_driver_deinit(&d);
if (ret != 0)
    error();
```

To add a new kind of device to the structure `starpu_driver`, one needs to:

1. Add a member to the union `starpu_driver::id`
2. Modify the internal function `_starpu_launch_drivers()` to make sure the driver is not always launched.
3. Modify the function `starpu_driver_run()` so that it can handle another kind of architecture.
4. Write the new function `_starpu_run_foobar()` in the corresponding driver.

15.3 On-GPU Rendering

Graphical-oriented applications need to draw the result of their computations, typically on the very GPU where these happened. Technologies such as OpenGL/CUDA interoperability permit to let CUDA directly work on the OpenGL buffers, making them thus immediately ready for drawing, by mapping OpenGL buffer, textures or renderbuffer objects into CUDA. CUDA however imposes some technical constraints: peer memcpy has to be disabled, and the thread that runs OpenGL has to be the one that runs CUDA computations for that GPU.

To achieve this with StarPU, pass the option `--disable-cuda-memcpy-peer` to `./configure` (TODO: make it dynamic), OpenGL/GLUT has to be initialized first, and the interoperability mode has to be enabled by using the field `starpu_conf::cuda_opengl_interoperability`, and the driver loop has to be run by the application, by using the field `starpu_conf::not_launched_drivers` to prevent StarPU from running it in a separate thread, and by using `starpu_driver_run()` to run the loop. The examples `gl_interop` and `gl_interop_idle` show how it articulates in a simple case, where rendering is done in task callbacks. The former uses `glutMainLoopEvent` to make GLUT progress from the StarPU driver loop, while the latter uses `glutIdleFunc` to make StarPU progress from the GLUT main loop.

Then, to use an OpenGL buffer as a CUDA data, StarPU simply needs to be given the CUDA pointer at registration, for instance:

```
/* Get the CUDA worker id */
for (workerid = 0; workerid < starpu_worker_get_count(); workerid++)
    if (starpu_worker_get_type(workerid) == STARPU_CUDA_WORKER)
        break;

/* Build a CUDA pointer pointing at the OpenGL buffer */
cudaGraphicsResourceGetMappedPointer((void**)&output, &num_bytes, resource);

/* And register it to StarPU */
starpu_vector_data_register(&handle, starpu_worker_get_memory_node
```

```

        (workerid),
        output, num_bytes / sizeof(float4), sizeof(float4));

/* The handle can now be used as usual */
starpu_task_insert(&c1, STARPU_RW, handle, 0);

/* ... */

/* This gets back data into the OpenGL buffer */
starpu_data_unregister(handle);

```

and display it e.g. in the callback function.

15.4 Using StarPU With MKL 11 (Intel Composer XE 2013)

Some users had issues with MKL 11 and StarPU (versions 1.1rc1 and 1.0.5) on Linux with MKL, using 1 thread for MKL and doing all the parallelism using StarPU (no multithreaded tasks), setting the environment variable `MKL_NUM_THREADS` to 1, and using the threaded MKL library, with `iomp5`.

Using this configuration, StarPU only uses 1 core, no matter the value of `STARPU_NCPU`. The problem is actually a thread pinning issue with MKL.

The solution is to set the environment variable `KMP_AFFINITY` to `disabled` (http://software.intel.com/sites/products/documentation/studio/composer/en-us/2011Update/compiler_c/optaps/common/optaps_openmp_thread_affinity.htm).

15.5 Thread Binding on NetBSD

When using StarPU on a NetBSD machine, if the topology discovery library `hwloc` is used, thread binding will fail. To prevent the problem, you should at least use the version 1.7 of `hwloc`, and also issue the following call:

```
$ sysctl -w security.models.extensions.user_set_cpu_affinity=1
```

Or add the following line in the file `/etc/sysctl.conf`

```
security.models.extensions.user_set_cpu_affinity=1
```

15.6 StarPU permanently eats 100% of all CPUs

Yes, this is on purpose.

By default, StarPU uses active polling on task queues, so as to minimize wake-up latency for better overall performance.

If eating CPU time is a problem (e.g. application running on a desktop), pass option `--enable-blocking-drivers` to `./configure`. This will add some overhead when putting CPU workers to sleep or waking them, but avoid eating 100% CPU permanently.

15.7 Interleaving StarPU and non-StarPU code

If your application only partially uses StarPU, and you do not want to call `starpu_init()` / `starpu_shutdown()` at the beginning/end of each section, StarPU workers will poll for work between the sections. To avoid this behavior, you can "pause" StarPU with the `starpu_pause()` function. This will prevent the StarPU workers from accepting new work (tasks that are already in progress will not be frozen), and stop them from polling for more work.

Note that this does not prevent you from submitting new tasks, but they won't execute until `starpu_resume()` is called. Also note that StarPU must not be paused when you call `starpu_shutdown()`, and that this function pair works in a push/pull manner, i.e you need to match the number of calls to these functions to clear their effect.

One way to use these functions could be:

```
starpu_init(NULL);
starpu_pause(); // To submit all the tasks without a single one executing
submit_some_tasks();
starpu_resume(); // The tasks start executing

starpu_task_wait_for_all();
starpu_pause(); // Stop the workers from polling

starpu_resume();
starpu_shutdown();
```

15.8 When running with CUDA or OpenCL devices, I am seeing less CPU cores

Yes, this is on purpose.

Since GPU devices are way faster than CPUs, StarPU needs to react quickly when a task is finished, to feed the GPU with another task (StarPU actually submits a couple of tasks in advance so as to pipeline this, but filling the pipeline still has to be happening often enough), and thus it has to dedicate threads for this, and this is a very CPU-consuming duty. StarPU thus dedicates one CPU core for driving each GPU.

Such dedication is also useful when a codelet is hybrid, i.e. while kernels are running on the GPU, the codelet can run some computation, which thus be run by the CPU core instead of driving the GPU.

15.9 StarPU does not see my CUDA device

First make sure that CUDA is properly running outside StarPU: build and run the following program with `-lcudart`:

```
#include <stdio.h>
#include <cuda.h>
#include <cuda_runtime.h>

int main(void) {
    int n, i, version;
    cudaError_t err;

    err = cudaGetDeviceCount(&n);
    if (err)
    {
        fprintf(stderr, "cuda error %d\n", err);
        exit(1);
    }
    cudaDriverGetVersion(&version);
    printf("driver version %d\n", version);
    cudaRuntimeGetVersion(&version);
```

```

printf("runtime version %d\n", version);
printf("\n");

for (i = 0; i < n; i++) {
    struct cudaDeviceProp props;
    printf("CUDA%d\n", i);
    err = cudaGetDeviceProperties(&props, i);
    if (err)
    {
        fprintf(stderr, "cuda error %d\n", err);
        continue;
    }
    printf("%s\n", props.name);
    printf("%.3f GB\n", (float) props.totalGlobalMem / (1<<30));
    printf("%u MP\n", props.multiProcessorCount);
    printf("\n");
}
return 0;
}

```

If that program does not find your device, the problem is not at the StarPU level, but the CUDA drivers, check the documentation of your CUDA setup.

15.10 StarPU does not see my OpenCL device

First make sure that OpenCL is properly running outside StarPU: build and run the following program with `-lOpenCL`:

```

#include <CL/cl.h>
#include <stdio.h>
#include <assert.h>

int main(void) {
    cl_device_id did[16];
    cl_int err;
    cl_platform_id pid, pids[16];
    cl_uint nbplat, nb;
    char buf[128];
    size_t size;
    int i, j;

    err = clGetPlatformIDs(sizeof(pids)/sizeof(pids[0]), pids, &nbplat);
    assert(err == CL_SUCCESS);
    printf("%u platforms\n", nbplat);
    for (j = 0; j < nbplat; j++) {
        pid = pids[j];
        printf("    platform %d\n", j);
        err = clGetPlatformInfo(pid, CL_PLATFORM_VERSION, sizeof(buf)-1, buf, &size);
        assert(err == CL_SUCCESS);
        buf[size] = 0;
        printf("        platform version %s\n", buf);

        err = clGetDeviceIDs(pid, CL_DEVICE_TYPE_ALL, sizeof(did)/sizeof(did[0]), did, &nb);
        assert(err == CL_SUCCESS);
        printf("%d devices\n", nb);
        for (i = 0; i < nb; i++) {
            err = clGetDeviceInfo(did[i], CL_DEVICE_VERSION, sizeof(buf)-1, buf, &size);
            buf[size] = 0;
            printf("    device %d version %s\n", i, buf);
        }
    }

    return 0;
}

```

If that program does not find your device, the problem is not at the StarPU level, but the OpenCL drivers, check the documentation of your OpenCL implementation.

15.11 I keep getting a "Incorrect performance model file" error

The performance model file, used by StarPU to record the performance of codelets, seem to have been corrupted. Perhaps a previous run of StarPU stopped abruptly, and thus could not save it properly. You can have a look at the file if you can fix it, but the simplest way is to just remove the file and run again, StarPU will just have to re-perform calibration for the corresponding codelet.

Part IV

StarPU Extensions

Chapter 16

Out Of Core

16.1 Introduction

When using StarPU, one may need to store more data than what the main memory (RAM) can store. This part describes the method to add a new memory node on a disk and to use it.

Similarly to what happens with GPUs (it's actually exactly the same code), when available main memory becomes scarce, StarPU will evict unused data to the disk, thus leaving room for new allocations. Whenever some evicted data is needed again for a task, StarPU will automatically fetch it back from the disk.

The principle is that one first registers a disk location, seen by StarPU as a `void*`, which can be for instance a Unix path for the `stdio`, `unistd` or `unistd_o_direct` backends, or a `leveldb` database for the `leveldb` backend, an `HDF5` file path for the `HDF5` backend, etc. The disk backend opens this place with the `plug` method.

StarPU can then start using it to allocate room and store data there with the disk write method, without user intervention.

The user can also use `starpu_disk_open()` to explicitly open an object within the disk, e.g. a file name in the `stdio` or `unistd` cases, or a database key in the `leveldb` case, and then use `starpu*_register` functions to turn it into a StarPU data handle. StarPU will then use this file as external source of data, and automatically read and write data as appropriate.

16.2 Use a new disk memory

To use a disk memory node, you have to register it with this function:

```
int new_dd = starpu_disk_register(&starpu_disk_unistd_ops, (void
*) "/tmp/", 1024*1024*200);
```

Here, we use the `unistd` library to realize the read/write operations, i.e. `fread/fwrite`. This structure must have a path where to store files, as well as the maximum size the software can afford storing on the disk.

Don't forget to check if the result is correct!

This can also be achieved by just setting environment variables:

```
export STARPU_DISK_SWAP=/tmp
export STARPU_DISK_SWAP_BACKEND=unistd
export STARPU_DISK_SWAP_SIZE=200
```

The backend can be set to stdio (some caching is done by libc), unistd (only caching in the kernel), unistd_o_direct (no caching), leveldb, or hdf5.

When that register call is made, StarPU will benchmark the disk. This can take some time.

Warning: the size thus has to be at least `STARPU_DISK_SIZE_MIN` bytes !

StarPU will then automatically try to evict unused data to this new disk. One can also use the standard StarPU memory node API to prefetch data etc., see the [Standard Memory Library](#) and the [Data Interfaces](#) .

The disk is unregistered during the [starpu_shutdown\(\)](#).

16.3 Data Registration

StarPU will only be able to achieve Out-Of-Core eviction if it controls memory allocation. For instance, if the application does the following:

```
p = malloc(1024*1024*sizeof(float)); fill_with_data(p); starpu_matrix_data←
_register(&h, STARPU_MAIN_RAM, (uintptr_t) p, 1024, 1024, 1024, sizeof(float));
```

StarPU will not be able to release the corresponding memory since it's the application which allocated it, and StarPU can not know how, and thus how to release it. One thus have to use the following instead:

```
starpu_matrix_data_register(&h, -1, NULL, 1024, 1024, 1024, sizeof(float));
starpu_task_insert(cl_fill_with_data, STARPU_W, h, 0);
```

Which makes StarPU automatically do the allocation when the task running `cl_fill_with_data` gets executed. And then if its needs to, it will be able to release it after having pushed the data to the disk.

16.4 Using Wont Use

By default, StarPU uses a Least-Recently-Used (LRU) algorithm to determine which data should be evicted to the disk. This algorithm can be hinted by telling which data will no be used in the coming future thanks to [starpu_↵data_wont_use\(\)](#), for instance:

```
starpu_task_insert(&cl_work, STARPU_RW, h, 0); starpu_data_wont_use(h);
```

StarPU will mark the data as "inactive" and tend to evict to the disk that data rather than others.

16.5 Examples: disk_copy

```

/* Try to write into disk memory
 * Use mechanism to push datas from main ram to disk ram
 */

#include <starpu.h>
#include <stdlib.h>
#include <stdio.h>
#include <math.h>

/* size of one vector */
#define NX (30*1000000/sizeof(double))
#define FPRINTF(ofile, fmt, ...) do { if (!getenv("STARPU_SSILENT")) {fprintf(ofile, fmt, ## __VA_ARGS__);
} while(0)

int main(int argc, char **argv)
{
    double * A,*B,*C,*D,*E,*F;

    /* limit main ram to force to push in disk */
    setenv("STARPU_LIMIT_CPU_MEM", "160", 1);

    /* Initialize StarPU with default configuration */
    int ret = starpu_init(NULL);

    if (ret == -ENODEV) goto enodev;

    /* register a disk */
    int new_dd = starpu_disk_register(&starpu_disk_unistd_ops
, (void *) "/tmp/", 1024*1024*200);
    /* can't write on /tmp/ */
    if (new_dd == -ENOENT) goto enoent;

    /* allocate two memory spaces */
    starpu_malloc_flags((void **)&A, NX*sizeof(double), STARPU_MALLOC_COUNT
);
    starpu_malloc_flags((void **)&F, NX*sizeof(double), STARPU_MALLOC_COUNT
);

    FPRINTF(stderr, "TEST DISK MEMORY \n");

    unsigned int j;
    /* initialization with bad values */
    for(j = 0; j < NX; ++j)
    {
        A[j] = j;
        F[j] = -j;
    }

    starpu_data_handle_t vector_handleA, vector_handleB, vector_handleC,
vector_handleD, vector_handleE, vector_handleF;

    /* register vector in starpu */
    starpu_vector_data_register(&vector_handleA, STARPU_MAIN_RAM
, (uintptr_t)A, NX, sizeof(double));
    starpu_vector_data_register(&vector_handleB, -1, (uintptr_t) NULL, NX,
sizeof(double));
    starpu_vector_data_register(&vector_handleC, -1, (uintptr_t) NULL, NX,
sizeof(double));
    starpu_vector_data_register(&vector_handleD, -1, (uintptr_t) NULL, NX,
sizeof(double));
    starpu_vector_data_register(&vector_handleE, -1, (uintptr_t) NULL, NX,
sizeof(double));
    starpu_vector_data_register(&vector_handleF, STARPU_MAIN_RAM
, (uintptr_t)F, NX, sizeof(double));

    /* copy vector A->B, B->C... */
    starpu_data_cpy(vector_handleB, vector_handleA, 0, NULL, NULL);
    starpu_data_cpy(vector_handleC, vector_handleB, 0, NULL, NULL);
    starpu_data_cpy(vector_handleD, vector_handleC, 0, NULL, NULL);
    starpu_data_cpy(vector_handleE, vector_handleD, 0, NULL, NULL);
    starpu_data_cpy(vector_handleF, vector_handleE, 0, NULL, NULL);

    /* StarPU does not need to manipulate the array anymore so we can stop
 * monitoring it */

    /* free them */
    starpu_data_unregister(vector_handleA);
    starpu_data_unregister(vector_handleB);
    starpu_data_unregister(vector_handleC);
    starpu_data_unregister(vector_handleD);
    starpu_data_unregister(vector_handleE);
    starpu_data_unregister(vector_handleF);

```

```

/* check if computation is correct */
int try = 1;
for (j = 0; j < NX; ++j)
    if (A[j] != F[j])
    {
        printf("Fail A %f != F %f \n", A[j], F[j]);
        try = 0;
    }

/* free last vectors */
starpu_free_flags(A, NX*sizeof(double), STARPU_MALLOC_COUNT);
starpu_free_flags(F, NX*sizeof(double), STARPU_MALLOC_COUNT);

/* terminate StarPU, no task can be submitted after */
starpu_shutdown();

if(try)
    FPRINTF(stderr, "TEST SUCCESS\n");
else
    FPRINTF(stderr, "TEST FAIL\n");
return (try ? EXIT_SUCCESS : EXIT_FAILURE);

enodev:
return 77;
enoent:
return 77;
}

```

16.6 Examples: disk_compute

```

/* Try to write into disk memory
 * Use mechanism to push datas from main ram to disk ram
 */

#include <starpu.h>
#include <stdlib.h>
#include <stdio.h>
#include <sys/types.h>
#include <unistd.h>
#include <math.h>

#define NX (1024)

int main(int argc, char **argv)
{
    /* Initialize StarPU with default configuration */
    int ret = starpu_init(NULL);

    if (ret == -ENODEV) goto enodev;

    /* Initialize path and name */
    char pid_str[16];
    int pid = getpid();
    snprintf(pid_str, 16, "%d", pid);

    const char *name_file_start = "STARPU_DISK_COMPUTE_DATA_";
    const char *name_file_end = "STARPU_DISK_COMPUTE_DATA_RESULT_";

    char * path_file_start = malloc(strlen(base) + 1 + strlen(name_file_start) + 1);
    strcpy(path_file_start, base);
    strcat(path_file_start, "/");
    strcat(path_file_start, name_file_start);

    char * path_file_end = malloc(strlen(base) + 1 + strlen(name_file_end) + 1);
    strcpy(path_file_end, base);
    strcat(path_file_end, "/");
    strcat(path_file_end, name_file_end);

    /* register a disk */
    int new_dd = starpu_disk_register(&starpu_disk_unistd_ops
, (void *) base, 1024*1024*1);
    /* can't write on /tmp/ */
    if (new_dd == -ENOENT) goto enoent;

    unsigned dd = (unsigned) new_dd;

    printf("TEST DISK MEMORY \n");

    /* Imagine, you want to compute datas */
    int *A;

```

```

int *C;

starpu_malloc_flags((void **)&A, NX*sizeof(int), STARPU_MALLOC_COUNT);
starpu_malloc_flags((void **)&C, NX*sizeof(int), STARPU_MALLOC_COUNT);

unsigned int j;
/* you register them in a vector */
for(j = 0; j < NX; ++j)
{
    A[j] = j;
    C[j] = 0;
}

/* you create a file to store the vector ON the disk */
FILE * f = fopen(path_file_start, "wb+");
if (f == NULL)
    goto enoent2;

/* store it in the file */
fwrite(A, sizeof(int), NX, f);

/* close the file */
fclose(f);

/* create a file to store result */
f = fopen(path_file_end, "wb+");
if (f == NULL)
    goto enoent2;

/* replace all datas by 0 */
fwrite(C, sizeof(int), NX, f);

/* close the file */
fclose(f);

/* And now, you want to use your datas in StarPU */
/* Open the file ON the disk */
void * data = starpu_disk_open(dd, (void *) name_file_start, NX*sizeof(int));
void * data_result = starpu_disk_open(dd, (void *) name_file_end, NX*sizeof(int));

starpu_data_handle_t vector_handleA, vector_handleC;

/* register vector in starpu */
starpu_vector_data_register(&vector_handleA, dd, (uintptr_t) data, NX,
sizeof(int));

/* and do what you want with it, here we copy it into an other vector */
starpu_vector_data_register(&vector_handleC, dd, (uintptr_t) data_result
, NX, sizeof(int));

starpu_data_cpy(vector_handleC, vector_handleA, 0, NULL, NULL);

/* free them */
starpu_data_unregister(vector_handleA);
starpu_data_unregister(vector_handleC);

/* close them in StarPU */
starpu_disk_close(dd, data, NX*sizeof(int));
starpu_disk_close(dd, data_result, NX*sizeof(int));

/* check results */
f = fopen(path_file_end, "rb+");
if (f == NULL)
    goto enoent;
/* take datas */
int size = fread(C, sizeof(int), NX, f);

/* close the file */
fclose(f);

int try = 1;
for (j = 0; j < NX; ++j)
    if (A[j] != C[j])
    {
        printf("Fail A %d != C %d \n", A[j], C[j]);
        try = 0;
    }

starpu_free_flags(A, NX*sizeof(int), STARPU_MALLOC_COUNT);
starpu_free_flags(C, NX*sizeof(int), STARPU_MALLOC_COUNT);

```

```

    unlink(path_file_start);
    unlink(path_file_end);

    free(path_file_start);
    free(path_file_end);

    /* terminate StarPU, no task can be submitted after */
    starpu_shutdown();

    if(try)
        printf("TEST SUCCESS\n");
    else
        printf("TEST FAIL\n");
    return (try ? EXIT_SUCCESS : EXIT_FAILURE);

enodev:
    return 77;
enoent2:
    starpu_free_flags(A, NX*sizeof(int), STARPU_MALLOC_COUNT);
    starpu_free_flags(C, NX*sizeof(int), STARPU_MALLOC_COUNT);
enoent:
    unlink(path_file_start);
    unlink(path_file_end);

    free(path_file_start);
    free(path_file_end);

    starpu_shutdown();
    return 77;
}

```

16.7 Performances

Scheduling heuristics for Out-of-core are still relatively experimental. The tricky part is that you usually have to find a compromise between privileging locality (which avoids back and forth with the disk) and privileging the critical path, i.e. taking into account priorities to avoid lack of parallelism at the end of the task graph.

It is notably better to avoid defining different priorities to tasks with low priority, since that will make the scheduler want to schedule them by levels of priority, at the depense of locality.

The scheduling algorithms worth trying are thus `dmdar` and `lws`, which privilege data locality over priorities. There will be work on this area in the coming future.

16.8 Disk functions

There are various ways to operate a disk memory node, described by the structure `starpu_disk_ops`. For instance, the variable `starpu_disk_unistd_ops` uses read/write functions.

All structures are in [Out Of Core](#).

Chapter 17

MPI Support

The integration of MPI transfers within task parallelism is done in a very natural way by the means of asynchronous interactions between the application and StarPU. This is implemented in a separate `libstarpumpi` library which basically provides "StarPU" equivalents of `MPI_*` functions, where `void *` buffers are replaced with `starpu_↵data_handle_t`, and all GPU-RAM-NIC transfers are handled efficiently by StarPU-MPI. The user has to use the usual `mpirun` command of the MPI implementation to start StarPU on the different MPI nodes.

An MPI Insert Task function provides an even more seamless transition to a distributed application, by automatically issuing all required data transfers according to the task graph and an application-provided distribution.

17.1 Example used in this documentation

The example below will be used as the base for this documentation. It initializes a token on node 0, and the token is passed from node to node, incremented by one on each step. The code is not using StarPU yet.

```
for (loop = 0; loop < nloops; loop++) {
    int tag = loop*size + rank;

    if (loop == 0 && rank == 0)
    {
        token = 0;
        fprintf(stdout, "Start with token value %d\n", token);
    }
    else
    {
        MPI_Recv(&token, 1, MPI_INT, (rank+size-1)%size, tag, MPI_COMM_WORLD);
    }

    token++;

    if (loop == last_loop && rank == last_rank)
    {
        fprintf(stdout, "Finished: token value %d\n", token);
    }
    else
    {
        MPI_Send(&token, 1, MPI_INT, (rank+1)%size, tag+1, MPI_COMM_WORLD);
    }
}
```

17.2 About not using the MPI support

Although StarPU provides MPI support, the application programmer may want to keep his MPI communications as they are for a start, and only delegate task execution to StarPU. This is possible by just using `starpu_data_acquire()`, for instance:

```
for (loop = 0; loop < nloops; loop++) {
    int tag = loop*size + rank;

    /* Acquire the data to be able to write to it */
    starpu_data_acquire(token_handle, STARPU_W);
    if (loop == 0 && rank == 0)
    {
        token = 0;
        fprintf(stdout, "Start with token value %d\n", token);
    }
    else
    {
        MPI_Recv(&token, 1, MPI_INT, (rank+size-1)%size, tag, MPI_COMM_WORLD);
    }
    starpu_data_release(token_handle);

    /* Task delegation to StarPU to increment the token. The execution might
     * be performed on a CPU, a GPU, etc. */
    increment_token();

    /* Acquire the update data to be able to read from it */
    starpu_data_acquire(token_handle, STARPU_R);
    if (loop == last_loop && rank == last_rank)
    {
        fprintf(stdout, "Finished: token value %d\n", token);
    }
    else
    {
        MPI_Send(&token, 1, MPI_INT, (rank+1)%size, tag+1, MPI_COMM_WORLD);
    }
    starpu_data_release(token_handle);
}
```

In that case, `libstarpumpi` is not needed. One can also use `MPI_Isend()` and `MPI_Irecv()`, by calling `starpu_data_release()` after `MPI_Wait()` or `MPI_Test()` have notified completion.

It is however better to use `libstarpumpi`, to save the application from having to synchronize with `starpu_data_acquire()`, and instead just submit all tasks and communications asynchronously, and wait for the overall completion.

17.3 Simple Example

The flags required to compile or link against the MPI layer are accessible with the following commands:

```
$ pkg-config --cflags starpumpi-1.2 # options for the compiler
$ pkg-config --libs starpumpi-1.2  # options for the linker
```

```
void increment_token(void)
{
    struct starpu_task *task = starpu_task_create();

    task->cl = &increment_cl;
    task->handles[0] = token_handle;

    starpu_task_submit(task);
}

int main(int argc, char **argv)
{
    int rank, size;

    starpu_init(NULL);
```

```

starpu_mpi_init(&argc, &argv, 1);
starpu_mpi_comm_rank(MPI_COMM_WORLD, &rank);
starpu_mpi_comm_size(MPI_COMM_WORLD, &size);

starpu_vector_data_register(&token_handle, STARPU_MAIN_RAM, (
    uintptr_t)&token, 1, sizeof(unsigned));

unsigned nloops = NITER;
unsigned loop;

unsigned last_loop = nloops - 1;
unsigned last_rank = size - 1;

for (loop = 0; loop < nloops; loop++)
{
    int tag = loop*size + rank;

    if (loop == 0 && rank == 0)
    {
        starpu_data_acquire(token_handle, STARPU_W);
        token = 0;
        fprintf(stdout, "Start with token value %d\n", token);
        starpu_data_release(token_handle);
    }
    else
    {
        starpu_mpi_irecv_detached(token_handle, (rank+size-1)%size, tag,
            MPI_COMM_WORLD, NULL, NULL);
    }

    increment_token();

    if (loop == last_loop && rank == last_rank)
    {
        starpu_data_acquire(token_handle, STARPU_R);
        fprintf(stdout, "Finished: token value %d\n", token);
        starpu_data_release(token_handle);
    }
    else
    {
        starpu_mpi_isend_detached(token_handle, (rank+1)%size, tag+1,
            MPI_COMM_WORLD, NULL, NULL);
    }
}

starpu_task_wait_for_all();

starpu_mpi_shutdown();
starpu_shutdown();

if (rank == last_rank)
{
    fprintf(stderr, "[%d] token = %d == %d * %d ?\n", rank, token, nloops, size);
    STARPU_ASSERT(token == nloops*size);
}

```

We have here replaced `MPI_Recv()` and `MPI_Send()` with `starpu_mpi_irecv_detached()` and `starpu_mpi_isend_detached()`, which just submit the communication to be performed. The implicit sequential consistency dependencies provide synchronization between mpi reception and emission and the corresponding tasks. The only remaining synchronization with `starpu_data_acquire()` is at the beginning and the end.

17.4 How to Initialize StarPU-MPI

As seen in the previous example, one has to call `starpu_mpi_init()` to initialize StarPU-MPI. The third parameter of the function indicates if MPI should be initialized by StarPU or if the application will do it itself. If the application initializes MPI itself, it must call `MPI_Init_thread()` with `MPI_THREAD_SERIALIZED` or `MPI_THREAD_MULTIPLE`, since StarPU-MPI uses a separate thread to perform the communications. `MPI_THREAD_MULTIPLE` is necessary if the application also performs some MPI communications.

17.5 Point To Point Communication

The standard point to point communications of MPI have been implemented. The semantic is similar to the MPI one, but adapted to the DSM provided by StarPU. A MPI request will only be submitted when the data is available in the main memory of the node submitting the request.

There are two types of asynchronous communications: the classic asynchronous communications and the detached communications. The classic asynchronous communications (`starpu_mpi_isend()` and `starpu_mpi_irecv()`) need to be followed by a call to `starpu_mpi_wait()` or to `starpu_mpi_test()` to wait for or to test the completion of the communication. Waiting for or testing the completion of detached communications is not possible, this is done internally by StarPU-MPI, on completion, the resources are automatically released. This mechanism is similar to the pthread detach state attribute which determines whether a thread will be created in a joinable or a detached state.

Internally, all communication are divided in 2 communications, a first message is used to exchange an envelope describing the data (i.e its tag and its size), the data itself is sent in a second message. All MPI communications submitted by StarPU uses a unique tag which has a default value, and can be accessed with the functions `starpu_mpi_get_communication_tag()` and `starpu_mpi_set_communication_tag()`. The matching of tags with corresponding requests is done within StarPU-MPI.

For any userland communication, the call of the corresponding function (e.g `starpu_mpi_isend()`) will result in the creation of a StarPU-MPI request, the function `starpu_data_acquire_cb()` is then called to asynchronously request StarPU to fetch the data in main memory; when the data is ready and the corresponding buffer has already been received by MPI, it will be copied in the memory of the data, otherwise the request is stored in the *early requests list*. Sending requests are stored in the *ready requests list*.

While requests need to be processed, the StarPU-MPI progression thread does the following:

1. it polls the *ready requests list*. For all the ready requests, the appropriate function is called to post the corresponding MPI call. For example, an initial call to `starpu_mpi_isend()` will result in a call to `MPI_Isend()`. If the request is marked as detached, the request will then be added in the *detached requests list*.
2. it posts a `MPI_Irecv()` to retrieve a data envelope.
3. it polls the *detached requests list*. For all the detached requests, it tests its completion of the MPI request by calling `MPI_Test()`. On completion, the data handle is released, and if a callback was defined, it is called.
4. finally, it checks if a data envelope has been received. If so, if the data envelope matches a request in the *early requests list* (i.e the request has already been posted by the application), the corresponding MPI call is posted (similarly to the first step above).

If the data envelope does not match any application request, a temporary handle is created to receive the data, a StarPU-MPI request is created and added into the *ready requests list*, and thus will be processed in the first step of the next loop.

[MPIPtpCommunication](#) gives the list of all the point to point communications defined in StarPU-MPI.

17.6 Exchanging User Defined Data Interface

New data interfaces defined as explained in [Defining A New Data Interface](#) can also be used within StarPU-MPI and exchanged between nodes. Two functions needs to be defined through the type `starpu_data_interface_ops`. The function `starpu_data_interface_ops::pack_data` takes a handle and returns a contiguous memory buffer allocated with

```
starpu_malloc_flags(ptr, size, 0)
```

along with its size where data to be conveyed to another node should be copied. The reversed operation is implemented in the function `starpu_data_interface_ops::unpack_data` which takes a contiguous memory buffer and recreates the data handle.

```

static int complex_pack_data(starpu_data_handle_t handle, unsigned node, void **ptr,
                             ssize_t *count)
{
    STARPU_ASSERT(starpu_data_test_if_allocated_on_node(handle, node));

    struct starpu_complex_interface *complex_interface =
        (struct starpu_complex_interface *) starpu_data_get_interface_on_node(
            handle, node);

    *count = complex_get_size(handle);
    starpu_malloc_flags(ptr, *count, 0);
    memcpy(*ptr, complex_interface->real, complex_interface->nx*sizeof(double));
    memcpy(*ptr+complex_interface->nx*sizeof(double), complex_interface->imaginary,
        complex_interface->nx*sizeof(double));

    return 0;
}

static int complex_unpack_data(starpu_data_handle_t handle, unsigned node, void *ptr,
                               size_t count)
{
    STARPU_ASSERT(starpu_data_test_if_allocated_on_node(handle, node));

    struct starpu_complex_interface *complex_interface =
        (struct starpu_complex_interface *) starpu_data_get_interface_on_node(
            handle, node);

    memcpy(complex_interface->real, ptr, complex_interface->nx*sizeof(double));
    memcpy(complex_interface->imaginary, ptr+complex_interface->nx*sizeof(double),
        complex_interface->nx*sizeof(double));

    return 0;
}

static struct starpu_data_interface_ops interface_complex_ops =
{
    ...
    .pack_data = complex_pack_data,
    .unpack_data = complex_unpack_data
};

```

Instead of defining pack and unpack operations, users may want to attach a MPI type to their user defined data interface. The function `starpu_mpi_datatype_register()` allows to do so. This function takes 3 parameters: the data handle for which the MPI datatype is going to be defined, a function's pointer that will create the MPI datatype, and a function's pointer that will free the MPI datatype.

```

starpu_data_interface handle;
starpu_complex_data_register(&handle, STARPU_MAIN_RAM, real, imaginary, 2);
starpu_mpi_datatype_register(handle, starpu_complex_interface_datatype_allocate
    , starpu_complex_interface_datatype_free);

```

The functions to create and free the MPI datatype are defined as follows.

```

void starpu_complex_interface_datatype_allocate(starpu_data_handle_t handle,
        MPI_Datatype *mpi_datatype)
{
    int ret;

    int blocklengths[2];
    MPI_Aint displacements[2];
    MPI_Datatype types[2] = {MPI_DOUBLE, MPI_DOUBLE};

    struct starpu_complex_interface *complex_interface =
        (struct starpu_complex_interface *) starpu_data_get_interface_on_node(
            handle, STARPU_MAIN_RAM);

    MPI_Address(complex_interface, displacements);
    MPI_Address(&complex_interface->imaginary, displacements+1);
    displacements[1] -= displacements[0];
    displacements[0] = 0;

    blocklengths[0] = complex_interface->nx;
    blocklengths[1] = complex_interface->nx;

    ret = MPI_Type_create_struct(2, blocklengths, displacements, types, mpi_datatype);
    STARPU_ASSERT_MSG(ret == MPI_SUCCESS, "MPI_Type_contiguous failed");

    ret = MPI_Type_commit(mpi_datatype);
}

```

```

        STARPU_ASSERT_MSG(ret == MPI_SUCCESS, "MPI_Type_commit failed");
    }

void starpu_complex_interface_datatype_free(MPI_Datatype *mpi_datatype)
{
    MPI_Type_free(mpi_datatype);
}

```

Note that it is important to make sure no communication is going to occur before the function `starpu_mpi_datatype_register()` is called. This would produce an undefined result as the data may be received before the function is called, and so the MPI datatype would not be known by the StarPU-MPI communication engine, and the data would be processed with the pack and unpack operations.

```

starpu_data_interface handle;
starpu_complex_data_register(&handle, STARPU_MAIN_RAM, real, imaginary, 2);
starpu_mpi_datatype_register(handle, starpu_complex_interface_datatype_allocate
    , starpu_complex_interface_datatype_free);

starpu_mpi_barrier(MPI_COMM_WORLD);

```

17.7 MPI Insert Task Utility

To save the programmer from having to explicit all communications, StarPU provides an "MPI Insert Task Utility". The principle is that the application decides a distribution of the data over the MPI nodes by allocating it and notifying StarPU of this decision, i.e. tell StarPU which MPI node "owns" which data. It also decides, for each handle, an MPI tag which will be used to exchange the content of the handle. All MPI nodes then process the whole task graph, and StarPU automatically determines which node actually execute which task, and trigger the required MPI transfers.

The list of functions is described in [MPIInsertTask](#).

Here an stencil example showing how to use `starpu_mpi_task_insert()`. One first needs to define a distribution function which specifies the locality of the data. Note that the data needs to be registered to MPI by calling `starpu_mpi_data_register()`. This function allows to set the distribution information and the MPI tag which should be used when communicating the data. It also allows to automatically clear the MPI communication cache when unregistering the data.

```

/* Returns the MPI node number where data is */
int my_distrib(int x, int y, int nb_nodes) {
    /* Block distrib */
    return ((int)(x / sqrt(nb_nodes) + (y / sqrt(nb_nodes)) * sqrt(nb_nodes))) % nb_nodes;

    // /* Other examples useful for other kinds of computations */
    // /* / distrib */
    // return (x+y) % nb_nodes;

    // /* Block cyclic distrib */
    // unsigned side = sqrt(nb_nodes);
    // return x % side + (y % side) * side;
}

```

Now the data can be registered within StarPU. Data which are not owned but will be needed for computations can be registered through the lazy allocation mechanism, i.e. with a `home_node` set to `-1`. StarPU will automatically allocate the memory when it is used for the first time.

One can note an optimization here (the `else if` test): we only register data which will be needed by the tasks that we will execute.

```

unsigned matrix[X][Y];
starpu_data_handle_t data_handles[X][Y];

for(x = 0; x < X; x++) {
    for(y = 0; y < Y; y++) {
        int mpi_rank = my_distrib(x, y, size);
        if (mpi_rank == my_rank)
            /* Owning data */
            starpu_variable_data_register(&data_handles[x][y], STARPU_MAIN_RAM
            ,
            (uintptr_t)&(matrix[x][y]), sizeof(unsigned));
        else if (my_rank == my_distrib(x+1, y, size) || my_rank == my_distrib(x-1, y, size)
            || my_rank == my_distrib(x, y+1, size) || my_rank == my_distrib(x, y-1, size))
            /* I don't own this index, but will need it for my computations */
            starpu_variable_data_register(&data_handles[x][y], -1,
            (uintptr_t) NULL, sizeof(unsigned));
        else
            /* I know it's useless to allocate anything for this */
            data_handles[x][y] = NULL;
        if (data_handles[x][y]) {
            starpu_mpi_data_register(data_handles[x][y], x*X+y, mpi_rank);
        }
    }
}

```

Now `starpu_mpi_task_insert()` can be called for the different steps of the application.

```

for(loop=0 ; loop<niter; loop++)
    for (x = 1; x < X-1; x++)
        for (y = 1; y < Y-1; y++)
            starpu_mpi_task_insert(MPI_COMM_WORLD, &stencil5_c1,
            STARPU_RW, data_handles[x][y],
            STARPU_R, data_handles[x-1][y],
            STARPU_R, data_handles[x+1][y],
            STARPU_R, data_handles[x][y-1],
            STARPU_R, data_handles[x][y+1],
            0);
starpu_task_wait_for_all();

```

I.e. all MPI nodes process the whole task graph, but as mentioned above, for each task, only the MPI node which owns the data being written to (here, `data_handles[x][y]`) will actually run the task. The other MPI nodes will automatically send the required data.

To tune the placement of tasks among MPI nodes, one can use `STARPU_EXECUTE_ON_NODE` or `STARPU_EXECUTE_ON_DATA` to specify an explicit node, or the node of a given data (e.g. one of the parameters), or use `starpu_mpi_node_selection_register_policy()` and `STARPU_NODE_SELECTION_POLICY` to provide a dynamic policy.

A function `starpu_mpi_task_build()` is also provided with the aim to only construct the task structure. All MPI nodes need to call the function, which posts the required send/rcv on the various nodes which have to. Only the node which is to execute the task will then return a valid task structure, others will return `NULL`. This node must submit the task. All nodes then need to call the function `starpu_mpi_task_post_build()` – with the same list of arguments as `starpu_mpi_task_build()` – to post all the necessary data communications meant to happen after the task execution.

```

struct starpu_task *task;
task = starpu_mpi_task_build(MPI_COMM_WORLD, &c1,
    STARPU_RW, data_handles[0],
    STARPU_R, data_handles[1],
    0);
if (task) starpu_task_submit(task);
starpu_mpi_task_post_build(MPI_COMM_WORLD, &c1,
    STARPU_RW, data_handles[0],
    STARPU_R, data_handles[1],
    0);

```

17.8 Pruning MPI task insertion

Making all MPI nodes process the whole graph can be a concern with a growing number of nodes. To avoid this, the application can prune the task for loops according to the data distribution, so as to only submit tasks on nodes which have to care about them (either to execute them, or to send the required data).

A way to do some of this quite easily can be to just add an `if` like this:

```
for(loop=0 ; loop<niter; loop++)
    for (x = 1; x < X-1; x++)
        for (y = 1; y < Y-1; y++)
            if (my_distrib(x,y,size) == my_rank
                || my_distrib(x-1,y,size) == my_rank
                || my_distrib(x+1,y,size) == my_rank
                || my_distrib(x,y-1,size) == my_rank
                || my_distrib(x,y+1,size) == my_rank)
                starpu_mpi_task_insert(MPI_COMM_WORLD, &stencil5_c1,
                                       STARPU_RW, data_handles[x][y],
                                       STARPU_R, data_handles[x-1][y],
                                       STARPU_R, data_handles[x+1][y],
                                       STARPU_R, data_handles[x][y-1],
                                       STARPU_R, data_handles[x][y+1],
                                       0);

starpu_task_wait_for_all();
```

This permits to drop the cost of function call argument passing and parsing.

If the `my_distrib` function can be inlined by the compiler, the latter can improve the test.

If the `size` can be made a compile-time constant, the compiler can considerably improve the test further.

If the distribution function is not too complex and the compiler is very good, the latter can even optimize the `for` loops, thus dramatically reducing the cost of task submission.

To estimate quickly how long task submission takes, and notably how much pruning saves, a quick and easy way is to measure the submission time of just one of the MPI nodes. This can be achieved by running the application on just one MPI node with the following environment variables:

```
export STARPU_DISABLE_KERNELS=1
export STARPU_MPI_FAKE_RANK=2
export STARPU_MPI_FAKE_SIZE=1024
```

Here we have disabled the kernel function call to skip the actual computation time and only keep submission time, and we have asked StarPU to fake running on MPI node 2 out of 1024 nodes.

17.9 Temporary Data

To be able to use `starpu_mpi_task_insert()`, one has to call `starpu_mpi_data_register()`, so that StarPU-MPI can know what it needs to do for each data. Parameters of `starpu_mpi_data_register()` are normally the same on all nodes for a given data, so that all nodes agree on which node owns the data, and which tag is used to transfer its value.

It can however be useful to register e.g. some temporary data on just one node, without having to register a dumb handle on all nodes, while only one node will actually need to know about it. In this case, nodes which will not need the data can just pass `NULL` to `starpu_mpi_task_insert()`:


```

starpu_data_handle_t data0 = NULL;
if (rank == 0) {
    starpu_variable_data_register(&data0, STARPU_MAIN_RAM,
    (uintptr_t) &val0, sizeof(val0));
    starpu_mpi_data_register(data0, 0, rank);
}
starpu_mpi_task_insert(MPI_COMM_WORLD, &cl, STARPU_W, data0, 0); /* Executes
on node 0 */

```

Here, nodes whose rank is not 0 will simply not take care of the data, and consider it to be on another node.

This can be mixed various way, for instance here node 1 determines that it does not have to care about data0, but knows that it should send the value of its data1 to node 0, which owns data and thus will need the value of data1 to execute the task:

```

starpu_data_handle_t data0 = NULL, data1, data;
if (rank == 0) {
    starpu_variable_data_register(&data0, STARPU_MAIN_RAM,
    (uintptr_t) &val0, sizeof(val0));
    starpu_mpi_data_register(data0, -1, rank);
    starpu_variable_data_register(&data1, -1, 0, sizeof(vall));
    starpu_variable_data_register(&data, STARPU_MAIN_RAM, (
    uintptr_t) &val, sizeof(val));
} else if (rank == 1) {
    starpu_variable_data_register(&data1, STARPU_MAIN_RAM,
    (uintptr_t) &vall, sizeof(vall));
    starpu_variable_data_register(&data, -1, 0, sizeof(val));
}
starpu_mpi_data_register(data, 42, 0);
starpu_mpi_data_register(data1, 43, 1);
starpu_mpi_task_insert(MPI_COMM_WORLD, &cl, STARPU_W, data, STARPU_R,
data0, STARPU_R, data1, 0); /* Executes on node 0 */

```

17.10 Per-node Data

Further than temporary data on just one node, one may want per-node data, to e.g. replicate some computation because that is less expensive than communicating the value over MPI:

```

starpu_data_handle pernode, data0, data1;
starpu_variable_data_register(&pernode, -1, 0, sizeof(val));
starpu_mpi_data_register(pernode, -1, STARPU_MPI_PER_NODE);

/* Normal data: one on node0, one on node1 */
if (rank == 0) {
    starpu_variable_data_register(&data0, STARPU_MAIN_RAM,
    (uintptr_t) &val0, sizeof(val0));
    starpu_variable_data_register(&data1, -1, 0, sizeof(vall));
} else if (rank == 1) {
    starpu_variable_data_register(&data0, -1, 0, sizeof(vall));
    starpu_variable_data_register(&data1, STARPU_MAIN_RAM,
    (uintptr_t) &vall, sizeof(vall));
}
starpu_mpi_data_register(data0, 42, 0);
starpu_mpi_data_register(data1, 43, 1);

starpu_mpi_task_insert(MPI_COMM_WORLD, &cl, STARPU_W, pernode, 0); /* Will be
replicated on all nodes */

starpu_mpi_task_insert(MPI_COMM_WORLD, &cl2, STARPU_RW, data0, STARPU_R,
pernode); /* Will execute on node 0, using its own pernode*/
starpu_mpi_task_insert(MPI_COMM_WORLD, &cl2, STARPU_RW, data1, STARPU_R,
pernode); /* Will execute on node 1, using its own pernode*/

```

One can turn a normal data into pernode data, by first broadcasting it to all nodes:

```

starpu_data_handle data;
starpu_variable_data_register(&data, -1, 0, sizeof(val));
starpu_mpi_data_register(data, 42, 0);

/* Compute some value */
starpu_mpi_task_insert(MPI_COMM_WORLD, &cl, STARPU_W, data, 0); /* Node 0
computes it */

/* Get it on all nodes */
starpu_mpi_get_data_on_all_nodes_detached(MPI_COMM_WORLD, data);
/* And turn it per-node */
starpu_mpi_data_set_rank(data, STARPU_MPI_PER_NODE);

```

The data can then be used just like pernode above.

17.11 MPI cache support

StarPU-MPI automatically optimizes duplicate data transmissions: if an MPI node B needs a piece of data D from MPI node A for several tasks, only one transmission of D will take place from A to B, and the value of D will be kept on B as long as no task modifies D.

If a task modifies D, B will wait for all tasks which need the previous value of D, before invalidating the value of D. As a consequence, it releases the memory occupied by D. Whenever a task running on B needs the new value of D, allocation will take place again to receive it.

Since tasks can be submitted dynamically, StarPU-MPI can not know whether the current value of data D will again be used by a newly-submitted task before being modified by another newly-submitted task, so until a task is submitted to modify the current value, it can not decide by itself whether to flush the cache or not. The application can however explicitly tell StarPU-MPI to flush the cache by calling `starpu_mpi_cache_flush()` or `starpu_mpi_cache_flush_all_data()`, for instance in case the data will not be used at all any more (see for instance the cholesky example in `mpi/examples/matrix_decomposition`), or at least not in the close future. If a newly-submitted task actually needs the value again, another transmission of D will be initiated from A to B. A mere `starpu_mpi_cache_flush_all_data()` can for instance be added at the end of the whole algorithm, to express that no data will be reused after this (or at least that it is not interesting to keep them in cache). It may however be interesting to add fine-grained `starpu_mpi_cache_flush()` calls during the algorithm; the effect for the data deallocation will be the same, but it will additionally release some pressure from the StarPU-MPI cache hash table during task submission.

One can determine whether a piece of is cached with `starpu_mpi_cached_receive()` and `starpu_mpi_cached_send()`.

The whole caching behavior can be disabled thanks to the `STARPU_MPI_CACHE` environment variable. The variable `STARPU_MPI_CACHE_STATS` can be set to 1 to enable the runtime to display messages when data are added or removed from the cache holding the received data.

17.12 MPI Data migration

The application can dynamically change its mind about the data distribution, to balance the load over MPI nodes for instance. This can be done very simply by requesting an explicit move and then change the registered rank. For instance, we here switch to a new distribution function `my_distrib2`: we first register any data which wasn't registered already and will be needed, then migrate the data, and register the new location.

```
for(x = 0; x < X; x++) {
    for (y = 0; y < Y; y++) {
        int mpi_rank = my_distrib2(x, y, size);
        if (!data_handles[x][y] && (mpi_rank == my_rank
            || my_rank == my_distrib(x+1, y, size) || my_rank == my_distrib(x-1, y, size)
            || my_rank == my_distrib(x, y+1, size) || my_rank == my_distrib(x, y-1, size)))
            /* Register newly-needed data */
            starpu_variable_data_register(&data_handles[x][y], -1,
                (uintptr_t)NULL, sizeof(unsigned));
        if (data_handles[x][y]) {
            /* Migrate the data */
            starpu_mpi_data_migrate(MPI_COMM_WORLD, data_handles[x][y], mpi_rank);
        }
    }
}
```

From then on, further tasks submissions will use the new data distribution, which will thus change both MPI communications and task assignments.

Very importantly, since all nodes have to agree on which node owns which data so as to determine MPI communications and task assignments the same way, all nodes have to perform the same data migration, and at the same point among task submissions. It thus does not require a strict synchronization, just a clear separation of task submissions before and after the data redistribution.

Before data unregistration, it has to be migrated back to its original home node (the value, at least), since that is where the user-provided buffer resides. Otherwise the unregistration will complain that it does not have the latest value on the original home node.

```

for(x = 0; x < X; x++) {
    for (y = 0; y < Y; y++) {
        if (data_handles[x][y]) {
            int mpi_rank = my_distrib(x, y, size);
            /* Get back data to original place where the user-provided buffer is. */
            starpu_mpi_get_data_on_node_detached(MPI_COMM_WORLD,
            data_handles[x][y], mpi_rank, NULL, NULL);
            /* And unregister it */
            starpu_data_unregister(data_handles[x][y]);
        }
    }
}

```

17.13 MPI Collective Operations

The functions are described in [MPICollectiveOperations](#).

```

if (rank == root)
{
    /* Allocate the vector */
    vector = malloc(nblocks * sizeof(float *));
    for(x=0 ; x<nblocks ; x++)
    {
        starpu_malloc((void **)&vector[x], block_size*sizeof(float));
    }
}

/* Allocate data handles and register data to StarPU */
data_handles = malloc(nblocks*sizeof(starpu_data_handle_t *));
for(x = 0; x < nblocks ; x++)
{
    int mpi_rank = my_distrib(x, nodes);
    if (rank == root) {
        starpu_vector_data_register(&data_handles[x], STARPU_MAIN_RAM
        , (uintptr_t)vector[x],
        blocks_size, sizeof(float));
    }
    else if ((mpi_rank == rank) || ((rank == mpi_rank+1 || rank == mpi_rank-1))) {
        /* I own this index, or i will need it for my computations */
        starpu_vector_data_register(&data_handles[x], -1, (uintptr_t)NULL,
        block_size, sizeof(float));
    }
    else {
        /* I know it's useless to allocate anything for this */
        data_handles[x] = NULL;
    }
    if (data_handles[x]) {
        starpu_mpi_data_register(data_handles[x], x*nblocks+y, mpi_rank);
    }
}

/* Scatter the matrix among the nodes */
starpu_mpi_scatter_detached(data_handles, nblocks, root, MPI_COMM_WORLD);

/* Calculation */
for(x = 0; x < nblocks ; x++) {
    if (data_handles[x]) {
        int owner = starpu_data_get_rank(data_handles[x]);
        if (owner == rank) {
            starpu_task_insert(&c1, STARPU_RW, data_handles[x], 0);
        }
    }
}

/* Gather the matrix on main node */
starpu_mpi_gather_detached(data_handles, nblocks, 0, MPI_COMM_WORLD);

```


Chapter 18

FFT Support

StarPU provides `libstarpuffft`, a library whose design is very similar to both `fftw` and `cufft`, the difference being that it takes benefit from both CPUs and GPUs. It should however be noted that GPUs do not have the same precision as CPUs, so the results may differ by a negligible amount.

Different precisions are available, namely float, double and long double precisions, with the following `fftw` naming conventions:

- double precision structures and functions are named e.g. `starpufft_execute()`
- float precision structures and functions are named e.g. `starpufftf_execute()`
- long double precision structures and functions are named e.g. `starpufftl_execute()`

The documentation below is given with names for double precision, replace `starpufft_` with `starpufftf_` or `starpufftl_` as appropriate.

Only complex numbers are supported at the moment.

The application has to call `starpufft_init()` before calling `starpufft` functions.

Either main memory pointers or data handles can be provided.

- To provide main memory pointers, use `starpufft_start()` or `starpufft_execute()`. Only one FFT can be performed at a time, because StarPU will have to register the data on the fly. In the `starpufft_start()` case, `starpufft_cleanup()` needs to be called to unregister the data.
- To provide data handles (which is preferable), use `starpufft_start_handle()` (preferred) or `starpufft_execute_handle()`. Several FFTs tasks can be submitted for a given plan, which permits e.g. to start a series of FFT with just one plan. `starpufft_start_handle()` is preferable since it does not wait for the task completion, and thus permits to enqueue a series of tasks.

All functions are defined in [FFT Support](#).

18.1 Compilation

The flags required to compile or link against the FFT library are accessible with the following commands:

```
$ pkg-config --cflags starpufft-1.2 # options for the compiler
$ pkg-config --libs starpufft-1.2  # options for the linker
```

Also pass the option `-static` if the application is to be linked statically.

Chapter 19

MIC/SCC Support

19.1 Compilation

SCC support just needs the presence of the RCCE library.

MIC Xeon Phi support actually needs two compilations of StarPU, one for the host and one for the device. The `PATH` environment variable has to include the path to the cross-compilation toolchain, for instance `/usr/linux-k10m-4.7/bin`. The `SINK_PKG_CONFIG_PATH` environment variable should include the path to the cross-compiled `hwloc.pc`. The script `mic-configure` can then be used to achieve the two compilations: it basically calls `configure` as appropriate from two new directories: `build_mic` and `build_host`. `make` and `make install` can then be used as usual and will recurse into both directories. If different configuration options are needed for the host and for the mic, one can use `-with-host-param=-with-fxt` for instance to specify the `-with-fxt` option for the host only, or `-with-mic-param=-with-fxt` for the mic only.

One can also run StarPU just natively on the Xeon Phi, i.e. it will only run directly on the Phi without any exchange with the host CPU. The binaries in `build_mic` can be run that way.

For MPI support, you will probably have to specify different MPI compiler path or option for the host and the device builds, for instance:

```
./mic-configure --with-mic-param=--with-mpicc="/.../mpicc -mmic" \
  --with-host-param=--with-mpicc="/.../mpicc"
```

In case you have troubles with the `coi` or `scif` libraries (the Intel paths are really not standard, it seems...), you can still make a build in native mode only, by using `mic-configure --enable-native-mic` (and notably without `--enable-mic` since in that case we don't need mic offloading support).

19.2 Porting Applications To MIC Xeon Phi / SCC

The simplest way to port an application to MIC Xeon Phi or SCC is to set the field `starpu_codelet::cpu_funcs_name`, to provide StarPU with the function name of the CPU implementation, so for instance:

```
struct starpu_codelet cl = {
    .cpu_funcs = {myfunc},
    .cpu_funcs_name = {"myfunc"},
    .nbuffers = 1,
}
```

StarPU will thus simply use the existing CPU implementation (cross-rebuilt in the MIC Xeon Phi case). The functions have to be globally-visible (i.e. not `static`) for StarPU to be able to look them up, and `-rdynamic` must be passed to `gcc` (or `-export-dynamic` to `ld`) so that symbols of the main program are visible.

If you have used the `.where` field, you additionally need to add in it `STARPU_MIC` for the Xeon Phi, and/or `STARPU_SCC` for the SCC.

For non-native MIC Xeon Phi execution, the 'main' function of the application, on the sink, should call `starpu_init()` immediately upon start-up; the `starpu_init()` function never returns. On the host, the 'main' function may freely perform application related initialization calls as usual, before calling `starpu_init()`.

For MIC Xeon Phi, the application may programmatically detect whether executing on the sink or on the host, by checking whether the `STARPU_SINK` environment variable is defined (on the sink) or not (on the host).

For SCC execution, the function `starpu_initialize()` also has to be used instead of `starpu_init()`, so as to pass `argc` and `argv`.

19.3 Launching Programs

SCC programs are started through RCCE.

MIC programs are started from the host. StarPU automatically starts the same program on MIC devices. It however needs to get the MIC-cross-built binary. It will look for the file given by the environment variable `STARPU_MIC_SINK_PROGRAM_NAME` or in the directory given by the environment variable `STARPU_MIC_SINK_PROGRAM_PATH`, or in the field `starpu_conf::mic_sink_program_path`. It will also look in the current directory for the same binary name plus the suffix `-mic` or `_mic`.

The testsuite can be started by simply running `make check` from the top directory. It will recurse into both `build_host` to run tests with only the host, and into `build_mic` to run tests with both the host and the MIC devices. Single tests with the host and the MIC can be run by starting `./loader-cross.sh ./the_test` from `build_mic/tests`.

Chapter 20

C Extensions

When GCC plug-in support is available, StarPU builds a plug-in for the GNU Compiler Collection (GCC), which defines extensions to languages of the C family (C, C++, Objective-C) that make it easier to write StarPU code. This feature is only available for GCC 4.5 and later; it is known to work with GCC 4.5, 4.6, and 4.7. You may need to install a specific `-dev` package of your distro, such as `gcc-4.6-plugin-dev` on Debian and derivatives. In addition, the plug-in's test suite is only run when GNU Guile (<http://www.gnu.org/software/guile/>) is found at `configure`-time. Building the GCC plug-in can be disabled by configuring with `--disable-gcc-extensions`.

Those extensions include syntactic sugar for defining tasks and their implementations, invoking a task, and manipulating data buffers. Use of these extensions can be made conditional on the availability of the plug-in, leading to valid C sequential code when the plug-in is not used ([Using C Extensions Conditionally](#)).

When StarPU has been installed with its GCC plug-in, programs that use these extensions can be compiled this way:

```
$ gcc -c -fplugin='pkg-config starpu-1.2 --variable=gccplugin' foo.c
```

When the plug-in is not available, the above `pkg-config` command returns the empty string.

In addition, the `-fplugin-arg-starpu-verbose` flag can be used to obtain feedback from the compiler as it analyzes the C extensions used in source files.

This section describes the C extensions implemented by StarPU's GCC plug-in. It does not require detailed knowledge of the StarPU library.

Note: this is still an area under development and subject to change.

20.1 Defining Tasks

The StarPU GCC plug-in views tasks as “extended” C functions:

- tasks may have several implementations—e.g., one for CPUs, one written in OpenCL, one written in CUDA;
- tasks may have several implementations of the same target—e.g., several CPU implementations;
- when a task is invoked, it may run in parallel, and StarPU is free to choose any of its implementations.

Tasks and their implementations must be *declared*. These declarations are annotated with attributes (<http://gcc.gnu.org/onlinedocs/gcc/Attribute-Syntax.html#Attribute-Syntax>): the declaration of a task is a regular C function declaration with an additional `task` attribute, and task implementations are declared with a `task_implementation` attribute.

The following function attributes are provided:

task Declare the given function as a StarPU task. Its return type must be `void`. When a function declared as `task` has a user-defined body, that body is interpreted as the implicit definition of the task's CPU implementation (see example below). In all cases, the actual definition of a task's body is automatically generated by the compiler.

Under the hood, declaring a task leads to the declaration of the corresponding `codelet` ([Codelet and Tasks](#)). If one or more task implementations are declared in the same compilation unit, then the codelet and the function itself are also defined; they inherit the scope of the task.

Scalar arguments to the task are passed by value and copied to the target device if need be—technically, they are passed as the buffer `starpu_task::cl_arg` ([Codelet and Tasks](#)).

Pointer arguments are assumed to be registered data buffers—the handles argument of a task (`starpu_task::handles`); `const`-qualified pointer arguments are viewed as read-only buffers ([STARPU_R](#)), and non-`const`-qualified buffers are assumed to be used read-write ([STARPU_RW](#)). In addition, the `output` type attribute can be as a type qualifier for output pointer or array parameters ([STARPU_W](#)).

task_implementation (target, task) Declare the given function as an implementation of `task` to run on `target`. `target` must be a string, currently one of "cpu", "opencl", or "cuda".

Here is an example:

```
#define __output __attribute__((output))

static void matmul (const float *A, const float *B,
                  __output float *C,
                  unsigned nx, unsigned ny, unsigned nz)
    __attribute__((task));

static void matmul_cpu (const float *A, const float *B,
                      __output float *C,
                      unsigned nx, unsigned ny, unsigned nz)
    __attribute__((task_implementation ("cpu", matmul)));

static void
matmul_cpu (const float *A, const float *B, __output float *C,
            unsigned nx, unsigned ny, unsigned nz)
{
    unsigned i, j, k;

    for (j = 0; j < ny; j++)
        for (i = 0; i < nx; i++)
        {
            for (k = 0; k < nz; k++)
                C[j * nx + i] += A[j * nz + k] * B[k * nx + i];
        }
}
```

A `matmult` task is defined; it has only one implementation, `matmult_cpu`, which runs on the CPU. Variables `A` and `B` are input buffers, whereas `C` is considered an input/output buffer.

For convenience, when a function declared with the `task` attribute has a user-defined body, that body is assumed to be that of the CPU implementation of a task, which we call an implicit task CPU implementation. Thus, the above snippet can be simplified like this:

```

#define __output __attribute__ ((output))

static void matmul (const float *A, const float *B,
                  __output float *C,
                  unsigned nx, unsigned ny, unsigned nz)
    __attribute__ ((task));

/* Implicit definition of the CPU implementation of the
   'matmul' task. */
static void
matmul (const float *A, const float *B, __output float *C,
       unsigned nx, unsigned ny, unsigned nz)
{
    unsigned i, j, k;

    for (j = 0; j < ny; j++)
        for (i = 0; i < nx; i++)
        {
            for (k = 0; k < nz; k++)
                C[j * nx + i] += A[j * nz + k] * B[k * nx + i];
        }
}

```

Use of implicit CPU task implementations as above has the advantage that the code is valid sequential code when StarPU's GCC plug-in is not used ([Using C Extensions Conditionally](#)).

CUDA and OpenCL implementations can be declared in a similar way:

```

static void matmul_cuda (const float *A, const float *B, float *C,
                       unsigned nx, unsigned ny, unsigned nz)
    __attribute__ ((task_implementation ("cuda", matmul)));

static void matmul_opengl (const float *A, const float *B, float *C,
                          unsigned nx, unsigned ny, unsigned nz)
    __attribute__ ((task_implementation ("opengl", matmul)));

```

The CUDA and OpenCL implementations typically either invoke a kernel written in CUDA or OpenCL (for similar code, [CUDA Kernel](#), and [OpenCL Kernel](#)), or call a library function that uses CUDA or OpenCL under the hood, such as CUBLAS functions:

```

static void
matmul_cuda (const float *A, const float *B, float *C,
            unsigned nx, unsigned ny, unsigned nz)
{
    cublasSgemm ('n', 'n', nx, ny, nz,
                1.0f, A, 0, B, 0,
                0.0f, C, 0);
    cudaStreamSynchronize (starpu_cuda_get_local_stream ());
}

```

A task can be invoked like a regular C function:

```

matmul (&A[i * zdim * bydim + k * bzdime * bydim],
        &B[k * xdim * bzdime + j * bxdime * bzdime],
        &C[i * xdim * bydim + j * bxdime * bydim],
        bxdime, bydim, bzdime);

```

This leads to an asynchronous invocation, whereby `matmul`'s implementation may run in parallel with the continuation of the caller.

The next section describes how memory buffers must be handled in StarPU-GCC code. For a complete example, see the `gcc-plugin/examples` directory of the source distribution, and [Vector Scaling Using the C Extension](#).

20.2 Initialization, Termination, and Synchronization

The following pragmas allow user code to control StarPU's life time and to synchronize with tasks.

#pragma starpu initialize Initialize StarPU. This call is compulsory and is *never* added implicitly. One of the reasons this has to be done explicitly is that it provides greater control to user code over its resource usage.

#pragma starpu shutdown Shut down StarPU, giving it an opportunity to write profiling info to a file on disk, for instance ([Off-line Performance Feedback](#)).

#pragma starpu wait Wait for all task invocations to complete, as with [starpu_task_wait_for_all\(\)](#).

20.3 Registered Data Buffers

Data buffers such as matrices and vectors that are to be passed to tasks must be registered. Registration allows StarPU to handle data transfers among devices—e.g., transferring an input buffer from the CPU's main memory to a task scheduled to run a GPU ([StarPU Data Management Library](#)).

The following pragmas are provided:

#pragma starpu register ptr [size] Register `ptr` as a `size`-element buffer. When `ptr` has an array type whose size is known, `size` may be omitted. Alternatively, the `registered` attribute can be used (see below.)

#pragma starpu unregister ptr Unregister the previously-registered memory area pointed to by `ptr`. As a side-effect, `ptr` points to a valid copy in main memory.

#pragma starpu acquire ptr Acquire in main memory an up-to-date copy of the previously-registered memory area pointed to by `ptr`, for read-write access.

#pragma starpu release ptr Release the previously-register memory area pointed to by `ptr`, making it available to the tasks.

Additionally, the following attributes offer a simple way to allocate and register storage for arrays:

registered This attributes applies to local variables with an array type. Its effect is to automatically register the array's storage, as per `#pragma starpu register`. The array is automatically unregistered when the variable's scope is left. This attribute is typically used in conjunction with the `heap_allocated` attribute, described below.

heap_allocated This attributes applies to local variables with an array type. Its effect is to automatically allocate the array's storage on the heap, using `starpu_malloc()` under the hood. The heap-allocated array is automatically freed when the variable's scope is left, as with automatic variables.

The following example illustrates use of the `heap_allocated` attribute:

```

extern void cholesky(unsigned nblocks, unsigned size,
                    float mat[nblocks][nblocks][size])
    __attribute__((task));

int
main (int argc, char *argv[])
{
#pragma starpu initialize

    /* ... */

    int nblocks, size;
    parse_args (&nblocks, &size);

    /* Allocate an array of the required size on the heap,
       and register it. */

    {
        float matrix[nblocks][nblocks][size]
            __attribute__((heap_allocated, registered));

        cholesky (nblocks, size, matrix);
    }

#pragma starpu wait

    /* MATRIX is automatically unregistered & freed here. */

#pragma starpu shutdown

    return EXIT_SUCCESS;
}

```

20.4 Using C Extensions Conditionally

The C extensions described in this chapter are only available when GCC and its StarPU plug-in are in use. Yet, it is possible to make use of these extensions when they are available—leading to hybrid CPU/GPU code—and discard them when they are not available—leading to valid sequential code.

To that end, the GCC plug-in defines the C preprocessor macro — `STARPU_GCC_PLUGIN` — when it is being used. When defined, this macro expands to an integer denoting the version of the supported C extensions.

The code below illustrates how to define a task and its implementations in a way that allows it to be compiled without the GCC plug-in:

```

/* This program is valid, whether or not StarPU's GCC plug-in
   is being used. */

#include <stdlib.h>

/* The attribute below is ignored when GCC is not used. */
static void matmul (const float *A, const float *B, float * C,
                   unsigned nx, unsigned ny, unsigned nz)
    __attribute__((task));

static void
matmul (const float *A, const float *B, float * C,
        unsigned nx, unsigned ny, unsigned nz)
{
    /* Code of the CPU kernel here... */
}

#ifdef STARPU_GCC_PLUGIN
/* Optional OpenCL task implementation. */

static void matmul_opencl (const float *A, const float *B, float * C,
                          unsigned nx, unsigned ny, unsigned nz)
    __attribute__((task_implementation ("opencl", matmul)));

static void
matmul_opencl (const float *A, const float *B, float * C,
               unsigned nx, unsigned ny, unsigned nz)
{
    /* Code that invokes the OpenCL kernel here... */
}
#endif

```

```

int
main (int argc, char *argv[])
{
    /* The pragmas below are simply ignored when StarPU-GCC
       is not used. */
    #pragma starpu initialize

    float A[123][42][7], B[123][42][7], C[123][42][7];

    #pragma starpu register A
    #pragma starpu register B
    #pragma starpu register C

    /* When StarPU-GCC is used, the call below is asynchronous;
       otherwise, it is synchronous. */
    matmul ((float *) A, (float *) B, (float *) C, 123, 42, 7);

    #pragma starpu wait
    #pragma starpu shutdown

    return EXIT_SUCCESS;
}

```

The above program is a valid StarPU program when StarPU's GCC plug-in is used; it is also a valid sequential program when the plug-in is not used.

Note that attributes such as `task` as well as `starpu` pragmas are simply ignored by GCC when the StarPU plug-in is not loaded. However, `gcc -Wall` emits a warning for unknown attributes and pragmas, which can be inconvenient. In addition, other compilers may be unable to parse the attribute syntax (In practice, Clang and several proprietary compilers implement attributes.), so you may want to wrap attributes in macros like this:

```

/* Use the 'task' attribute only when StarPU's GCC plug-in
   is available. */
#ifdef STARPU_GCC_PLUGIN
# define __task __attribute__((task))
#else
# define __task
#endif

static void matmul (const float *A, const float *B, float *C,
                    unsigned nx, unsigned ny, unsigned nz) __task;

```

Chapter 21

Native Fortran Support

StarPU provides the necessary routines and support to natively access most of its functionalities from Fortran 2008+ codes.

All symbols (functions, constants) are defined in `fstarpu_mod.f90`. Every symbol of the Native Fortran support API is prefixed by `fstarpu_`.

Note: Mixing uses of `fstarpu_` and `starpu_` symbols in the same Fortran code has unspecified behaviour. See [Valid API Mixes and Language Mixes](#) for a discussion about valid and unspecified combinations.

21.1 Implementation Details and Specificities

21.1.1 Prerequisites

The Native Fortran support relies on Fortran 2008 specific constructs, as well as on the support of interoperability of assumed-shape arrays introduced as part of Fortran's Technical Specification ISO/IEC TS 29113:2012, for which no equivalent are available in previous versions of the standard. It has currently been tested successfully with GNU GFortran 4.9, GFortran 5.x, GFortran 6.x and the Intel Fortran Compiler \geq 2016. It is known not to work with GNU GFortran $<$ 4.9, Intel Fortran Compiler $<$ 2016.

See Section [Using StarPU with Older Fortran Compilers](#) on information on how to write StarPU Fortran code with older compilers.

21.1.2 Configuration

The Native Fortran API is enabled and its companion `fstarpu_mod.f90` Fortran module source file is installed by default when a Fortran compiler is found, unless the detected Fortran compiler is known not to support the requirements for the Native Fortran API. The support can be disabled through the configure option `--disable-fortran`. Conditional compiled source codes may check for the availability of the Native Fortran Support by testing whether the preprocessor macro `STARPU_HAVE_FC` is defined or not.

21.1.3 Examples

Several examples using the Native Fortran API are provided in StarPU's `examples/native_fortran/` examples directory, to showcase the Fortran flavor of various basic and more advanced StarPU features.

21.1.4 Compiling a Native Fortran Application

The Fortran module `fstarpu_mod.f90` installed in StarPU's `include/` directory provides all the necessary API definitions. It must be compiled with the same compiler (same vendor, same version) as the application itself, and the resulting `fstarpu_mod.o` object file must be linked with the application executable.

Each example provided in StarPU's `examples/native_fortran/` examples directory comes with its own dedicated Makefile for out-of-tree build. Such example Makefiles may be used as starting points for building application codes with StarPU.

21.2 Fortran Translation for Common StarPU API Idioms

All these examples assume that the standard Fortran module `iso_c_binding` is in use.

- Specifying a NULL pointer

```
type(c_ptr) :: my_ptr ! variable to store the pointer
! [...]
my_ptr = c_null_ptr ! assign standard constant for null ptr
```

- Obtaining a pointer to some object:

```
real(8), dimension(:), allocatable, target :: va
type(c_ptr) :: p_va ! variable to store a pointer to array va
! [...]
p_va = c_loc(va)
```

- Obtaining a pointer to some subroutine:

```
! pointed routine definition
recursive subroutine myfunc () bind(C)
! [...]
type(c_funptr) :: p_fun ! variable to store the routine pointer
! [...]
p_fun = c_funloc(my_func)
```

- Obtaining the size of some object:

```
real(8) :: a
integer(c_size_t) :: sz_a ! variable to store the size of a
! [...]
sz_a = c_sizeof(a)
```

- Obtaining the length of an array dimension:

```
real(8), dimension(:,:), allocatable, target :: vb
integer(c_int) :: ln_vb_1 ! variable to store the length of vb's dimension 1
integer(c_int) :: ln_vb_2 ! variable to store the length of vb's dimension 2
! [...]
ln_vb_1 = 1+ubound(vb,1)-lbound(vb,1) ! get length of dimension 1 of vb
ln_vb_2 = 1+ubound(vb,2)-lbound(vb,2) ! get length of dimension 2 of vb
```

- Specifying a string constant:

```
type(c_ptr) :: my_cl ! a StarPU codelet
! [...]

! set the name of a codelet to string 'my_codelet':
call fstarpu_codelet_set_name(my_cl, c_char_"my_codelet"/c_null_char)

! note: using the C_CHAR_ prefix and the //C_NULL_CHAR concatenation at the end ensures
! that the string constant is properly '\0' terminated, and compatible with StarPU's
! internal C routines
!
! note: plain Fortran string constants are not '\0' terminated, and as such, must not be
! passed to starpu routines.
```

- Combining multiple flag constants with a bitwise 'or':

```
type(c_ptr) :: my_cl ! a pointer for the codelet structure
! [...]

! add a managed buffer to a codelet, specifying both the Read/Write access mode and the Locality hint
call fstarpu_codelet_add_buffer(my_cl, fstarpu_rw.ior.fstarpu_locality)
```


21.3 Uses, Initialization and Shutdown

The snippet below show an example of minimal StarPU code using the Native Fortran support. The program should use the standard module `iso_c_binding` as well as StarPU's `fstarpu_mod`. The StarPU runtime engine is initialized with a call to function `fstarpu_init`, which returns an integer status of 0 if successful or non-0 otherwise. Eventually, a call to `fstarpu_shutdown` ends the runtime engine and frees all internal StarPU data structures.

```

program nf_initexit
  use iso_c_binding      ! C interfacing module
  use fstarpu_mod        ! StarPU interfacing module
  implicit none          ! Fortran recommended best practice

  integer(c_int) :: err  ! return status for fstarpu_init

  ! initialize StarPU with default settings
  err = fstarpu_init(c_null_ptr)
  if (err /= 0) then
    stop 1              ! StarPU initialization failure
  end if

  ! - add StarPU Native Fortran API calls here

  ! shut StarPU down
  call fstarpu_shutdown()
end program nf_initexit

```

21.4 Fortran Flavor of StarPU's Variadic Insert_task

Fortran does not have a construction similar to C variadic functions on which `starpu_insert_task` relies at the time of this writing. However, Fortran's variable length arrays of `c_ptr` elements enable to emulate much of the convenience of C's variadic functions. This is the approach retained for implementing `fstarpu_insert_task`.

The general syntax for using `fstarpu_insert_task` is as follows:

```

call fstarpu_insert_task((/ <codelet ptr>      &
  [, <access mode flags>, <data handle>]*      &
  [, <argument type constant>, <argument>]*    &
  , c_null_ptr /))

```

There is thus a unique array argument `(/ . . . /)` passed to `fstarpu_insert_task` which itself contains the task settings. Each element of the array must be of type `type(c_ptr)`. The last element of the array must be `C_NULL_PTR`.

Example extracted from `nf_vector.f90`:

```

call fstarpu_insert_task((/ cl_vec,          & ! codelet
  fstarpu_r, dh_va,                          & ! a first data handle
  fstarpu_rw.ior.fstarpu_locality, dh_vb,    & ! a second data handle
  c_null_ptr /))                             & ! no more args

```

21.5 Functions and Subroutines Expecting Data Structures Arguments

Several StarPU structures that are expected to be passed to the C API, are replaced by function/subroutine wrapper sets to allocate, set fields and free such structure. This strategy has been preferred over defining native Fortran equivalent of such structures using Fortran's derived types, to avoid potential layout mismatch between C and Fortran StarPU data structures. Examples of such data structures wrappers include `fstarpu_conf_allocate` and `alike`, `fstarpu_codelet_allocate` and `alike`, `fstarpu_data_filter_allocate` and `alike`.

Here is an example of allocating, filling and deallocating a codelet structure:

```
! a pointer for the codelet structure
type(c_ptr) :: cl_vec
! [...]
! allocate an empty codelet structure
cl_vec = fstarpu_codelet_allocate()
! add a CPU implementation function to the codelet
call fstarpu_codelet_add_cpu_func(cl_vec, c_funloc(cl_cpu_func_vec))
! set the codelet name
call fstarpu_codelet_set_name(cl_vec, c_char_"my_vec_codelet"/c_null_char)
! add a Read-only mode data buffer to the codelet
call fstarpu_codelet_add_buffer(cl_vec, fstarpu_r)
! add a Read-Write mode data buffer to the codelet
call fstarpu_codelet_add_buffer(cl_vec, fstarpu_rw.ior.fstarpu_locality)
! [...]
! free codelet structure
call fstarpu_codelet_free(cl_vec)
```

21.6 Additional Notes about the Native Fortran Support

21.6.1 Using StarPU with Older Fortran Compilers

When using older compilers, Fortran applications may still interoperate with StarPU using C marshalling functions as exemplified in StarPU's `examples/fortran/` and `examples/fortran90/` example directories, though the process will be less convenient.

Basically, the main FORTRAN code calls some C wrapper functions to submit tasks to StarPU. Then, when StarPU starts a task, another C wrapper function calls the FORTRAN routine for the task.

Note that this marshalled FORTRAN support remains available even when specifying configure option `--disable-fortran` (which only disables StarPU's native Fortran layer).

21.6.2 Valid API Mixes and Language Mixes

Mixing uses of `fstarpu_` and `starpu_` symbols in the same Fortran code has unspecified behaviour. Using `fstarpu_` symbols in C code has unspecified behaviour.

For multi-language applications using both C and Fortran source files:

- C source files must use `starpu_` symbols exclusively
- Fortran sources must uniformly use either `fstarpu_` symbols exclusively, or `starpu_` symbols exclusively. Every other combination has unspecified behaviour.

Chapter 22

SOCL OpenCL Extensions

SOCL is an OpenCL implementation based on StarPU. It gives a unified access to every available OpenCL device: applications can now share entities such as Events, Contexts or Command Queues between several OpenCL implementations.

In addition, command queues that are created without specifying a device provide automatic scheduling of the submitted commands on OpenCL devices contained in the context to which the command queue is attached.

Setting the `CL_QUEUE_OUT_OF_ORDER_EXEC_MODE_ENABLE` flag on a command queue also allows StarPU to reorder kernels queued on the queue, otherwise they would be serialized and several command queues would be necessary to see kernels dispatched on the various OpenCL devices.

Note: this is still an area under development and subject to change.

When compiling StarPU, SOCL will be enabled if a valid OpenCL implementation is found on your system. To be able to run the SOCL test suite, the environment variable `SOCL_OCL_LIB_OPENCL` needs to be defined to the location of the file `libOpenCL.so` of the OCL ICD implementation. You should for example add the following line in your file `.bashrc`

```
export SOCL_OCL_LIB_OPENCL=/usr/lib/x86_64-linux-gnu/libOpenCL.so
```

You can then run the test suite in the directory `socl/examples`.

```
$ make check
...
PASS: basic/basic
PASS: testmap/testmap
PASS: clinfo/clininfo
PASS: matmul/matmul
PASS: mansched/mansched
=====
All 5 tests passed
=====
```

The environment variable `OCL_ICD_VENDORS` has to point to the directory where the `socl.icd` ICD file is installed. When compiling StarPU, the files are in the directory `socl/vendors`. With an installed version of StarPU, the files are installed in the directory `$prefix/share/starpu/opencl/vendors`.

To run the tests by hand, you have to call for example,

```
$ LD_PRELOAD=$SOCL_OCL_LIB_OPENCL OCL_ICD_VENDORS=socl/vendors/ socl/examples/clinfo/clinfo
Number of platforms: 2
  Platform Profile: FULL_PROFILE
  Platform Version: OpenCL 1.1 CUDA 4.2.1
  Platform Name: NVIDIA CUDA
  Platform Vendor: NVIDIA Corporation
  Platform Extensions: cl_khr_byte_addressable_store cl_khr_icd cl_khr_gl_sharing cl_nv_compiler_options cl_nv

  Platform Profile: FULL_PROFILE
  Platform Version: OpenCL 1.0 SOCL Edition (0.1.0)
  Platform Name: SOCL Platform
  Platform Vendor: Inria
  Platform Extensions: cl_khr_icd
....
$
```

To enable the use of CPU cores via OpenCL, one can set the [STARPU_OPENCL_ON_CPUS](#) environment variable to 1 and [STARPU_NCPUS](#) to 0 (to avoid using CPUs both via the OpenCL driver and the normal CPU driver).

Chapter 23

SimGrid Support

StarPU can use Simgrid in order to simulate execution on an arbitrary platform. This was tested with simgrid from 3.11 to 3.16, and 3.18 to 3.20. Other versions may have compatibility issues. 3.17 notably does not build at all.

23.1 Preparing Your Application For Simulation

There are a few technical details which need to be handled for an application to be simulated through Simgrid.

If the application uses `gettimeofday` to make its performance measurements, the real time will be used, which will be bogus. To get the simulated time, it has to use `starpu_timing_now()` which returns the virtual timestamp in us.

For some technical reason, the application's `.c` file which contains `main()` has to be recompiled with `starpu_simgrid_↵_wrap.h`, which in the simgrid case will `# define` `main()` into `starpu_main()`, and it is `libstarpu` which will provide the real `main()` and will call the application's `main()`.

To be able to test with crazy data sizes, one may want to only allocate application data if `STARPU_SIMGRID` is not defined. Passing a `NULL` pointer to `starpu_data_register` functions is fine, data will never be read/written to by StarPU in Simgrid mode anyway.

To be able to run the application with e.g. CUDA simulation on a system which does not have CUDA installed, one can fill the `cuda_funcs` with `(void*)1`, to express that there is a CUDA implementation, even if one does not actually provide it. StarPU will not actually run it in Simgrid mode anyway by default (unless the `STARPU_CODELET_SI↵MGRID_EXECUTE` flag is set in the codelet)

```
static struct starpu_codelet c111 =
{
    .cpu_funcs = {chol_cpu_codelet_update_u11},
    .cpu_funcs_name = {"chol_cpu_codelet_update_u11"},
#ifdef STARPU_USE_CUDA
    .cuda_funcs = {chol_cublas_codelet_update_u11},
#elif defined(STARPU_SIMGRID)
    .cuda_funcs = {(void*)1},
#endif
    .nbuffers = 1,
    .modes = {STARPU_RW},
    .model = &chol_model_11
};
```

23.2 Calibration

The idea is to first compile StarPU normally, and run the application, so as to automatically benchmark the bus and the codelets.

```
$ ./configure && make
$ STARPU_SCHED=dmda ./examples/matvecmult/matvecmult
[starpu][_starpu_load_history_based_model] Warning: model matvecmult
  is not calibrated, forcing calibration for this run. Use the
  STARPU_CALIBRATE environment variable to control this.
$ ...
$ STARPU_SCHED=dmda ./examples/matvecmult/matvecmult
TEST PASSED
```

Note that we force to use the scheduler `dmda` to generate performance models for the application. The application may need to be run several times before the model is calibrated.

23.3 Simulation

Then, recompile StarPU, passing `--enable-simgrid` to `./configure`. Make sure to keep all other `./configure` options the same, and notably options such as `-enable-maxcudadev`.

```
$ ./configure --enable-simgrid
```

To specify the location of SimGrid, you can either set the environment variables `SIMGRID_CFLAGS` and `SIMGRID_LIBS`, or use the configure options `--with-simgrid-dir`, `--with-simgrid-include-dir` and `--with-simgrid-lib-dir`, for example

```
$ ./configure --with-simgrid-dir=/opt/local/simgrid
```

You can then re-run the application.

```
$ make
$ STARPU_SCHED=dmda ./examples/matvecmult/matvecmult
TEST FAILED !!!
```

It is normal that the test fails: since the computation are not actually done (that is the whole point of simgrid), the result is wrong, of course.

If the performance model is not calibrated enough, the following error message will be displayed

```
$ STARPU_SCHED=dmda ./examples/matvecmult/matvecmult
[starpu][_starpu_load_history_based_model] Warning: model matvecmult
  is not calibrated, forcing calibration for this run. Use the
  STARPU_CALIBRATE environment variable to control this.
[starpu][_starpu_simgrid_execute_job][assert failure] Codelet
  matvecmult does not have a perfmodel, or is not calibrated enough
```

The number of devices can be chosen as usual with `STARPU_NCPU`, `STARPU_NCUDA`, and `STARPU_NOENCL`, and the amount of GPU memory with `STARPU_LIMIT_CUDA_MEM`, `STARPU_LIMIT_CUDA_devid_MEM`, `STARPU_LIMIT_OPENCL_MEM`, and `STARPU_LIMIT_OPENCL_devid_MEM`.

23.4 Simulation On Another Machine

The simgrid support even permits to perform simulations on another machine, your desktop, typically. To achieve this, one still needs to perform the Calibration step on the actual machine to be simulated, then copy them to your desktop machine (the `$STARPU_HOME/.starpu` directory). One can then perform the Simulation step on the desktop machine, by setting the environment variable `STARPU_HOSTNAME` to the name of the actual machine, to make StarPU use the performance models of the simulated machine even on the desktop machine.

If the desktop machine does not have CUDA or OpenCL, StarPU is still able to use simgrid to simulate execution with CUDA/OpenCL devices, but the application source code will probably disable the CUDA and OpenCL codelets in that case. Since during simgrid execution, the functions of the codelet are actually not called by default, one can use dummy functions such as the following to still permit CUDA or OpenCL execution.

23.5 Simulation Examples

StarPU ships a few performance models for a couple of systems: attila, mirage, idgraf, and sirocco. See section [Simulated benchmarks](#) for the details.

23.6 Simulations On Fake Machines

It is possible to build fake machines which do not exist, by modifying the platform file in `$STARPU_HOME/.starpu/sampling/bus/machine.platform.xml` by hand: one can add more CPUs, add GPUs (but the performance model file has to be extended as well), change the available GPU memory size, PCI memory bandwidth, etc.

23.7 Tweaking Simulation

The simulation can be tweaked, to be able to tune it between a very accurate simulation and a very simple simulation (which is thus close to scheduling theory results), see the `STARPU_SIMGRID_CUDA_MALLOC_COST` and `STARPU_SIMGRID_CUDA_QUEUE_COST` environment variables.

23.8 MPI Applications

StarPU-MPI applications can also be run in simgrid mode. It needs to be compiled with `mpicc`, and run using the `starpu_smpirun` script, for instance:

```
$ STARPU_SCHED=dmda starpu_smpirun -platform cluster.xml -hostfile hostfile ./mpi/tests/pingpong
```

Where `cluster.xml` is a Simgrid-MPI platform description, and `hostfile` the list of MPI nodes to be used. StarPU currently only supports homogeneous MPI clusters: for each MPI node it will just replicate the architecture referred by `STARPU_HOSTNAME`.

23.9 Debugging Applications

By default, simgrid uses its own implementation of threads, which prevents gdb from being able to inspect stacks of all threads. To be able to fully debug an application running with simgrid, pass the `-cfg=contexts/factory↵:thread` option to the application, to make simgrid use system threads, which gdb will be able to manipulate as usual.

It is also worth noting Simgrid 3.21's new parameter `-cfg=simix/breakpoint` which allows to put a breakpoint at a precise (deterministic!) timing of the execution. If for instance in an execution trace we see that something odd is happening at time 19000ms, we can use `-cfg=simix/breakpoint:19.000` and SIGTRAP will be raised at that point, which will thus interrupt execution within gdb, allowing to inspect e.g. scheduler state, etc.

23.10 Memory Usage

Since kernels are not actually run and data transfers are not actually performed, the data memory does not actually need to be allocated. This allows for instance to simulate the execution of applications processing very big data on a small laptop.

The application can for instance pass 1 (or whatever bogus pointer) to starpu data registration functions, instead of allocating data. This will however require the application to take care of not trying to access the data, and will not work in MPI mode, which performs transfers.

Another way is to pass the `STARPU_MALLOC_SIMULATION_FOLDED` flag to the `starpu_malloc_flags()` function. This will make it allocate a memory area which one can read/write, but optimized so that this does not actually consume memory. Of course, the values read from such area will be bogus, but this allows the application to keep e.g. data load, store, initialization as it is, and also work in MPI mode.

Note however that notably Linux kernels refuse obvious memory overcommitting by default, so a single allocation can typically not be bigger than the amount of physical memory, see <https://www.kernel.org/doc/↵Documentation/vm/overcommit-accounting>. This prevents for instance from allocating a single huge matrix. Allocating a huge matrix in several tiles is not a problem, however. `sysctl vm.overcommit_↵memory=1` can also be used to allow such overcommit.

Note however that this folding is done by remapping the same file several times, and Linux kernels will also refuse to create too many memory areas. `sysctl vm.max_map_count` can be used to check and change the default (65535). By default, StarPU uses a 1MiB file, so it hopefully fits in the CPU cache. This however limits the amount of such folded memory to a bit below 64GiB. The `STARPU_MALLOC_SIMULATION_FOLD` environment variable can be used to increase the size of the file.

Chapter 24

OpenMP Runtime Support

StarPU provides the necessary routines and support to implement an OpenMP (<http://www.openmp.org/>) runtime compliant with the revision 3.1 of the language specification, and compliant with the task-related data dependency functionalities introduced in the revision 4.0 of the language. This StarPU OpenMP Runtime Support (SORS) has been designed to be targetted by OpenMP compilers such as the Klang-OMP compiler. Most supported OpenMP directives can both be implemented inline or as outlined functions.

All functions are defined in [OpenMP Runtime Support](#).

24.1 Implementation Details and Specificities

24.1.1 Main Thread

When using the SORS, the main thread gets involved in executing OpenMP tasks just like every other threads, in order to be compliant with the specification execution model. This contrasts with StarPU's usual execution model where the main thread submit tasks but does not take part in executing them.

24.1.2 Extended Task Semantics

The semantics of tasks generated by the SORS are extended with respect to regular StarPU tasks in that SORS' tasks may block and be preempted by SORS call, whereas regular StarPU tasks cannot. SORS tasks may coexist with regular StarPU tasks. However, only the tasks created using SORS API functions inherit from extended semantics.

24.2 Configuration

The SORS can be compiled into `libstarpu` through the configure option `--enable-openmp`. Conditional compiled source codes may check for the availability of the OpenMP Runtime Support by testing whether the C preprocessor macro `STARPU_OPENMP` is defined or not.

24.3 Uses, Initialization and Shutdown

The SORS needs to be executed/terminated by the `starpu_omp_init()` / `starpu_omp_shutdown()` instead of `starpu_omp_init()` / `starpu_shutdown()`. This requirement is necessary to make sure that the main thread gets the proper execution environment to run OpenMP tasks. These calls will usually be performed by a compiler runtime. Thus, they can be executed from a constructor/destructor such as this:

```
__attribute__((constructor))
static void omp_constructor(void)
{
    int ret = starpu_omp_init();
    STARPU_CHECK_RETURN_VALUE(ret, "starpu_omp_init");
}

__attribute__((destructor))
static void omp_destructor(void)
{
    starpu_omp_shutdown();
}
```

See also

[starpu_omp_init\(\)](#)
[starpu_omp_shutdown\(\)](#)

24.4 Parallel Regions and Worksharing

The SORS provides functions to create OpenMP parallel regions as well as mapping work on participating workers. The current implementation does not provide nested active parallel regions: Parallel regions may be created recursively, however only the first level parallel region may have more than one worker. From an internal point-of-view, the SORS' parallel regions are implemented as a set of implicit, extended semantics StarPU tasks, following the execution model of the OpenMP specification. Thus the SORS' parallel region tasks may block and be preempted, by SORS calls, enabling constructs such as barriers.

24.4.1 Parallel Regions

Parallel regions can be created with the function `starpu_omp_parallel_region()` which accepts a set of attributes as parameter. The execution of the calling task is suspended until the parallel region completes. The field `starpu_omp_parallel_region_attr::cl` is a regular StarPU codelet. However only CPU codelets are supported for parallel regions. Here is an example of use:

```
void parallel_region_f(void *buffers[], void *args)
{
    (void) buffers;
    (void) args;
    pthread_t tid = pthread_self();
    int worker_id = starpu_worker_get_id();
    printf("[tid %p] task thread = %d\n", (void *)tid, worker_id);
}

void f(void)
{
    struct starpu_omp_parallel_region_attr attr;
    memset(&attr, 0, sizeof(attr));
    attr.cl.cpu_funcs[0] = parallel_region_f;
    attr.cl.where = STARPU_CPU;
    attr.if_clause = 1;
    starpu_omp_parallel_region(&attr);
    return 0;
}
```

See also

[struct starpu_omp_parallel_region_attr](#)
[starpu_omp_parallel_region\(\)](#)

24.4.2 Parallel For

OpenMP `for` loops are provided by the [`starpu_omp_for\(\)`](#) group of functions. Variants are available for inline or outlined implementations. The SORS supports `static`, `dynamic`, and `guided` loop scheduling clauses. The `auto` scheduling clause is implemented as `static`. The `runtime` scheduling clause honors the scheduling mode selected through the environment variable `OMP_SCHEDULE` or the [`starpu_omp_set_schedule\(\)`](#) function. For loops with the `ordered` clause are also supported. An implicit barrier can be enforced or skipped at the end of the worksharing construct, according to the value of the `nowait` parameter.

The canonical family of [`starpu_omp_for\(\)`](#) functions provide each instance with the first iteration number and the number of iterations (possibly zero) to perform. The alternate family of [`starpu_omp_for_alt\(\)`](#) functions provide each instance with the (possibly empty) range of iterations to perform, including the first and excluding the last.

The family of [`starpu_omp_ordered\(\)`](#) functions enable to implement OpenMP's ordered construct, a region with a parallel for loop that is guaranteed to be executed in the sequential order of the loop iterations.

```
void for_g(unsigned long long i, unsigned long long nb_i, void *arg)
{
    (void) arg;
    for (; nb_i > 0; i++, nb_i--)
    {
        array[i] = 1;
    }
}

void parallel_region_f(void *buffers[], void *args)
{
    (void) buffers;
    (void) args;
    starpu_omp_for(for_g, NULL, NB_ITERS, CHUNK, starpu_omp_sched_static
, 0, 0);
}
```

See also

- [starpu_omp_for\(\)](#)
- [starpu_omp_for_inline_first\(\)](#)
- [starpu_omp_for_inline_next\(\)](#)
- [starpu_omp_for_alt\(\)](#)
- [starpu_omp_for_inline_first_alt\(\)](#)
- [starpu_omp_for_inline_next_alt\(\)](#)
- [starpu_omp_ordered\(\)](#)
- [starpu_omp_ordered_inline_begin\(\)](#)
- [starpu_omp_ordered_inline_end\(\)](#)

24.4.3 Sections

OpenMP `sections` worksharing constructs are supported using the set of [`starpu_omp_sections\(\)`](#) variants. The general principle is either to provide an array of per-section functions or a single function that will redirect to execution to the suitable per-section functions. An implicit barrier can be enforced or skipped at the end of the worksharing construct, according to the value of the `nowait` parameter.

```
void parallel_region_f(void *buffers[], void *args)
{
    (void) buffers;
    (void) args;

    section_funcs[0] = f;
    section_funcs[1] = g;
    section_funcs[2] = h;
    section_funcs[3] = i;

    section_args[0] = arg_f;
    section_args[1] = arg_g;
    section_args[2] = arg_h;
    section_args[3] = arg_i;

    starpu_omp_sections(4, section_f, section_args, 0);
}
```

See also

[starpu_omp_sections\(\)](#)
[starpu_omp_sections_combined\(\)](#)

24.4.4 Single

OpenMP `single` worksharing constructs are supported using the set of [starpu_omp_single\(\)](#) variants. An implicit barrier can be enforced or skipped at the end of the worksharing construct, according to the value of the `nowait` parameter.

```
void single_f(void *arg)
{
    (void) arg;
    pthread_t tid = pthread_self();
    int worker_id = starpu_worker_get_id();
    printf("[tid %p] task thread = %d -- single\n", (void *)tid, worker_id);
}

void parallel_region_f(void *buffers[], void *args)
{
    (void) buffers;
    (void) args;
    starpu_omp_single(single_f, NULL, 0);
}
```

The SORS also provides dedicated support for `single` sections with `copyprivate` clauses through the [starpu_omp_single_copyprivate\(\)](#) function variants. The OpenMP `master` directive is supported as well using the [starpu_omp_master\(\)](#) function variants.

See also

[starpu_omp_master\(\)](#)
[starpu_omp_master_inline\(\)](#)
[starpu_omp_single\(\)](#)
[starpu_omp_single_inline\(\)](#)
[starpu_omp_single_copyprivate\(\)](#)
[starpu_omp_single_copyprivate_inline_begin\(\)](#)
[starpu_omp_single_copyprivate_inline_end\(\)](#)

24.5 Tasks

The SORS implements the necessary support of OpenMP 3.1 and OpenMP 4.0's so-called explicit tasks, together with OpenMP 4.0's data dependency management.

24.5.1 Explicit Tasks

Explicit OpenMP tasks are created with the SORS using the [starpu_omp_task_region\(\)](#) function. The implementation supports `if`, `final`, `untied` and `mergeable` clauses as defined in the OpenMP specification. Unless specified otherwise by the appropriate clause(s), the created task may be executed by any participating worker of the current parallel region.

The current SORS implementation requires explicit tasks to be created within the context of an active parallel region. In particular, an explicit task cannot be created by the main thread outside of a parallel region. Explicit OpenMP tasks created using [starpu_omp_task_region\(\)](#) are implemented as StarPU tasks with extended semantics, and may as such be blocked and preempted by SORS routines.

The current SORS implementation supports recursive explicit tasks creation, to ensure compliance with the OpenMP specification. However, it should be noted that StarPU is not designed nor optimized for efficiently scheduling of recursive task applications.

The code below shows how to create 4 explicit tasks within a parallel region.

```

void task_region_g(void *buffers[], void *args)
{
    (void) buffers;
    (void) args;
    pthread_t tid = pthread_self();
    int worker_id = starpu_worker_get_id();
    printf("[tid %p] task thread = %d: explicit task \"%g\"\n", (void *)tid, worker_id);
}

void parallel_region_f(void *buffers[], void *args)
{
    (void) buffers;
    (void) args;
    struct starpu_omp_task_region_attr attr;

    memset(&attr, 0, sizeof(attr));
    attr.cl.cpu_funcs[0] = task_region_g;
    attr.cl.where = STARPU_CPU;
    attr.if_clause = 1;
    attr.final_clause = 0;
    attr.untied_clause = 1;
    attr.mergeable_clause = 0;
    starpu_omp_task_region(&attr);
    starpu_omp_task_region(&attr);
    starpu_omp_task_region(&attr);
    starpu_omp_task_region(&attr);
}

```

See also

[struct starpu_omp_task_region_attr](#)
[starpu_omp_task_region\(\)](#)

24.5.2 Data Dependencies

The SORS implements inter-tasks data dependencies as specified in OpenMP 4.0. Data dependencies are expressed using regular StarPU data handles ([starpu_data_handle_t](#)) plugged into the task's `attr.cl` codelet. The family of [starpu_vector_data_register\(\)](#) -like functions and the [starpu_data_lookup\(\)](#) function may be used to register a memory area and to retrieve the current data handle associated with a pointer respectively. The testcase `./tests/openmp/task_02.c` gives a detailed example of using OpenMP 4.0 tasks dependencies with the SORS implementation.

Note: the OpenMP 4.0 specification only supports data dependencies between sibling tasks, that is tasks created by the same implicit or explicit parent task. The current SORS implementation also only supports data dependencies between sibling tasks. Consequently the behaviour is unspecified if dependencies are expressed between tasks that have not been created by the same parent task.

24.5.3 TaskWait and TaskGroup

The SORS implements both the `taskwait` and `taskgroup` OpenMP task synchronization constructs specified in OpenMP 4.0, with the [starpu_omp_taskwait\(\)](#) and [starpu_omp_taskgroup\(\)](#) functions respectively.

An example of [starpu_omp_taskwait\(\)](#) use, creating two explicit tasks and waiting for their completion:

```

void task_region_g(void *buffers[], void *args)
{
    (void) buffers;
    (void) args;
    printf("Hello, World!\n");
}

void parallel_region_f(void *buffers[], void *args)
{
    (void) buffers;
    (void) args;
    struct starpu_omp_task_region_attr attr;

```

```

memset(&attr, 0, sizeof(attr));
attr.cl.cpu_funcs[0] = task_region_g;
attr.cl.where        = STARPU_CPU;
attr.if_clause       = 1;
attr.final_clause    = 0;
attr.untied_clause   = 1;
attr.mergeable_clause = 0;
starpu_omp_task_region(&attr);
starpu_omp_task_region(&attr);
starpu_omp_taskwait();

```

An example of `starpu_omp_taskgroup()` use, creating a task group of two explicit tasks:

```

void task_region_g(void *buffers[], void *args)
{
    (void) buffers;
    (void) args;
    printf("Hello, World!\n");
}

void taskgroup_f(void *arg)
{
    (void) arg;
    struct starpu_omp_task_region_attr attr;
    memset(&attr, 0, sizeof(attr));
    attr.cl.cpu_funcs[0] = task_region_g;
    attr.cl.where        = STARPU_CPU;
    attr.if_clause       = 1;
    attr.final_clause    = 0;
    attr.untied_clause   = 1;
    attr.mergeable_clause = 0;
    starpu_omp_task_region(&attr);
    starpu_omp_task_region(&attr);
}

void parallel_region_f(void *buffers[], void *args)
{
    (void) buffers;
    (void) args;
    starpu_omp_taskgroup(taskgroup_f, (void *)NULL);
}

```

See also

[starpu_omp_task_region\(\)](#)
[starpu_omp_taskwait\(\)](#)
[starpu_omp_taskgroup\(\)](#)
[starpu_omp_taskgroup_inline_begin\(\)](#)
[starpu_omp_taskgroup_inline_end\(\)](#)

24.6 Synchronization Support

The SORS implements objects and method to build common OpenMP synchronization constructs.

24.6.1 Simple Locks

The SORS Simple Locks are opaque `starpu_omp_lock_t` objects enabling multiple tasks to synchronize with each others, following the Simple Lock constructs defined by the OpenMP specification. In accordance with such specification, simple locks may not be acquired multiple times by the same task, without being released in-between; otherwise, deadlocks may result. Codes requiring the possibility to lock multiple times recursively should use Nestable Locks ([Nestable Locks](#)). Codes NOT requiring the possibility to lock multiple times recursively should use Simple Locks as they incur less processing overhead than Nestable Locks.

See also

[starpu_omp_lock_t](#)
[starpu_omp_init_lock\(\)](#)
[starpu_omp_destroy_lock\(\)](#)
[starpu_omp_set_lock\(\)](#)
[starpu_omp_unset_lock\(\)](#)
[starpu_omp_test_lock\(\)](#)

24.6.2 Nestable Locks

The SORS Nestable Locks are opaque [starpu_omp_nest_lock_t](#) objects enabling multiple tasks to synchronize with each others, following the Nestable Lock constructs defined by the OpenMP specification. In accordance with such specification, nestable locks may be acquired multiple times recursively by the same task without deadlocking. Nested locking and unlocking operations must be well parenthesized at any time, otherwise deadlock and/or undefined behaviour may occur. Codes requiring the possibility to lock multiple times recursively should use Nestable Locks. Codes NOT requiring the possibility to lock multiple times recursively should use Simple Locks ([Simple Locks](#)) instead, as they incur less processing overhead than Nestable Locks.

See also

[starpu_omp_nest_lock_t](#)
[starpu_omp_init_nest_lock\(\)](#)
[starpu_omp_destroy_nest_lock\(\)](#)
[starpu_omp_set_nest_lock\(\)](#)
[starpu_omp_unset_nest_lock\(\)](#)
[starpu_omp_test_nest_lock\(\)](#)

24.6.3 Critical Sections

The SORS implements support for OpenMP critical sections through the family of `starpu_omp_critical` functions. Critical sections may optionally be named. There is a single, common anonymous critical section. Mutual exclusion only occur within the scope of single critical section, either a named one or the anonymous one.

See also

[starpu_omp_critical\(\)](#)
[starpu_omp_critical_inline_begin\(\)](#)
[starpu_omp_critical_inline_end\(\)](#)

24.6.4 Barriers

The SORS provides the [starpu_omp_barrier\(\)](#) function to implement barriers over parallel region teams. In accordance with the OpenMP specification, the [starpu_omp_barrier\(\)](#) function waits for every implicit task of the parallel region to reach the barrier and every explicit task launched by the parallel region to complete, before returning.

See also

[starpu_omp_barrier\(\)](#)

Part V

StarPU Reference API

Chapter 25

Execution Configuration Through Environment Variables

The behavior of the StarPU library and tools may be tuned thanks to the following environment variables.

25.1 Configuring Workers

STARPU_NCPU Specify the number of CPU workers (thus not including workers dedicated to control accelerators). Note that by default, StarPU will not allocate more CPU workers than there are physical CPUs, and that some CPUs are used to control the accelerators.

STARPU_NCPUS This variable is deprecated. You should use [STARPU_NCPU](#).

STARPU_NCUDA Specify the number of CUDA devices that StarPU can use. If [STARPU_NCUDA](#) is lower than the number of physical devices, it is possible to select which CUDA devices should be used by the means of the environment variable [STARPU_WORKERS_CUDAID](#). By default, StarPU will create as many CUDA workers as there are CUDA devices.

STARPU_NWORKER_PER_CUDA Specify the number of workers per CUDA device, and thus the number of kernels which will be concurrently running on the devices. The default value is 1.

STARPU_CUDA_PIPELINE Specify how many asynchronous tasks are submitted in advance on CUDA devices. This for instance permits to overlap task management with the execution of previous tasks, but it also allows concurrent execution on Fermi cards, which otherwise bring spurious synchronizations. The default is 2. Setting the value to 0 forces a synchronous execution of all tasks.

STARPU_NOPENCL OpenCL equivalent of the environment variable [STARPU_NCUDA](#).

STARPU_OPENCL_PIPELINE Specify how many asynchronous tasks are submitted in advance on OpenCL devices. This for instance permits to overlap task management with the execution of previous tasks, but it also allows concurrent execution on Fermi cards, which otherwise bring spurious synchronizations. The default is 2. Setting the value to 0 forces a synchronous execution of all tasks.

STARPU_OPENCL_ON_CPUS By default, the OpenCL driver only enables GPU and accelerator devices. By setting the environment variable [STARPU_OPENCL_ON_CPUS](#) to 1, the OpenCL driver will also enable CPU devices.

STARPU_OPENCL_ONLY_ON_CPUS By default, the OpenCL driver enables GPU and accelerator devices. By setting the environment variable [STARPU_OPENCL_ONLY_ON_CPUS](#) to 1, the OpenCL driver will ONLY enable CPU devices.

STARPU_NMIC MIC equivalent of the environment variable [STARPU_NCUDA](#), i.e. the number of MIC devices to use.

STARPU_NMICTHREADS Number of threads to use on the MIC devices.

STARPU_NSCC SCC equivalent of the environment variable [STARPU_NCUDA](#).

STARPU_WORKERS_NOBIND Setting it to non-zero will prevent StarPU from binding its threads to CPUs. This is for instance useful when running the testsuite in parallel.

STARPU_WORKERS_CPUID Passing an array of integers in [STARPU_WORKERS_CPUID](#) specifies on which logical CPU the different workers should be bound. For instance, if `STARPU_WORKERS_CPUID = "0 1 4 5"`, the first worker will be bound to logical CPU #0, the second CPU worker will be bound to logical CPU #1 and so on. Note that the logical ordering of the CPUs is either determined by the OS, or provided by the library `hwloc` in case it is available. Ranges can be provided: for instance, `STARPU_WORKERS_CPUID = "1-3 5"` will bind the first three workers on logical CPUs #1, #2, and #3, and the fourth worker on logical CPU #5. Unbound ranges can also be provided: `STARPU_WORKERS_CPUID = "1-"` will bind the workers starting from logical CPU #1 up to last CPU.

Note that the first workers correspond to the CUDA workers, then come the OpenCL workers, and finally the CPU workers. For example if we have `STARPU_NCUDA=1`, `STARPU_NOPENCL=1`, `STARPU_NCPU=2` and `STARPU_WORKERS_CPUID = "0 2 1 3"`, the CUDA device will be controlled by logical CPU #0, the OpenCL device will be controlled by logical CPU #2, and the logical CPUs #1 and #3 will be used by the CPU workers.

If the number of workers is larger than the array given in [STARPU_WORKERS_CPUID](#), the workers are bound to the logical CPUs in a round-robin fashion: if `STARPU_WORKERS_CPUID = "0 1"`, the first and the third (resp. second and fourth) workers will be put on CPU #0 (resp. CPU #1).

This variable is ignored if the field `starpu_conf::use_explicit_workers_bindid` passed to `starpu_init()` is set.

STARPU_WORKERS_CUDAID Similarly to the [STARPU_WORKERS_CPUID](#) environment variable, it is possible to select which CUDA devices should be used by StarPU. On a machine equipped with 4 GPUs, setting `STARPU_WORKERS_CUDAID = "1 3"` and `STARPU_NCUDA=2` specifies that 2 CUDA workers should be created, and that they should use CUDA devices #1 and #3 (the logical ordering of the devices is the one reported by CUDA).

This variable is ignored if the field `starpu_conf::use_explicit_workers_cuda_gpuid` passed to `starpu_init()` is set.

STARPU_WORKERS_OPENCLID OpenCL equivalent of the [STARPU_WORKERS_CUDAID](#) environment variable.

This variable is ignored if the field `starpu_conf::use_explicit_workers_opencl_gpuid` passed to `starpu_init()` is set.

STARPU_WORKERS_MICID MIC equivalent of the [STARPU_WORKERS_CUDAID](#) environment variable.

This variable is ignored if the field `starpu_conf::use_explicit_workers_mic_deviceid` passed to `starpu_init()` is set.

STARPU_WORKERS_SCCID SCC equivalent of the [STARPU_WORKERS_CUDAID](#) environment variable.

This variable is ignored if the field `starpu_conf::use_explicit_workers_scc_deviceid` passed to `starpu_init()` is set.

STARPU_WORKER_TREE Define to 1 to enable the tree iterator in schedulers.

STARPU_SINGLE_COMBINED_WORKER If set, StarPU will create several workers which won't be able to work concurrently. It will by default create combined workers which size goes from 1 to the total number of CPU workers in the system. [STARPU_MIN_WORKERSIZE](#) and [STARPU_MAX_WORKERSIZE](#) can be used to change this default.

STARPU_MIN_WORKERSIZE [STARPU_MIN_WORKERSIZE](#) permits to specify the minimum size of the combined workers (instead of the default 2)

STARPU_MAX_WORKERSIZE [STARPU_MAX_WORKERSIZE](#) permits to specify the minimum size of the combined workers (instead of the number of CPU workers in the system)

STARPU_SYNTHESIZE_ARITY_COMBINED_WORKER Let the user decide how many elements are allowed between combined workers created from hwloc information. For instance, in the case of sockets with 6 cores without shared L2 caches, if **STARPU_SYNTHESIZE_ARITY_COMBINED_WORKER** is set to 6, no combined worker will be synthesized beyond one for the socket and one per core. If it is set to 3, 3 intermediate combined workers will be synthesized, to divide the socket cores into 3 chunks of 2 cores. If it is set to 2, 2 intermediate combined workers will be synthesized, to divide the the socket cores into 2 chunks of 3 cores, and then 3 additional combined workers will be synthesized, to divide the former synthesized workers into a bunch of 2 cores, and the remaining core (for which no combined worker is synthesized since there is already a normal worker for it).

The default, 2, thus makes StarPU tend to building a binary trees of combined workers.

STARPU_DISABLE_ASYNCHRONOUS_COPY Disable asynchronous copies between CPU and GPU devices. The AMD implementation of OpenCL is known to fail when copying data asynchronously. When using this implementation, it is therefore necessary to disable asynchronous data transfers.

STARPU_DISABLE_ASYNCHRONOUS_CUDA_COPY Disable asynchronous copies between CPU and CUDA devices.

STARPU_DISABLE_ASYNCHRONOUS_OPENCL_COPY Disable asynchronous copies between CPU and OpenCL devices. The AMD implementation of OpenCL is known to fail when copying data asynchronously. When using this implementation, it is therefore necessary to disable asynchronous data transfers.

STARPU_DISABLE_ASYNCHRONOUS_MIC_COPY Disable asynchronous copies between CPU and MIC devices.

STARPU_ENABLE_CUDA_GPU_GPU_DIRECT Enable (1) or Disable (0) direct CUDA transfers from GPU to GPU, without copying through RAM. The default is Enabled. This permits to test the performance effect of GPU-Direct.

STARPU_DISABLE_PINNING Disable (1) or Enable (0) pinning host memory allocated through `starpu_malloc`, `starpu_memory_pin` and friends. The default is Enabled. This permits to test the performance effect of memory pinning.

STARPU_MIC_SINK_PROGRAM_NAME todo

STARPU_MIC_SINK_PROGRAM_PATH todo

STARPU_MIC_PROGRAM_PATH todo

25.2 Configuring The Scheduling Engine

STARPU_SCHED Choose between the different scheduling policies proposed by StarPU: work random, stealing, greedy, with performance models, etc.

Use `STARPU_SCHED=help` to get the list of available schedulers.

STARPU_MIN_PRIO Set the minimum priority used by priorities-aware schedulers.

STARPU_MAX_PRIO Set the maximum priority used by priorities-aware schedulers.

STARPU_CALIBRATE If this variable is set to 1, the performance models are calibrated during the execution. If it is set to 2, the previous values are dropped to restart calibration from scratch. Setting this variable to 0 disable calibration, this is the default behaviour.

Note: this currently only applies to `dm` and `dmnda` scheduling policies.

STARPU_CALIBRATE_MINIMUM This defines the minimum number of calibration measurements that will be made before considering that the performance model is calibrated. The default value is 10.

STARPU_BUS_CALIBRATE If this variable is set to 1, the bus is recalibrated during initialization.

STARPU_PREFETCH This variable indicates whether data prefetching should be enabled (0 means that it is disabled). If prefetching is enabled, when a task is scheduled to be executed e.g. on a GPU, StarPU will request an asynchronous transfer in advance, so that data is already present on the GPU when the task starts. As a result, computation and data transfers are overlapped. Note that prefetching is enabled by default in StarPU.

STARPU_SCHED_ALPHA To estimate the cost of a task StarPU takes into account the estimated computation time (obtained thanks to performance models). The alpha factor is the coefficient to be applied to it before adding it to the communication part.

STARPU_SCHED_BETA To estimate the cost of a task StarPU takes into account the estimated data transfer time (obtained thanks to performance models). The beta factor is the coefficient to be applied to it before adding it to the computation part.

STARPU_SCHED_GAMMA Define the execution time penalty of a joule ([Energy-based Scheduling](#)).

STARPU_IDLE_POWER Define the idle power of the machine ([Energy-based Scheduling](#)).

STARPU_PROFILING Enable on-line performance monitoring ([Enabling On-line Performance Monitoring](#)).

25.3 Extensions

SOCL_OCL_LIB_OPENCL THE SOCL test suite is only run when the environment variable [SOCL_OCL_LIB_OPENCL](#) is defined. It should contain the location of the file `libOpenCL.so` of the OCL ICD implementation.

OCL_ICD_VENDORS When using SOCL with OpenCL ICD (<https://forge.imag.fr/projects/ocl-icd/>), this variable may be used to point to the directory where ICD files are installed. The default directory is `/etc/OpenCL/vendors`. StarPU installs ICD files in the directory `$prefix/share/starpu/opencl/vendors`.

STARPU_COMM_STATS Communication statistics for starpumpi ([MPI Support](#)) will be enabled when the environment variable [STARPU_COMM_STATS](#) is defined to an value other than 0.

STARPU_MPI_CACHE Communication cache for starpumpi ([MPI Support](#)) will be disabled when the environment variable [STARPU_MPI_CACHE](#) is set to 0. It is enabled by default or for any other values of the variable [STARPU_MPI_CACHE](#).

STARPU_MPI_COMM Communication trace for starpumpi ([MPI Support](#)) will be enabled when the environment variable [STARPU_MPI_COMM](#) is set to 1, and StarPU has been configured with the option `--enable-verbose`.

STARPU_MPI_CACHE_STATS When set to 1, statistics are enabled for the communication cache ([MPI Support](#)). For now, it prints messages on the standard output when data are added or removed from the received communication cache.

STARPU_MPI_FAKE_SIZE Setting to a number makes StarPU believe that there are as many MPI nodes, even if it was run on only one MPI node. This allows e.g. to simulate the execution of one of the nodes of a big cluster without actually running the rest. It of course does not provide computation results and timing.

STARPU_MPI_FAKE_RANK Setting to a number makes StarPU believe that it runs the given MPI node, even if it was run on only one MPI node. This allows e.g. to simulate the execution of one of the nodes of a big cluster without actually running the rest. It of course does not provide computation results and timing.

STARPU_SIMGRID_CUDA_MALLOC_COST When set to 1 (which is the default), CUDA malloc costs are taken into account in simgrid mode.

STARPU_SIMGRID_CUDA_QUEUE_COST When set to 1 (which is the default), CUDA task and transfer queueing costs are taken into account in simgrid mode.

STARPU_PCI_FLAT When unset or set to 0, the platform file created for simgrid will contain PCI bandwidths and routes.

STARPU_SIMGRID_QUEUE_MALLOC_COST When unset or set to 1, simulate within simgrid the GPU transfer queueing.

STARPU_MALLOC_SIMULATION_FOLD This defines the size of the file used for folding virtual allocation, in MiB. The default is 1, thus allowing 64GiB virtual memory when Linux's `sysctl vm.max_map_count` value is the default 65535.

25.4 Miscellaneous And Debug

STARPU_HOME This specifies the main directory in which StarPU stores its configuration files. The default is `$HOME` on Unix environments, and `$USERPROFILE` on Windows environments.

STARPU_PATH Only used on Windows environments. This specifies the main directory in which StarPU is installed ([Running a Basic StarPU Application on Microsoft Visual C](#))

STARPU_PERF_MODEL_DIR This specifies the main directory in which StarPU stores its performance model files. The default is `$STARPU_HOME/.starpu/sampling`.

STARPU_PERF_MODEL_HOMOGENEOUS_CPU When this is set to 0, StarPU will assume that CPU devices do not have the same performance, and thus use different performance models for them, thus making kernel calibration much longer, since measurements have to be made for each CPU core.

STARPU_PERF_MODEL_HOMOGENEOUS_CUDA When this is set to 1, StarPU will assume that all CUDA devices have the same performance, and thus share performance models for them, thus allowing kernel calibration to be much faster, since measurements only have to be once for all CUDA GPUs.

STARPU_PERF_MODEL_HOMOGENEOUS_OPENCL When this is set to 1, StarPU will assume that all OPENCL devices have the same performance, and thus share performance models for them, thus allowing kernel calibration to be much faster, since measurements only have to be once for all OPENCL GPUs.

STARPU_PERF_MODEL_HOMOGENEOUS_MIC When this is set to 1, StarPU will assume that all MIC devices have the same performance, and thus share performance models for them, thus allowing kernel calibration to be much faster, since measurements only have to be once for all MIC GPUs.

STARPU_PERF_MODEL_HOMOGENEOUS_SCC When this is set to 1, StarPU will assume that all SCC devices have the same performance, and thus share performance models for them, thus allowing kernel calibration to be much faster, since measurements only have to be once for all SCC GPUs.

STARPU_HOSTNAME When set, force the hostname to be used when dealing performance model files. Models are indexed by machine name. When running for example on a homogenous cluster, it is possible to share the models between machines by setting `export STARPU_HOSTNAME=some_global_name`.

STARPU_OPENCL_PROGRAM_DIR This specifies the directory where the OpenCL codelet source files are located. The function `starpu_opencload_program_source()` looks for the codelet in the current directory, in the directory specified by the environment variable `STARPU_OPENCL_PROGRAM_DIR`, in the directory `share/starpu/opencload` of the installation directory of StarPU, and finally in the source directory of StarPU.

STARPU_SILENT This variable allows to disable verbose mode at runtime when StarPU has been configured with the option `--enable-verbose`. It also disables the display of StarPU information and warning messages.

STARPU_LOGFILENAME This variable specifies in which file the debugging output should be saved to.

STARPU_FXT_PREFIX This variable specifies in which directory to save the trace generated if FxT is enabled. It needs to have a trailing '/' character.

STARPU_FXT_TRACE This variable specifies whether to generate (1) or not (0) the FxT trace in `/tmp/prof_file_XXX_YYY`. The default is 1 (generate it)

STARPU_LIMIT_CUDA_devid_MEM This variable specifies the maximum number of megabytes that should be available to the application on the CUDA device with the identifier `devid`. This variable is intended to be used for experimental purposes as it emulates devices that have a limited amount of memory. When defined, the variable overwrites the value of the variable `STARPU_LIMIT_CUDA_MEM`.

STARPU_LIMIT_CUDA_MEM This variable specifies the maximum number of megabytes that should be available to the application on each CUDA devices. This variable is intended to be used for experimental purposes as it emulates devices that have a limited amount of memory.

STARPU_LIMIT_OPENCL_devid_MEM This variable specifies the maximum number of megabytes that should be available to the application on the OpenCL device with the identifier `devid`. This variable is intended to be used for experimental purposes as it emulates devices that have a limited amount of memory. When defined, the variable overwrites the value of the variable [STARPU_LIMIT_OPENCL_MEM](#).

STARPU_LIMIT_OPENCL_MEM This variable specifies the maximum number of megabytes that should be available to the application on each OpenCL devices. This variable is intended to be used for experimental purposes as it emulates devices that have a limited amount of memory.

STARPU_LIMIT_CPU_MEM This variable specifies the maximum number of megabytes that should be available to the application in the main CPU memory. Setting it enables allocation cache in main memory. Setting it to zero lets StarPU overflow memory.

STARPU_MINIMUM_AVAILABLE_MEM This specifies the minimum percentage of memory that should be available in GPUs (or in main memory, when using out of core), below which a reclaiming pass is performed. The default is 5%.

STARPU_TARGET_AVAILABLE_MEM This specifies the target percentage of memory that should be reached in GPUs (or in main memory, when using out of core), when performing a periodic reclaiming pass. The default is 10%.

STARPU_MINIMUM_CLEAN_BUFFERS This specifies the minimum percentage of number of buffers that should be clean in GPUs (or in main memory, when using out of core), below which asynchronous writebacks will be issued. The default is to disable asynchronous writebacks.

STARPU_TARGET_CLEAN_BUFFERS This specifies the target percentage of number of buffers that should be reached in GPUs (or in main memory, when using out of core), when performing an asynchronous writeback pass. The default is to disable asynchronous writebacks.

STARPU_DISK_SWAP This specifies a path where StarPU can push data when the main memory is getting full.

STARPU_DISK_SWAP_BACKEND This specifies then backend to be used by StarPU to push data when the main memory is getting full. The default is `unstd` (i.e. using read/write functions), other values are `stdio` (i.e. using `fread/fwrite`), `unstd_o_direct` (i.e. using read/write with `O_DIRECT`), and `leveldb` (i.e. using a `leveldb` database).

STARPU_DISK_SWAP_SIZE This specifies then maximum size in MiB to be used by StarPU to push data when the main memory is getting full. The default is unlimited.

STARPU_LIMIT_MAX_SUBMITTED_TASKS This variable allows the user to control the task submission flow by specifying to StarPU a maximum number of submitted tasks allowed at a given time, i.e. when this limit is reached task submission becomes blocking until enough tasks have completed, specified by [STARPU_LIMIT_MIN_SUBMITTED_TASKS](#). Setting it enables allocation cache buffer reuse in main memory.

STARPU_LIMIT_MIN_SUBMITTED_TASKS This variable allows the user to control the task submission flow by specifying to StarPU a submitted task threshold to wait before unblocking task submission. This variable has to be used in conjunction with [STARPU_LIMIT_MAX_SUBMITTED_TASKS](#) which puts the task submission thread to sleep. Setting it enables allocation cache buffer reuse in main memory.

STARPU_TRACE_BUFFER_SIZE This sets the buffer size for recording trace events in MiB. Setting it to a big size allows to avoid pauses in the trace while it is recorded on the disk. This however also consumes memory, of course. The default value is 64.

STARPU_GENERATE_TRACE When set to 1, this variable indicates that StarPU should automatically generate a Paje trace when `starpu_shutdown()` is called.

STARPU_MEMORY_STATS When set to 0, disable the display of memory statistics on data which have not been unregistered at the end of the execution ([Memory Feedback](#)).

STARPU_MAX_MEMORY_USE When set to 1, display at the end of the execution the maximum memory used by StarPU for internal data structures during execution.

STARPU_BUS_STATS When defined, statistics about data transfers will be displayed when calling `starpu_↵ shutdown()` ([Profiling](#)).

STARPU_WORKER_STATS When defined, statistics about the workers will be displayed when calling `starpu_↵ shutdown()` ([Profiling](#)). When combined with the environment variable `STARPU_PROFILING`, it displays the energy consumption ([Energy-based Scheduling](#)).

STARPU_STATS When set to 0, data statistics will not be displayed at the end of the execution of an application ([Data Statistics](#)).

STARPU_WATCHDOG_TIMEOUT When set to a value other than 0, allows to make StarPU print an error message whenever StarPU does not terminate any task for the given time (in μ s), but lets the application continue normally. Should be used in combination with `STARPU_WATCHDOG_CRASH` (see [Detection Stuck Conditions](#)).

STARPU_WATCHDOG_CRASH When set to a value other than 0, it triggers a crash when the watch dog is reached, thus allowing to catch the situation in gdb, etc (see [Detection Stuck Conditions](#))

STARPU_WATCHDOG_DELAY This delays the activation of the watchdog by the given time (in μ s). This can be convenient for letting the application initialize data etc. before starting to look for idle time.

STARPU_TASK_BREAK_ON_PUSH When this variable contains a job id, StarPU will raise SIGTRAP when the task with that job id is being pushed to the scheduler, which will be nicely caught by debuggers (see [Debugging Scheduling](#))

STARPU_TASK_BREAK_ON_SCHED When this variable contains a job id, StarPU will raise SIGTRAP when the task with that job id is being scheduled by the scheduler (at a scheduler-specific point), which will be nicely caught by debuggers. This only works for schedulers which have such a scheduling point defined (see [Debugging Scheduling](#))

STARPU_TASK_BREAK_ON_POP When this variable contains a job id, StarPU will raise SIGTRAP when the task with that job id is being popped from the scheduler, which will be nicely caught by debuggers (see [Debugging Scheduling](#))

STARPU_TASK_BREAK_ON_EXEC When this variable contains a job id, StarPU will raise SIGTRAP when the task with that job id is being executed, which will be nicely caught by debuggers (see [Debugging Scheduling](#))

STARPU_DISABLE_KERNELS When set to a value other than 1, it disables actually calling the kernel functions, thus allowing to quickly check that the task scheme is working properly, without performing the actual application-provided computation.

STARPU_HISTORY_MAX_ERROR History-based performance models will drop measurements which are really far from the measured average. This specifies the allowed variation. The default is 50 (%), i.e. the measurement is allowed to be x1.5 faster or /1.5 slower than the average.

STARPU_RAND_SEED The random scheduler and some examples use random numbers for their own working. Depending on the examples, the seed is by default just always 0 or the current time() (unless simgrid mode is enabled, in which case it is always 0). `STARPU_RAND_SEED` allows to set the seed to a specific value.

STARPU_IDLE_TIME When set to a value being a valid filename, a corresponding file will be created when shutting down StarPU. The file will contain the sum of all the workers' idle time.

STARPU_GLOBAL_ARBITER When set to a positive value, StarPU will create an arbiter, which implements an advanced but centralized management of concurrent data accesses (see [Concurrent Data Accesses](#)).

STARPU_IDLE_FILE If the environment variable `STARPU_IDLE_FILE` is defined, a file named after its contents will be created at the end of the execution. The file will contain the sum of the idle times of all the workers.

25.5 Configuring The Hypervisor

SC_HYPERVISOR_POLICY Choose between the different resizing policies proposed by StarPU for the hypervisor: `idle`, `app_driven`, `feft_lp`, `teft_lp`; `ispeed_lp`, `throughput_lp` etc.

Use `SC_HYPERVISOR_POLICY=help` to get the list of available policies for the hypervisor

SC_HYPERVISOR_TRIGGER_RESIZE Choose how should the hypervisor be triggered: `speed` if the resizing algorithm should be called whenever the speed of the context does not correspond to an optimal precomputed value, `idle` if the resizing algorithm should be called whenever the workers are idle for a period longer than the value indicated when configuring the hypervisor.

SC_HYPERVISOR_START_RESIZE Indicate the moment when the resizing should be available. The value correspond to the percentage of the total time of execution of the application. The default value is the resizing frame.

SC_HYPERVISOR_MAX_SPEED_GAP Indicate the ratio of speed difference between contexts that should trigger the hypervisor. This situation may occur only when a theoretical speed could not be computed and the hypervisor has no value to compare the speed to. Otherwise the resizing of a context is not influenced by the the speed of the other contexts, but only by the the value that a context should have.

SC_HYPERVISOR_STOP_PRINT By default the values of the speed of the workers is printed during the execution of the application. If the value 1 is given to this environment variable this printing is not done.

SC_HYPERVISOR_LAZY_RESIZE By default the hypervisor resizes the contexts in a lazy way, that is workers are firstly added to a new context before removing them from the previous one. Once this workers are clearly taken into account into the new context (a task was popped there) we remove them from the previous one. However if the application would like that the change in the distribution of workers should change right away this variable should be set to 0

SC_HYPERVISOR_SAMPLE_CRITERIA By default the hypervisor uses a sample of flops when computing the speed of the contexts and of the workers. If this variable is set to `time` the hypervisor uses a sample of time (10% of an approximation of the total execution time of the application)

Chapter 26

Compilation Configuration

The behavior of the StarPU library and tools may be tuned thanks to the following configure options.

26.1 Common Configuration

-enable-debug Enable debugging messages.

-enable-spinlock-check Enable checking that spinlocks are taken and released properly.

-enable-fast Disable assertion checks, which saves computation time.

-enable-verbose Increase the verbosity of the debugging messages. This can be disabled at runtime by setting the environment variable `STARPU_SILENT` to any value. `-enable-verbose=extra` increase even more the verbosity.

```
$ STARPU_SILENT=1 ./vector_scal
```

-enable-coverage Enable flags for the coverage tool `gcov`.

-enable-quick-check Specify tests and examples should be run on a smaller data set, i.e allowing a faster execution time

-enable-long-check Enable some exhaustive checks which take a really long time.

-enable-new-check Enable new testcases which are known to fail.

-with-hwloc Specify `hwloc` should be used by StarPU. `hwloc` should be found by the means of the tool `pkg-config`.

-with-hwloc=prefix Specify `hwloc` should be used by StarPU. `hwloc` should be found in the directory specified by `prefix`

-without-hwloc Specify `hwloc` should not be used by StarPU.

-disable-build-doc Disable the creation of the documentation. This should be done on a machine which does not have the tools `doxygen` and `latex` (plus the packages `latex-xcolor` and `texlive-latex-extra`).

-disable-icc Disable the usage of the ICC compiler. When found, some specific ICC examples are compiled.

Additionally, the script `configure` recognize many variables, which can be listed by typing `./configure -help`. For example, `./configure NVCCFLAGS="-arch sm_20"` adds a flag for the compilation of CUDA kernels, and `NVCC_CC=gcc-5` allows to change the C++ compiler used by `nvcc`.

26.2 Configuring Workers

- enable-blocking-drivers** By default, StarPU keeps CPU workers awake permanently, for better reactivity. This option makes StarPU put CPU workers to real sleep when there are not enough tasks to compute.
Use at most `count` CPU cores. This information is then available as the macro `STARPU_MAXCPUS`.
- enable-maxcpus=count** Use at most `count` CPU cores. This information is then available as the macro `STARPU_MAXCPUS`.
- disable-cpu** Disable the use of CPUs of the machine. Only GPUs etc. will be used.
- enable-maxcudadev=count** Use at most `count` CUDA devices. This information is then available as the macro `STARPU_MAXCUDADEVs`.
- disable-cuda** Disable the use of CUDA, even if a valid CUDA installation was detected.
- with-cuda-dir=prefix** Search for CUDA under `prefix`, which should notably contain the file `include/cuda.h`.
- with-cuda-include-dir=dir** Search for CUDA headers under `dir`, which should notably contain the file `cuda.h`. This defaults to `/include` appended to the value given to `--with-cuda-dir`.
- with-cuda-lib-dir=dir** Search for CUDA libraries under `dir`, which should notably contain the CUDA shared libraries—e.g., `libcuda.so`. This defaults to `/lib` appended to the value given to `--with-cuda-dir`.
- disable-cuda-memcpy-peer** Explicitly disable peer transfers when using CUDA 4.0.
- enable-maxopencldev=count** Use at most `count` OpenCL devices. This information is then available as the macro `STARPU_MAXOPENCLDEVs`.
- disable-opencl** Disable the use of OpenCL, even if the SDK is detected.
- with-opencl-dir=prefix** Search for an OpenCL implementation under `prefix`, which should notably contain `include/CL/cl.h` (or `include/OpenCL/cl.h` on Mac OS).
- with-opencl-include-dir=dir** Search for OpenCL headers under `dir`, which should notably contain `CL/cl.h` (or `OpenCL/cl.h` on Mac OS). This defaults to `/include` appended to the value given to `--with-opencl-dir`.
- with-opencl-lib-dir=dir** Search for an OpenCL library under `dir`, which should notably contain the OpenCL shared libraries—e.g. `libOpenCL.so`. This defaults to `/lib` appended to the value given to `--with-opencl-dir`.
- enable-opencl-simulator** Enable considering the provided OpenCL implementation as a simulator, i.e. use the kernel duration returned by OpenCL profiling information as wallclock time instead of the actual measured real time. This requires simgrid support.
- enable-maximplementations=count** Allow for at most `count` codelet implementations for the same target device. This information is then available as the macro `STARPU_MAXIMPLEMENTATIONS` macro.
- enable-max-sched-ctxs=count** Allow for at most `count` scheduling contexts This information is then available as the macro `STARPU_NMAX_SCHED_CTXS`.
- disable-asynchronous-copy** Disable asynchronous copies between CPU and GPU devices. The AMD implementation of OpenCL is known to fail when copying data asynchronously. When using this implementation, it is therefore necessary to disable asynchronous data transfers.
- disable-asynchronous-cuda-copy** Disable asynchronous copies between CPU and CUDA devices.
- disable-asynchronous-opencl-copy** Disable asynchronous copies between CPU and OpenCL devices. The AMD implementation of OpenCL is known to fail when copying data asynchronously. When using this implementation, it is therefore necessary to disable asynchronous data transfers.
- enable-maxmicthreads** Specify the maximum number of MIC threads
- disable-asynchronous-mic-copy** Disable asynchronous copies between CPU and MIC devices.
- enable-maxnodes=count** Use at most `count` memory nodes. This information is then available as the macro `STARPU_MAXNODES`. Reducing it allows to considerably reduce memory used by StarPU data structures.

26.3 Extension Configuration

-enable-mpi-verbose Increase the verbosity of the MPI debugging messages. This can be disabled at runtime by setting the environment variable `STARPU_SILENT` to any value. `-enable-mpi-verbose=extra` increase even more the verbosity.

```
$ STARPU_SILENT=1 mpirun -np 2 ./insert_task
```

-disable-fortran Disable the fortran extension. By default, it is enabled when a fortran compiler is found.

-disable-socl Disable the SOCL extension ([SOCL OpenCL Extensions](#)). By default, it is enabled when an OpenCL implementation is found.

-disable-starpu-top Disable the StarPU-Top interface ([StarPU-Top Interface](#)). By default, it is enabled when the required dependencies are found.

-disable-gcc-extensions Disable the GCC plug-in ([C Extensions](#)). By default, it is enabled when the GCC compiler provides a plug-in support.

-with-mpicc=path Use the compiler `mpicc` at `path`, for StarPU-MPI. ([MPI Support](#)).

-enable-mpi-progression-hook Enable the activity polling method for StarPU-MPI. This is however experimental, do not enable it unless you know what you are doing.

-with-coi-dir Specify the directory to the COI library for MIC support. The default value is `/opt/intel/mic/coi`

-mic-host Specify the precise MIC architecture host identifier. The default value is `x86_64-k10m-linux`

-enable-openmp Enable OpenMP Support ([The StarPU OpenMP Runtime Support \(SORS\)](#))

26.4 Advanced Configuration

-enable-perf-debug Enable performance debugging through gprof.

-enable-model-debug Enable performance model debugging.

-enable-fxt-lock Enable additional trace events which describes locks behaviour. This is however extremely heavy and should only be enabled when debugging insides of StarPU.

-enable-stats (see `../src/datawizard/datastats.c`) Enable gathering of various data statistics ([Data Statistics](#)).

-enable-maxbuffers Define the maximum number of buffers that tasks will be able to take as parameters, then available as the macro `STARPU_NMAXBUFS`.

-enable-allocation-cache Enable the use of a data allocation cache to avoid the cost of it with CUDA. Still experimental.

-enable-opengl-render Enable the use of OpenGL for the rendering of some examples.

-enable-blas-lib=prefix Specify the blas library to be used by some of the examples. Librairies available :

- none [default] : no BLAS library is used
- atlas: use ATLAS library
- goto: use GotoBLAS library
- openblas: use OpenBLAS library
- mkl: use MKL library (you may need to set specific CFLAGS and LDFLAGS with `-with-mkl-cflags` and `-with-mkl-ldflags`)

-enable-leveldb Enable linking with LevelDB if available

- disable-starpufft** Disable the build of libstarpufft, even if `fftw` or `cuFFT` is available.
- enable-starpufft-examples** Enable the compilation and the execution of the libstarpufft examples. By default, they are neither compiled nor checked.
- with-fxt=prefix** Search for FxT under `prefix`. FxT (<http://savannah.nongnu.org/projects/fkt>) is used to generate traces of scheduling events, which can then be rendered them using ViTE ([Off-line Performance Feedback](#)). `prefix` should notably contain `include/fxt/fxt.h`.
- with-perf-model-dir=dir** Store performance models under `dir`, instead of the current user's home.
- with-goto-dir=prefix** Search for GotoBLAS under `prefix`, which should notably contain `libgoto.so` or `libgoto2.so`.
- with-atlas-dir=prefix** Search for ATLAS under `prefix`, which should notably contain `include/cblas.h`.
- with-mkl-cflags=cflags** Use `cflags` to compile code that uses the MKL library.
- with-mkl-ldflags=ldflags** Use `ldflags` when linking code that uses the MKL library. Note that the MKL website (<http://software.intel.com/en-us/articles/intel-mkl-link-line-advisor/>) provides a script to determine the linking flags.
- disable-glpk** Disable the use of libglpk for computing area bounds.
- disable-build-tests** Disable the build of tests.
- disable-build-examples** Disable the build of examples.
- disable-build-tests** Disable the build of tests.
- enable-sc-hypervisor** Enable the Scheduling Context Hypervisor plugin ([Scheduling Context Hypervisor](#)). By default, it is disabled.
- enable-memory-stats** Enable memory statistics ([Memory Feedback](#)).
- enable-simgrid** Enable simulation of execution in simgrid, to allow easy experimentation with various numbers of cores and GPUs, or amount of memory, etc. Experimental.
The path to simgrid can be specified through the `SIMGRID_CFLAGS` and `SIMGRID_LIBS` environment variables, for instance:

```
export SIMGRID_CFLAGS="-I/usr/local/simgrid/include"
export SIMGRID_LIBS="-L/usr/local/simgrid/lib -lsimgrid"
```
- with-simgrid-dir** Similar to the option [--enable-simgrid](#) but also allows to specify the location to the SimGrid library.
- with-simgrid-include-dir** Similar to the option [--enable-simgrid](#) but also allows to specify the location to the SimGrid include directory.
- with-simgrid-lib-dir** Similar to the option [--enable-simgrid](#) but also allows to specify the location to the SimGrid lib directory.
- with-mpirun=path** Use the mpirun at `path`
- enable-calibration-heuristic** Allows to set the maximum authorized percentage of deviation for the history-based calibrator of StarPU. A correct value of this parameter must be in `[0..100]`. The default value of this parameter is 10. Experimental.

Chapter 27

Module Index

27.1 Modules

Here is a list of all modules:

Bitmap	210
Codelet And Tasks	289
CUDA Extensions	342
Data Interfaces	233
Data Management	221
Out Of Core	281
Data Partition	269
Expert Mode	418
Explicit Dependencies	321
FFT Support	391
FxT Support	388
Implicit Data Dependencies	324
Initialization and Termination	180
Insert_Task	315
Theoretical Lower Bound on Execution Time	341
MIC Extensions	383
Miscellaneous Helpers	386
Modularized Scheduler Interface	461
MPI Support	393
Multiformat Data Interface	287
OpenCL Extensions	345
OpenMP Runtime Support	354
Parallel Tasks	415
Performance Model	326
Profiling	335
Running Drivers	417
SCC Extensions	385
Scheduling Contexts	426
Scheduling Policy	437
Standard Memory Library	188
Task Bundles	410
Task Lists	412
Threads	197
Toolbox	193
StarPU-Top Interface	419

Tree	445
Versioning	179
Workers' Properties	213
Scheduling Context Hypervisor - Building a new resizing policy	454
Scheduling Context Hypervisor - Regular usage	448

Chapter 28

Module Documentation a.k.a StarPU's API

28.1 Versioning

Macros

- `#define STARPU_MAJOR_VERSION`
- `#define STARPU_MINOR_VERSION`
- `#define STARPU_RELEASE_VERSION`

Functions

- `void starpu_get_version (int *major, int *minor, int *release)`

28.1.1 Detailed Description

28.1.2 Macro Definition Documentation

28.1.2.1 STARPU_MAJOR_VERSION

```
#define STARPU_MAJOR_VERSION
```

Define the major version of StarPU. This is the version used when compiling the application.

28.1.2.2 STARPU_MINOR_VERSION

```
#define STARPU_MINOR_VERSION
```

Define the minor version of StarPU. This is the version used when compiling the application.

28.1.2.3 STARPU_RELEASE_VERSION

```
#define STARPU_RELEASE_VERSION
```

Define the release version of StarPU. This is the version used when compiling the application.

28.1.3 Function Documentation

28.1.3.1 starpu_get_version()

```
void starpu_get_version (
    int * major,
    int * minor,
    int * release )
```

Return as 3 integers the version of StarPU used when running the application.

28.2 Initialization and Termination

Data Structures

- struct [starpu_driver](#)
- union [starpu_driver.id](#)
- struct [starpu_conf](#)

Functions

- int [starpu_init](#) (struct [starpu_conf](#) *conf) [STARPU_WARN_UNUSED_RESULT](#)
- int [starpu_initialize](#) (struct [starpu_conf](#) *user_conf, int *argc, char ***argv)
- int [starpu_conf_init](#) (struct [starpu_conf](#) *conf)
- void [starpu_shutdown](#) (void)
- void [starpu_pause](#) (void)
- void [starpu_resume](#) (void)
- int [starpu_asynchronous_copy_disabled](#) (void)
- int [starpu_asynchronous_cuda_copy_disabled](#) (void)
- int [starpu_asynchronous_opengl_copy_disabled](#) (void)
- int [starpu_asynchronous_mic_copy_disabled](#) (void)
- void [starpu_topology_print](#) (FILE *f)

28.2.1 Detailed Description

28.2.2 Data Structure Documentation

28.2.2.1 struct starpu_driver

structure for a driver

Data Fields

enum starpu_worker_archtype	type	The type of the driver. Only STARPU_CPU_WORKER , STARPU_CUDA_WORKER and STARPU_OPENCL_WORKER are currently supported.
union starpu_driver	id	The identifier of the driver.

28.2.2.2 union starpu_driver.id

Data Fields

unsigned	cpu_id	
unsigned	cuda_id	
cl_device_id	opencl_id	

28.2.2.3 struct starpu_conf

This structure is passed to the [starpu_init\(\)](#) function in order to configure StarPU. It has to be initialized with [starpu_conf_init\(\)](#). When the default value is used, StarPU automatically selects the number of processing units and takes the default scheduling policy. The environment variables overwrite the equivalent parameters.

Data Fields

int	magic	Will be initialized by starpu_conf_init() . Should not be set by hand.
const char *	sched_policy_name	This is the name of the scheduling policy. This can also be specified with the environment variable STARPU_SCHED . (default = NULL).
struct starpu_sched_policy *	sched_policy	This is the definition of the scheduling policy. This field is ignored if starpu_conf::sched_policy_name is set. (default = NULL)
int	ncpus	This is the number of CPU cores that StarPU can use. This can also be specified with the environment variable STARPU_NCPU . (default = -1)
int	ncuda	This is the number of CUDA devices that StarPU can use. This can also be specified with the environment variable STARPU_NCUDA . (default = -1)
int	nopencl	This is the number of OpenCL devices that StarPU can use. This can also be specified with the environment variable STARPU_NOPENCL . (default = -1)

Data Fields

int	nmic	This is the number of MIC devices that StarPU can use. This can also be specified with the environment variable STARPU_NMIC . (default = -1)
int	nscc	This is the number of SCC devices that StarPU can use. This can also be specified with the environment variable STARPU_NSICC . (default = -1)
unsigned	use_explicit_workers_bindid	If this flag is set, the starpu_conf::workers_bindid array indicates where the different workers are bound, otherwise StarPU automatically selects where to bind the different workers. This can also be specified with the environment variable STARPU_WORKERS_CPUID . (default = 0)
unsigned	workers_bindid[STARPU_NMAXWORKERS]	If the starpu_conf::use_explicit_workers_bindid flag is set, this array indicates where to bind the different workers. The i-th entry of the starpu_conf::workers_bindid indicates the logical identifier of the processor which should execute the i-th worker. Note that the logical ordering of the CPUs is either determined by the OS, or provided by the hwloc library in case it is available.
unsigned	use_explicit_workers_cuda_gpuid	If this flag is set, the CUDA workers will be attached to the CUDA devices specified in the starpu_conf::workers_cuda_gpuid array. Otherwise, StarPU affects the CUDA devices in a round-robin fashion. This can also be specified with the environment variable STARPU_WORKERS_CUDAID . (default = 0)
unsigned	workers_cuda_gpuid[STARPU_NMAXWORKERS]	If the starpu_conf::use_explicit_workers_cuda_gpuid flag is set, this array contains the logical identifiers of the CUDA devices (as used by <code>cudaGetDevice()</code>).

Data Fields

unsigned	use_explicit_workers_opencl_gpuid	If this flag is set, the OpenCL workers will be attached to the OpenCL devices specified in the <code>starpu_conf::workers_opencl_gpuid</code> array. Otherwise, StarPU affects the OpenCL devices in a round-robin fashion. This can also be specified with the environment variable <code>STARPU_WORKERS_OPENCLID</code> . (default = 0)
unsigned	workers_opencl_gpuid[<code>STARPU_NMAXWORKERS</code>]	If the flag <code>starpu_conf::use_explicit_workers_opencl_gpuid</code> is set, this array contains the logical identifiers of the OpenCL devices to be used.
unsigned	use_explicit_workers_mic_deviceid	If this flag is set, the MIC workers will be attached to the MIC devices specified in the array <code>starpu_conf::workers_mic_deviceid</code> . Otherwise, StarPU affects the MIC devices in a round-robin fashion. This can also be specified with the environment variable <code>STARPU_WORKERS_MICID</code> . (default = 0)
unsigned	workers_mic_deviceid[<code>STARPU_NMAXWORKERS</code>]	If the flag <code>starpu_conf::use_explicit_workers_mic_deviceid</code> is set, the array contains the logical identifiers of the MIC devices to be used.
unsigned	use_explicit_workers_scc_deviceid	If this flag is set, the SCC workers will be attached to the SCC devices specified in the array <code>starpu_conf::workers_scc_deviceid</code> . (default = 0)
unsigned	workers_scc_deviceid[<code>STARPU_NMAXWORKERS</code>]	If the flag <code>starpu_conf::use_explicit_workers_scc_deviceid</code> is set, the array contains the logical identifiers of the SCC devices to be used. Otherwise, StarPU affects the SCC devices in a round-robin fashion. This can also be specified with the environment variable <code>STARPU_WORKERS_SCCID</code> .
int	bus_calibrate	If this flag is set, StarPU will recalibrate the bus. If this value is equal to <code>-1</code> , the default value is used. This can also be specified with the environment variable <code>STARPU_BUS_CALIBRATE</code> . (default = 0)

Data Fields

int	calibrate	If this flag is set, StarPU will calibrate the performance models when executing tasks. If this value is equal to <code>-1</code> , the default value is used. If the value is equal to <code>1</code> , it will force continuing calibration. If the value is equal to <code>2</code> , the existing performance models will be overwritten. This can also be specified with the environment variable <code>STARPU_CALIBRATE</code> . (default = 0)
int	single_combined_worker	By default, StarPU executes parallel tasks concurrently. Some parallel libraries (e.g. most OpenMP implementations) however do not support concurrent calls to parallel code. In such case, setting this flag makes StarPU only start one parallel task at a time (but other CPU and GPU tasks are not affected and can be run concurrently). The parallel task scheduler will however still try varying combined worker sizes to look for the most efficient ones. This can also be specified with the environment variable <code>STARPU_SINGLE_COMBINED_WORKER</code> . (default = 0)
char *	mic_sink_program_path	Path to the kernel to execute on the MIC device, compiled for MIC architecture. When set to <code>NULL</code> , StarPU automatically looks next to the host program location. (default = <code>NULL</code>)
int	disable_asynchronous_copy	This flag should be set to 1 to disable asynchronous copies between CPUs and all accelerators. This can also be specified with the environment variable <code>STARPU_DISABLE_ASYNCHRONOUS_COPY</code> . The AMD implementation of OpenCL is known to fail when copying data asynchronously. When using this implementation, it is therefore necessary to disable asynchronous data transfers. This can also be specified at compilation time by giving to the configure script the option <code>--disable-asynchronous-copy</code> . (default = 0)

Data Fields

int	disable_asynchronous_cuda_copy	This flag should be set to 1 to disable asynchronous copies between CPUs and CUDA accelerators. This can also be specified with the environment variable <code>STARPU_DISABLE_ASYNCHRONOUS_CUDA_COPY</code> . This can also be specified at compilation time by giving to the configure script the option <code>--disable-asynchronous-cuda-copy</code> . (default = 0)
int	disable_asynchronous_opengl_copy	This flag should be set to 1 to disable asynchronous copies between CPUs and OpenGL accelerators. This can also be specified with the environment variable <code>STARPU_DISABLE_ASYNCHRONOUS_OPENGL_COPY</code> . The AMD implementation of OpenGL is known to fail when copying data asynchronously. When using this implementation, it is therefore necessary to disable asynchronous data transfers. This can also be specified at compilation time by giving to the configure script the option <code>--disable-asynchronous-opengl-copy</code> . (default = 0)
int	disable_asynchronous_mic_copy	This flag should be set to 1 to disable asynchronous copies between CPUs and MIC accelerators. This can also be specified with the environment variable <code>STARPU_DISABLE_ASYNCHRONOUS_MIC_COPY</code> . This can also be specified at compilation time by giving to the configure script the option <code>--disable-asynchronous-mic-copy</code> . (default = 0).
unsigned *	cuda_opengl_interoperability	Enable CUDA/OpenGL interoperation on these CUDA devices. This can be set to an array of CUDA device identifiers for which <code>cudaGLSetGLDevice()</code> should be called instead of <code>cudaSetDevice()</code> . Its size is specified by the <code>starpu_conf::n_cuda_opengl_interoperability</code> field below (default = NULL)
unsigned	n_cuda_opengl_interoperability	todo
struct <code>starpu_driver</code> *	not_launched_drivers	Array of drivers that should not be launched by StarPU. The application will run in one of its own threads. (default = NULL)

Data Fields

unsigned	n_not_launched_drivers	The number of StarPU drivers that should not be launched by StarPU. (default = 0)
unsigned	trace_buffer_size	Specifies the buffer size used for FxT tracing. Starting from FxT version 0.2.12, the buffer will automatically be flushed when it fills in, but it may still be interesting to specify a bigger value to avoid any flushing (which would disturb the trace).
int	global_sched_ctx_min_priority	
int	global_sched_ctx_max_priority	

28.2.3 Function Documentation

28.2.3.1 starpu_init()

```
int starpu_init (
    struct starpu_conf * conf )
```

This is StarPU initialization method, which must be called prior to any other StarPU call. It is possible to specify StarPU's configuration (e.g. scheduling policy, number of cores, ...) by passing a non-null argument. Default configuration is used if the passed argument is NULL. Upon successful completion, this function returns 0. Otherwise, -ENODEV indicates that no worker was available (so that StarPU was not initialized).

28.2.3.2 starpu_initialize()

```
int starpu_initialize (
    struct starpu_conf * user_conf,
    int * argc,
    char *** argv )
```

This is the same as [starpu_init\(\)](#), but also takes the `argc` and `argv` as defined by the application. This is needed for SCC execution to initialize the communication library. Do not call [starpu_init\(\)](#) and [starpu_initialize\(\)](#) in the same program.

28.2.3.3 starpu_conf_init()

```
int starpu_conf_init (
    struct starpu_conf * conf )
```

This function initializes the `conf` structure passed as argument with the default values. In case some configuration parameters are already specified through environment variables, [starpu_conf_init\(\)](#) initializes the fields of the structure according to the environment variables. For instance if `STARPU_CALIBRATE` is set, its value is put in the field `starpu_conf::calibrate` of the structure passed as argument. Upon successful completion, this function returns 0. Otherwise, -EINVAL indicates that the argument was NULL.

28.2.3.4 `starpu_shutdown()`

```
void starpu_shutdown (
    void )
```

This is StarPU termination method. It must be called at the end of the application: statistics and other post-mortem debugging information are not guaranteed to be available until this method has been called.

28.2.3.5 `starpu_pause()`

```
void starpu_pause (
    void )
```

This call is used to suspend the processing of new tasks by workers. It can be used in a program where StarPU is used during only a part of the execution. Without this call, the workers continue to poll for new tasks in a tight loop, wasting CPU time. The symmetric call to [starpu_resume\(\)](#) should be used to unfreeze the workers.

28.2.3.6 `starpu_resume()`

```
void starpu_resume (
    void )
```

This is the symmetrical call to [starpu_pause\(\)](#), used to resume the workers polling for new tasks.

28.2.3.7 `starpu_asynchronous_copy_disabled()`

```
int starpu_asynchronous_copy_disabled (
    void )
```

Return 1 if asynchronous data transfers between CPU and accelerators are disabled.

28.2.3.8 `starpu_asynchronous_cuda_copy_disabled()`

```
int starpu_asynchronous_cuda_copy_disabled (
    void )
```

Return 1 if asynchronous data transfers between CPU and CUDA accelerators are disabled.

28.2.3.9 `starpu_asynchronous_opengl_copy_disabled()`

```
int starpu_asynchronous_opengl_copy_disabled (
    void )
```

Return 1 if asynchronous data transfers between CPU and OpenCL accelerators are disabled.

28.2.3.10 starpu_asynchronous_mic_copy_disabled()

```
int starpu_asynchronous_mic_copy_disabled (
    void )
```

Return 1 if asynchronous data transfers between CPU and MIC devices are disabled.

28.2.3.11 starpu_topology_print()

```
void starpu_topology_print (
    FILE * f )
```

Prints a description of the topology on f.

28.3 Standard Memory Library**Macros**

- `#define starpu_data_malloc_pinned_if_possible`
- `#define starpu_data_free_pinned_if_possible`
- `#define STARPU_MALLOC_PINNED`
- `#define STARPU_MALLOC_COUNT`
- `#define STARPU_MALLOC_NORECLAIM`
- `#define STARPU_MALLOC_SIMULATION_FOLDED`
- `#define STARPU_MEMORY_WAIT`
- `#define STARPU_MEMORY_OVERFLOW`

Functions

- `int starpu_malloc_flags` (void **A, size_t dim, int flags) STARPU_ATTRIBUTE_ALLOC_SIZE(2)
- `void starpu_malloc_set_align` (size_t align)
- `int starpu_malloc` (void **A, size_t dim) STARPU_ATTRIBUTE_ALLOC_SIZE(2)
- `int starpu_free` (void *A)
- `int starpu_free_flags` (void *A, size_t dim, int flags)
- `int starpu_memory_pin` (void *addr, size_t size)
- `int starpu_memory_unpin` (void *addr, size_t size)
- `starpu_ssize_t starpu_memory_get_total` (unsigned node)
- `starpu_ssize_t starpu_memory_get_available` (unsigned node)
- `int starpu_memory_allocate` (unsigned node, size_t size, int flags)
- `void starpu_memory_deallocate` (unsigned node, size_t size)
- `void starpu_memory_wait_available` (unsigned node, size_t size)

28.3.1 Detailed Description**28.3.2 Macro Definition Documentation**

28.3.2.1 `starpu_data_malloc_pinned_if_possible`

```
#define starpu_data_malloc_pinned_if_possible
```

Deprecated Equivalent to [starpu_malloc\(\)](#). This macro is provided to avoid breaking old codes.

28.3.2.2 `starpu_data_free_pinned_if_possible`

```
#define starpu_data_free_pinned_if_possible
```

Deprecated Equivalent to [starpu_free\(\)](#). This macro is provided to avoid breaking old codes.

28.3.2.3 `STARPU_MALLOC_PINNED`

```
#define STARPU_MALLOC_PINNED
```

Value passed to the function [starpu_malloc_flags\(\)](#) to indicate the memory allocation should be pinned.

28.3.2.4 `STARPU_MALLOC_COUNT`

```
#define STARPU_MALLOC_COUNT
```

Value passed to the function [starpu_malloc_flags\(\)](#) to indicate the memory allocation should be in the limit defined by the environment variables [STARPU_LIMIT_CUDA_devid_MEM](#), [STARPU_LIMIT_CUDA_MEM](#), [STARPU_LIMIT_OPENCL_devid_MEM](#), [STARPU_LIMIT_OPENCL_MEM](#) and [STARPU_LIMIT_CPU_MEM](#) (see Section [How to Limit Memory Used By StarPU And Cache Buffer Allocations](#)). If no memory is available, it tries to reclaim memory from StarPU. Memory allocated this way needs to be freed by calling the function [starpu_free_flags\(\)](#) with the same flag.

28.3.2.5 `STARPU_MALLOC_NORECLAIM`

```
#define STARPU_MALLOC_NORECLAIM
```

Value passed to the function [starpu_malloc_flags\(\)](#) along [STARPU_MALLOC_COUNT](#) to indicate that while the memory allocation should be kept in the limits defined for [STARPU_MALLOC_COUNT](#), no reclaiming should be performed by [starpu_malloc_flags](#) itself, thus potentially overflowing the memory node a bit. StarPU will reclaim memory after next task termination, according to the [STARPU_MINIMUM_AVAILABLE_MEM](#) and [STARPU_TARGET_AVAILABLE_MEM](#) environment variables. If [STARPU_MEMORY_WAIT](#) is set, no overflowing will happen, [starpu_malloc_flags\(\)](#) will wait for other eviction mechanisms to release enough memory.

28.3.2.6 STARPU_MALLOC_SIMULATION_FOLDED

```
#define STARPU_MALLOC_SIMULATION_FOLDED
```

Value passed to the function [starpu_malloc_flags\(\)](#) to indicate that when StarPU is using simgrid, the allocation can be "folded", i.e. a memory area is allocated, but its content is actually a replicate of the same memory area, to avoid having to actually allocate that much memory. This thus allows to have a memory area that does not actually consumes memory, to which one can read from and write to normally, but get bogus values.

28.3.2.7 STARPU_MEMORY_WAIT

```
#define STARPU_MEMORY_WAIT
```

Value passed to [starpu_memory_allocate\(\)](#) to specify that the function should wait for the requested amount of memory to become available, and atomically allocate it.

28.3.2.8 STARPU_MEMORY_OVERFLOW

```
#define STARPU_MEMORY_OVERFLOW
```

Value passed to [starpu_memory_allocate\(\)](#) to specify that the function should allocate the amount of memory, even if that means overflowing the total size of the memory node.

28.3.3 Function Documentation

28.3.3.1 starpu_malloc_flags()

```
int starpu_malloc_flags (
    void ** A,
    size_t dim,
    int flags )
```

Performs a memory allocation based on the constraints defined by the given flag.

28.3.3.2 starpu_malloc_set_align()

```
void starpu_malloc_set_align (
    size_t align )
```

This function sets an alignment constraints for [starpu_malloc\(\)](#) allocations. align must be a power of two. This is for instance called automatically by the OpenCL driver to specify its own alignment constraints.

28.3.3.3 `starpu_malloc()`

```
int starpu_malloc (
    void ** A,
    size_t dim )
```

This function allocates data of the given size `dim` in main memory, and returns the pointer to the allocated data through `A`. It will also try to pin it in CUDA or OpenCL, so that data transfers from this buffer can be asynchronous, and thus permit data transfer and computation overlapping. The allocated buffer must be freed thanks to the [starpu_free\(\)](#) function.

28.3.3.4 `starpu_free()`

```
int starpu_free (
    void * A )
```

This function frees memory which has previously been allocated with [starpu_malloc\(\)](#).

28.3.3.5 `starpu_free_flags()`

```
int starpu_free_flags (
    void * A,
    size_t dim,
    int flags )
```

This function frees memory by specifying its size. The given flags should be consistent with the ones given to [starpu_malloc_flags\(\)](#) when allocating the memory.

28.3.3.6 `starpu_memory_pin()`

```
int starpu_memory_pin (
    void * addr,
    size_t size )
```

This function pins the given memory area, so that CPU-GPU transfers can be done asynchronously with DMAs. The memory must be unpinned with [starpu_memory_unpin\(\)](#) before being freed. Returns 0 on success, -1 on error.

28.3.3.7 `starpu_memory_unpin()`

```
int starpu_memory_unpin (
    void * addr,
    size_t size )
```

This function unpins the given memory area previously pinned with [starpu_memory_pin\(\)](#). Returns 0 on success, -1 on error.

28.3.3.8 starpu_memory_get_total()

```
ssize_t starpu_memory_get_total (
    unsigned node )
```

If a memory limit is defined on the given node (see Section [How to Limit Memory Used By StarPU And Cache Buffer Allocations](#)), return the amount of total memory on the node. Otherwise return -1.

28.3.3.9 starpu_memory_get_available()

```
ssize_t starpu_memory_get_available (
    unsigned node )
```

If a memory limit is defined on the given node (see Section [How to Limit Memory Used By StarPU And Cache Buffer Allocations](#)), return the amount of available memory on the node. Otherwise return -1.

28.3.3.10 starpu_memory_allocate()

```
int starpu_memory_allocate (
    unsigned node,
    size_t size,
    int flags )
```

Try to allocate memory on the given node

Parameters

<i>size</i>	amount of memory to allocate
<i>node</i>	node where the memory is to be allocated

Returns

1 if the given amount of memory was allocated on the given node

If a memory limit is defined on the given node (see Section [How to Limit Memory Used By StarPU And Cache Buffer Allocations](#)), try to allocate some of it. This does not actually allocate memory, but only accounts for it. This can be useful when the application allocates data another way, but want StarPU to be aware of the allocation size e.g. for memory reclaiming. By default, the function returns -ENOMEM if there is not enough room on the given node. *flags* can be either STARPU_MEMORY_WAIT or STARPU_MEMORY_OVERFLOW to change this.

28.3.3.11 starpu_memory_deallocate()

```
void starpu_memory_deallocate (
    unsigned node,
    size_t size )
```

Indicates the given amount of memory is going to be deallocated from the given node

Parameters

<i>size</i>	amount of memory to be deallocated
<i>node</i>	node where the memory is going to be deallocated

If a memory limit is defined on the given node (see Section [How to Limit Memory Used By StarPU And Cache Buffer Allocations](#)), free some of it. This does not actually free memory, but only accounts for it, like `starpu_memory_↵allocate()`. The amount does not have to be exactly the same as what was passed to `starpu_memory_allocate()`, only the eventual amount needs to be the same, i.e. one call to `starpu_memory_allocate()` can be followed by several calls to `starpu_memory_deallocate()` to declare the deallocation piece by piece.

28.3.3.12 `starpu_memory_wait_available()`

```
void starpu_memory_wait_available (
    unsigned node,
    size_t size )
```

If a memory limit is defined on the given node (see Section [How to Limit Memory Used By StarPU And Cache Buffer Allocations](#)), this will wait for `size` bytes to become available on `node`. Of course, since another thread may be allocating memory concurrently, this does not necessarily mean that this amount will be actually available, just that it was reached. To atomically wait for some amount of memory and reserve it, `starpu_memory_allocate()` should be used with the `STARPU_MEMORY_WAIT` flag.

28.4 Toolbox

The following macros allow to make GCC extensions portable, and to have a code which can be compiled with any C compiler.

Macros

- `#define STARPU_GNUC_PREREQ(maj, min)`
- `#define STARPU_UNLIKELY(expr)`
- `#define STARPU_LIKELY(expr)`
- `#define STARPU_ATTRIBUTE_UNUSED`
- `#define STARPU_ATTRIBUTE_INTERNAL`
- `#define STARPU_ATTRIBUTE_MALLOC`
- `#define STARPU_ATTRIBUTE_WARN_UNUSED_RESULT`
- `#define STARPU_ATTRIBUTE_PURE`
- `#define STARPU_ATTRIBUTE_ALIGNED(size)`
- `#define STARPU_WARN_UNUSED_RESULT`
- `#define STARPU_POISON_PTR`
- `#define STARPU_MIN(a, b)`
- `#define STARPU_MAX(a, b)`
- `#define STARPU_ASSERT(x)`
- `#define STARPU_ASSERT_MSG(x, msg, ...)`
- `#define STARPU_ABORT()`
- `#define STARPU_ABORT_MSG(msg, ...)`
- `#define STARPU_CHECK_RETURN_VALUE(err, message, ...)`
- `#define STARPU_CHECK_RETURN_VALUE_IS(err, value, message, ...)`
- `#define STARPU_RMB()`
- `#define STARPU_WMB()`

Functions

- static `__starpu_inline` int [starpu_get_env_number](#) (const char *str)

28.4.1 Detailed Description

The following macros allow to make GCC extensions portable, and to have a code which can be compiled with any C compiler.

28.4.2 Macro Definition Documentation

28.4.2.1 STARPU_GNUC_PREREQ

```
#define STARPU_GNUC_PREREQ(  
    maj,  
    min )
```

Return true (non-zero) if GCC version MAJ.MIN or later is being used (macro taken from glibc.)

28.4.2.2 STARPU_UNLIKELY

```
#define STARPU_UNLIKELY(  
    expr )
```

When building with a GNU C Compiler, this macro allows programmers to mark an expression as unlikely.

28.4.2.3 STARPU_LIKELY

```
#define STARPU_LIKELY(  
    expr )
```

When building with a GNU C Compiler, this macro allows programmers to mark an expression as likely.

28.4.2.4 STARPU_ATTRIBUTE_UNUSED

```
#define STARPU_ATTRIBUTE_UNUSED
```

When building with a GNU C Compiler, this macro is defined to `__attribute__((unused))`

28.4.2.5 STARPU_ATTRIBUTE_INTERNAL

```
#define STARPU_ATTRIBUTE_INTERNAL
```

When building with a GNU C Compiler, this macro is defined to `__attribute__((visibility ("internal")))`

28.4.2.6 STARPU_ATTRIBUTE_MALLOC

```
#define STARPU_ATTRIBUTE_MALLOC
```

When building with a GNU C Compiler, this macro is defined to `__attribute__((malloc))`

28.4.2.7 STARPU_ATTRIBUTE_WARN_UNUSED_RESULT

```
#define STARPU_ATTRIBUTE_WARN_UNUSED_RESULT
```

When building with a GNU C Compiler, this macro is defined to `__attribute__((warn_unused_result))`

28.4.2.8 STARPU_ATTRIBUTE_PURE

```
#define STARPU_ATTRIBUTE_PURE
```

When building with a GNU C Compiler, this macro is defined to `__attribute__((pure))`

28.4.2.9 STARPU_ATTRIBUTE_ALIGNED

```
#define STARPU_ATTRIBUTE_ALIGNED(  
    size )
```

When building with a GNU C Compiler, this macro is defined to `__attribute__((aligned(size)))`

28.4.2.10 STARPU_WARN_UNUSED_RESULT

```
#define STARPU_WARN_UNUSED_RESULT
```

When building with a GNU C Compiler, this macro is defined to `__attribute__((__warn_unused_result__))`

28.4.2.11 STARPU_POISON_PTR

```
#define STARPU_POISON_PTR
```

This macro defines a value which can be used to mark pointers as invalid values.

28.4.2.12 STARPU_MIN

```
#define STARPU_MIN(  
    a,  
    b )
```

This macro returns the min of the two parameters.

28.4.2.13 STARPU_MAX

```
#define STARPU_MAX(  
    a,  
    b )
```

This macro returns the max of the two parameters.

28.4.2.14 STARPU_ASSERT

```
#define STARPU_ASSERT(  
    x )
```

Unless StarPU has been configured with the option `--enable-fast`, this macro will abort if the expression is false.

28.4.2.15 STARPU_ASSERT_MSG

```
#define STARPU_ASSERT_MSG(  
    x,  
    msg,  
    ... )
```

Unless StarPU has been configured with the option `--enable-fast`, this macro will abort if the expression is false. The given message will be displayed.

28.4.2.16 STARPU_ABORT

```
#define STARPU_ABORT( )
```

This macro aborts the program.

28.4.2.17 STARPU_ABORT_MSG

```
#define STARPU_ABORT_MSG(  
    msg,  
    ... )
```

This macro aborts the program, and displays the given message.

28.4.2.18 STARPU_CHECK_RETURN_VALUE

```
#define STARPU_CHECK_RETURN_VALUE(  
    err,  
    message,  
    ... )
```

If `err` has a value which is not 0, the given message is displayed before aborting.

28.4.2.19 STARPU_CHECK_RETURN_VALUE_IS

```
#define STARPU_CHECK_RETURN_VALUE_IS(  
    err,  
    value,  
    message,  
    ... )
```

If `err` has a value which is not `value`, the given message is displayed before aborting.

28.4.2.20 STARPU_RMB

```
#define STARPU_RMB( )
```

This macro can be used to do a synchronization.

28.4.2.21 STARPU_WMB

```
#define STARPU_WMB( )
```

This macro can be used to do a synchronization.

28.4.3 Function Documentation

28.4.3.1 starpu_get_env_number()

```
int starpu_get_env_number (  
    const char * str ) [static]
```

If `str` is the name of a existing environment variable which is defined to an integer, the function returns the value of the integer. It returns 0 otherwise.

28.5 Threads

This section describes the thread facilities provided by StarPU. The thread function are either implemented on top of the pthread library or the Simgrid library when the simulated performance mode is enabled ([SimGrid Support](#)).

Macros

- `#define STARPU_PTHREAD_CREATE_ON(name, thread, attr, routine, arg, where)`
- `#define STARPU_PTHREAD_CREATE(thread, attr, routine, arg)`
- `#define STARPU_PTHREAD_MUTEX_INIT(mutex, attr)`
- `#define STARPU_PTHREAD_MUTEX_DESTROY(mutex)`
- `#define STARPU_PTHREAD_MUTEX_LOCK(mutex)`
- `#define STARPU_PTHREAD_MUTEX_UNLOCK(mutex)`
- `#define STARPU_PTHREAD_KEY_CREATE(key, destr)`
- `#define STARPU_PTHREAD_KEY_DELETE(key)`
- `#define STARPU_PTHREAD_SETSPECIFIC(key, ptr)`
- `#define STARPU_PTHREAD_GETSPECIFIC(key)`
- `#define STARPU_PTHREAD_RWLOCK_INIT(rwlock, attr)`
- `#define STARPU_PTHREAD_RWLOCK_RDLOCK(rwlock)`
- `#define STARPU_PTHREAD_RWLOCK_WRLOCK(rwlock)`
- `#define STARPU_PTHREAD_RWLOCK_UNLOCK(rwlock)`
- `#define STARPU_PTHREAD_RWLOCK_DESTROY(rwlock)`
- `#define STARPU_PTHREAD_COND_INIT(cond, attr)`
- `#define STARPU_PTHREAD_COND_DESTROY(cond)`
- `#define STARPU_PTHREAD_COND_SIGNAL(cond)`
- `#define STARPU_PTHREAD_COND_BROADCAST(cond)`
- `#define STARPU_PTHREAD_COND_WAIT(cond, mutex)`
- `#define STARPU_PTHREAD_BARRIER_INIT(barrier, attr, count)`
- `#define STARPU_PTHREAD_BARRIER_DESTROY(barrier)`
- `#define STARPU_PTHREAD_BARRIER_WAIT(barrier)`
- `#define STARPU_PTHREAD_MUTEX_INITIALIZER`
- `#define STARPU_PTHREAD_COND_INITIALIZER`

Functions

- `int starpu_thread_create (starpu_thread_t *thread, const starpu_thread_attr_t *attr, void *(*start_routine)(void *), void *arg)`
- `int starpu_thread_join (starpu_thread_t thread, void **retval)`
- `int starpu_thread_exit (void *retval) STARPU_ATTRIBUTE_NORETURN`
- `int starpu_thread_attr_init (starpu_thread_attr_t *attr)`
- `int starpu_thread_attr_destroy (starpu_thread_attr_t *attr)`
- `int starpu_thread_attr_setdetachstate (starpu_thread_attr_t *attr, int detachstate)`
- `int starpu_thread_mutex_init (starpu_thread_mutex_t *mutex, const starpu_thread_mutexattr_t *mutexattr)`
- `int starpu_thread_mutex_destroy (starpu_thread_mutex_t *mutex)`
- `int starpu_thread_mutex_lock (starpu_thread_mutex_t *mutex)`
- `int starpu_thread_mutex_unlock (starpu_thread_mutex_t *mutex)`
- `int starpu_thread_mutex_trylock (starpu_thread_mutex_t *mutex)`
- `int starpu_thread_mutexattr_gettype (const starpu_thread_mutexattr_t *attr, int *type)`
- `int starpu_thread_mutexattr_settype (starpu_thread_mutexattr_t *attr, int type)`
- `int starpu_thread_mutexattr_destroy (starpu_thread_mutexattr_t *attr)`
- `int starpu_thread_mutexattr_init (starpu_thread_mutexattr_t *attr)`
- `int starpu_thread_key_create (starpu_thread_key_t *key, void(*destr_function)(void *))`
- `int starpu_thread_key_delete (starpu_thread_key_t key)`
- `int starpu_thread_setspecific (starpu_thread_key_t key, const void *pointer)`
- `void * starpu_thread_getspecific (starpu_thread_key_t key)`
- `int starpu_thread_cond_init (starpu_thread_cond_t *cond, starpu_thread_condattr_t *cond_attr)`
- `int starpu_thread_cond_signal (starpu_thread_cond_t *cond)`
- `int starpu_thread_cond_broadcast (starpu_thread_cond_t *cond)`

- int [starpu_pthread_cond_wait](#) (starpu_pthread_cond_t *cond, starpu_pthread_mutex_t *mutex)
- int [starpu_pthread_cond_timedwait](#) (starpu_pthread_cond_t *cond, starpu_pthread_mutex_t *mutex, const struct timespec *abstime)
- int [starpu_pthread_cond_destroy](#) (starpu_pthread_cond_t *cond)
- int [starpu_pthread_rwlock_init](#) (starpu_pthread_rwlock_t *rwlock, const starpu_pthread_rwlockattr_t *attr)
- int [starpu_pthread_rwlock_destroy](#) (starpu_pthread_rwlock_t *rwlock)
- int [starpu_pthread_rwlock_rdlock](#) (starpu_pthread_rwlock_t *rwlock)
- int [starpu_pthread_rwlock_tryrdlock](#) (starpu_pthread_rwlock_t *rwlock)
- int [starpu_pthread_rwlock_wrlock](#) (starpu_pthread_rwlock_t *rwlock)
- int [starpu_pthread_rwlock_trywrlock](#) (starpu_pthread_rwlock_t *rwlock)
- int [starpu_pthread_rwlock_unlock](#) (starpu_pthread_rwlock_t *rwlock)
- int [starpu_pthread_barrier_init](#) (starpu_pthread_barrier_t *barrier, const starpu_pthread_barrierattr_t *attr, unsigned count)
- int [starpu_pthread_barrier_destroy](#) (starpu_pthread_barrier_t *barrier)
- int [starpu_pthread_barrier_wait](#) (starpu_pthread_barrier_t *barrier)
- int [starpu_pthread_spin_init](#) (starpu_pthread_spinlock_t *lock, int pshared)
- int [starpu_pthread_spin_destroy](#) (starpu_pthread_spinlock_t *lock)
- int [starpu_pthread_spin_lock](#) (starpu_pthread_spinlock_t *lock)
- int [starpu_pthread_spin_trylock](#) (starpu_pthread_spinlock_t *lock)
- int [starpu_pthread_spin_unlock](#) (starpu_pthread_spinlock_t *lock)
- void [starpu_sleep](#) (float nb_sec)

28.5.1 Detailed Description

This section describes the thread facilities provided by StarPU. The thread function are either implemented on top of the pthread library or the Simgrid library when the simulated performance mode is enabled ([SimGrid Support](#)).

28.5.2 Macro Definition Documentation

28.5.2.1 STARPU_PTHREAD_CREATE_ON

```
#define STARPU_PTHREAD_CREATE_ON(
    name,
    thread,
    attr,
    routine,
    arg,
    where )
```

This macro calls the function [starpu_pthread_create_on\(\)](#) and aborts on error.

28.5.2.2 STARPU_PTHREAD_CREATE

```
#define STARPU_PTHREAD_CREATE(
    thread,
    attr,
    routine,
    arg )
```

This macro calls the function [starpu_pthread_create\(\)](#) and aborts on error.

28.5.2.3 STARPU_PTHREAD_MUTEX_INIT

```
#define STARPU_PTHREAD_MUTEX_INIT(  
    mutex,  
    attr )
```

This macro calls the function [starpu_pthread_mutex_init\(\)](#) and aborts on error.

28.5.2.4 STARPU_PTHREAD_MUTEX_DESTROY

```
#define STARPU_PTHREAD_MUTEX_DESTROY(  
    mutex )
```

This macro calls the function [starpu_pthread_mutex_destroy\(\)](#) and aborts on error.

28.5.2.5 STARPU_PTHREAD_MUTEX_LOCK

```
#define STARPU_PTHREAD_MUTEX_LOCK(  
    mutex )
```

This macro calls the function [starpu_pthread_mutex_lock\(\)](#) and aborts on error.

28.5.2.6 STARPU_PTHREAD_MUTEX_UNLOCK

```
#define STARPU_PTHREAD_MUTEX_UNLOCK(  
    mutex )
```

This macro calls the function [starpu_pthread_mutex_unlock\(\)](#) and aborts on error.

28.5.2.7 STARPU_PTHREAD_KEY_CREATE

```
#define STARPU_PTHREAD_KEY_CREATE(  
    key,  
    destr )
```

This macro calls the function [starpu_pthread_key_create\(\)](#) and aborts on error.

28.5.2.8 STARPU_PTHREAD_KEY_DELETE

```
#define STARPU_PTHREAD_KEY_DELETE(  
    key )
```

This macro calls the function [starpu_pthread_key_delete\(\)](#) and aborts on error.

28.5.2.9 STARPU_PTHREAD_SETSPECIFIC

```
#define STARPU_PTHREAD_SETSPECIFIC(  
    key,  
    ptr )
```

This macro calls the function [starpu_pthread_setspecific\(\)](#) and aborts on error.

28.5.2.10 STARPU_PTHREAD_GETSPECIFIC

```
#define STARPU_PTHREAD_GETSPECIFIC(  
    key )
```

This macro calls the function [starpu_pthread_getspecific\(\)](#) and aborts on error.

28.5.2.11 STARPU_PTHREAD_RWLOCK_INIT

```
#define STARPU_PTHREAD_RWLOCK_INIT(  
    rwlock,  
    attr )
```

This macro calls the function [starpu_pthread_rwlock_init\(\)](#) and aborts on error.

28.5.2.12 STARPU_PTHREAD_RWLOCK_RDLOCK

```
#define STARPU_PTHREAD_RWLOCK_RDLOCK(  
    rwlock )
```

This macro calls the function [starpu_pthread_rwlock_rdlock\(\)](#) and aborts on error.

28.5.2.13 STARPU_PTHREAD_RWLOCK_WRLOCK

```
#define STARPU_PTHREAD_RWLOCK_WRLOCK(  
    rwlock )
```

This macro calls the function [starpu_pthread_rwlock_wrlock\(\)](#) and aborts on error.

28.5.2.14 STARPU_PTHREAD_RWLOCK_UNLOCK

```
#define STARPU_PTHREAD_RWLOCK_UNLOCK(  
    rwlock )
```

This macro calls the function [starpu_pthread_rwlock_unlock\(\)](#) and aborts on error.

28.5.2.15 STARPU_PTHREAD_RWLOCK_DESTROY

```
#define STARPU_PTHREAD_RWLOCK_DESTROY(  
    rwlock )
```

This macro calls the function [starpu_pthread_rwlock_destroy\(\)](#) and aborts on error.

28.5.2.16 STARPU_PTHREAD_COND_INIT

```
#define STARPU_PTHREAD_COND_INIT(  
    cond,  
    attr )
```

This macro calls the function [starpu_pthread_cond_init\(\)](#) and aborts on error.

28.5.2.17 STARPU_PTHREAD_COND_DESTROY

```
#define STARPU_PTHREAD_COND_DESTROY(  
    cond )
```

This macro calls the function [starpu_pthread_cond_destroy\(\)](#) and aborts on error.

28.5.2.18 STARPU_PTHREAD_COND_SIGNAL

```
#define STARPU_PTHREAD_COND_SIGNAL(  
    cond )
```

This macro calls the function [starpu_pthread_cond_signal\(\)](#) and aborts on error.

28.5.2.19 STARPU_PTHREAD_COND_BROADCAST

```
#define STARPU_PTHREAD_COND_BROADCAST(  
    cond )
```

This macro calls the function [starpu_pthread_cond_broadcast\(\)](#) and aborts on error.

28.5.2.20 STARPU_PTHREAD_COND_WAIT

```
#define STARPU_PTHREAD_COND_WAIT(  
    cond,  
    mutex )
```

This macro calls the function [starpu_pthread_cond_wait\(\)](#) and aborts on error.

28.5.2.21 STARPU_PTHREAD_BARRIER_INIT

```
#define STARPU_PTHREAD_BARRIER_INIT(  
    barrier,  
    attr,  
    count )
```

This macro calls the function [starpu_pthread_barrier_init\(\)](#) and aborts on error.

28.5.2.22 STARPU_PTHREAD_BARRIER_DESTROY

```
#define STARPU_PTHREAD_BARRIER_DESTROY(  
    barrier )
```

This macro calls the function [starpu_thread_barrier_destroy\(\)](#) and aborts on error.

28.5.2.23 STARPU_PTHREAD_BARRIER_WAIT

```
#define STARPU_PTHREAD_BARRIER_WAIT(  
    barrier )
```

This macro calls the function [starpu_thread_barrier_wait\(\)](#) and aborts on error.

28.5.2.24 STARPU_PTHREAD_MUTEX_INITIALIZER

```
STARPU_PTHREAD_MUTEX_INITIALIZER
```

This macro initializes the mutex given in parameter.

28.5.2.25 STARPU_PTHREAD_COND_INITIALIZER

```
STARPU_PTHREAD_COND_INITIALIZER
```

This macro initializes the condition variable given in parameter.

28.5.3 Function Documentation

28.5.3.1 starpu_thread_create()

```
int starpu_thread_create (  
    starpu_thread_t * thread,  
    const starpu_thread_attr_t * attr,  
    void (*)(void *) start_routine,  
    void * arg )
```

This function starts a new thread in the calling process. The new thread starts execution by invoking `start_routine`; `arg` is passed as the sole argument of `start_routine`.

28.5.3.2 starpu_thread_join()

```
int starpu_thread_join (  
    starpu_thread_t thread,  
    void ** retval )
```

This function waits for the thread specified by `thread` to terminate. If that thread has already terminated, then the function returns immediately. The thread specified by `thread` must be joinable.

28.5.3.3 `starpu_pthread_exit()`

```
int starpu_pthread_exit (
    void * retval )
```

This function terminates the calling thread and returns a value via `retval` that (if the thread is joinable) is available to another thread in the same process that calls `starpu_pthread_join()`.

28.5.3.4 `starpu_pthread_attr_init()`

```
int starpu_pthread_attr_init (
    starpu_pthread_attr_t * attr )
```

This function initializes the thread attributes object pointed to by `attr` with default attribute values.

It does not do anything when the simulated performance mode is enabled ([SimGrid Support](#)).

28.5.3.5 `starpu_pthread_attr_destroy()`

```
int starpu_pthread_attr_destroy (
    starpu_pthread_attr_t * attr )
```

This function destroys a thread attributes object which is no longer required. Destroying a thread attributes object has no effect on threads that were created using that object.

It does not do anything when the simulated performance mode is enabled ([SimGrid Support](#)).

28.5.3.6 `starpu_pthread_attr_setdetachstate()`

```
int starpu_pthread_attr_setdetachstate (
    starpu_pthread_attr_t * attr,
    int detachstate )
```

This function sets the detach state attribute of the thread attributes object referred to by `attr` to the value specified in `detachstate`. The detach state attribute determines whether a thread created using the thread attributes object `attr` will be created in a joinable or a detached state.

It does not do anything when the simulated performance mode is enabled ([SimGrid Support](#)).

28.5.3.7 `starpu_pthread_mutex_init()`

```
int starpu_pthread_mutex_init (
    starpu_pthread_mutex_t * mutex,
    const starpu_pthread_mutexattr_t * mutexattr )
```

This function initializes the mutex object pointed to by `mutex` according to the mutex attributes specified in `mutexattr`. If `mutexattr` is NULL, default attributes are used instead.

28.5.3.8 `starpu_pthread_mutex_destroy()`

```
int starpu_pthread_mutex_destroy (
    starpu_pthread_mutex_t * mutex )
```

This function destroys a mutex object, freeing the resources it might hold. The mutex must be unlocked on entrance.

28.5.3.9 `starpu_pthread_mutex_lock()`

```
int starpu_pthread_mutex_lock (
    starpu_pthread_mutex_t * mutex )
```

This function locks the given mutex. If the mutex is currently unlocked, it becomes locked and owned by the calling thread, and the function returns immediately. If the mutex is already locked by another thread, the function suspends the calling thread until the mutex is unlocked.

This function also produces trace when the configure option `--enable-fxt-lock` is enabled.

28.5.3.10 `starpu_pthread_mutex_unlock()`

```
int starpu_pthread_mutex_unlock (
    starpu_pthread_mutex_t * mutex )
```

This function unlocks the given mutex. The mutex is assumed to be locked and owned by the calling thread on entrance to `starpu_pthread_mutex_unlock()`.

This function also produces trace when the configure option `--enable-fxt-lock` is enabled.

28.5.3.11 `starpu_pthread_mutex_trylock()`

```
int starpu_pthread_mutex_trylock (
    starpu_pthread_mutex_t * mutex )
```

This function behaves identically to `starpu_pthread_mutex_lock()`, except that it does not block the calling thread if the mutex is already locked by another thread (or by the calling thread in the case of a “fast” mutex). Instead, the function returns immediately with the error code EBUSY.

This function also produces trace when the configure option `--enable-fxt-lock` is enabled.

28.5.3.12 `starpu_pthread_mutexattr_gettype()`

```
int starpu_pthread_mutexattr_gettype (
    const starpu_pthread_mutexattr_t * attr,
    int * type )
```

todo

28.5.3.13 starpu_pthread_mutexattr_settype()

```
int starpu_pthread_mutexattr_settype (
    starpu_pthread_mutexattr_t * attr,
    int type )
```

todo

28.5.3.14 starpu_pthread_mutexattr_destroy()

```
int starpu_pthread_mutexattr_destroy (
    starpu_pthread_mutexattr_t * attr )
```

todo

28.5.3.15 starpu_pthread_mutexattr_init()

```
int starpu_pthread_mutexattr_init (
    starpu_pthread_mutexattr_t * attr )
```

todo

28.5.3.16 starpu_pthread_key_create()

```
int starpu_pthread_key_create (
    starpu_pthread_key_t * key,
    void(*) (void *) destr_function )
```

This function allocates a new TSD key. The key is stored in the location pointed to by `key`.

28.5.3.17 starpu_pthread_key_delete()

```
int starpu_pthread_key_delete (
    starpu_pthread_key_t key )
```

This function deallocates a TSD key. It does not check whether non-NULL values are associated with that key in the currently executing threads, nor call the destructor function associated with the key.

28.5.3.18 starpu_pthread_setspecific()

```
int starpu_pthread_setspecific (
    starpu_pthread_key_t key,
    const void * pointer )
```

This function changes the value associated with `key` in the calling thread, storing the given `pointer` instead.

28.5.3.19 `starpu_thread_getspecific()`

```
void * starpu_thread_getspecific (
    starpu_thread_key_t key )
```

This function returns the value associated with `key` on success, and `NULL` on error.

28.5.3.20 `starpu_thread_cond_init()`

```
int starpu_thread_cond_init (
    starpu_thread_cond_t * cond,
    starpu_thread_condattr_t * cond_attr )
```

This function initializes the condition variable `cond`, using the condition attributes specified in `cond_attr`, or default attributes if `cond_attr` is `NULL`.

28.5.3.21 `starpu_thread_cond_signal()`

```
int starpu_thread_cond_signal (
    starpu_thread_cond_t * cond )
```

This function restarts one of the threads that are waiting on the condition variable `cond`. If no threads are waiting on `cond`, nothing happens. If several threads are waiting on `cond`, exactly one is restarted, but it not specified which.

28.5.3.22 `starpu_thread_cond_broadcast()`

```
int starpu_thread_cond_broadcast (
    starpu_thread_cond_t * cond )
```

This function restarts all the threads that are waiting on the condition variable `cond`. Nothing happens if no threads are waiting on `cond`.

28.5.3.23 `starpu_thread_cond_wait()`

```
int starpu_thread_cond_wait (
    starpu_thread_cond_t * cond,
    starpu_thread_mutex_t * mutex )
```

This function atomically unlocks the mutex (as per [starpu_thread_mutex_unlock\(\)](#)) and waits for the condition variable `cond` to be signaled. The thread execution is suspended and does not consume any CPU time until the condition variable is signaled. The mutex must be locked by the calling thread on entrance to [starpu_thread_cond_wait\(\)](#). Before returning to the calling thread, the function re-acquires mutex (as per [starpu_thread_mutex_lock\(\)](#)).

This function also produces trace when the configure option `--enable-fxt-lock` is enabled.

28.5.3.24 `starpu_thread_cond_timedwait()`

```
int starpu_thread_cond_timedwait (
    starpu_thread_cond_t * cond,
    starpu_thread_mutex_t * mutex,
    const struct timespec * abstime )
```

This function atomically unlocks `mutex` and waits on `cond`, as [starpu_thread_cond_wait\(\)](#) does, but it also bounds the duration of the wait.

28.5.3.25 `starpu_thread_cond_destroy()`

```
int starpu_thread_cond_destroy (
    starpu_thread_cond_t * cond )
```

This function destroys a condition variable, freeing the resources it might hold. No threads must be waiting on the condition variable on entrance to the function.

28.5.3.26 `starpu_thread_rwlock_init()`

```
int starpu_thread_rwlock_init (
    starpu_thread_rwlock_t * rwlock,
    const starpu_thread_rwlockattr_t * attr )
```

This function is the same as [starpu_thread_mutex_init\(\)](#).

28.5.3.27 `starpu_thread_rwlock_destroy()`

```
int starpu_thread_rwlock_destroy (
    starpu_thread_rwlock_t * rwlock )
```

This function is the same as [starpu_thread_mutex_destroy\(\)](#).

28.5.3.28 `starpu_thread_rwlock_rdlock()`

```
int starpu_thread_rwlock_rdlock (
    starpu_thread_rwlock_t * rwlock )
```

This function is the same as [starpu_thread_mutex_lock\(\)](#).

28.5.3.29 `starpu_thread_rwlock_tryrdlock()`

```
int starpu_thread_rwlock_tryrdlock (
    starpu_thread_rwlock_t * rwlock )
```

todo

28.5.3.30 starpu_thread_rwlock_wrlock()

```
int starpu_thread_rwlock_wrlock (
    starpu_thread_rwlock_t * rwlock )
```

This function is the same as [starpu_thread_mutex_lock\(\)](#).

28.5.3.31 starpu_thread_rwlock_trywrlock()

```
int starpu_thread_rwlock_trywrlock (
    starpu_thread_rwlock_t * rwlock )
```

todo

28.5.3.32 starpu_thread_rwlock_unlock()

```
int starpu_thread_rwlock_unlock (
    starpu_thread_rwlock_t * rwlock )
```

This function is the same as [starpu_thread_mutex_unlock\(\)](#).

28.5.3.33 starpu_thread_barrier_init()

```
int starpu_thread_barrier_init (
    starpu_thread_barrier_t * barrier,
    const starpu_thread_barrierattr_t * attr,
    unsigned count )
```

todo

28.5.3.34 starpu_thread_barrier_destroy()

```
int starpu_thread_barrier_destroy (
    starpu_thread_barrier_t * barrier )
```

todo

28.5.3.35 starpu_thread_barrier_wait()

```
int starpu_thread_barrier_wait (
    starpu_thread_barrier_t * barrier )
```

todo

28.5.3.36 `starpu_thread_spin_init()`

```
int starpu_thread_spin_init (
    starpu_thread_spinlock_t * lock,
    int pshared )
```

todo

28.5.3.37 `starpu_thread_spin_destroy()`

```
int starpu_thread_spin_destroy (
    starpu_thread_spinlock_t * lock )
```

todo

28.5.3.38 `starpu_thread_spin_lock()`

```
int starpu_thread_spin_lock (
    starpu_thread_spinlock_t * lock )
```

todo

28.5.3.39 `starpu_thread_spin_trylock()`

```
int starpu_thread_spin_trylock (
    starpu_thread_spinlock_t * lock )
```

todo

28.5.3.40 `starpu_thread_spin_unlock()`

```
int starpu_thread_spin_unlock (
    starpu_thread_spinlock_t * lock )
```

todo

28.5.3.41 `starpu_sleep()`

```
void starpu_sleep (
    float nb_sec )
```

This is the same as calling Unix' sleep function, except that it takes a float to allow sub-second sleeping, and when StarPU is compiled in simgrid mode it does not really sleep but just makes simgrid record that the thread has taken some time to sleep.

28.6 Bitmap

This section describes the bitmap facilities provided by StarPU.

Functions

- `struct starpu_bitmap * starpu_bitmap_create` (void) [STARPU_ATTRIBUTE_MALLOC](#)
- void `starpu_bitmap_destroy` (struct starpu_bitmap *b)
- void `starpu_bitmap_set` (struct starpu_bitmap *b, int e)
- void `starpu_bitmap_unset` (struct starpu_bitmap *b, int e)
- void `starpu_bitmap_unset_all` (struct starpu_bitmap *b)
- int `starpu_bitmap_get` (struct starpu_bitmap *b, int e)
- void `starpu_bitmap_unset_and` (struct starpu_bitmap *a, struct starpu_bitmap *b, struct starpu_bitmap *c)
- void `starpu_bitmap_or` (struct starpu_bitmap *a, struct starpu_bitmap *b)
- int `starpu_bitmap_and_get` (struct starpu_bitmap *b1, struct starpu_bitmap *b2, int e)
- int `starpu_bitmap_cardinal` (struct starpu_bitmap *b)
- int `starpu_bitmap_first` (struct starpu_bitmap *b)
- int `starpu_bitmap_last` (struct starpu_bitmap *b)
- int `starpu_bitmap_next` (struct starpu_bitmap *b, int e)
- int `starpu_bitmap_has_next` (struct starpu_bitmap *b, int e)

28.6.1 Detailed Description

This section describes the bitmap facilities provided by StarPU.

28.6.2 Function Documentation

28.6.2.1 `starpu_bitmap_create()`

```
struct starpu_bitmap * starpu_bitmap_create (
    void )
```

create a empty `starpu_bitmap`

28.6.2.2 `starpu_bitmap_destroy()`

```
void starpu_bitmap_destroy (
    struct starpu_bitmap * b )
```

free a `starpu_bitmap`

28.6.2.3 `starpu_bitmap_set()`

```
void starpu_bitmap_set (
    struct starpu_bitmap * b,
    int e )
```

set bit `e` in `b`

28.6.2.4 starpu_bitmap_unset()

```
void starpu_bitmap_unset (
    struct starpu_bitmap * b,
    int e )
```

unset bit *e* in *b*

28.6.2.5 starpu_bitmap_unset_all()

```
void starpu_bitmap_unset_all (
    struct starpu_bitmap * b )
```

unset all bits in *b*

28.6.2.6 starpu_bitmap_get()

```
int starpu_bitmap_get (
    struct starpu_bitmap * b,
    int e )
```

return true iff bit *e* is set in *b*

28.6.2.7 starpu_bitmap_unset_and()

```
void starpu_bitmap_unset_and (
    struct starpu_bitmap * a,
    struct starpu_bitmap * b,
    struct starpu_bitmap * c )
```

Basically compute `starpu_bitmap_unset_all(a) ; a = b & c;`

28.6.2.8 starpu_bitmap_or()

```
void starpu_bitmap_or (
    struct starpu_bitmap * a,
    struct starpu_bitmap * b )
```

Basically compute `a |= b`

28.6.2.9 starpu_bitmap_and_get()

```
int starpu_bitmap_and_get (
    struct starpu_bitmap * b1,
    struct starpu_bitmap * b2,
    int e )
```

return 1 iff *e* set in *b1* AND *e* set in *b2*

28.6.2.10 starpu_bitmap_cardinal()

```
int starpu_bitmap_cardinal (
    struct starpu_bitmap * b )
```

return the number of set bits in b

28.6.2.11 starpu_bitmap_first()

```
int starpu_bitmap_first (
    struct starpu_bitmap * b )
```

return the index of first set bit of b, -1 if none

28.6.2.12 starpu_bitmap_last()

```
int starpu_bitmap_last (
    struct starpu_bitmap * b )
```

return the position of the last set bit of b, -1 if none

28.6.2.13 starpu_bitmap_next()

```
int starpu_bitmap_next (
    struct starpu_bitmap * b,
    int e )
```

return the position of set bit right after e in b, -1 if none

28.6.2.14 starpu_bitmap_has_next()

```
int starpu_bitmap_has_next (
    struct starpu_bitmap * b,
    int e )
```

todo

28.7 Workers' Properties

Data Structures

- struct [starpu_worker_collection](#)
- struct [starpu_sched_ctx_iterator](#)

Macros

- `#define STARPU_NMAXWORKERS`
- `#define STARPU_MAXCPUS`
- `#define STARPU_MAXNODES`
- `#define starpu_worker_get_id_check()`

Enumerations

- enum `starpu_node_kind` {
`STARPU_UNUSED`, `STARPU_CPU_RAM`, `STARPU_CUDA_RAM`, `STARPU_OPENCL_RAM`,
`STARPU_DISK_RAM`, `STARPU_MIC_RAM`, `STARPU_SCC_RAM`, `STARPU_SCC_SHM` }
- enum `starpu_worker_archtype` {
`STARPU_CPU_WORKER`, `STARPU_CUDA_WORKER`, `STARPU_OPENCL_WORKER`, `STARPU_MIC_`
`WORKER`,
`STARPU_SCC_WORKER`, `STARPU_ANY_WORKER` }
- enum `starpu_worker_collection_type` { `STARPU_WORKER_TREE`, `STARPU_WORKER_LIST` }

Functions

- unsigned `starpu_worker_get_count` (void)
- int `starpu_worker_get_count_by_type` (enum `starpu_worker_archtype` type)
- unsigned `starpu_cpu_worker_get_count` (void)
- unsigned `starpu_cuda_worker_get_count` (void)
- unsigned `starpu_mic_worker_get_count` (void)
- unsigned `starpu_mic_device_get_count` (void)
- unsigned `starpu_scc_worker_get_count` (void)
- unsigned `starpu_opencl_worker_get_count` (void)
- int `starpu_worker_get_id` (void)
- int `starpu_worker_get_ids_by_type` (enum `starpu_worker_archtype` type, int *workerids, int maxsize)
- int `starpu_worker_get_by_type` (enum `starpu_worker_archtype` type, int num)
- int `starpu_worker_get_by_devid` (enum `starpu_worker_archtype` type, int devid)
- int `starpu_worker_get_devid` (int id)
- enum `starpu_worker_archtype` `starpu_worker_get_type` (int id)
- void `starpu_worker_get_name` (int id, char *dst, size_t maxlen)
- unsigned `starpu_worker_get_memory_node` (unsigned workerid)
- enum `starpu_node_kind` `starpu_node_get_kind` (unsigned node)
- char * `starpu_worker_get_type_as_string` (enum `starpu_worker_archtype` type)

28.7.1 Detailed Description

28.7.2 Data Structure Documentation

28.7.2.1 struct `starpu_worker_collection`

A scheduling context manages a collection of workers that can be memorized using different data structures. Thus, a generic structure is available in order to simplify the choice of its type. Only the list data structure is available but further data structures (like tree) implementations are foreseen.

Data Fields

- int * [workerids](#)
- void * [collection_private](#)
- unsigned [nworkers](#)
- void * [masters](#)
- unsigned [nmasters](#)
- char [present](#) [[STARPU_NMAXWORKERS](#)]
- char [is_master](#) [[STARPU_NMAXWORKERS](#)]
- enum [starpu_worker_collection_type](#) type
- unsigned(* [has_next](#))(struct [starpu_worker_collection](#) *workers, struct [starpu_sched_ctx_iterator](#) *it)
- int(* [get_next](#))(struct [starpu_worker_collection](#) *workers, struct [starpu_sched_ctx_iterator](#) *it)
- unsigned(* [has_next_master](#))(struct [starpu_worker_collection](#) *workers, struct [starpu_sched_ctx_iterator](#) *it)
- int(* [get_next_master](#))(struct [starpu_worker_collection](#) *workers, struct [starpu_sched_ctx_iterator](#) *it)
- int(* [add](#))(struct [starpu_worker_collection](#) *workers, int worker)
- int(* [remove](#))(struct [starpu_worker_collection](#) *workers, int worker)
- void(* [init](#))(struct [starpu_worker_collection](#) *workers)
- void(* [deinit](#))(struct [starpu_worker_collection](#) *workers)
- void(* [init_iterator](#))(struct [starpu_worker_collection](#) *workers, struct [starpu_sched_ctx_iterator](#) *it)

28.7.2.1.1 Field Documentation

28.7.2.1.1.1 [workerids](#)

```
void * starpu_worker_collection::workerids
```

The workerids managed by the collection

28.7.2.1.1.2 [nworkers](#)

```
unsigned starpu_worker_collection::nworkers
```

The number of workers in the collection

28.7.2.1.1.3 [type](#)

```
enum starpu\_worker\_collection\_type starpu_worker_collection::type
```

The type of structure (currently [STARPU_WORKER_LIST](#) is the only one available)

28.7.2.1.1.4 [has_next](#)

```
unsigned(* starpu_worker_collection::has_next)(struct starpu\_worker\_collection *workers, struct starpu\_sched\_ctx\_iterator *it)
```

Checks if there is another element in collection

28.7.2.1.1.5 get_next

```
int(* starpu_worker_collection::get_next)(struct starpu_worker_collection *workers, struct
starpu_sched_ctx_iterator *it)
```

return the next element in the collection

28.7.2.1.1.6 add

```
int(* starpu_worker_collection::add)(struct starpu_worker_collection *workers, int worker)
```

add a new element in the collection

28.7.2.1.1.7 remove

```
int(* starpu_worker_collection::remove)(struct starpu_worker_collection *workers, int worker)
```

remove an element from the collection

28.7.2.1.1.8 init

```
void(* starpu_worker_collection::init)(struct starpu_worker_collection *workers)
```

Initialize the collection

28.7.2.1.1.9 deinit

```
void(* starpu_worker_collection::deinit)(struct starpu_worker_collection *workers)
```

Deinitialize the collection

28.7.2.1.1.10 init_iterator

```
void(* starpu_worker_collection::init_iterator)(struct starpu_worker_collection *workers,
struct starpu_sched_ctx_iterator *it)
```

Initialize the cursor if there is one

28.7.2.2 struct starpu_sched_ctx_iterator

Structure needed to iterate on the collection

Data Fields

int	cursor	The index of the current worker in the collection, needed when iterating on the collection.
void *	value	
void *	possible_value	
char	visited[STARPU_NMAXWORKERS]	

28.7.3 Macro Definition Documentation

28.7.3.1 STARPU_NMAXWORKERS

```
#define STARPU_NMAXWORKERS
```

Define the maximum number of workers managed by StarPU.

28.7.3.2 STARPU_MAXCPUS

```
#define STARPU_MAXCPUS
```

Define the maximum number of CPU workers managed by StarPU. The default value can be modified at configure by using the option `--enable-maxcpus`.

28.7.3.3 STARPU_MAXNODES

```
#define STARPU_MAXNODES
```

Define the maximum number of memory nodes managed by StarPU. The default value can be modified at configure by using the option `--enable-maxnodes`. Reducing it allows to considerably reduce memory used by StarPU data structures.

28.7.3.4 starpu_worker_get_id_check

```
unsigned starpu_worker_get_id_check( )
```

This is the same as `starpu_worker_get_id`, but aborts when called from outside a worker (i.e. when `starpu_worker_get_id()` would return -1).

28.7.4 Enumeration Type Documentation

28.7.4.1 starpu_node_kind

```
enum starpu_node_kind
```

TODO

Enumerator

STARPU_UNUSED	TODO
STARPU_CPU_RAM	TODO
STARPU_CUDA_RAM	TODO
STARPU_OPENCL_RAM	TODO
STARPU_MIC_RAM	TODO
STARPU_SCC_RAM	This node kind is not used anymore, but implementations in interfaces will be useful for MPI.

28.7.4.2 starpu_worker_archtype

enum [starpu_worker_archtype](#)

Worker Architecture Type

Enumerator

STARPU_CPU_WORKER	CPU core
STARPU_CUDA_WORKER	NVIDIA CUDA device
STARPU_OPENCL_WORKER	OpenCL device
STARPU_MIC_WORKER	Intel MIC device
STARPU_SCC_WORKER	Intel SCC device
STARPU_ANY_WORKER	any worker, used in the hypervisor

28.7.4.3 starpu_worker_collection_type

enum [starpu_worker_collection_type](#)

Types of structures the worker collection can implement

Enumerator

STARPU_WORKER_LIST	The collection is an array
--------------------	----------------------------

28.7.5 Function Documentation

28.7.5.1 starpu_worker_get_count()

```
unsigned starpu_worker_get_count (
    void )
```

This function returns the number of workers (i.e. processing units executing StarPU tasks). The returned value should be at most [STARPU_NMAXWORKERS](#).

28.7.5.2 starpu_worker_get_count_by_type()

```
int starpu_worker_get_count_by_type (
    enum starpu\_worker\_archtype type )
```

Returns the number of workers of the given type. A positive (or NULL) value is returned in case of success, -EINVAL indicates that the type is not valid otherwise.

28.7.5.3 `starpu_cpu_worker_get_count()`

```
unsigned starpu_cpu_worker_get_count (  
    void )
```

This function returns the number of CPUs controlled by StarPU. The returned value should be at most [STARPU_MAXCPUS](#).

28.7.5.4 `starpu_cuda_worker_get_count()`

```
unsigned starpu_cuda_worker_get_count (  
    void )
```

This function returns the number of CUDA devices controlled by StarPU. The returned value should be at most [STARPU_MAXCUDADEVES](#).

28.7.5.5 `starpu_mic_worker_get_count()`

```
unsigned starpu_mic_worker_get_count (  
    void )
```

This function returns the number of MIC workers controlled by StarPU.

28.7.5.6 `starpu_mic_device_get_count()`

```
unsigned starpu_mic_device_get_count (  
    void )
```

This function returns the number of MIC devices controlled by StarPU. The returned value should be at most [STARPU_MAXMICDEVES](#).

28.7.5.7 `starpu_scc_worker_get_count()`

```
unsigned starpu_scc_worker_get_count (  
    void )
```

This function returns the number of SCC devices controlled by StarPU. The returned value should be at most [STARPU_MAXSCCDEVES](#).

28.7.5.8 `starpu_opengl_worker_get_count()`

```
unsigned starpu_opengl_worker_get_count (  
    void )
```

This function returns the number of OpenGL devices controlled by StarPU. The returned value should be at most [STARPU_MAXOPENCLDEVES](#).

28.7.5.9 `starpu_worker_get_id()`

```
int starpu_worker_get_id (
    void )
```

This function returns the identifier of the current worker, i.e the one associated to the calling thread. The returned value is either -1 if the current context is not a StarPU worker (i.e. when called from the application outside a task or a callback), or an integer between 0 and `starpu_worker_get_count()` - 1.

28.7.5.10 `starpu_worker_get_ids_by_type()`

```
int starpu_worker_get_ids_by_type (
    enum starpu_worker_archtype type,
    int * workerids,
    int maxsize )
```

This function gets the list of identifiers of workers with the given type. It fills the array `workerids` with the identifiers of the workers that have the type indicated in the first argument. The argument `maxsize` indicates the size of the array `workerids`. The returned value gives the number of identifiers that were put in the array. -ERANGE is returned if `maxsize` is lower than the number of workers with the appropriate type: in that case, the array is filled with the `maxsize` first elements. To avoid such overflows, the value of `maxsize` can be chosen by the means of the function `starpu_worker_get_count_by_type()`, or by passing a value greater or equal to `STARPU_NMAXWORKERS`.

28.7.5.11 `starpu_worker_get_by_type()`

```
int starpu_worker_get_by_type (
    enum starpu_worker_archtype type,
    int num )
```

This returns the identifier of the `num`-th worker that has the specified type `type`. If there are no such worker, -1 is returned.

28.7.5.12 `starpu_worker_get_by_devid()`

```
int starpu_worker_get_by_devid (
    enum starpu_worker_archtype type,
    int devid )
```

This returns the identifier of the worker that has the specified type `type` and device id `devid` (which may not be the `n`-th, if some devices are skipped for instance). If there are no such worker, -1 is returned.

28.7.5.13 `starpu_worker_get_devid()`

```
int starpu_worker_get_devid (
    int id )
```

This function returns the device id of the given worker. The worker should be identified with the value returned by the `starpu_worker_get_id()` function. In the case of a CUDA worker, this device identifier is the logical device identifier exposed by CUDA (used by the function `cudaGetDevice()` for instance). The device identifier of a CPU worker is the logical identifier of the core on which the worker was bound; this identifier is either provided by the OS or by the library `hwloc` in case it is available.

28.7.5.14 `starpu_worker_get_type()`

```
enum starpu\_worker\_archtype starpu_worker_get_type (
    int id )
```

This function returns the type of processing unit associated to a worker. The worker identifier is a value returned by the function [starpu_worker_get_id\(\)](#). The returned value indicates the architecture of the worker: [STARPU_CPU_WORKER](#) for a CPU core, [STARPU_CUDA_WORKER](#) for a CUDA device, and [STARPU_OPENCL_WORKER](#) for a OpenCL device. The value returned for an invalid identifier is unspecified.

28.7.5.15 `starpu_worker_get_name()`

```
void starpu_worker_get_name (
    int id,
    char * dst,
    size_t maxlen )
```

This function allows to get the name of a given worker. StarPU associates a unique human readable string to each processing unit. This function copies at most the `maxlen` first bytes of the unique string associated to a worker identified by its identifier `id` into the `dst` buffer. The caller is responsible for ensuring that `dst` is a valid pointer to a buffer of `maxlen` bytes at least. Calling this function on an invalid identifier results in an unspecified behaviour.

28.7.5.16 `starpu_worker_get_memory_node()`

```
unsigned starpu_worker_get_memory_node (
    unsigned workerid )
```

This function returns the identifier of the memory node associated to the worker identified by `workerid`.

28.7.5.17 `starpu_node_get_kind()`

```
enum starpu\_node\_kind starpu_node_get_kind (
    unsigned node )
```

Returns the type of the given node as defined by [starpu_node_kind](#). For example, when defining a new data interface, this function should be used in the allocation function to determine on which device the memory needs to be allocated.

28.7.5.18 `starpu_worker_get_type_as_string()`

```
char * starpu_worker_get_type_as_string (
    enum starpu\_worker\_archtype type )
```

Returns the given worker type as a string.

28.8 Data Management

This section describes the data management facilities provided by StarPU. We show how to use existing data interfaces in [Data Interfaces](#), but developers can design their own data interfaces if required.

Typedefs

- typedef struct _starpu_data_state * [starpu_data_handle_t](#)
- typedef struct starpu_arbiter * [starpu_arbiter_t](#)

Enumerations

- enum [starpu_data_access_mode](#) {
[STARPU_NONE](#), [STARPU_R](#), [STARPU_W](#), [STARPU_RW](#),
[STARPU_SCRATCH](#), [STARPU_REDUX](#), [STARPU_COMMUTE](#), [STARPU_SSEND](#),
[STARPU_LOCALITY](#), [STARPU_ACCESS_MODE_MAX](#) }

Basic Data Management API

Data management is done at a high-level in StarPU: rather than accessing a mere list of contiguous buffers, the tasks may manipulate data that are described by a high-level construct which we call data interface.

An example of data interface is the "vector" interface which describes a contiguous data array on a specific memory node. This interface is a simple structure containing the number of elements in the array, the size of the elements, and the address of the array in the appropriate address space (this address may be invalid if there is no valid copy of the array in the memory node). More informations on the data interfaces provided by StarPU are given in [Data Interfaces](#).

When a piece of data managed by StarPU is used by a task, the task implementation is given a pointer to an interface describing a valid copy of the data that is accessible from the current processing unit.

Every worker is associated to a memory node which is a logical abstraction of the address space from which the processing unit gets its data. For instance, the memory node associated to the different CPU workers represents main memory (RAM), the memory node associated to a GPU is DRAM embedded on the device. Every memory node is identified by a logical index which is accessible from the function [starpu_worker_get_memory_node\(\)](#). When registering a piece of data to StarPU, the specified memory node indicates where the piece of data initially resides (we also call this memory node the home node of a piece of data).

- void [starpu_data_register](#) ([starpu_data_handle_t](#) *handleptr, int home_node, void *data_interface, struct [starpu_data_interface_ops](#) *ops)
- void [starpu_data_ptr_register](#) ([starpu_data_handle_t](#) handle, unsigned node)
- void [starpu_data_register_same](#) ([starpu_data_handle_t](#) *handledst, [starpu_data_handle_t](#) handlesrc)
- void [starpu_data_unregister](#) ([starpu_data_handle_t](#) handle)
- void [starpu_data_unregister_no_coherency](#) ([starpu_data_handle_t](#) handle)
- void [starpu_data_unregister_submit](#) ([starpu_data_handle_t](#) handle)
- void [starpu_data_invalidate](#) ([starpu_data_handle_t](#) handle)
- void [starpu_data_invalidate_submit](#) ([starpu_data_handle_t](#) handle)
- void [starpu_data_set_wt_mask](#) ([starpu_data_handle_t](#) handle, uint32_t wt_mask)
- void [starpu_data_set_name](#) ([starpu_data_handle_t](#) handle, const char *name)
- void [starpu_data_set_coordinates_array](#) ([starpu_data_handle_t](#) handle, int dimensions, int dims[])
- void [starpu_data_set_coordinates](#) ([starpu_data_handle_t](#) handle, unsigned dimensions,...)
- int [starpu_data_fetch_on_node](#) ([starpu_data_handle_t](#) handle, unsigned node, unsigned async)
- int [starpu_data_prefetch_on_node](#) ([starpu_data_handle_t](#) handle, unsigned node, unsigned async)
- int [starpu_data_idle_prefetch_on_node](#) ([starpu_data_handle_t](#) handle, unsigned node, unsigned async)
- void [starpu_data_wont_use](#) ([starpu_data_handle_t](#) handle)
- [starpu_data_handle_t](#) [starpu_data_lookup](#) (const void *ptr)
- int [starpu_data_request_allocation](#) ([starpu_data_handle_t](#) handle, unsigned node)
- void [starpu_data_query_status](#) ([starpu_data_handle_t](#) handle, int memory_node, int *is_allocated, int *is←_valid, int *is_requested)
- void [starpu_data_advise_as_important](#) ([starpu_data_handle_t](#) handle, unsigned is_important)
- void [starpu_data_set_reduction_methods](#) ([starpu_data_handle_t](#) handle, struct [starpu_codelet](#) *redux_cl, struct [starpu_codelet](#) *init_cl)
- struct [starpu_data_interface_ops](#) * [starpu_data_get_interface_ops](#) ([starpu_data_handle_t](#) handle)
- void [starpu_data_set_user_data](#) ([starpu_data_handle_t](#) handle, void *user_data)
- void * [starpu_data_get_user_data](#) ([starpu_data_handle_t](#) handle)

Access registered data from the application

- `#define STARPU_ACQUIRE_NO_NODE`
- `#define STARPU_ACQUIRE_ALL_NODES`
- `#define STARPU_DATA_ACQUIRE_CB(handle, mode, code)`
- `int starpu_data_acquire (starpu_data_handle_t handle, enum starpu_data_access_mode mode)`
- `int starpu_data_acquire_cb (starpu_data_handle_t handle, enum starpu_data_access_mode mode, void(*callback)(void *), void *arg)`
- `int starpu_data_acquire_cb_sequential_consistency (starpu_data_handle_t handle, enum starpu_data_access_mode mode, void(*callback)(void *), void *arg, int sequential_consistency)`
- `int starpu_data_acquire_try (starpu_data_handle_t handle, enum starpu_data_access_mode mode)`
- `int starpu_data_acquire_on_node (starpu_data_handle_t handle, int node, enum starpu_data_access_mode mode)`
- `int starpu_data_acquire_on_node_cb (starpu_data_handle_t handle, int node, enum starpu_data_access_mode mode, void(*callback)(void *), void *arg)`
- `int starpu_data_acquire_on_node_cb_sequential_consistency (starpu_data_handle_t handle, int node, enum starpu_data_access_mode mode, void(*callback)(void *), void *arg, int sequential_consistency)`
- `int starpu_data_acquire_on_node_cb_sequential_consistency_sync_jobids (starpu_data_handle_t handle, int node, enum starpu_data_access_mode mode, void(*callback)(void *), void *arg, int sequential_consistency, long *pre_sync_jobid, long *post_sync_jobid)`
- `int starpu_data_acquire_on_node_try (starpu_data_handle_t handle, int node, enum starpu_data_access_mode mode)`
- `void starpu_data_release (starpu_data_handle_t handle)`
- `void starpu_data_release_on_node (starpu_data_handle_t handle, int node)`
- `starpu_arbiter_t starpu_arbiter_create (void) STARPU_ATTRIBUTE_MALLOC`
- `void starpu_data_assign_arbiter (starpu_data_handle_t handle, starpu_arbiter_t arbiter)`
- `void starpu_arbiter_destroy (starpu_arbiter_t arbiter)`

28.8.1 Detailed Description

This section describes the data management facilities provided by StarPU. We show how to use existing data interfaces in [Data Interfaces](#), but developers can design their own data interfaces if required.

28.8.2 Macro Definition Documentation

28.8.2.1 STARPU_ACQUIRE_NO_NODE

```
#define STARPU_ACQUIRE_NO_NODE
```

This macro can be used to acquire data, but not require it to be available on a given node, only enforce R/W dependencies. This can for instance be used to wait for tasks which produce the data, but without requesting a fetch to the main memory.

28.8.2.2 STARPU_ACQUIRE_ALL_NODES

```
#define STARPU_ACQUIRE_ALL_NODES
```

This is the same as `STARPU_ACQUIRE_NO_NODE`, but will lock the data on all nodes, preventing them from being evicted for instance. This is mostly useful inside starpu only.

28.8.2.3 STARPU_DATA_ACQUIRE_CB

```
#define STARPU_DATA_ACQUIRE_CB(  
    handle,  
    mode,  
    code )
```

[STARPU_DATA_ACQUIRE_CB\(\)](#) is the same as [starpu_data_acquire_cb\(\)](#), except that the code to be executed in a callback is directly provided as a macro parameter, and the data `handle` is automatically released after it. This permits to easily execute code which depends on the value of some registered data. This is non-blocking too and may be called from task callbacks.

28.8.3 Typedef Documentation

28.8.3.1 starpu_data_handle_t

[starpu_data_handle_t](#)

StarPU uses [starpu_data_handle_t](#) as an opaque handle to manage a piece of data. Once a piece of data has been registered to StarPU, it is associated to a [starpu_data_handle_t](#) which keeps track of the state of the piece of data over the entire machine, so that we can maintain data consistency and locate data replicates for instance.

28.8.3.2 starpu_arbiter_t

[starpu_arbiter_t](#)

This is an arbiter, which implements an advanced but centralized management of concurrent data accesses, see [Concurrent Data Accesses](#) for the details.

28.8.4 Enumeration Type Documentation

28.8.4.1 starpu_data_access_mode

enum [starpu_data_access_mode](#)

This datatype describes a data access mode.

Enumerator

STARPU_NONE	TODO
STARPU_R	read-only mode.
STARPU_W	write-only mode.
STARPU_RW	read-write mode. This is equivalent to STARPU_R STARPU_W

Enumerator

STARPU_SCRATCH	A temporary buffer is allocated for the task, but StarPU does not enforce data consistency—i.e. each device has its own buffer, independently from each other (even for CPUs), and no data transfer is ever performed. This is useful for temporary variables to avoid allocating/freeing buffers inside each task. Currently, no behavior is defined concerning the relation with the STARPU_R and STARPU_W modes and the value provided at registration — i.e., the value of the scratch buffer is undefined at entry of the codelet function. It is being considered for future extensions at least to define the initial value. For now, data to be used in STARPU_SCRATCH mode should be registered with node <code>-1</code> and a <code>NULL</code> pointer, since the value of the provided buffer is simply ignored for now.
STARPU_REDUX	todo
STARPU_COMMUTE	In addition to that, STARPU_COMMUTE can be passed along STARPU_W or STARPU_RW to express that StarPU can let tasks commute, which is useful e.g. when bringing a contribution into some data, which can be done in any order (but still require sequential consistency against reads or non-commutative writes).
STARPU_SSEND	used in starpu_mpi_insert_task() to specify the data has to be sent using a synchronous and non-blocking mode (see starpu_mpi_issend())
STARPU_LOCALITY	used to tell the scheduler which data is the most important for the task, and should thus be used to try to group tasks on the same core or cache, etc. For now only the <code>ws</code> and <code>lws</code> schedulers take this flag into account, and only when rebuild with <code>USE_LOCALITY</code> flag defined in the <code>src/sched_policies/work_stealing_policy.c</code> source code.

28.8.5 Function Documentation

28.8.5.1 `starpu_data_register()`

```
void starpu_data_register (
    starpu_data_handle_t * handleptr,
    int home_node,
    void * data_interface,
    struct starpu_data_interface_ops * ops )
```

Register a piece of data into the handle located at the `handleptr` address. The `data_interface` buffer contains the initial description of the data in the `home_node`. The `ops` argument is a pointer to a structure describing the different methods used to manipulate this type of interface. See [starpu_data_interface_ops](#) for more details on this structure. If `home_node` is `-1`, StarPU will automatically allocate the memory when it is used for the first time in write-only mode. Once such data handle has been automatically allocated, it is possible to access it using any access mode. Note that StarPU supplies a set of predefined types of interface (e.g. vector or matrix) which can be registered by the means of helper functions (e.g. [starpu_vector_data_register\(\)](#) or [starpu_matrix_data_register\(\)](#)).

28.8.5.2 `starpu_data_ptr_register()`

```
void starpu_data_ptr_register (
    starpu_data_handle_t handle,
    unsigned node )
```

Register that a buffer for `handle` on `node` will be set. This is typically used by `starpu_*_ptr_register` helpers before setting the interface pointers for this node, to tell the core that that is now allocated.

28.8.5.3 `starpu_data_register_same()`

```
void starpu_data_register_same (
    starpu_data_handle_t * handledst,
    starpu_data_handle_t handlesrc )
```

Register a new piece of data into the handle `handledst` with the same interface as the handle `handlesrc`.

28.8.5.4 `starpu_data_unregister()`

```
void starpu_data_unregister (
    starpu_data_handle_t handle )
```

This function unregisters a data handle from StarPU. If the data was automatically allocated by StarPU because the home node was -1, all automatically allocated buffers are freed. Otherwise, a valid copy of the data is put back into the home node in the buffer that was initially registered. Using a data handle that has been unregistered from StarPU results in an undefined behaviour. In case we do not need to update the value of the data in the home node, we can use the function [starpu_data_unregister_no_coherency\(\)](#) instead.

28.8.5.5 `starpu_data_unregister_no_coherency()`

```
void starpu_data_unregister_no_coherency (
    starpu_data_handle_t handle )
```

This is the same as [starpu_data_unregister\(\)](#), except that StarPU does not put back a valid copy into the home node, in the buffer that was initially registered.

28.8.5.6 `starpu_data_unregister_submit()`

```
void starpu_data_unregister_submit (
    starpu_data_handle_t handle )
```

Destroy the data `handle` once it is no longer needed by any submitted task. No coherency is assumed.

28.8.5.7 `starpu_data_invalidate()`

```
void starpu_data_invalidate (
    starpu_data_handle_t handle )
```

Destroy all replicates of the data handle immediately. After data invalidation, the first access to the handle must be performed in write-only mode. Accessing an invalidated data in read-mode results in undefined behaviour.

28.8.5.8 `starpu_data_invalidate_submit()`

```
void starpu_data_invalidate_submit (
    starpu_data_handle_t handle )
```

Submits invalidation of the data handle after completion of previously submitted tasks.

28.8.5.9 `starpu_data_set_wt_mask()`

```
void starpu_data_set_wt_mask (
    starpu_data_handle_t handle,
    uint32_t wt_mask )
```

This function sets the write-through mask of a given data (and its children), i.e. a bitmask of nodes where the data should be always replicated after modification. It also prevents the data from being evicted from these nodes when memory gets scarce. When the data is modified, it is automatically transferred into those memory node. For instance a `1<0` write-through mask means that the CUDA workers will commit their changes in main memory (node 0).

28.8.5.10 `starpu_data_set_name()`

```
void starpu_data_set_name (
    starpu_data_handle_t handle,
    const char * name )
```

Set the name of the data, to be shown in various profiling tools.

28.8.5.11 `starpu_data_set_coordinates_array()`

```
void starpu_data_set_coordinates_array (
    starpu_data_handle_t handle,
    int dimensions,
    int dims[] )
```

Set the coordinates of the data, to be shown in various profiling tools. `dimensions` is the size of the `dims` array. This can be for instance the tile coordinates within a big matrix.

28.8.5.12 `starpu_data_set_coordinates()`

```
void starpu_data_set_coordinates (
    starpu_data_handle_t handle,
    unsigned dimensions,
    ... )
```

Set the coordinates of the data, to be shown in various profiling tools. `dimensions` is the number of subsequent `int` parameters. This can be for instance the tile coordinates within a big matrix.

28.8.5.13 `starpu_data_fetch_on_node()`

```
int starpu_data_fetch_on_node (
    starpu_data_handle_t handle,
    unsigned node,
    unsigned async )
```

Issue a fetch request for a given data to a given node, i.e. requests that the data be replicated to the given node as soon as possible, so that it is available there for tasks. If the `async` parameter is 0, the call will block until the transfer is achieved, else the call will return immediately, after having just queued the request. In the latter case, the request will asynchronously wait for the completion of any task writing on the data.

28.8.5.14 `starpu_data_prefetch_on_node()`

```
int starpu_data_prefetch_on_node (
    starpu_data_handle_t handle,
    unsigned node,
    unsigned async )
```

Issue a prefetch request for a given data to a given node, i.e. requests that the data be replicated to the given node when there is room for it, so that it is available there for tasks. If the `async` parameter is 0, the call will block until the transfer is achieved, else the call will return immediately, after having just queued the request. In the latter case, the request will asynchronously wait for the completion of any task writing on the data.

28.8.5.15 `starpu_data_idle_prefetch_on_node()`

```
int starpu_data_idle_prefetch_on_node (
    starpu_data_handle_t handle,
    unsigned node,
    unsigned async )
```

Issue an idle prefetch request for a given data to a given node, i.e. requests that the data be replicated to the given node, so that it is available there for tasks, but only when the bus is really idle. If the `async` parameter is 0, the call will block until the transfer is achieved, else the call will return immediately, after having just queued the request. In the latter case, the request will asynchronously wait for the completion of any task writing on the data.

28.8.5.16 `starpu_data_wont_use()`

```
void starpu_data_wont_use (
    starpu_data_handle_t handle )
```

Advise StarPU that this handle will not be used in the close future, and is thus a good candidate for eviction from GPUs. StarPU will thus write its value back to its home node when the bus is idle, and select this data in priority for eviction when memory gets low.

28.8.5.17 `starpu_data_lookup()`

```
starpu_data_handle_t starpu_data_lookup (
    const void * ptr )
```

Return the handle corresponding to the data pointed to by the `ptr` host pointer.

28.8.5.18 `starpu_data_request_allocation()`

```
int starpu_data_request_allocation (
    starpu_data_handle_t handle,
    unsigned node )
```

Explicitly ask StarPU to allocate room for a piece of data on the specified memory node.

28.8.5.19 starpu_data_query_status()

```
void starpu_data_query_status (
    starpu_data_handle_t handle,
    int memory_node,
    int * is_allocated,
    int * is_valid,
    int * is_requested )
```

Query the status of `handle` on the specified `memory_node`.

28.8.5.20 starpu_data_advise_as_important()

```
void starpu_data_advise_as_important (
    starpu_data_handle_t handle,
    unsigned is_important )
```

This function allows to specify that a piece of data can be discarded without impacting the application.

28.8.5.21 starpu_data_set_reduction_methods()

```
void starpu_data_set_reduction_methods (
    starpu_data_handle_t handle,
    struct starpu_codelet * redux_cl,
    struct starpu_codelet * init_cl )
```

This sets the codelets to be used for `handle` when it is accessed in the mode [STARPU_REDUX](#). Per-worker buffers will be initialized with the codelet `init_cl`, and reduction between per-worker buffers will be done with the codelet `redux_cl`.

28.8.5.22 starpu_data_get_interface_ops()

```
struct starpu_data_interface_ops * starpu_data_get_interface_ops (
    starpu_data_handle_t handle )
```

todo

28.8.5.23 starpu_data_set_user_data()

```
void starpu_data_set_user_data (
    starpu_data_handle_t handle,
    void * user_data )
```

This sets the "user_data" field for the `handle` to `user_data`. It can then be retrieved with `starpu_data_get_user_data`. `user_data` can be any application-defined value, for instance a pointer to an object-oriented container for the data.

28.8.5.24 starpu_data_get_user_data()

```
void * starpu_data_get_user_data (
    starpu_data_handle_t handle )
```

This retrieves the "user_data" field previously set for the `handle`.

28.8.5.25 starpu_data_acquire()

```
int starpu_data_acquire (
    starpu_data_handle_t handle,
    enum starpu_data_access_mode mode )
```

The application must call this function prior to accessing registered data from main memory outside tasks. StarPU ensures that the application will get an up-to-date copy of the data in main memory located where the data was originally registered, and that all concurrent accesses (e.g. from tasks) will be consistent with the access mode specified in the mode argument. [starpu_data_release\(\)](#) must be called once the application no longer needs to access the piece of data. Note that implicit data dependencies are also enforced by [starpu_data_acquire\(\)](#), i.e. [starpu_data_acquire\(\)](#) will wait for all tasks scheduled to work on the data, unless they have been disabled explicitly by calling [starpu_data_set_default_sequential_consistency_flag\(\)](#) or [starpu_data_set_sequential_consistency_flag\(\)](#). [starpu_data_acquire\(\)](#) is a blocking call, so that it cannot be called from tasks or from their callbacks (in that case, [starpu_data_acquire\(\)](#) returns `-EDEADLK`). Upon successful completion, this function returns 0.

28.8.5.26 starpu_data_acquire_cb()

```
int starpu_data_acquire_cb (
    starpu_data_handle_t handle,
    enum starpu_data_access_mode mode,
    void(*) (void *) callback,
    void * arg )
```

Asynchronous equivalent of [starpu_data_acquire\(\)](#). When the data specified in `handle` is available in the appropriate access mode, the `callback` function is executed. The application may access the requested data during the execution of this `callback`. The `callback` function must call [starpu_data_release\(\)](#) once the application no longer needs to access the piece of data. Note that implicit data dependencies are also enforced by [starpu_data_acquire_cb\(\)](#) in case they are not disabled. Contrary to [starpu_data_acquire\(\)](#), this function is non-blocking and may be called from task callbacks. Upon successful completion, this function returns 0.

28.8.5.27 starpu_data_acquire_cb_sequential_consistency()

```
int starpu_data_acquire_cb_sequential_consistency (
    starpu_data_handle_t handle,
    enum starpu_data_access_mode mode,
    void(*) (void *) callback,
    void * arg,
    int sequential_consistency )
```

Equivalent of [starpu_data_acquire_cb\(\)](#) with the possibility of enabling or disabling data dependencies. When the data specified in `handle` is available in the appropriate access mode, the `callback` function is executed. The application may access the requested data during the execution of this `callback`. The `callback` function must call [starpu_data_release\(\)](#) once the application no longer needs to access the piece of data. Note that implicit data dependencies are also enforced by [starpu_data_acquire_cb_sequential_consistency\(\)](#) in case they are not disabled specifically for the given `handle` or by the parameter `sequential_consistency`. Similarly to [starpu_data_acquire_cb\(\)](#), this function is non-blocking and may be called from task callbacks. Upon successful completion, this function returns 0.

28.8.5.28 `starpu_data_acquire_try()`

```
int starpu_data_acquire_try (
    starpu_data_handle_t handle,
    enum starpu_data_access_mode mode )
```

The application can call this function instead of `starpu_data_acquire()` so as to acquire the data like `starpu_data_acquire()`, but only if all previously-submitted tasks have completed, in which case `starpu_data_acquire_try()` returns 0. StarPU will have ensured that the application will get an up-to-date copy of `handle` in main memory located where the data was originally registered. `starpu_data_release()` must be called once the application no longer needs to access the piece of data.

If not all previously-submitted tasks have completed, `starpu_data_acquire_try` returns `-EAGAIN`, and `starpu_data_release()` must not be called.

28.8.5.29 `starpu_data_acquire_on_node()`

```
int starpu_data_acquire_on_node (
    starpu_data_handle_t handle,
    int node,
    enum starpu_data_access_mode mode )
```

This is the same as `starpu_data_acquire()`, except that the data will be available on the given memory node instead of main memory. `STARPU_ACQUIRE_NO_NODE` and `STARPU_ACQUIRE_ALL_NODES` can be used instead of an explicit node number.

28.8.5.30 `starpu_data_acquire_on_node_cb()`

```
int starpu_data_acquire_on_node_cb (
    starpu_data_handle_t handle,
    int node,
    enum starpu_data_access_mode mode,
    void(*) (void *) callback,
    void * arg )
```

This is the same as `starpu_data_acquire_cb()`, except that the data will be available on the given memory node instead of main memory. `STARPU_ACQUIRE_NO_NODE` and `STARPU_ACQUIRE_ALL_NODES` can be used instead of an explicit node number.

28.8.5.31 `starpu_data_acquire_on_node_cb_sequential_consistency()`

```
int starpu_data_acquire_on_node_cb_sequential_consistency (
    starpu_data_handle_t handle,
    int node,
    enum starpu_data_access_mode mode,
    void(*) (void *) callback,
    void * arg,
    int sequential_consistency )
```

This is the same as `starpu_data_acquire_cb_sequential_consistency()`, except that the data will be available on the given memory node instead of main memory. `STARPU_ACQUIRE_NO_NODE` and `STARPU_ACQUIRE_ALL_NODES` can be used instead of an explicit node number.

28.8.5.32 starpu_data_acquire_on_node_cb_sequential_consistency_sync_jobids()

```
int starpu_data_acquire_on_node_cb_sequential_consistency_sync_jobids (
    starpu_data_handle_t handle,
    int node,
    enum starpu_data_access_mode mode,
    void(*) (void *) callback,
    void * arg,
    int sequential_consistency,
    long * pre_sync_jobid,
    long * post_sync_jobid )
```

This is the same as [starpu_data_acquire_on_node_cb_sequential_consistency\(\)](#), except that the *pre_sync_jobid* and *post_sync_jobid* parameters can be used to retrieve the jobid of the synchronization tasks. *pre_sync_jobid* happens just before the acquisition, and *post_sync_jobid* happens just after the release.

28.8.5.33 starpu_data_acquire_on_node_try()

```
int starpu_data_acquire_on_node_try (
    starpu_data_handle_t handle,
    int node,
    enum starpu_data_access_mode mode )
```

This is the same as [starpu_data_acquire_try\(\)](#), except that the data will be available on the given memory node instead of main memory. [STARPU_ACQUIRE_NO_NODE](#) and `::STARPU_ACQUIRE_NO_NODE_LOCK_ALL` can be used instead of an explicit node number.

28.8.5.34 starpu_data_release()

```
void starpu_data_release (
    starpu_data_handle_t handle )
```

This function releases the piece of data acquired by the application either by [starpu_data_acquire\(\)](#) or by [starpu_data_acquire_cb\(\)](#).

28.8.5.35 starpu_data_release_on_node()

```
void starpu_data_release_on_node (
    starpu_data_handle_t handle,
    int node )
```

This is the same as [starpu_data_release\(\)](#), except that the data will be available on the given memory *node* instead of main memory. The *node* parameter must be exactly the same as the corresponding [starpu_data_acquire_on_node*](#) call.

28.8.5.36 starpu_arbiter_create()

```
starpu_arbiter_t starpu_arbiter_create (
    void )
```

This creates a data access arbiter, see [Concurrent Data Accesses](#) for the details

28.8.5.37 `starpu_data_assign_arbiter()`

```
void starpu_data_assign_arbiter (
    starpu_data_handle_t handle,
    starpu_arbiter_t arbiter )
```

This makes accesses to `handle` managed by `arbiter`

28.8.5.38 `starpu_arbiter_destroy()`

```
void starpu_arbiter_destroy (
    starpu_arbiter_t arbiter )
```

This destroys the `arbiter`. This must only be called after all data assigned to it have been unregistered.

28.9 Data Interfaces

Data Structures

- struct `starpu_data_interface_ops`
- struct `starpu_data_copy_methods`
- struct `starpu_variable_interface`
- struct `starpu_vector_interface`
- struct `starpu_matrix_interface`
- struct `starpu_block_interface`
- struct `starpu_bcsr_interface`
- struct `starpu_csr_interface`
- struct `starpu_coo_interface`

Enumerations

- enum `starpu_data_interface_id` {
`STARPU_UNKNOWN_INTERFACE_ID, STARPU_MATRIX_INTERFACE_ID, STARPU_BLOCK_INTERFACE_ID, STARPU_VECTOR_INTERFACE_ID,`
`STARPU_CSR_INTERFACE_ID, STARPU_BCSR_INTERFACE_ID, STARPU_VARIABLE_INTERFACE_ID, STARPU_VOID_INTERFACE_ID,`
`STARPU_MULTIFORMAT_INTERFACE_ID, STARPU_COO_INTERFACE_ID, STARPU_MAX_INTERFACE_ID`
`}`

Registering Data

There are several ways to register a memory region so that it can be managed by StarPU. The functions below allow the registration of vectors, 2D matrices, 3D matrices as well as BCSR and CSR sparse matrices.

- void [starpu_void_data_register](#) ([starpu_data_handle_t](#) *handle)
- void [starpu_variable_data_register](#) ([starpu_data_handle_t](#) *handle, int home_node, uintptr_t ptr, size_t size)
- void [starpu_variable_ptr_register](#) ([starpu_data_handle_t](#) handle, unsigned node, uintptr_t ptr, uintptr_t dev_↵_handle, size_t offset)
- void [starpu_vector_data_register](#) ([starpu_data_handle_t](#) *handle, int home_node, uintptr_t ptr, uint32_t nx, size_t elemsize)
- void [starpu_vector_ptr_register](#) ([starpu_data_handle_t](#) handle, unsigned node, uintptr_t ptr, uintptr_t dev_↵_handle, size_t offset)
- void [starpu_matrix_data_register](#) ([starpu_data_handle_t](#) *handle, int home_node, uintptr_t ptr, uint32_t ld, uint32_t nx, uint32_t ny, size_t elemsize)
- void [starpu_matrix_ptr_register](#) ([starpu_data_handle_t](#) handle, unsigned node, uintptr_t ptr, uintptr_t dev_↵_handle, size_t offset, uint32_t ld)
- void [starpu_block_data_register](#) ([starpu_data_handle_t](#) *handle, int home_node, uintptr_t ptr, uint32_t ldy, uint32_t ldz, uint32_t nx, uint32_t ny, uint32_t nz, size_t elemsize)
- void [starpu_block_ptr_register](#) ([starpu_data_handle_t](#) handle, unsigned node, uintptr_t ptr, uintptr_t dev_↵_handle, size_t offset, uint32_t ldy, uint32_t ldz)
- void [starpu_bcsr_data_register](#) ([starpu_data_handle_t](#) *handle, int home_node, uint32_t nnz, uint32_t nrow, uintptr_t nzval, uint32_t *colind, uint32_t *rowptr, uint32_t firstentry, uint32_t r, uint32_t c, size_t elemsize)
- void [starpu_csr_data_register](#) ([starpu_data_handle_t](#) *handle, int home_node, uint32_t nnz, uint32_t nrow, uintptr_t nzval, uint32_t *colind, uint32_t *rowptr, uint32_t firstentry, size_t elemsize)
- void [starpu_coo_data_register](#) ([starpu_data_handle_t](#) *handleptr, int home_node, uint32_t nx, uint32_t ny, uint32_t n_values, uint32_t *columns, uint32_t *rows, uintptr_t values, size_t elemsize)
- void * [starpu_data_get_interface_on_node](#) ([starpu_data_handle_t](#) handle, unsigned memory_node)

Accessing Data Interfaces

Each data interface is provided with a set of field access functions. The ones using a void * parameter aimed to be used in codelet implementations (see for example the code in [Vector Scaling Using StarPU's API](#)).

- void * [starpu_data_handle_to_pointer](#) ([starpu_data_handle_t](#) handle, unsigned node)
- int [starpu_data_pointer_is_inside](#) ([starpu_data_handle_t](#) handle, unsigned node, void *ptr)
- void * [starpu_data_get_local_ptr](#) ([starpu_data_handle_t](#) handle)
- enum [starpu_data_interface_id](#) [starpu_data_get_interface_id](#) ([starpu_data_handle_t](#) handle)
- size_t [starpu_data_get_size](#) ([starpu_data_handle_t](#) handle)
- int [starpu_data_pack](#) ([starpu_data_handle_t](#) handle, void **ptr, starpu_ssize_t *count)
- int [starpu_data_unpack](#) ([starpu_data_handle_t](#) handle, void *ptr, size_t count)

Accessing Variable Data Interfaces

- #define [STARPU_VARIABLE_GET_PTR](#)(interface)
- #define [STARPU_VARIABLE_GET_ELEMSIZE](#)(interface)
- #define [STARPU_VARIABLE_GET_DEV_HANDLE](#)(interface)
- #define [STARPU_VARIABLE_GET_OFFSET](#)(interface)
- size_t [starpu_variable_get_elemsize](#) ([starpu_data_handle_t](#) handle)
- uintptr_t [starpu_variable_get_local_ptr](#) ([starpu_data_handle_t](#) handle)

Accessing Vector Data Interfaces

- `#define STARPU_VECTOR_GET_PTR(interface)`
- `#define STARPU_VECTOR_GET_DEV_HANDLE(interface)`
- `#define STARPU_VECTOR_GET_OFFSET(interface)`
- `#define STARPU_VECTOR_GET_NX(interface)`
- `#define STARPU_VECTOR_GET_ELEMSIZE(interface)`
- `#define STARPU_VECTOR_GET_SLICE_BASE(interface)`
- `uint32_t starpu_vector_get_nx (starpu_data_handle_t handle)`
- `size_t starpu_vector_get_elemsize (starpu_data_handle_t handle)`
- `uintptr_t starpu_vector_get_local_ptr (starpu_data_handle_t handle)`

Accessing Matrix Data Interfaces

- `#define STARPU_MATRIX_GET_PTR(interface)`
- `#define STARPU_MATRIX_GET_DEV_HANDLE(interface)`
- `#define STARPU_MATRIX_GET_OFFSET(interface)`
- `#define STARPU_MATRIX_GET_NX(interface)`
- `#define STARPU_MATRIX_GET_NY(interface)`
- `#define STARPU_MATRIX_GET_LD(interface)`
- `#define STARPU_MATRIX_GET_ELEMSIZE(interface)`
- `uint32_t starpu_matrix_get_nx (starpu_data_handle_t handle)`
- `uint32_t starpu_matrix_get_ny (starpu_data_handle_t handle)`
- `uint32_t starpu_matrix_get_local_ld (starpu_data_handle_t handle)`
- `uintptr_t starpu_matrix_get_local_ptr (starpu_data_handle_t handle)`
- `size_t starpu_matrix_get_elemsize (starpu_data_handle_t handle)`

Accessing Block Data Interfaces

- `#define STARPU_BLOCK_GET_PTR(interface)`
- `#define STARPU_BLOCK_GET_DEV_HANDLE(interface)`
- `#define STARPU_BLOCK_GET_OFFSET(interface)`
- `#define STARPU_BLOCK_GET_NX(interface)`
- `#define STARPU_BLOCK_GET_NY(interface)`
- `#define STARPU_BLOCK_GET_NZ(interface)`
- `#define STARPU_BLOCK_GET_LDY(interface)`
- `#define STARPU_BLOCK_GET_LDZ(interface)`
- `#define STARPU_BLOCK_GET_ELEMSIZE(interface)`
- `uint32_t starpu_block_get_nx (starpu_data_handle_t handle)`
- `uint32_t starpu_block_get_ny (starpu_data_handle_t handle)`
- `uint32_t starpu_block_get_nz (starpu_data_handle_t handle)`
- `uint32_t starpu_block_get_local_ldy (starpu_data_handle_t handle)`
- `uint32_t starpu_block_get_local_ldz (starpu_data_handle_t handle)`
- `uintptr_t starpu_block_get_local_ptr (starpu_data_handle_t handle)`
- `size_t starpu_block_get_elemsize (starpu_data_handle_t handle)`

Accessing BCSR Data Interfaces

- `#define STARPU_BCSR_GET_NNZ(interface)`
- `#define STARPU_BCSR_GET_NZVAL(interface)`
- `#define STARPU_BCSR_GET_NZVAL_DEV_HANDLE(interface)`
- `#define STARPU_BCSR_GET_COLIND(interface)`
- `#define STARPU_BCSR_GET_COLIND_DEV_HANDLE(interface)`
- `#define STARPU_BCSR_GET_ROWPTR(interface)`
- `#define STARPU_BCSR_GET_ROWPTR_DEV_HANDLE(interface)`
- `#define STARPU_BCSR_GET_OFFSET`
- `uint32_t starpu_bcsr_get_nnz (starpu_data_handle_t handle)`
- `uint32_t starpu_bcsr_get_nrow (starpu_data_handle_t handle)`
- `uint32_t starpu_bcsr_get_firstentry (starpu_data_handle_t handle)`
- `uintptr_t starpu_bcsr_get_local_nzval (starpu_data_handle_t handle)`
- `uint32_t * starpu_bcsr_get_local_colind (starpu_data_handle_t handle)`
- `uint32_t * starpu_bcsr_get_local_rowptr (starpu_data_handle_t handle)`
- `uint32_t starpu_bcsr_get_r (starpu_data_handle_t handle)`
- `uint32_t starpu_bcsr_get_c (starpu_data_handle_t handle)`
- `size_t starpu_bcsr_get_elemsize (starpu_data_handle_t handle)`

Accessing CSR Data Interfaces

- `#define STARPU_CSR_GET_NNZ(interface)`
- `#define STARPU_CSR_GET_NROW(interface)`
- `#define STARPU_CSR_GET_NZVAL(interface)`
- `#define STARPU_CSR_GET_NZVAL_DEV_HANDLE(interface)`
- `#define STARPU_CSR_GET_COLIND(interface)`
- `#define STARPU_CSR_GET_COLIND_DEV_HANDLE(interface)`
- `#define STARPU_CSR_GET_ROWPTR(interface)`
- `#define STARPU_CSR_GET_ROWPTR_DEV_HANDLE(interface)`
- `#define STARPU_CSR_GET_OFFSET`
- `#define STARPU_CSR_GET_FIRSTENTRY(interface)`
- `#define STARPU_CSR_GET_ELEMSIZE(interface)`
- `uint32_t starpu_csr_get_nnz (starpu_data_handle_t handle)`
- `uint32_t starpu_csr_get_nrow (starpu_data_handle_t handle)`
- `uint32_t starpu_csr_get_firstentry (starpu_data_handle_t handle)`
- `uintptr_t starpu_csr_get_local_nzval (starpu_data_handle_t handle)`
- `uint32_t * starpu_csr_get_local_colind (starpu_data_handle_t handle)`
- `uint32_t * starpu_csr_get_local_rowptr (starpu_data_handle_t handle)`
- `size_t starpu_csr_get_elemsize (starpu_data_handle_t handle)`

Accessing COO Data Interfaces

- `#define STARPU_COO_GET_COLUMNS(interface)`
- `#define STARPU_COO_GET_COLUMNS_DEV_HANDLE(interface)`
- `#define STARPU_COO_GET_ROWS(interface)`
- `#define STARPU_COO_GET_ROWS_DEV_HANDLE(interface)`
- `#define STARPU_COO_GET_VALUES(interface)`
- `#define STARPU_COO_GET_VALUES_DEV_HANDLE(interface)`
- `#define STARPU_COO_GET_OFFSET`
- `#define STARPU_COO_GET_NX(interface)`
- `#define STARPU_COO_GET_NY(interface)`
- `#define STARPU_COO_GET_NVALUES(interface)`
- `#define STARPU_COO_GET_ELEMSIZE(interface)`

Defining Interface

Applications can provide their own interface as shown in [Defining A New Data Interface](#).

- `uintptr_t starpu_malloc_on_node_flags` (unsigned `dst_node`, `size_t` `size`, `int` `flags`)
- `void starpu_free_on_node_flags` (unsigned `dst_node`, `uintptr_t` `addr`, `size_t` `size`, `int` `flags`)
- `uintptr_t starpu_malloc_on_node` (unsigned `dst_node`, `size_t` `size`)
- `void starpu_free_on_node` (unsigned `dst_node`, `uintptr_t` `addr`, `size_t` `size`)
- `void starpu_malloc_on_node_set_default_flags` (unsigned `node`, `int` `flags`)
- `int starpu_interface_copy` (`uintptr_t` `src`, `size_t` `src_offset`, unsigned `src_node`, `uintptr_t` `dst`, `size_t` `dst_offset`, unsigned `dst_node`, `size_t` `size`, `void *``async_data`)
- `uint32_t starpu_hash_crc32c_be_n` (const `void *``input`, `size_t` `n`, `uint32_t` `inputcrc`)
- `uint32_t starpu_hash_crc32c_be` (`uint32_t` `input`, `uint32_t` `inputcrc`)
- `uint32_t starpu_hash_crc32c_string` (const `char *``str`, `uint32_t` `inputcrc`)
- `int starpu_data_interface_get_next_id` (`void`)

28.9.1 Detailed Description

28.9.2 Data Structure Documentation

28.9.2.1 `struct starpu_data_interface_ops`

Per-interface data transfer methods.

Data Fields

- `void(* register_data_handle)(starpu_data_handle_t handle, unsigned home_node, void *data_interface)`
- `starpu_ssize_t(* allocate_data_on_node)(void *data_interface, unsigned node)`
- `void(* free_data_on_node)(void *data_interface, unsigned node)`
- `const struct starpu_data_copy_methods * copy_methods`
- `void(* handle_to_pointer)(starpu_data_handle_t handle, unsigned node)`
- `int(* pointer_is_inside)(void *data_interface, unsigned node, void *ptr)`
- `size_t(* get_size)(starpu_data_handle_t handle)`
- `uint32_t(* footprint)(starpu_data_handle_t handle)`
- `int(* compare)(void *data_interface_a, void *data_interface_b)`
- `void(* display)(starpu_data_handle_t handle, FILE *f)`
- `starpu_ssize_t(* describe)(void *data_interface, char *buf, size_t size)`
- `enum starpu_data_interface_id interfaceid`
- `size_t interface_size`
- `char is_multiformat`
- `char dontcache`
- `struct starpu_multiformat_data_interface_ops *(* get_mf_ops)(void *data_interface)`
- `int(* pack_data)(starpu_data_handle_t handle, unsigned node, void **ptr, starpu_ssize_t *count)`
- `int(* unpack_data)(starpu_data_handle_t handle, unsigned node, void *ptr, size_t count)`
- `char * name`

28.9.2.1.1 Field Documentation

28.9.2.1.1.1 register_data_handle

```
void(* starpu_data_interface_ops::register_data_handle)(starpu_data_handle_t handle, unsigned
home_node, void *data_interface)
```

Register an existing interface into a data handle. This iterates over all memory nodes to initialize all fields of the data interface on each of them. Since data is not allocated yet except on the home node, pointers should be left as NULL except on the `home_node`, for which the pointers should be copied from the given `data_interface`, which was filled with the application's pointers.

28.9.2.1.1.2 allocate_data_on_node

```
starpu_ssize_t(* starpu_data_interface_ops::allocate_data_on_node)(void *data_interface, unsigned
node)
```

Allocate data for the interface on a given node. This should use `starpu_malloc_on_node` to perform the allocation(s), and fill the pointers in the data interface. It should return the size of the allocated memory, or -ENOMEM if memory could not be allocated.

28.9.2.1.1.3 free_data_on_node

```
void(* starpu_data_interface_ops::free_data_on_node)(void *data_interface, unsigned node)
```

Free data of the interface on a given node.

28.9.2.1.1.4 copy_methods

```
const struct starpu_data_copy_methods * starpu_data_interface_ops::copy_methods
```

This provides a series of methods for performing ram/cuda/opencl synchronous and asynchronous transfers.

28.9.2.1.1.5 handle_to_pointer

```
void *(* starpu_data_interface_ops::handle_to_pointer)(starpu_data_handle_t handle, unsigned
node)
```

Return the current pointer (if any) for the handle on the given node.

28.9.2.1.1.6 pointer_is_inside

```
int(* starpu_data_interface_ops::pointer_is_inside)(void *data_interface, unsigned node, void
*pointer)
```

Return whether the given `pointer` is within the data for the given interface on the given node.

28.9.2.1.1.7 get_size

```
size_t(* starpu_data_interface_ops::get_size)(starpu_data_handle_t handle)
```

Return an estimation of the size of data, for performance models.

28.9.2.1.1.8 footprint

```
uint32_t (* starpu_data_interface_ops::footprint) (starpu_data_handle_t handle)
```

Return a 32bit footprint which characterizes the data size and layout (nx, ny, ld, elemsize, etc.)

28.9.2.1.1.9 compare

```
int (* starpu_data_interface_ops::compare) (void *data_interface_a, void *data_interface_b)
```

Compare the data size and layout of two interfaces (nx, ny, ld, elemsize, etc.). It should return 1 if the two interfaces size and layout match, and 0 otherwise.

28.9.2.1.1.10 display

```
void (* starpu_data_interface_ops::display) (starpu_data_handle_t handle, FILE *f)
```

Dump the sizes of a handle to a file.

28.9.2.1.1.11 describe

```
starpu_ssize_t (* starpu_data_interface_ops::describe) (void *data_interface, char *buf, size_t size)
```

Describe the data into a string in a brief way, such as one letter to describe the type of data, and the data dimensions.

28.9.2.1.1.12 interfaceid

```
enum starpu_data_interface_id starpu_data_interface_ops::interfaceid
```

An identifier that is unique to each interface.

28.9.2.1.1.13 interface_size

```
size_t starpu_data_interface_ops::interface_size
```

The size of the interface data descriptor.

28.9.2.1.1.14 is_multiformat

```
char starpu_data_interface_ops::is_multiformat
```

todo

28.9.2.1.1.15 dontcache

```
char starpu_data_interface_ops::dontcache
```

If set to non-zero, StarPU will never try to reuse an allocated buffer for a different handle. This can be notably useful for application-defined interfaces which have a dynamic size, and for which it thus does not make sense to reuse the buffer since will probably not have the proper size.

28.9.2.1.1.16 get_mf_ops

```
struct starpu_multiformat_data_interface_ops *(* starpu_data_interface_ops::get_mf_ops)(void
*data_interface)
```

todo

28.9.2.1.1.17 pack_data

```
int(* starpu_data_interface_ops::pack_data)(starpu_data_handle_t handle, unsigned node, void
**ptr, starpu_ssize_t *count)
```

Pack the data handle into a contiguous buffer at the address allocated with `starpu_malloc_flags(ptr, size, 0)` (and thus returned in `ptr`) and set the size of the newly created buffer in `count`. If `ptr` is `NULL`, the function should not copy the data in the buffer but just set `count` to the size of the buffer which would have been allocated. The special value `-1` indicates the size is yet unknown.

28.9.2.1.1.18 unpack_data

```
int(* starpu_data_interface_ops::unpack_data)(starpu_data_handle_t handle, unsigned node, void
*ptr, size_t count)
```

Unpack the data handle from the contiguous buffer at the address `ptr` of size `count`

28.9.2.1.1.19 name

```
enum starpu_data_interface_id starpu_data_interface_ops::name
```

Name of the interface

28.9.2.2 struct starpu_data_copy_methods

Defines the per-interface methods. If the `any_to_any` method is provided, it will be used by default if no more specific method is provided. It can still be useful to provide more specific method in case of e.g. available particular CUDA or OpenCL support.

Data Fields

- `int(* can_copy)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node, unsigned handling_node)`
- `int(* ram_to_ram)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node)`
- `int(* ram_to_cuda)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node)`
- `int(* ram_to_opengl)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node)`
- `int(* ram_to_mic)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node)`
- `int(* cuda_to_ram)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node)`
- `int(* cuda_to_cuda)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node)`
- `int(* cuda_to_opengl)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node)`
- `int(* opengl_to_ram)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node)`
- `int(* opengl_to_cuda)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node)`
- `int(* opengl_to_opengl)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node)`
- `int(* mic_to_ram)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node)`
- `int(* scc_src_to_sink)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node)`

- `int(* scc_sink_to_src)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node)`
- `int(* scc_sink_to_sink)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node)`
- `int(* ram_to_cuda_async)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node, starpu_cudaStream_t stream)`
- `int(* cuda_to_ram_async)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node, starpu_cudaStream_t stream)`
- `int(* cuda_to_cuda_async)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node, starpu_cudaStream_t stream)`
- `int(* ram_to_opencil_async)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node, cl_event *event)`
- `int(* opencil_to_ram_async)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node, cl_event *event)`
- `int(* opencil_to_opencil_async)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node, cl_event *event)`
- `int(* ram_to_mic_async)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node)`
- `int(* mic_to_ram_async)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node)`
- `int(* any_to_any)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node, void *async_data)`

28.9.2.2.1 Field Documentation

28.9.2.2.1.1 can_copy

```
int(* starpu_data_copy_methods::can_copy)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node, unsigned handling_node)
```

If defined, allows the interface to declare whether it supports transferring from `src_interface` on node `src_node` to `dst_interface` on node `dst_node`, run from node `handling_node`. If not defined, it is assumed that the interface supports all transfers.

28.9.2.2.1.2 ram_to_ram

```
int(* starpu_data_copy_methods::ram_to_ram)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node)
```

Define how to copy data from the `src_interface` interface on the `src_node` CPU node to the `dst_interface` interface on the `dst_node` CPU node. Return 0 on success.

28.9.2.2.1.3 ram_to_cuda

```
int(* starpu_data_copy_methods::ram_to_cuda)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node)
```

Define how to copy data from the `src_interface` interface on the `src_node` CPU node to the `dst_interface` interface on the `dst_node` CUDA node. Return 0 on success.

28.9.2.2.1.4 ram_to_opencil

```
int(* starpu_data_copy_methods::ram_to_opencil)(void *src_interface, unsigned src_node, void *dst_interface, unsigned dst_node)
```

Define how to copy data from the `src_interface` interface on the `src_node` CPU node to the `dst_interface` interface on the `dst_node` OpenCL node. Return 0 on success.

28.9.2.2.1.5 ram_to_mic

```
int (* starpu_data_copy_methods::ram_to_mic) (void *src_interface, unsigned src_node, void *dst_↵
_interface, unsigned dst_node)
```

Define how to copy data from the `src_interface` interface on the `src_node` CPU node to the `dst_↵`
interface interface on the `dst_node` MIC node. Return 0 on success.

28.9.2.2.1.6 cuda_to_ram

```
int (* starpu_data_copy_methods::cuda_to_ram) (void *src_interface, unsigned src_node, void
*dst_interface, unsigned dst_node)
```

Define how to copy data from the `src_interface` interface on the `src_node` CUDA node to the `dst_↵`
interface interface on the `dst_node` CPU node. Return 0 on success.

28.9.2.2.1.7 cuda_to_cuda

```
int (* starpu_data_copy_methods::cuda_to_cuda) (void *src_interface, unsigned src_node, void
*dst_interface, unsigned dst_node)
```

Define how to copy data from the `src_interface` interface on the `src_node` CUDA node to the `dst_↵`
interface interface on the `dst_node` CUDA node. Return 0 on success.

28.9.2.2.1.8 cuda_to_opengl

```
int (* starpu_data_copy_methods::cuda_to_opengl) (void *src_interface, unsigned src_node, void
*dst_interface, unsigned dst_node)
```

Define how to copy data from the `src_interface` interface on the `src_node` CUDA node to the `dst_↵`
interface interface on the `dst_node` OpenGL node. Return 0 on success.

28.9.2.2.1.9 opengl_to_ram

```
int (* starpu_data_copy_methods::opengl_to_ram) (void *src_interface, unsigned src_node, void
*dst_interface, unsigned dst_node)
```

Define how to copy data from the `src_interface` interface on the `src_node` OpenGL node to the `dst_↵`
interface interface on the `dst_node` CPU node. Return 0 on success.

28.9.2.2.1.10 opengl_to_cuda

```
int (* starpu_data_copy_methods::opengl_to_cuda) (void *src_interface, unsigned src_node, void
*dst_interface, unsigned dst_node)
```

Define how to copy data from the `src_interface` interface on the `src_node` OpenGL node to the `dst_↵`
interface interface on the `dst_node` CUDA node. Return 0 on success.

28.9.2.2.1.11 opengl_to_opengl

```
int (* starpu_data_copy_methods::opengl_to_opengl) (void *src_interface, unsigned src_node, void
*dst_interface, unsigned dst_node)
```

Define how to copy data from the `src_interface` interface on the `src_node` OpenGL node to the `dst_↵`
interface interface on the `dst_node` OpenGL node. Return 0 on success.

28.9.2.2.1.12 mic_to_ram

```
int(* starpu_data_copy_methods::mic_to_ram)(void *src_interface, unsigned src_node, void *dst_↵
_interface, unsigned dst_node)
```

Define how to copy data from the `src_interface` interface on the `src_node` MIC node to the `dst_↵`
interface interface on the `dst_node` CPU node. Return 0 on success.

28.9.2.2.1.13 scc_src_to_sink

```
int(* starpu_data_copy_methods::scc_src_to_sink)(void *src_interface, unsigned src_node, void
*dst_interface, unsigned dst_node)
```

Define how to copy data from the `src_interface` interface on the `src_node` node to the `dst_interface`
interface on the `dst_node` node. Must return 0 if the transfer was actually completed completely synchronously,
or -EAGAIN if at least some transfers are still ongoing and should be awaited for by the core.

28.9.2.2.1.14 scc_sink_to_src

```
int(* starpu_data_copy_methods::scc_sink_to_src)(void *src_interface, unsigned src_node, void
*dst_interface, unsigned dst_node)
```

Define how to copy data from the `src_interface` interface on the `src_node` node to the `dst_interface`
interface on the `dst_node` node. Must return 0 if the transfer was actually completed completely synchronously,
or -EAGAIN if at least some transfers are still ongoing and should be awaited for by the core.

28.9.2.2.1.15 scc_sink_to_sink

```
int(* starpu_data_copy_methods::scc_sink_to_sink)(void *src_interface, unsigned src_node, void
*dst_interface, unsigned dst_node)
```

Define how to copy data from the `src_interface` interface on the `src_node` node to the `dst_interface`
interface on the `dst_node` node. Must return 0 if the transfer was actually completed completely synchronously,
or -EAGAIN if at least some transfers are still ongoing and should be awaited for by the core.

28.9.2.2.1.16 ram_to_cuda_async

```
int(* starpu_data_copy_methods::ram_to_cuda_async)(void *src_interface, unsigned src_node, void
*dst_interface, unsigned dst_node, cudaStream_t stream)
```

Define how to copy data from the `src_interface` interface on the `src_node` CPU node to the `dst_↵`
interface interface on the `dst_node` CUDA node, using the given stream. Must return 0 if the transfer was
actually completed completely synchronously, or -EAGAIN if at least some transfers are still ongoing and should be
awaited for by the core.

28.9.2.2.1.17 cuda_to_ram_async

```
int(* starpu_data_copy_methods::cuda_to_ram_async)(void *src_interface, unsigned src_node, void
*dst_interface, unsigned dst_node, cudaStream_t stream)
```

Define how to copy data from the `src_interface` interface on the `src_node` CUDA node to the `dst_↵`
interface interface on the `dst_node` CPU node, using the given stream. Must return 0 if the transfer was
actually completed completely synchronously, or -EAGAIN if at least some transfers are still ongoing and should be
awaited for by the core.

28.9.2.2.1.18 cuda_to_cuda_async

```
int (* starpu_data_copy_methods::cuda_to_cuda_async)(void *src_interface, unsigned src_node,
void *dst_interface, unsigned dst_node, cudaStream_t stream)
```

Define how to copy data from the `src_interface` interface on the `src_node` CUDA node to the `dst_interface` interface on the `dst_node` CUDA node, using the given stream. Must return 0 if the transfer was actually completed completely synchronously, or -EAGAIN if at least some transfers are still ongoing and should be awaited for by the core.

28.9.2.2.1.19 ram_to_opengl_async

```
int (* starpu_data_copy_methods::ram_to_opengl_async)(void *src_interface, unsigned src_node,
void *dst_interface, unsigned dst_node, cl_event *event)
```

Define how to copy data from the `src_interface` interface on the `src_node` CPU node to the `dst_interface` interface on the `dst_node` OpenCL node, by recording in event, a pointer to a `cl_event`, the event of the last submitted transfer. Must return 0 if the transfer was actually completed completely synchronously, or -EAGAIN if at least some transfers are still ongoing and should be awaited for by the core.

28.9.2.2.1.20 opengl_to_ram_async

```
int (* starpu_data_copy_methods::opengl_to_ram_async)(void *src_interface, unsigned src_node,
void *dst_interface, unsigned dst_node, cl_event *event)
```

Define how to copy data from the `src_interface` interface on the `src_node` OpenCL node to the `dst_interface` interface on the `dst_node` CPU node, by recording in event, a pointer to a `cl_event`, the event of the last submitted transfer. Must return 0 if the transfer was actually completed completely synchronously, or -EAGAIN if at least some transfers are still ongoing and should be awaited for by the core.

28.9.2.2.1.21 opengl_to_opengl_async

```
int (* starpu_data_copy_methods::opengl_to_opengl_async)(void *src_interface, unsigned src_node,
void *dst_interface, unsigned dst_node, cl_event *event)
```

Define how to copy data from the `src_interface` interface on the `src_node` OpenCL node to the `dst_interface` interface on the `dst_node` OpenCL node, by recording in event, a pointer to a `cl_event`, the event of the last submitted transfer. Must return 0 if the transfer was actually completed completely synchronously, or -EAGAIN if at least some transfers are still ongoing and should be awaited for by the core.

28.9.2.2.1.22 ram_to_mic_async

```
int (* starpu_data_copy_methods::ram_to_mic_async)(void *src_intreface, unsigned src_node, void
*dst_interface, unsigned dst_node)
```

Define how to copy data from the `src_interface` interface on the `src_node` CPU node to the `dst_interface` interface on the `dst_node` MIC node. Must return 0 if the transfer was actually completed completely synchronously, or -EAGAIN if at least some transfers are still ongoing and should be awaited for by the core.

28.9.2.2.1.23 mic_to_ram_async

```
int (* starpu_data_copy_methods::mic_to_ram_async)(void *src_intreface, unsigned src_node, void
*dst_interface, unsigned dst_node)
```

Define how to copy data from the `src_interface` interface on the `src_node` MIC node to the `dst_interface` interface on the `dst_node` CPU node. Must return 0 if the transfer was actually completed completely synchronously, or -EAGAIN if at least some transfers are still ongoing and should be awaited for by the core.

28.9.2.2.1.24 any_to_any

```
int(* starpu_data_copy_methods::any_to_any)(void *src_interface, unsigned src_node, void *dst↵
_interface, unsigned dst_node, void *async_data)
```

Define how to copy data from the `src_interface` interface on the `src_node` node to the `dst_interface` interface on the `dst_node` node. This is meant to be implemented through the `starpu_interface_copy()` helper, to which `async_data` should be passed as such, and will be used to manage asynchronicity. This must return `-EAGAIN` if any of the `starpu_interface_copy()` calls has returned `-EAGAIN` (i.e. at least some transfer is still ongoing), and return 0 otherwise.

28.9.2.3 struct starpu_variable_interface

Variable interface for a single data (not a vector, a matrix, a list, ...)

Data Fields

enum <code>starpu_data_interface_id</code>	id	Identifier of the interface
<code>uintptr_t</code>	ptr	local pointer of the variable
<code>uintptr_t</code>	dev_handle	device handle of the variable.
<code>size_t</code>	offset	offset in the variable
<code>size_t</code>	elemsize	size of the variable

28.9.2.4 struct starpu_vector_interface

Vector interface

Data Fields

enum <code>starpu_data_interface_id</code>	id	Identifier of the interface
<code>uintptr_t</code>	ptr	local pointer of the vector
<code>uintptr_t</code>	dev_handle	device handle of the vector.
<code>size_t</code>	offset	offset in the vector
<code>uint32_t</code>	nx	number of elements on the x-axis of the vector
<code>size_t</code>	elemsize	size of the elements of the vector
<code>uint32_t</code>	slice_base	vector slice base, used by the StarPU OpenMP runtime support

28.9.2.5 struct starpu_matrix_interface

Matrix interface for dense matrices

Data Fields

enum <code>starpu_data_interface_id</code>	id	Identifier of the interface
<code>uintptr_t</code>	ptr	local pointer of the matrix
<code>uintptr_t</code>	dev_handle	device handle of the matrix.
<code>size_t</code>	offset	offset in the matrix

Data Fields

uint32_t	nx	number of elements on the x-axis of the matrix
uint32_t	ny	number of elements on the y-axis of the matrix
uint32_t	ld	number of elements between each row of the matrix. Maybe be equal to starpu_matrix_interface::nx when there is no padding.
size_t	elemsize	size of the elements of the matrix

28.9.2.6 struct starpu_block_interface

Block interface for 3D dense blocks

Data Fields

enum starpu_data_interface_id	id	identifier of the interface
uintptr_t	ptr	local pointer of the block
uintptr_t	dev_handle	device handle of the block.
size_t	offset	offset in the block.
uint32_t	nx	number of elements on the x-axis of the block.
uint32_t	ny	number of elements on the y-axis of the block.
uint32_t	nz	number of elements on the z-axis of the block.
uint32_t	ldy	number of elements between two lines
uint32_t	ldz	number of elements between two planes
size_t	elemsize	size of the elements of the block.

28.9.2.7 struct starpu_bcsr_interface

BCSR interface for sparse matrices (blocked compressed sparse row representation)

Data Fields

enum starpu_data_interface_id	id	Identifier of the interface
uint32_t	nnz	number of non-zero BLOCKS
uint32_t	nrow	number of rows (in terms of BLOCKS)
uintptr_t	nzval	non-zero values
uint32_t *	colind	array of nnz elements, colind[i] is the block-column index for block i in nzval
uint32_t *	rowptr	array of nrow+1 elements, rowptr[i] is the block-index (in nzval) of the first block of row i. By convention, rowptr[nrow] is the number of blocks, this allows an easier access of the matrix's elements for the kernels.
uint32_t	firstentry	k for k-based indexing (0 or 1 usually). Also useful when partitionning the matrix.
uint32_t	r	height of the blocks
uint32_t	c	size of the blocks
size_t	elemsize	width of the blocks size of the elements of the matrix

28.9.2.8 struct starpu_csr_interface

CSR interface for sparse matrices (compressed sparse row representation)

Data Fields

enum starpu_data_interface_id	id	Identifier of the interface
uint32_t	nnz	number of non-zero entries
uint32_t	nrow	number of rows
uintptr_t	nzval	non-zero values
uint32_t *	colind	position of non-zero entries on the row
uint32_t *	rowptr	index (in nzval) of the first entry of the row
uint32_t	firstentry	k for k-based indexing (0 or 1 usually). also useful when partitionning the matrix.
size_t	elemsize	size of the elements of the matrix

28.9.2.9 struct starpu_coo_interface

COO Matrices

Data Fields

enum starpu_data_interface_id	id	identifier of the interface
uint32_t *	columns	column array of the matrix
uint32_t *	rows	row array of the matrix
uintptr_t	values	values of the matrix
uint32_t	nx	number of elements on the x-axis of the matrix
uint32_t	ny	number of elements on the y-axis of the matrix
uint32_t	n_values	number of values registered in the matrix
size_t	elemsize	size of the elements of the matrix

28.9.3 Macro Definition Documentation

28.9.3.1 STARPU_VARIABLE_GET_PTR

```
#define STARPU_VARIABLE_GET_PTR(  
    interface )
```

Return a pointer to the variable designated by `interface`.

28.9.3.2 STARPU_VARIABLE_GET_ELEMSIZE

```
#define STARPU_VARIABLE_GET_ELEMSIZE(  
    interface )
```

Return the size of the variable designated by `interface`.

28.9.3.3 STARPU_VARIABLE_GET_DEV_HANDLE

```
#define STARPU_VARIABLE_GET_DEV_HANDLE(  
    interface )
```

Return a device handle for the variable designated by *interface*, to be used on OpenCL. The offset documented below has to be used in addition to this.

28.9.3.4 STARPU_VARIABLE_GET_OFFSET

```
#define STARPU_VARIABLE_GET_OFFSET(  
    interface )
```

Return the offset in the variable designated by *interface*, to be used with the device handle.

28.9.3.5 STARPU_VECTOR_GET_PTR

```
#define STARPU_VECTOR_GET_PTR(  
    interface )
```

Return a pointer to the array designated by *interface*, valid on CPUs and CUDA only. For OpenCL, the device handle and offset need to be used instead.

28.9.3.6 STARPU_VECTOR_GET_DEV_HANDLE

```
#define STARPU_VECTOR_GET_DEV_HANDLE(  
    interface )
```

Return a device handle for the array designated by *interface*, to be used on OpenCL. the offset documented below has to be used in addition to this.

28.9.3.7 STARPU_VECTOR_GET_OFFSET

```
#define STARPU_VECTOR_GET_OFFSET(  
    interface )
```

Return the offset in the array designated by *interface*, to be used with the device handle.

28.9.3.8 STARPU_VECTOR_GET_NX

```
#define STARPU_VECTOR_GET_NX(  
    interface )
```

Return the number of elements registered into the array designated by *interface*.

28.9.3.9 STARPU_VECTOR_GET_ELEMSIZE

```
#define STARPU_VECTOR_GET_ELEMSIZE(  
    interface )
```

Return the size of each element of the array designated by *interface*.

28.9.3.10 STARPU_VECTOR_GET_SLICE_BASE

```
#define STARPU_VECTOR_GET_SLICE_BASE(  
    interface )
```

Return the OpenMP slice base annotation of each element of the array designated by *interface*.

See also

[starpu_omp_vector_annotate](#)

28.9.3.11 STARPU_MATRIX_GET_PTR

```
#define STARPU_MATRIX_GET_PTR(  
    interface )
```

Return a pointer to the matrix designated by *interface*, valid on CPUs and CUDA devices only. For OpenCL devices, the device handle and offset need to be used instead.

28.9.3.12 STARPU_MATRIX_GET_DEV_HANDLE

```
#define STARPU_MATRIX_GET_DEV_HANDLE(  
    interface )
```

Return a device handle for the matrix designated by *interface*, to be used on OpenCL. The offset documented below has to be used in addition to this.

28.9.3.13 STARPU_MATRIX_GET_OFFSET

```
#define STARPU_MATRIX_GET_OFFSET(  
    interface )
```

Return the offset in the matrix designated by *interface*, to be used with the device handle.

28.9.3.14 STARPU_MATRIX_GET_NX

```
#define STARPU_MATRIX_GET_NX(  
    interface )
```

Return the number of elements on the x-axis of the matrix designated by *interface*.

28.9.3.15 STARPU_MATRIX_GET_NY

```
#define STARPU_MATRIX_GET_NY(  
    interface )
```

Return the number of elements on the y-axis of the matrix designated by *interface*.

28.9.3.16 STARPU_MATRIX_GET_LD

```
#define STARPU_MATRIX_GET_LD(  
    interface )
```

Return the number of elements between each row of the matrix designated by *interface*. May be equal to nx when there is no padding.

28.9.3.17 STARPU_MATRIX_GET_ELEMSIZE

```
#define STARPU_MATRIX_GET_ELEMSIZE(  
    interface )
```

Return the size of the elements registered into the matrix designated by *interface*.

28.9.3.18 STARPU_BLOCK_GET_PTR

```
#define STARPU_BLOCK_GET_PTR(  
    interface )
```

Return a pointer to the block designated by *interface*.

28.9.3.19 STARPU_BLOCK_GET_DEV_HANDLE

```
#define STARPU_BLOCK_GET_DEV_HANDLE(  
    interface )
```

Return a device handle for the block designated by *interface*, to be used on OpenCL. The offset document below has to be used in addition to this.

28.9.3.20 STARPU_BLOCK_GET_OFFSET

```
#define STARPU_BLOCK_GET_OFFSET(  
    interface )
```

Return the offset in the block designated by *interface*, to be used with the device handle.

28.9.3.21 STARPU_BLOCK_GET_NX

```
#define STARPU_BLOCK_GET_NX(  
    interface )
```

Return the number of elements on the x-axis of the block designated by *interface*.

28.9.3.22 STARPU_BLOCK_GET_NY

```
#define STARPU_BLOCK_GET_NY(  
    interface )
```

Return the number of elements on the y-axis of the block designated by *interface*.

28.9.3.23 STARPU_BLOCK_GET_NZ

```
#define STARPU_BLOCK_GET_NZ(  
    interface )
```

Return the number of elements on the z-axis of the block designated by *interface*.

28.9.3.24 STARPU_BLOCK_GET_LDY

```
#define STARPU_BLOCK_GET_LDY(  
    interface )
```

Return the number of elements between each row of the block designated by *interface*. May be equal to *nx* when there is no padding.

28.9.3.25 STARPU_BLOCK_GET_LDZ

```
#define STARPU_BLOCK_GET_LDZ(  
    interface )
```

Return the number of elements between each z plane of the block designated by *interface*. May be equal to *nx*ny* when there is no padding.

28.9.3.26 STARPU_BLOCK_GET_ELEMSIZE

```
#define STARPU_BLOCK_GET_ELEMSIZE(  
    interface )
```

Return the size of the elements of the block designated by *interface*.

28.9.3.27 STARPU_BCSR_GET_NNZ

```
#define STARPU_BCSR_GET_NNZ(  
    interface )
```

Return the number of non-zero values in the matrix designated by *interface*.

28.9.3.28 STARPU_BCSR_GET_NZVAL

```
#define STARPU_BCSR_GET_NZVAL(  
    interface )
```

Return a pointer to the non-zero values of the matrix designated by *interface*.

28.9.3.29 STARPU_BCSR_GET_NZVAL_DEV_HANDLE

```
#define STARPU_BCSR_GET_NZVAL_DEV_HANDLE(  
    interface )
```

Return a device handle for the array of non-zero values in the matrix designated by *interface*. The offset documented below has to be used in addition to this.

28.9.3.30 STARPU_BCSR_GET_COLIND

```
#define STARPU_BCSR_GET_COLIND(  
    interface )
```

Return a pointer to the column index of the matrix designated by *interface*.

28.9.3.31 STARPU_BCSR_GET_COLIND_DEV_HANDLE

```
#define STARPU_BCSR_GET_COLIND_DEV_HANDLE(  
    interface )
```

Return a device handle for the column index of the matrix designated by *interface*. The offset documented below has to be used in addition to this.

28.9.3.32 STARPU_BCSR_GET_ROWPTR

```
#define STARPU_BCSR_GET_ROWPTR(  
    interface )
```

Return a pointer to the row pointer array of the matrix designated by *interface*.

28.9.3.33 STARPU_BCSR_GET_ROWPTR_DEV_HANDLE

```
#define STARPU_BCSR_GET_ROWPTR_DEV_HANDLE(  
    interface )
```

Return a device handle for the row pointer array of the matrix designated by *interface*. The offset documented below has to be used in addition to this.

28.9.3.34 STARPU_BCSR_GET_OFFSET

```
#define STARPU_BCSR_GET_OFFSET
```

Return the offset in the arrays (colind, rowptr, nzval) of the matrix designated by *interface*, to be used with the device handles.

28.9.3.35 STARPU_CSR_GET_NNZ

```
#define STARPU_CSR_GET_NNZ(  
    interface )
```

Return the number of non-zero values in the matrix designated by *interface*.

28.9.3.36 STARPU_CSR_GET_NROW

```
#define STARPU_CSR_GET_NROW(  
    interface )
```

Return the size of the row pointer array of the matrix designated by *interface*.

28.9.3.37 STARPU_CSR_GET_NZVAL

```
#define STARPU_CSR_GET_NZVAL(  
    interface )
```

Return a pointer to the non-zero values of the matrix designated by *interface*.

28.9.3.38 STARPU_CSR_GET_NZVAL_DEV_HANDLE

```
#define STARPU_CSR_GET_NZVAL_DEV_HANDLE(  
    interface )
```

Return a device handle for the array of non-zero values in the matrix designated by *interface*. The offset documented below has to be used in addition to this.

28.9.3.39 STARPU_CSR_GET_COLIND

```
#define STARPU_CSR_GET_COLIND(  
    interface )
```

Return a pointer to the column index of the matrix designated by *interface*.

28.9.3.40 STARPU_CSR_GET_COLIND_DEV_HANDLE

```
#define STARPU_CSR_GET_COLIND_DEV_HANDLE(  
    interface )
```

Return a device handle for the column index of the matrix designated by *interface*. The offset documented below has to be used in addition to this.

28.9.3.41 STARPU_CSR_GET_ROWPTR

```
#define STARPU_CSR_GET_ROWPTR(  
    interface )
```

Return a pointer to the row pointer array of the matrix designated by *interface*.

28.9.3.42 STARPU_CSR_GET_ROWPTR_DEV_HANDLE

```
#define STARPU_CSR_GET_ROWPTR_DEV_HANDLE(  
    interface )
```

Return a device handle for the row pointer array of the matrix designated by *interface*. The offset documented below has to be used in addition to this.

28.9.3.43 STARPU_CSR_GET_OFFSET

```
#define STARPU_CSR_GET_OFFSET
```

Return the offset in the arrays (colind, rowptr, nzval) of the matrix designated by *interface*, to be used with the device handles.

28.9.3.44 STARPU_CSR_GET_FIRSTENTRY

```
#define STARPU_CSR_GET_FIRSTENTRY(  
    interface )
```

Return the index at which all arrays (the column indexes, the row pointers...) of the *interface* start.

28.9.3.45 STARPU_CSR_GET_ELEMSIZE

```
#define STARPU_CSR_GET_ELEMSIZE(  
    interface )
```

Return the size of the elements registered into the matrix designated by *interface*.

28.9.3.46 STARPU_COO_GET_COLUMNS

```
#define STARPU_COO_GET_COLUMNS(  
    interface )
```

Return a pointer to the column array of the matrix designated by *interface*.

28.9.3.47 STARPU_COO_GET_COLUMNS_DEV_HANDLE

```
#define STARPU_COO_GET_COLUMNS_DEV_HANDLE(  
    interface )
```

Return a device handle for the column array of the matrix designated by *interface*, to be used on OpenCL. The offset documented below has to be used in addition to this.

28.9.3.48 STARPU_COO_GET_ROWS

```
#define STARPU_COO_GET_ROWS(  
    interface )
```

Return a pointer to the rows array of the matrix designated by *interface*.

28.9.3.49 STARPU_COO_GET_ROWS_DEV_HANDLE

```
#define STARPU_COO_GET_ROWS_DEV_HANDLE(  
    interface )
```

Return a device handle for the row array of the matrix designated by *interface*, to be used on OpenCL. The offset documented below has to be used in addition to this.

28.9.3.50 STARPU_COO_GET_VALUES

```
#define STARPU_COO_GET_VALUES(  
    interface )
```

Return a pointer to the values array of the matrix designated by *interface*.

28.9.3.51 STARPU_COO_GET_VALUES_DEV_HANDLE

```
#define STARPU_COO_GET_VALUES_DEV_HANDLE(  
    interface )
```

Return a device handle for the value array of the matrix designated by *interface*, to be used on OpenCL. The offset documented below has to be used in addition to this.

28.9.3.52 STARPU_COO_GET_OFFSET

```
#define STARPU_COO_GET_OFFSET
```

Return the offset in the arrays of the COO matrix designated by *interface*.

28.9.3.53 STARPU_COO_GET_NX

```
#define STARPU_COO_GET_NX(  
    interface )
```

Return the number of elements on the x-axis of the matrix designated by *interface*.

28.9.3.54 STARPU_COO_GET_NY

```
#define STARPU_COO_GET_NY(  
    interface )
```

Return the number of elements on the y-axis of the matrix designated by *interface*.

28.9.3.55 STARPU_COO_GET_NVALUES

```
#define STARPU_COO_GET_NVALUES(  
    interface )
```

Return the number of values registered in the matrix designated by *interface*.

28.9.3.56 STARPU_COO_GET_ELEMSIZE

```
#define STARPU_COO_GET_ELEMSIZE (
    interface )
```

Return the size of the elements registered into the matrix designated by `interface`.

28.9.4 Enumeration Type Documentation

28.9.4.1 starpu_data_interface_id

```
enum starpu_data_interface_id
```

Identifier for all predefined StarPU data interfaces

Enumerator

STARPU_UNKNOWN_INTERFACE_ID	Unknown interface
STARPU_MATRIX_INTERFACE_ID	Identifier for the matrix data interface
STARPU_BLOCK_INTERFACE_ID	Identifier for block data interface
STARPU_VECTOR_INTERFACE_ID	Identifier for the vector data interface
STARPU_CSR_INTERFACE_ID	Identifier for the csr data interface
STARPU_BCSR_INTERFACE_ID	Identifier for the bcsr data interface
STARPU_VARIABLE_INTERFACE_ID	Identifier for the variable data interface
STARPU_VOID_INTERFACE_ID	Identifier for the void data interface
STARPU_MULTIFORMAT_INTERFACE_ID	Identifier for the multiformat data interface
STARPU_COO_INTERFACE_ID	Identifier for the coo data interface
STARPU_MAX_INTERFACE_ID	Maximum number of data interfaces

28.9.5 Function Documentation

28.9.5.1 starpu_void_data_register()

```
void starpu_void_data_register (
    starpu_data_handle_t * handle )
```

Register a void interface. There is no data really associated to that interface, but it may be used as a synchronization mechanism. It also permits to express an abstract piece of data that is managed by the application internally: this makes it possible to forbid the concurrent execution of different tasks accessing the same `void` data in read-write concurrently.

28.9.5.2 `starpu_variable_data_register()`

```
void starpu_variable_data_register (
    starpu_data_handle_t * handle,
    int home_node,
    uintptr_t ptr,
    size_t size )
```

Register the `size` byte element pointed to by `ptr`, which is typically a scalar, and initialize `handle` to represent this data item.

Here an example of how to use the function.

```
float var;
starpu_data_handle_t var_handle;
starpu_variable_data_register(&var_handle, STARPU_MAIN_RAM, (
    uintptr_t)&var, sizeof(var));
```

28.9.5.3 `starpu_variable_ptr_register()`

```
void starpu_variable_ptr_register (
    starpu_data_handle_t handle,
    unsigned node,
    uintptr_t ptr,
    uintptr_t dev_handle,
    size_t offset )
```

Register into the `handle` that to store data on `node` it should use the buffer located at `ptr`, or device handle `dev_handle` and offset `offset` (for OpenCL, notably)

28.9.5.4 `starpu_vector_data_register()`

```
void starpu_vector_data_register (
    starpu_data_handle_t * handle,
    int home_node,
    uintptr_t ptr,
    uint32_t nx,
    size_t elemsize )
```

Register the `nx` `elemsize`-byte elements pointed to by `ptr` and initialize `handle` to represent it.

Here an example of how to use the function.

```
float vector[NX];
starpu_data_handle_t vector_handle;
starpu_vector_data_register(&vector_handle, STARPU_MAIN_RAM, (
    uintptr_t)vector, NX, sizeof(vector[0]));
```

28.9.5.5 `starpu_vector_ptr_register()`

```
void starpu_vector_ptr_register (
    starpu_data_handle_t handle,
    unsigned node,
    uintptr_t ptr,
    uintptr_t dev_handle,
    size_t offset )
```

Register into the `handle` that to store data on node `node` it should use the buffer located at `ptr`, or device handle `dev_handle` and offset `offset` (for OpenGL, notably)

28.9.5.6 `starpu_matrix_data_register()`

```
void starpu_matrix_data_register (
    starpu_data_handle_t * handle,
    int home_node,
    uintptr_t ptr,
    uint32_t ld,
    uint32_t nx,
    uint32_t ny,
    size_t elemsize )
```

Register the $n_x \times n_y$ 2D matrix of `elemsize`-byte elements pointed by `ptr` and initialize `handle` to represent it. `ld` specifies the number of elements between rows. a value greater than `nx` adds padding, which can be useful for alignment purposes.

Here an example of how to use the function.

```
float *matrix;
starpu_data_handle_t matrix_handle;
matrix = (float*)malloc(width * height * sizeof(float));
starpu_matrix_data_register(&matrix_handle, STARPU_MAIN_RAM, (
    uintptr_t)matrix, width, width, height, sizeof(float));
```

28.9.5.7 `starpu_matrix_ptr_register()`

```
void starpu_matrix_ptr_register (
    starpu_data_handle_t handle,
    unsigned node,
    uintptr_t ptr,
    uintptr_t dev_handle,
    size_t offset,
    uint32_t ld )
```

Register into the `handle` that to store data on node `node` it should use the buffer located at `ptr`, or device handle `dev_handle` and offset `offset` (for OpenGL, notably), with `ld` elements between rows.

28.9.5.8 `starpu_block_data_register()`

```
void starpu_block_data_register (
    starpu_data_handle_t * handle,
    int home_node,
    uintptr_t ptr,
    uint32_t ldy,
    uint32_t ldz,
    uint32_t nx,
    uint32_t ny,
    uint32_t nz,
    size_t elemsize )
```

Register the $n_x \times n_y \times n_z$ 3D matrix of `elemsize` byte elements pointed by `ptr` and initialize `handle` to represent it. Again, `ldy` and `ldz` specify the number of elements between rows and between z planes.

Here an example of how to use the function.

```
float *block;
starpu_data_handle_t block_handle;
block = (float*)malloc(nx*ny*nz*sizeof(float));
starpu_block_data_register(&block_handle, STARPU_MAIN_RAM, (
    uintptr_t)block, nx, nx*ny, nx, ny, nz, sizeof(float));
```

28.9.5.9 `starpu_block_ptr_register()`

```
void starpu_block_ptr_register (
    starpu_data_handle_t handle,
    unsigned node,
    uintptr_t ptr,
    uintptr_t dev_handle,
    size_t offset,
    uint32_t ldy,
    uint32_t ldz )
```

Register into the `handle` that to store data on `node` it should use the buffer located at `ptr`, or device handle `dev_handle` and offset `offset` (for OpenCL, notably), with `ldy` elements between rows and `ldz` elements between z planes.

28.9.5.10 `starpu_bcsr_data_register()`

```
void starpu_bcsr_data_register (
    starpu_data_handle_t * handle,
    int home_node,
    uint32_t nnz,
    uint32_t nrows,
    uintptr_t nzval,
    uint32_t * colind,
    uint32_t * rowptr,
    uint32_t firstentry,
    uint32_t r,
    uint32_t c,
    size_t elemsize )
```

This variant of `starpu_data_register()` uses the BCSR (Blocked Compressed Sparse Row Representation) sparse matrix interface. Register the sparse matrix made of `nnz` non-zero blocks of elements of size `elemsize` stored in `nzval` and initializes `handle` to represent it. Blocks have size `r * c`. `nrows` is the number of rows (in terms of blocks), `colind` is an array of `nnz` elements, `colind[i]` is the block-column index for block `i` in `nzval`, `rowptr` is an array of `nrows+1` elements, `rowptr[i]` is the block-index (in `nzval`) of the first block of row `i`. By convention, `rowptr[nrows]` is the number of blocks, this allows an easier access of the matrix's elements for the kernels. `firstentry` is the index of the first entry of the given arrays (usually 0 or 1).

Here an example of how to use the function.

```
/*
 * We use the following matrix:
 *
 * +-----+
 * | 0  1  0  0 |
 * | 2  3  0  0 |
 * | 4  5  8  9 |
 * | 6  7 10 11 |
 * +-----+
 *
 * nzval = [0, 1, 2, 3] ++ [4, 5, 6, 7] ++ [8, 9, 10, 11]
 * colind = [0, 0, 1]
 * rowptr = [0, 1, 3]
 * r = c = 2
 */

/* Size of the blocks */
int R = 2;
int C = 2;

int NROWS = 2;
int NNZ_BLOCKS = 3; /* out of 4 */
int NZVAL_SIZE = (R*C*NNZ_BLOCKS);

int nzval[NZVAL_SIZE] =
{
    0, 1, 2, 3, /* First block */
    4, 5, 6, 7, /* Second block */
    8, 9, 10, 11 /* Third block */
};
uint32_t colind[NNZ_BLOCKS] =
{
    0, /* block-column index for first block in nzval */
    0, /* block-column index for second block in nzval */
    1  /* block-column index for third block in nzval */
};
uint32_t rowptr[NROWS+1] =
{
    0, /* block-index in nzval of the first block of the first row. */
    1, /* block-index in nzval of the first block of the second row. */
    NNZ_BLOCKS /* number of blocks, to allow an easier element's access for the kernels */
};

starpu_data_handle_t bcsr_handle;
starpu_bcsr_data_register(&bcsr_handle,
    STARPU_MAIN_RAM,
    NNZ_BLOCKS,
    NROWS,
    (uintptr_t) nzval,
    colind,
    rowptr,
    0, /* firstentry */
    R,
    C,
    sizeof(nzval[0]));
```

28.9.5.11 starpu_csr_data_register()

```
void starpu_csr_data_register (
    starpu_data_handle_t * handle,
    int home_node,
```

```

uint32_t nnz,
uint32_t nrow,
uintptr_t nzval,
uint32_t * colind,
uint32_t * rowptr,
uint32_t firstentry,
size_t elemsize )

```

This variant of [starpu_data_register\(\)](#) uses the CSR (Compressed Sparse Row Representation) sparse matrix interface. TODO

28.9.5.12 [starpu_coo_data_register\(\)](#)

```

void starpu_coo_data_register (
    starpu_data_handle_t * handleptr,
    int home_node,
    uint32_t nx,
    uint32_t ny,
    uint32_t n_values,
    uint32_t * columns,
    uint32_t * rows,
    uintptr_t values,
    size_t elemsize )

```

Register the $n_x \times n_y$ 2D matrix given in the COO format, using the `columns`, `rows`, `values` arrays, which must have `n_values` elements of size `elemsize`. Initialize `handleptr`.

28.9.5.13 [starpu_data_get_interface_on_node\(\)](#)

```

void * starpu_data_get_interface_on_node (
    starpu_data_handle_t handle,
    unsigned memory_node )

```

Return the interface associated with `handle` on `memory_node`.

28.9.5.14 [starpu_data_handle_to_pointer\(\)](#)

```

void * starpu_data_handle_to_pointer (
    starpu_data_handle_t handle,
    unsigned node )

```

Return the pointer associated with `handle` on node `node` or NULL if `handle`'s interface does not support this operation or data for this `handle` is not allocated on that `node`.

28.9.5.15 [starpu_data_pointer_is_inside\(\)](#)

```

int starpu_data_pointer_is_inside (
    starpu_data_handle_t handle,
    unsigned node,
    void * pointer )

```

Return whether the given `pointer` is within the data for `handle` on node `node` (1) or not (0). If the handle interface does not support this operation, and thus the result is unknown, -1 is returned.

28.9.5.16 starpu_data_get_local_ptr()

```
void * starpu_data_get_local_ptr (
    starpu_data_handle_t handle )
```

Return the local pointer associated with `handle` or NULL if `handle`'s interface does not have data allocated locally

28.9.5.17 starpu_data_get_interface_id()

```
enum starpu_data_interface_id starpu_data_get_interface_id (
    starpu_data_handle_t handle )
```

Return the unique identifier of the interface associated with the given `handle`.

28.9.5.18 starpu_data_get_size()

```
size_t starpu_data_get_size (
    starpu_data_handle_t handle )
```

Return the size of the data associated with `handle`.

28.9.5.19 starpu_data_pack()

```
int starpu_data_pack (
    starpu_data_handle_t handle,
    void ** ptr,
    starpu_ssize_t * count )
```

Execute the packing operation of the interface of the data registered at `handle` (see [starpu_data_interface_ops](#)). This packing operation must allocate a buffer large enough at `ptr` and copy into the newly allocated buffer the data associated to `handle`. `count` will be set to the size of the allocated buffer. If `ptr` is NULL, the function should not copy the data in the buffer but just set `count` to the size of the buffer which would have been allocated. The special value -1 indicates the size is yet unknown.

28.9.5.20 starpu_data_unpack()

```
int starpu_data_unpack (
    starpu_data_handle_t handle,
    void * ptr,
    size_t count )
```

Unpack in `handle` the data located at `ptr` of size `count` as described by the interface of the data. The interface registered at `handle` must define a unpacking operation (see [starpu_data_interface_ops](#)). The memory at the address `ptr` is freed after calling the data unpacking operation.

28.9.5.21 starpu_variable_get_elemsize()

```
size_t starpu_variable_get_elemsize (
    starpu_data_handle_t handle )
```

Return the size of the variable designated by `handle`.

28.9.5.22 starpu_variable_get_local_ptr()

```
uintptr_t starpu_variable_get_local_ptr (
    starpu_data_handle_t handle )
```

Return a pointer to the variable designated by `handle`.

28.9.5.23 starpu_vector_get_nx()

```
uint32_t starpu_vector_get_nx (
    starpu_data_handle_t handle )
```

Return the number of elements registered into the array designated by `handle`.

28.9.5.24 starpu_vector_get_elemsize()

```
size_t starpu_vector_get_elemsize (
    starpu_data_handle_t handle )
```

Return the size of each element of the array designated by `handle`.

28.9.5.25 starpu_vector_get_local_ptr()

```
uintptr_t starpu_vector_get_local_ptr (
    starpu_data_handle_t handle )
```

Return the local pointer associated with `handle`.

28.9.5.26 starpu_matrix_get_nx()

```
uint32_t starpu_matrix_get_nx (
    starpu_data_handle_t handle )
```

Return the number of elements on the x-axis of the matrix designated by `handle`.

28.9.5.27 starpu_matrix_get_ny()

```
uint32_t starpu_matrix_get_ny (
    starpu_data_handle_t handle )
```

Return the number of elements on the y-axis of the matrix designated by `handle`.

28.9.5.28 starpu_matrix_get_local_ld()

```
uint32_t starpu_matrix_get_local_ld (
    starpu_data_handle_t handle )
```

Return the number of elements between each row of the matrix designated by `handle`. Maybe be equal to `nx` when there is no padding.

28.9.5.29 starpu_matrix_get_local_ptr()

```
uintptr_t starpu_matrix_get_local_ptr (
    starpu_data_handle_t handle )
```

Return the local pointer associated with `handle`.

28.9.5.30 starpu_matrix_get_elemsize()

```
size_t starpu_matrix_get_elemsize (
    starpu_data_handle_t handle )
```

Return the size of the elements registered into the matrix designated by `handle`.

28.9.5.31 starpu_block_get_nx()

```
uint32_t starpu_block_get_nx (
    starpu_data_handle_t handle )
```

Return the number of elements on the x-axis of the block designated by `handle`.

28.9.5.32 starpu_block_get_ny()

```
uint32_t starpu_block_get_ny (
    starpu_data_handle_t handle )
```

Return the number of elements on the y-axis of the block designated by `handle`.

28.9.5.33 starpu_block_get_nz()

```
uint32_t starpu_block_get_nz (
    starpu_data_handle_t handle )
```

Return the number of elements on the z-axis of the block designated by `handle`.

28.9.5.34 starpu_block_get_local_ldy()

```
uint32_t starpu_block_get_local_ldy (
    starpu_data_handle_t handle )
```

Return the number of elements between each row of the block designated by `handle`, in the format of the current memory node.

28.9.5.35 starpu_block_get_local_ldz()

```
uint32_t starpu_block_get_local_ldz (
    starpu_data_handle_t handle )
```

Return the number of elements between each z plane of the block designated by `handle`, in the format of the current memory node.

28.9.5.36 starpu_block_get_local_ptr()

```
uintptr_t starpu_block_get_local_ptr (
    starpu_data_handle_t handle )
```

Return the local pointer associated with `handle`.

28.9.5.37 starpu_block_get_elemsize()

```
size_t starpu_block_get_elemsize (
    starpu_data_handle_t handle )
```

Return the size of the elements of the block designated by `handle`.

28.9.5.38 starpu_bcsr_get_nnz()

```
uint32_t starpu_bcsr_get_nnz (
    starpu_data_handle_t handle )
```

Return the number of non-zero elements in the matrix designated by `handle`.

28.9.5.39 starpu_bcsr_get_nrow()

```
uint32_t starpu_bcsr_get_nrow (
    starpu_data_handle_t handle )
```

Return the number of rows (in terms of blocks of size $r \times c$) in the matrix designated by `handle`.

28.9.5.40 starpu_bcsr_get_firstentry()

```
uint32_t starpu_bcsr_get_firstentry (
    starpu_data_handle_t handle )
```

Return the index at which all arrays (the column indexes, the row pointers...) of the matrix designated by `handle`.

28.9.5.41 starpu_bcsr_get_local_nzval()

```
uintptr_t starpu_bcsr_get_local_nzval (
    starpu_data_handle_t handle )
```

Return a pointer to the non-zero values of the matrix designated by `handle`.

28.9.5.42 starpu_bcsr_get_local_colind()

```
uint32_t * starpu_bcsr_get_local_colind (
    starpu_data_handle_t handle )
```

Return a pointer to the column index, which holds the positions of the non-zero entries in the matrix designated by `handle`.

28.9.5.43 starpu_bcsr_get_local_rowptr()

```
uint32_t * starpu_bcsr_get_local_rowptr (
    starpu_data_handle_t handle )
```

Return the row pointer array of the matrix designated by `handle`.

28.9.5.44 starpu_bcsr_get_r()

```
uint32_t starpu_bcsr_get_r (
    starpu_data_handle_t handle )
```

Return the number of rows in a block.

28.9.5.45 starpu_bcsr_get_c()

```
uint32_t starpu_bcsr_get_c (
    starpu_data_handle_t handle )
```

Return the number of columns in a block.

28.9.5.46 starpu_bcsr_get_elemsize()

```
size_t starpu_bcsr_get_elemsize (
    starpu_data_handle_t handle )
```

Return the size of the elements in the matrix designated by `handle`.

28.9.5.47 starpu_csr_get_nnz()

```
uint32_t starpu_csr_get_nnz (
    starpu_data_handle_t handle )
```

Return the number of non-zero values in the matrix designated by `handle`.

28.9.5.48 starpu_csr_get_nrow()

```
uint32_t starpu_csr_get_nrow (
    starpu_data_handle_t handle )
```

Return the size of the row pointer array of the matrix designated by `handle`.

28.9.5.49 starpu_csr_get_firstentry()

```
uint32_t starpu_csr_get_firstentry (
    starpu_data_handle_t handle )
```

Return the index at which all arrays (the column indexes, the row pointers...) of the matrix designated by `handle`.

28.9.5.50 starpu_csr_get_local_nzval()

```
uintptr_t starpu_csr_get_local_nzval (
    starpu_data_handle_t handle )
```

Return a local pointer to the non-zero values of the matrix designated by `handle`.

28.9.5.51 starpu_csr_get_local_colind()

```
uint32_t * starpu_csr_get_local_colind (
    starpu_data_handle_t handle )
```

Return a local pointer to the column index of the matrix designated by `handle`.

28.9.5.52 starpu_csr_get_local_rowptr()

```
uint32_t * starpu_csr_get_local_rowptr (
    starpu_data_handle_t handle )
```

Return a local pointer to the row pointer array of the matrix designated by `handle`.

28.9.5.53 starpu_csr_get_elemsize()

```
size_t starpu_csr_get_elemsize (
    starpu_data_handle_t handle )
```

Return the size of the elements registered into the matrix designated by `handle`.

28.9.5.54 starpu_malloc_on_node_flags()

```
uintptr_t starpu_malloc_on_node_flags (
    unsigned dst_node,
    size_t size,
    int flags )
```

Allocate `size` bytes on node `dst_node` with the given allocation `flags`. This returns 0 if allocation failed, the allocation method should then return `-ENOMEM` as allocated size. Deallocation must be done with `starpu_free_on_node`.

28.9.5.55 starpu_free_on_node_flags()

```
void starpu_free_on_node_flags (
    unsigned dst_node,
    uintptr_t addr,
    size_t size,
    int flags )
```

Free `addr` of `size` bytes on node `dst_node` which was previously allocated with `starpu_malloc_on_node` with the given allocation `flags`.

28.9.5.56 starpu_malloc_on_node()

```
uintptr_t starpu_malloc_on_node (
    unsigned dst_node,
    size_t size )
```

Allocate `size` bytes on node `dst_node` with the default allocation flags. This returns 0 if allocation failed, the allocation method should then return `-ENOMEM` as allocated size. Deallocation must be done with `starpu_free_↵`
`on_node`.

28.9.5.57 starpu_free_on_node()

```
void starpu_free_on_node (
    unsigned dst_node,
    uintptr_t addr,
    size_t size )
```

Free `addr` of `size` bytes on node `dst_node` which was previously allocated with `starpu_malloc_on_node`.

28.9.5.58 starpu_malloc_on_node_set_default_flags()

```
void starpu_malloc_on_node_set_default_flags (
    unsigned node,
    int flags )
```

Define the default flags for allocations performed by `starpu_malloc_on_node()` and `starpu_free_on_node()`. The default is `STARPU_MALLOC_PINNED | STARPU_MALLOC_COUNT`.

28.9.5.59 starpu_interface_copy()

```
int starpu_interface_copy (
    uintptr_t src,
    size_t src_offset,
    unsigned src_node,
    uintptr_t dst,
    size_t dst_offset,
    unsigned dst_node,
    size_t size,
    void * async_data )
```

Copy `size` bytes from byte offset `src_offset` of `src` on `src_node` to byte offset `dst_offset` of `dst` on `dst_node`. This is to be used in the `any_to_any()` copy method, which is provided with the `async_data` to be passed to `starpu_interface_copy()`. this returns `-EAGAIN` if the transfer is still ongoing, or 0 if the transfer is already completed.

28.9.5.60 starpu_hash_crc32c_be_n()

```
uint32_t starpu_hash_crc32c_be_n (
    const void * input,
    size_t n,
    uint32_t inputcrc )
```

Compute the CRC of a byte buffer seeded by the `inputcrc` *current state*. The return value should be considered as the new *current state* for future CRC computation. This is used for computing data size footprint.

28.9.5.61 starpu_hash_crc32c_be()

```
uint32_t starpu_hash_crc32c_be (
    uint32_t input,
    uint32_t inputcrc )
```

Compute the CRC of a 32bit number seeded by the `inputcrc` *current state*. The return value should be considered as the new *current state* for future CRC computation. This is used for computing data size footprint.

28.9.5.62 starpu_hash_crc32c_string()

```
uint32_t starpu_hash_crc32c_string (
    const char * str,
    uint32_t inputcrc )
```

Compute the CRC of a string seeded by the `inputcrc` *current state*. The return value should be considered as the new *current state* for future CRC computation. This is used for computing data size footprint.

28.9.5.63 starpu_data_interface_get_next_id()

```
int starpu_data_interface_get_next_id (
    void )
```

Return the next available id for a newly created data interface ([Defining A New Data Interface](#)).

28.10 Data Partition

Data Structures

- struct [starpu_data_filter](#)

Basic API

- void [starpu_data_partition](#) ([starpu_data_handle_t](#) initial_handle, struct [starpu_data_filter](#) *f)
- void [starpu_data_unpartition](#) ([starpu_data_handle_t](#) root_data, unsigned gathering_node)
- int [starpu_data_get_nb_children](#) ([starpu_data_handle_t](#) handle)
- [starpu_data_handle_t](#) [starpu_data_get_child](#) ([starpu_data_handle_t](#) handle, unsigned i)
- [starpu_data_handle_t](#) [starpu_data_get_sub_data](#) ([starpu_data_handle_t](#) root_data, unsigned depth,...)
- [starpu_data_handle_t](#) [starpu_data_vget_sub_data](#) ([starpu_data_handle_t](#) root_data, unsigned depth, va_list pa)
- void [starpu_data_map_filters](#) ([starpu_data_handle_t](#) root_data, unsigned nfilters,...)
- void [starpu_data_vmap_filters](#) ([starpu_data_handle_t](#) root_data, unsigned nfilters, va_list pa)

Asynchronous API

- void [starpu_data_partition_plan](#) ([starpu_data_handle_t](#) initial_handle, struct [starpu_data_filter](#) *f, [starpu_data_handle_t](#) *children)
- void [starpu_data_partition_submit](#) ([starpu_data_handle_t](#) initial_handle, unsigned nparts, [starpu_data_handle_t](#) *children)
- void [starpu_data_partition_readonly_submit](#) ([starpu_data_handle_t](#) initial_handle, unsigned nparts, [starpu_data_handle_t](#) *children)
- void [starpu_data_partition_readwrite_upgrade_submit](#) ([starpu_data_handle_t](#) initial_handle, unsigned nparts, [starpu_data_handle_t](#) *children)
- void [starpu_data_unpartition_submit](#) ([starpu_data_handle_t](#) initial_handle, unsigned nparts, [starpu_data_handle_t](#) *children, int gathering_node)
- void [starpu_data_unpartition_readonly_submit](#) ([starpu_data_handle_t](#) initial_handle, unsigned nparts, [starpu_data_handle_t](#) *children, int gathering_node)
- void [starpu_data_partition_clean](#) ([starpu_data_handle_t](#) root_data, unsigned nparts, [starpu_data_handle_t](#) *children)

Predefined Vector Filter Functions

This section gives a partial list of the predefined partitioning functions for vector data. Examples on how to use them are shown in [Partitioning Data](#). The complete list can be found in the file [starpu_data_filters.h](#).

- void [starpu_vector_filter_block](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_vector_filter_block_shadow](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_vector_filter_list_long](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_vector_filter_list](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_vector_filter_divide_in_2](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)

Predefined Matrix Filter Functions

This section gives a partial list of the predefined partitioning functions for matrix data. Examples on how to use them are shown in [Partitioning Data](#). The complete list can be found in the file [starpu_data_filters.h](#).

- void [starpu_matrix_filter_block](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_matrix_filter_block_shadow](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_matrix_filter_vertical_block](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_matrix_filter_vertical_block_shadow](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)

Predefined Block Filter Functions

This section gives a partial list of the predefined partitioning functions for block data. Examples on how to use them are shown in [Partitioning Data](#). The complete list can be found in the file [starpu_data_filters.h](#). A usage example is available in `examples/filters/shadow3d.c`

- void [starpu_block_filter_block](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_block_filter_block_shadow](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_block_filter_vertical_block](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_block_filter_vertical_block_shadow](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_block_filter_depth_block](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_block_filter_depth_block_shadow](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)

Predefined BCSR Filter Functions

This section gives a partial list of the predefined partitioning functions for BCSR data. Examples on how to use them are shown in [Partitioning Data](#). The complete list can be found in the file [starpu_data_filters.h](#).

- void [starpu_bcsr_filter_canonical_block](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_csr_filter_vertical_block](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)

28.10.1 Detailed Description

28.10.2 Data Structure Documentation

28.10.2.1 struct [starpu_data_filter](#)

The filter structure describes a data partitioning operation, to be given to the [starpu_data_partition\(\)](#) function.

Data Fields

- void(* [filter_func](#))(void *father_interface, void *child_interface, struct [starpu_data_filter](#) *, unsigned id, unsigned nparts)
- unsigned [nchildren](#)
- unsigned(* [get_nchildren](#))(struct [starpu_data_filter](#) *, [starpu_data_handle_t](#) initial_handle)
- struct [starpu_data_interface_ops](#) *(* [get_child_ops](#))(struct [starpu_data_filter](#) *, unsigned id)
- unsigned [filter_arg](#)
- void * [filter_arg_ptr](#)

28.10.2.1.1 Field Documentation

28.10.2.1.1.1 filter_func

```
void(* starpu_data_filter::filter_func)(void *father_interface, void *child_interface, struct
starpu_data_filter *filter, unsigned i, unsigned nparts)
```

Fill the `child_interface` structure with interface information for the `i`-th child of the parent `father_↵` interface (among `nparts`). The `filter` structure is provided, allowing to inspect the `starpu_data_filter_↵` `::filter_arg` and `starpu_data_filter::filter_arg_ptr` parameters.

The details of what needs to be filled in `child_interface` vary according to the data interface, but generally speaking:

- `id` is usually just copied over from the father, when the sub data has the same structure as the father, e.g. a subvector is a vector, a submatrix is a matrix, etc. This is however not the case for instance when dividing a BCSR matrix into its dense blocks, which then are matrices.
- `nx`, `ny` and alike are usually divided by the number of subdata, depending how the subdivision is done (e.g. `nx` division vs `ny` division for vertical matrix division vs horizontal matrix division).
- `ld` for matrix interfaces are usually just copied over: the leading dimension (`ld`) usually does not change.
- `elemsize` is usually just copied over.
- `ptr`, the pointer to the data, has to be computed according to `i` and the father's `ptr`, so as to point to the start of the sub data. This should however be done only if the father has `ptr` different from NULL: in the OpenCL case notably, the `dev_handle` and `offset` fields are used instead.
- `dev_handle` should be just copied over from the parent.
- `offset` has to be computed according to `i` and the father's `offset`, so as to provide the offset of the start of the sub data. This is notably used for the OpenCL case.

28.10.2.1.1.2 nchildren

```
unsigned starpu_data_filter::nchildren
```

This is the number of parts to partition the data into.

28.10.2.1.1.3 get_nchildren

```
unsigned(* starpu_data_filter::get_nchildren)(struct starpu_data_filter *, starpu_data_handle_↵
_t initial_handle)
```

This returns the number of children. This can be used instead of `nchildren` when the number of children depends on the actual data (e.g. the number of blocks in a sparse matrix).

28.10.2.1.1.4 get_child_ops

```
struct starpu_data_interface_ops *(* starpu_data_filter::get_child_ops)(struct starpu_data_↵
filter *, unsigned id)
```

In case the resulting children use a different data interface, this function returns which interface is used by child number `id`.

28.10.2.1.1.5 filter_arg

```
unsigned starpu_data_filter::filter_arg
```

Additional parameter for the filter function

28.10.2.1.1.6 filter_arg_ptr

```
void * starpu_data_filter::filter_arg_ptr
```

Additional pointer parameter for the filter function, such as the sizes of the different parts.

28.10.3 Function Documentation

28.10.3.1 starpu_data_partition()

```
void starpu_data_partition (
    starpu_data_handle_t initial_handle,
    struct starpu_data_filter * f )
```

This requests partitioning one StarPU data `initial_handle` into several subdata according to the filter `f`.

Here an example of how to use the function.

```
struct starpu_data_filter f = {
    .filter_func = starpu_matrix_filter_block,
    .nchildren = nslicesx
};
starpu_data_partition(A_handle, &f);
```

28.10.3.2 starpu_data_unpartition()

```
void starpu_data_unpartition (
    starpu_data_handle_t root_data,
    unsigned gathering_node )
```

This unapplies one filter, thus unpartitioning the data. The pieces of data are collected back into one big piece in the `gathering_node` (usually `STARPU_MAIN_RAM`). Tasks working on the partitioned data must be already finished when calling `starpu_data_unpartition()`.

Here an example of how to use the function.

```
starpu_data_unpartition(A_handle, STARPU_MAIN_RAM);
```

28.10.3.3 starpu_data_get_nb_children()

```
int starpu_data_get_nb_children (
    starpu_data_handle_t handle )
```

This function returns the number of children.

28.10.3.4 starpu_data_get_child()

```
starpu_data_handle_t starpu_data_get_child (
    starpu_data_handle_t handle,
    unsigned i )
```

Return the *i*th child of the given *handle*, which must have been partitionned beforehand.

28.10.3.5 starpu_data_get_sub_data()

```
starpu_data_handle_t starpu_data_get_sub_data (
    starpu_data_handle_t root_data,
    unsigned depth,
    ... )
```

After partitioning a StarPU data by applying a filter, [starpu_data_get_sub_data\(\)](#) can be used to get handles for each of the data portions. *root_data* is the parent data that was partitioned. *depth* is the number of filters to traverse (in case several filters have been applied, to e.g. partition in row blocks, and then in column blocks), and the subsequent parameters are the indexes. The function returns a handle to the subdata.

Here an example of how to use the function.

```
h = starpu_data_get_sub_data(A_handle, 1, taskx);
```

28.10.3.6 starpu_data_vget_sub_data()

```
starpu_data_handle_t starpu_data_vget_sub_data (
    starpu_data_handle_t root_data,
    unsigned depth,
    va_list pa )
```

This function is similar to [starpu_data_get_sub_data\(\)](#) but uses a *va_list* for the parameter list.

28.10.3.7 starpu_data_map_filters()

```
void starpu_data_map_filters (
    starpu_data_handle_t root_data,
    unsigned nfilters,
    ... )
```

Applies *nfilters* filters to the handle designated by *root_handle* recursively. *nfilters* pointers to variables of the type [starpu_data_filter](#) should be given.

28.10.3.8 `starpu_data_vmap_filters()`

```
void starpu_data_vmap_filters (
    starpu_data_handle_t root_data,
    unsigned nfilters,
    va_list pa )
```

Applies `nfilters` filters to the handle designated by `root_handle` recursively. It uses a `va_list` of pointers to variables of the type `starpu_data_filter`.

28.10.3.9 `starpu_data_partition_plan()`

```
void starpu_data_partition_plan (
    starpu_data_handle_t initial_handle,
    struct starpu_data_filter * f,
    starpu_data_handle_t * children )
```

This plans for partitioning one StarPU data handle `initial_handle` into several subdata according to the filter `f`. The handles are returned into the `children` array, which has to be the same size as the number of parts described in `f`. These handles are not immediately usable, `starpu_data_partition_submit` has to be called to submit the actual partitioning.

Here is an example of how to use the function:

```
starpu_data_handle_t children[nslicesx];
struct starpu_data_filter f = {
    .filter_func = starpu_matrix_filter_block,
    .nchildren = nslicesx
};
starpu_data_partition_plan(A_handle, &f, children);
```

28.10.3.10 `starpu_data_partition_submit()`

```
void starpu_data_partition_submit (
    starpu_data_handle_t initial_handle,
    unsigned nparts,
    starpu_data_handle_t * children )
```

This submits the actual partitioning of `initial_handle` into the `nparts` `children` handles. This call is asynchronous, it only submits that the partitioning should be done, so that the `children` handles can now be used to submit tasks, and `initial_handle` can not be used to submit tasks any more (to guarantee coherency).

For instance,

```
starpu_data_partition_submit(A_handle, nslicesx, children);
```

28.10.3.11 starpu_data_partition_readonly_submit()

```
void starpu_data_partition_readonly_submit (
    starpu_data_handle_t initial_handle,
    unsigned nparts,
    starpu_data_handle_t * children )
```

This is the same as `starpu_data_partition_submit`, but does not invalidate `initial_handle`. This allows to continue using it, but the application has to be careful not to write to `initial_handle` or `children` handles, only read from them, since the coherency is otherwise not guaranteed. This thus allows to submit various tasks which concurrently read from various partitions of the data.

When the application wants to write to `initial_handle` again, it should call `starpu_data_unpartition_submit`, which will properly add dependencies between the reads on the `children` and the writes to be submitted.

If instead the application wants to write to `children` handles, it should call `starpu_data_partition_readwrite_upgrade_submit`, which will properly add dependencies between the reads on the `initial_handle` and the writes to be submitted.

28.10.3.12 starpu_data_partition_readwrite_upgrade_submit()

```
void starpu_data_partition_readwrite_upgrade_submit (
    starpu_data_handle_t initial_handle,
    unsigned nparts,
    starpu_data_handle_t * children )
```

This assumes that a partitioning of `initial_handle` has already been submitted in readonly mode through `starpu_data_partition_readonly_submit`, and will upgrade that partitioning into read-write mode for the `children`, by invalidating `initial_handle`, and adding the necessary dependencies.

28.10.3.13 starpu_data_unpartition_submit()

```
void starpu_data_unpartition_submit (
    starpu_data_handle_t initial_handle,
    unsigned nparts,
    starpu_data_handle_t * children,
    int gathering_node )
```

This assumes that `initial_handle` is partitioned into `children`, and submits an unpartitioning of it, i.e. submitting a gathering of the pieces on the requested `gathering_node` memory node, and submitting an invalidation of the children.

`gathering_node` can be set to -1 to let the runtime decide which memory node should be used to gather the pieces.

This call is asynchronous, it only submits that the unpartitioning should be done, so that the `children` handles should not be used to submit tasks any more, and `initial_handle` can now be used again to submit tasks.

28.10.3.14 starpu_data_unpartition_readonly_submit()

```
void starpu_data_unpartition_readonly_submit (
    starpu_data_handle_t initial_handle,
    unsigned nparts,
    starpu_data_handle_t * children,
    int gathering_node )
```

This assumes that `initial_handle` is partitioned into `children`, and submits just a readonly unpartitioning of it, i.e. submitting a gathering of the pieces on the requested `gathering_node` memory node. It does not invalidate the children. This brings `initial_handle` and `children` handles to the same state as obtained with `starpu_data_partition_readonly_submit`.

`gathering_node` can be set to -1 to let the runtime decide which memory node should be used to gather the pieces.

28.10.3.15 starpu_data_partition_clean()

```
void starpu_data_partition_clean (
    starpu_data_handle_t root_data,
    unsigned nparts,
    starpu_data_handle_t * children )
```

This should be used to clear the partition planning established between `root_data` and `children` with `starpu_data_partition_plan`. This will notably submit an unregister all the `children`, which can thus not be used any more afterwards.

28.10.3.16 starpu_vector_filter_block()

```
void starpu_vector_filter_block (
    void * father_interface,
    void * child_interface,
    struct starpu_data_filter * f,
    unsigned id,
    unsigned nparts )
```

Return in `child_interface` the `id` th element of the vector represented by `father_interface` once partitioned in `nparts` chunks of equal size.

28.10.3.17 starpu_vector_filter_block_shadow()

```
void starpu_vector_filter_block_shadow (
    void * father_interface,
    void * child_interface,
    struct starpu_data_filter * f,
    unsigned id,
    unsigned nparts )
```

Return in `child_interface` the `id` th element of the vector represented by `father_interface` once partitioned in `nparts` chunks of equal size with a shadow border `filter_arg_ptr`, thus getting a vector of size $(n-2*\text{shadow})/\text{nparts}+2*\text{shadow}$. The `filter_arg_ptr` field of `f` must be the shadow size casted into `void*`. **IMPORTANT:** This can only be used for read-only access, as no coherency is enforced for the shadowed parts. An usage example is available in `examples/filters/shadow.c`

28.10.3.18 starpu_vector_filter_list_long()

```
void starpu_vector_filter_list_long (
    void * father_interface,
    void * child_interface,
    struct starpu_data_filter * f,
    unsigned id,
    unsigned nparts )
```

Return in *child_interface* the *id* th element of the vector represented by *father_interface* once partitioned into *nparts* chunks according to the *filter_arg_ptr* field of *f*. The *filter_arg_ptr* field must point to an array of *nparts* long elements, each of which specifies the number of elements in each chunk of the partition.

28.10.3.19 starpu_vector_filter_list()

```
void starpu_vector_filter_list (
    void * father_interface,
    void * child_interface,
    struct starpu_data_filter * f,
    unsigned id,
    unsigned nparts )
```

Return in *child_interface* the *id* th element of the vector represented by *father_interface* once partitioned into *nparts* chunks according to the *filter_arg_ptr* field of *f*. The *filter_arg_ptr* field must point to an array of *nparts* `uint32_t` elements, each of which specifies the number of elements in each chunk of the partition.

28.10.3.20 starpu_vector_filter_divide_in_2()

```
void starpu_vector_filter_divide_in_2 (
    void * father_interface,
    void * child_interface,
    struct starpu_data_filter * f,
    unsigned id,
    unsigned nparts )
```

Return in *child_interface* the *id* th element of the vector represented by *father_interface* once partitioned in 2 chunks of equal size, ignoring *nparts*. Thus, *id* must be 0 or 1.

28.10.3.21 starpu_matrix_filter_block()

```
void starpu_matrix_filter_block (
    void * father_interface,
    void * child_interface,
    struct starpu_data_filter * f,
    unsigned id,
    unsigned nparts )
```

This partitions a dense Matrix along the x dimension, thus getting (x/*nparts*,y) matrices. If *nparts* does not divide x, the last submatrix contains the remainder.

28.10.3.22 starpu_matrix_filter_block_shadow()

```
void starpu_matrix_filter_block_shadow (
    void * father_interface,
    void * child_interface,
    struct starpu_data_filter * f,
    unsigned id,
    unsigned nparts )
```

This partitions a dense Matrix along the x dimension, with a shadow border *filter_arg_ptr*, thus getting $((x-2*shadow)/nparts + 2*shadow, y)$ matrices. If *nparts* does not divide $x-2*shadow$, the last submatrix contains the remainder. **IMPORTANT:** This can only be used for read-only access, as no coherency is enforced for the shadowed parts. A usage example is available in `examples/filters/shadow2d.c`

28.10.3.23 starpu_matrix_filter_vertical_block()

```
void starpu_matrix_filter_vertical_block (
    void * father_interface,
    void * child_interface,
    struct starpu_data_filter * f,
    unsigned id,
    unsigned nparts )
```

This partitions a dense Matrix along the y dimension, thus getting $(x, y/nparts)$ matrices. If *nparts* does not divide *y*, the last submatrix contains the remainder.

28.10.3.24 starpu_matrix_filter_vertical_block_shadow()

```
void starpu_matrix_filter_vertical_block_shadow (
    void * father_interface,
    void * child_interface,
    struct starpu_data_filter * f,
    unsigned id,
    unsigned nparts )
```

This partitions a dense Matrix along the y dimension, with a shadow border *filter_arg_ptr*, thus getting $(x, (y-2*shadow)/nparts + 2*shadow)$ matrices. If *nparts* does not divide $y-2*shadow$, the last submatrix contains the remainder. **IMPORTANT:** This can only be used for read-only access, as no coherency is enforced for the shadowed parts. A usage example is available in `examples/filters/shadow2d.c`

28.10.3.25 starpu_block_filter_block()

```
void starpu_block_filter_block (
    void * father_interface,
    void * child_interface,
    struct starpu_data_filter * f,
    unsigned id,
    unsigned nparts )
```

This partitions a block along the X dimension, thus getting $(x/nparts, y, z)$ 3D matrices. If *nparts* does not divide *x*, the last submatrix contains the remainder.

28.10.3.26 starpu_block_filter_block_shadow()

```
void starpu_block_filter_block_shadow (
    void * father_interface,
    void * child_interface,
    struct starpu_data_filter * f,
    unsigned id,
    unsigned nparts )
```

This partitions a block along the X dimension, with a shadow border *filter_arg_ptr*, thus getting $((x-2*shadow)/nparts + 2*shadow, y, z)$ blocks. If *nparts* does not divide *x*, the last submatrix contains the remainder. **IMPORTANT:** This can only be used for read-only access, as no coherency is enforced for the shadowed parts.

28.10.3.27 starpu_block_filter_vertical_block()

```
void starpu_block_filter_vertical_block (
    void * father_interface,
    void * child_interface,
    struct starpu_data_filter * f,
    unsigned id,
    unsigned nparts )
```

This partitions a block along the Y dimension, thus getting $(x, y/nparts, z)$ blocks. If *nparts* does not divide *y*, the last submatrix contains the remainder.

28.10.3.28 starpu_block_filter_vertical_block_shadow()

```
void starpu_block_filter_vertical_block_shadow (
    void * father_interface,
    void * child_interface,
    struct starpu_data_filter * f,
    unsigned id,
    unsigned nparts )
```

This partitions a block along the Y dimension, with a shadow border *filter_arg_ptr*, thus getting $(x, (y-2*shadow)/nparts + 2*shadow, z)$ 3D matrices. If *nparts* does not divide *y*, the last submatrix contains the remainder. **IMPORTANT:** This can only be used for read-only access, as no coherency is enforced for the shadowed parts.

28.10.3.29 starpu_block_filter_depth_block()

```
void starpu_block_filter_depth_block (
    void * father_interface,
    void * child_interface,
    struct starpu_data_filter * f,
    unsigned id,
    unsigned nparts )
```

This partitions a block along the Z dimension, thus getting $(x, y, z/nparts)$ blocks. If *nparts* does not divide *z*, the last submatrix contains the remainder.

28.10.3.30 starpu_block_filter_depth_block_shadow()

```
void starpu_block_filter_depth_block_shadow (
    void * father_interface,
    void * child_interface,
    struct starpu_data_filter * f,
    unsigned id,
    unsigned nparts )
```

This partitions a block along the Z dimension, with a shadow border *filter_arg_ptr*, thus getting (x,y,(z-2*shadow)/nparts +2*shadow) blocks. If *nparts* does not divide z, the last submatrix contains the remainder.

IMPORTANT: This can only be used for read-only access, as no coherency is enforced for the shadowed parts.

28.10.3.31 starpu_bcsr_filter_canonical_block()

```
void starpu_bcsr_filter_canonical_block (
    void * father_interface,
    void * child_interface,
    struct starpu_data_filter * f,
    unsigned id,
    unsigned nparts )
```

This partitions a block-sparse matrix into dense matrices.

28.10.3.32 starpu_csr_filter_vertical_block()

```
void starpu_csr_filter_vertical_block (
    void * father_interface,
    void * child_interface,
    struct starpu_data_filter * f,
    unsigned id,
    unsigned nparts )
```

This partitions a block-sparse matrix into vertical block-sparse matrices.

28.11 Out Of Core

Data Structures

- struct [starpu_disk_ops](#)

Macros

- `#define` [STARPU_DISK_SIZE_MIN](#)

Functions

- int [starpu_disk_register](#) (struct [starpu_disk_ops](#) *func, void *parameter, starpu_ssize_t size)
- void * [starpu_disk_open](#) (unsigned node, void *pos, size_t size)
- void [starpu_disk_close](#) (unsigned node, void *obj, size_t size)

Variables

- int [starpu_disk_swap_node](#)
- struct [starpu_disk_ops](#) [starpu_disk_stdio_ops](#)
- struct [starpu_disk_ops](#) [starpu_disk_unistd_ops](#)
- struct [starpu_disk_ops](#) [starpu_disk_unistd_o_direct_ops](#)
- struct [starpu_disk_ops](#) [starpu_disk_leveldb_ops](#)

28.11.1 Detailed Description

28.11.2 Data Structure Documentation

28.11.2.1 struct starpu_disk_ops

This is a set of functions to manipulate datas on disk.

Data Fields

- void [*\(* plug\)](#)(void *parameter, starpu_ssize_t size)
- void [*\(* unplug\)](#)(void *base)
- int [*\(* bandwidth\)](#)(unsigned node, void *base)
- void [*\(* alloc\)](#)(void *base, size_t size)
- void [*\(* free\)](#)(void *base, void *obj, size_t size)
- void [*\(* open\)](#)(void *base, void *pos, size_t size)
- void [*\(* close\)](#)(void *base, void *obj, size_t size)
- int [*\(* read\)](#)(void *base, void *obj, void *buf, off_t offset, size_t size)
- int [*\(* write\)](#)(void *base, void *obj, const void *buf, off_t offset, size_t size)
- int [*\(* full_read\)](#)(void *base, void *obj, void **ptr, size_t *size)
- int [*\(* full_write\)](#)(void *base, void *obj, void *ptr, size_t size)
- void [*\(* async_write\)](#)(void *base, void *obj, void *buf, off_t offset, size_t size)
- void [*\(* async_read\)](#)(void *base, void *obj, void *buf, off_t offset, size_t size)
- void [*\(* async_full_read\)](#)(void *base, void *obj, void **ptr, size_t *size)
- void [*\(* async_full_write\)](#)(void *base, void *obj, void *ptr, size_t size)
- void [*\(* copy\)](#)(void *base_src, void *obj_src, off_t offset_src, void *base_dst, void *obj_dst, off_t offset_dst, size_t size)
- void [*\(* wait_request\)](#)(void *async_channel)
- int [*\(* test_request\)](#)(void *async_channel)
- void [*\(* free_request\)](#)(void *async_channel)

28.11.2.1.1 Field Documentation

28.11.2.1.1.1 plug

```
void *(* starpu_disk_ops::plug)(void *parameters, size_t size)
```

Connect a disk memory at location `parameter` with size `size`, and return a base as `void*`, which will be passed by StarPU to all other methods.

28.11.2.1.1.2 unplug

```
void(* starpu_disk_ops::unplug)(void *base)
```

Disconnect a disk memory base.

28.11.2.1.1.3 bandwidth

```
int(* starpu_disk_ops::bandwidth)(unsigned node)
```

Measure the bandwidth and the latency for the disk `node` and save it. Returns 1 if it could measure it.

28.11.2.1.1.4 alloc

```
void *(* starpu_disk_ops::alloc)(void *base, size_t size)
```

Create a new location for datas of size `size`. This returns an opaque object pointer.

28.11.2.1.1.5 free

```
void(* starpu_disk_ops::free)(void *base, void *obj, size_t size)
```

Free a data `obj` previously allocated with `alloc`.

28.11.2.1.1.6 open

```
void *(* starpu_disk_ops::open)(void *base, void *pos, size_t size)
```

Open an existing location of datas, at a specific position `pos` dependent on the backend.

28.11.2.1.1.7 close

```
void(* starpu_disk_ops::close)(void *base, void *obj, size_t size)
```

Close, without deleting it, a location of datas `obj`.

28.11.2.1.1.8 read

```
int(* starpu_disk_ops::read)(void *base, void *obj, void *buf, off_t offset, size_t size)
```

Read `size` bytes of data from `obj` in `base`, at offset `offset`, and put into `buf`. Returns the actual number of read bytes.

28.11.2.1.1.9 write

```
int(* starpu_disk_ops::write)(void *base, void *obj, const void *buf, off_t offset, size_t size)
```

Write `size` bytes of data to `obj` in `base`, at offset `offset`, from `buf`. Returns 0 on success.

28.11.2.1.1.10 full_read

```
int (* starpu_disk_ops::full_read)(void *base, void *obj, void **ptr, size_t *size)
```

Read all data from `obj` of `base`, from offset 0. Returns it in an allocated buffer `ptr`, of size `size`

28.11.2.1.1.11 full_write

```
int (* starpu_disk_ops::full_write)(void *base, void *obj, void *ptr, size_t size)
```

Write data in `ptr` to `obj` of `base`, from offset 0, and truncate `obj` to `size`, so that a `full_read` will get it.

28.11.2.1.1.12 async_write

```
void (* starpu_disk_ops::async_write)(void *base, void *obj, const void *buf, off_t offset, size_t size)
```

Asynchronously write `size` bytes of data to `obj` in `base`, at offset `offset`, from `buf`. Returns a `void*` pointer that StarPU will pass to `__request` methods for testing for the completion.

28.11.2.1.1.13 async_read

```
void (* starpu_disk_ops::async_read)(void *base, void *obj, void *buf, off_t offset, size_t size)
```

Asynchronously read `size` bytes of data from `obj` in `base`, at offset `offset`, and put into `buf`. Returns a `void*` pointer that StarPU will pass to `__request` methods for testing for the completion.

28.11.2.1.1.14 async_full_read

```
void (* starpu_disk_ops::async_full_read)(void *base, void *obj, void **ptr, size_t *size)
```

Read all data from `obj` of `base`, from offset 0. Returns it in an allocated buffer `ptr`, of size `size`

28.11.2.1.1.15 async_full_write

```
void (* starpu_disk_ops::async_full_write)(void *base, void *obj, void *ptr, size_t size)
```

Write data in `ptr` to `obj` of `base`, from offset 0, and truncate `obj` to `size`, so that a `full_read` will get it.

28.11.2.1.1.16 copy

```
void (* starpu_disk_ops::copy)(void *base_src, void *obj_src, off_t offset_src, void *base_dst, void *obj_dst, off_t offset_dst, size_t size)
```

Copy from offset `offset_src` of disk object `obj_src` in `base_src` to offset `offset_dst` of disk object `obj_dst` in `base_dst`. Returns a `void*` pointer that StarPU will pass to `__request` methods for testing for the completion.

28.11.2.1.1.17 wait_request

```
void (* starpu_disk_ops::wait_request)(void *async_channel)
```

Wait for completion of request `async_channel` returned by a previous asynchronous read, write or copy.

28.11.2.1.18 test_request

```
void(* starpu_disk_ops::test_request)(void *async_channel)
```

Test for completion of request `async_channel` returned by a previous asynchronous read, write or copy. Returns 1 on completion, 0 otherwise.

28.11.2.1.19 free_request

```
void(* starpu_disk_ops::free_request)(void *async_channel)
```

Free the request allocated by a previous asynchronous read, write or copy.

28.11.3 Macro Definition Documentation**28.11.3.1 STARPU_DISK_SIZE_MIN**

```
#define STARPU_DISK_SIZE_MIN
```

Minimum size of a registered disk. The size of a disk is the last parameter of the function [starpu_disk_register\(\)](#).

28.11.4 Function Documentation**28.11.4.1 starpu_disk_register()**

```
int starpu_disk_register (
    struct starpu\_disk\_ops * func,
    void * parameter,
    starpu_ssize_t size )
```

Register a disk memory node with a set of functions to manipulate datas. The `plug` member of `func` will be passed `parameter`, and return a base which will be passed to all `func` methods.

SUCCESS: return the disk node.

FAIL: return an error code.

`size` must be at least [STARPU_DISK_SIZE_MIN](#) bytes ! `size` being negative means infinite size.

28.11.4.2 starpu_disk_open()

```
void * starpu_disk_open (
    unsigned node,
    void * pos,
    size_t size )
```

Open an existing file memory in a disk node. `size`: this is a size of your file. `pos` is specific position dependent on the backend, given to the `open` method of the disk operations. This returns an opaque object pointer.

28.11.4.3 starpu_disk_close()

```
void starpu_disk_close (
    unsigned node,
    void * obj,
    size_t size )
```

Close an existing data opened with starpu_disk_open.

28.11.5 Variable Documentation

28.11.5.1 starpu_disk_swap_node

```
starpu_disk_swap_node
```

This contains the node number of the disk swap, if set up through the STARPU_DISK_SWAP variable.

28.11.5.2 starpu_disk_stdio_ops

```
starpu_disk_stdio_ops
```

This set uses the stdio library (fwrite, fread...) to read/write on disk.

Warning: It creates one file per allocation !

It doesn't support asynchronous transfers.

28.11.5.3 starpu_disk_unistd_ops

```
starpu_disk_unistd_ops
```

This set uses the unistd library (write, read...) to read/write on disk.

Warning: It creates one file per allocation !

28.11.5.4 starpu_disk_unistd_o_direct_ops

```
starpu_disk_unistd_o_direct_ops
```

This set uses the unistd library (write, read...) to read/write on disk with the O_DIRECT flag.

Warning: It creates one file per allocation !

Only available on Linux systems.

28.11.5.5 starpu_disk_leveldb_ops

```
starpu_disk_leveldb_ops
```

This set uses the leveldb created by Google

Show here: <https://code.google.com/p/leveldb/>

It doesn't support asynchronous transfers.

28.12 Multiformat Data Interface

Data Structures

- struct [starpu_multiformat_data_interface_ops](#)
- struct [starpu_multiformat_interface](#)

Macros

- #define [STARPU_MULTIFORMAT_GET_CPU_PTR](#)(interface)
- #define [STARPU_MULTIFORMAT_GET_CUDA_PTR](#)(interface)
- #define [STARPU_MULTIFORMAT_GET_OPENCL_PTR](#)(interface)
- #define [STARPU_MULTIFORMAT_GET_MIC_PTR](#)(interface)
- #define [STARPU_MULTIFORMAT_GET_NX](#)(interface)

Functions

- void [starpu_multiformat_data_register](#) ([starpu_data_handle_t](#) *handle, int home_node, void *ptr, uint32_t nobjects, struct [starpu_multiformat_data_interface_ops](#) *format_ops)

28.12.1 Detailed Description

28.12.2 Data Structure Documentation

28.12.2.1 struct [starpu_multiformat_data_interface_ops](#)

The different fields are:

Data Fields

size_t	cpu_elsize	the size of each element on CPUs
size_t	opencl_elsize	the size of each element on OpenCL devices
struct starpu_codelet *	cpu_to_opencl_cl	pointer to a codelet which converts from CPU to OpenCL
struct starpu_codelet *	opencl_to_cpu_cl	pointer to a codelet which converts from OpenCL to CPU
size_t	cuda_elsize	the size of each element on CUDA devices
struct starpu_codelet *	cpu_to_cuda_cl	pointer to a codelet which converts from CPU to CUDA
struct starpu_codelet *	cuda_to_cpu_cl	pointer to a codelet which converts from CUDA to CPU
size_t	mic_elsize	the size of each element on MIC devices
struct starpu_codelet *	cpu_to_mic_cl	pointer to a codelet which converts from CPU to MIC
struct starpu_codelet *	mic_to_cpu_cl	pointer to a codelet which converts from MIC to CPU

28.12.2.2 struct [starpu_multiformat_interface](#)

todo

Data Fields

enum starpu_data_interface_id	id	
void *	cpu_ptr	
void *	cuda_ptr	
void *	opencl_ptr	
void *	mic_ptr	
uint32_t	nx	
struct starpu_multiformat_data_interface_ops *	ops	

28.12.3 Macro Definition Documentation

28.12.3.1 STARPU_MULTIFORMAT_GET_CPU_PTR

```
#define STARPU_MULTIFORMAT_GET_CPU_PTR(  
    interface )
```

returns the local pointer to the data with CPU format.

28.12.3.2 STARPU_MULTIFORMAT_GET_CUDA_PTR

```
#define STARPU_MULTIFORMAT_GET_CUDA_PTR(  
    interface )
```

returns the local pointer to the data with CUDA format.

28.12.3.3 STARPU_MULTIFORMAT_GET_OPENCL_PTR

```
#define STARPU_MULTIFORMAT_GET_OPENCL_PTR(  
    interface )
```

returns the local pointer to the data with OpenCL format.

28.12.3.4 STARPU_MULTIFORMAT_GET_MIC_PTR

```
#define STARPU_MULTIFORMAT_GET_MIC_PTR(  
    interface )
```

returns the local pointer to the data with MIC format.

28.12.3.5 STARPU_MULTIFORMAT_GET_NX

```
#define STARPU_MULTIFORMAT_GET_NX(  
    interface )
```

returns the number of elements in the data.

28.12.4 Function Documentation

28.12.4.1 starpu_multiformat_data_register()

```
void starpu_multiformat_data_register (  
    starpu_data_handle_t * handle,  
    int home_node,  
    void * ptr,  
    uint32_t nobjects,  
    struct starpu_multiformat_data_interface_ops * format_ops )
```

Register a piece of data that can be represented in different ways, depending upon the processing unit that manipulates it. It allows the programmer, for instance, to use an array of structures when working on a CPU, and a structure of arrays when working on a GPU. `nobjects` is the number of elements in the data. `format_ops` describes the format.

28.13 Codelet And Tasks

This section describes the interface to manipulate codelets and tasks.

Data Structures

- struct [starpu_codelet](#)
- struct [starpu_data_descr](#)
- struct [starpu_task](#)

Macros

- `#define` [STARPU_NOWHERE](#)
- `#define` [STARPU_CPU](#)
- `#define` [STARPU_CUDA](#)
- `#define` [STARPU_OPENCL](#)
- `#define` [STARPU_MIC](#)
- `#define` [STARPU_SCC](#)
- `#define` [STARPU_MAIN_RAM](#)
- `#define` [STARPU_MULTIPLE_CPU_IMPLEMENTATIONS](#)
- `#define` [STARPU_MULTIPLE_CUDA_IMPLEMENTATIONS](#)
- `#define` [STARPU_MULTIPLE_OPENCL_IMPLEMENTATIONS](#)
- `#define` [STARPU_NMAXBUFS](#)

- `#define STARPU_VARIABLE_NBUFFERS`
- `#define STARPU_TASK_INITIALIZER`
- `#define STARPU_TASK_GET_NBUFFERS(task)`
- `#define STARPU_TASK_GET_HANDLE(task, i)`
- `#define STARPU_TASK_SET_HANDLE(task, handle, i)`
- `#define STARPU_CODELET_GET_MODE(codelet, i)`
- `#define STARPU_CODELET_SET_MODE(codelet, mode, i)`
- `#define STARPU_TASK_GET_MODE(task, i)`
- `#define STARPU_TASK_SET_MODE(task, mode, i)`
- `#define STARPU_CODELET_GET_NODE(codelet, i)`
- `#define STARPU_CODELET_SET_NODE(codelet, __node, i)`
- `#define STARPU_TASK_INVALID`

Typedefs

- `typedef void(* starpu_cpu_func_t) (void **, void *)`
- `typedef void(* starpu_cuda_func_t) (void **, void *)`
- `typedef void(* starpu_opengl_func_t) (void **, void *)`
- `typedef starpu_mic_kernel_t(* starpu_mic_func_t) (void)`
- `typedef starpu_scc_kernel_t(* starpu_scc_func_t) (void)`
- `typedef void(* starpu_mic_kernel_t) (void **, void *)`
- `typedef void(* starpu_scc_kernel_t) (void **, void *)`

Enumerations

- `enum starpu_codelet_type { STARPU_SEQ, STARPU_SPMD, STARPU_FORKJOIN }`
- `enum starpu_task_status {
STARPU_TASK_INVALID, STARPU_TASK_INVALID, STARPU_TASK_BLOCKED, STARPU_TASK_READY,
STARPU_TASK_RUNNING, STARPU_TASK_FINISHED, STARPU_TASK_BLOCKED_ON_TAG, STARPU_TASK_BLOCKED_ON_TASK,
STARPU_TASK_BLOCKED_ON_DATA, STARPU_TASK_STOPPED }`

Functions

- `void starpu_codelet_init (struct starpu_codelet *cl)`
- `void starpu_task_init (struct starpu_task *task)`
- `struct starpu_task * starpu_task_create (void) STARPU_ATTRIBUTE_MALLOC`
- `struct starpu_task * starpu_task_dup (struct starpu_task *task)`
- `void starpu_task_clean (struct starpu_task *task)`
- `void starpu_task_destroy (struct starpu_task *task)`
- `int starpu_task_wait (struct starpu_task *task) STARPU_WARN_UNUSED_RESULT`
- `int starpu_task_submit (struct starpu_task *task) STARPU_WARN_UNUSED_RESULT`
- `int starpu_task_submit_to_ctx (struct starpu_task *task, unsigned sched_ctx_id)`
- `int starpu_task_wait_for_all (void)`
- `int starpu_task_wait_for_all_in_ctx (unsigned sched_ctx_id)`
- `int starpu_task_wait_for_n_submitted (unsigned n)`
- `int starpu_task_wait_for_n_submitted_in_ctx (unsigned sched_ctx_id, unsigned n)`
- `int starpu_task_nready (void)`
- `int starpu_task_nsubmitted (void)`
- `struct starpu_task * starpu_task_get_current (void)`
- `const char * starpu_task_get_name (struct starpu_task *task)`

- `const char * starpu_task_get_model_name` (struct `starpu_task` *task)
- `void starpu_codelet_display_stats` (struct `starpu_codelet` *cl)
- `int starpu_task_wait_for_no_ready` (void)
- `void starpu_task_set_implementation` (struct `starpu_task` *task, unsigned impl)
- `unsigned starpu_task_get_implementation` (struct `starpu_task` *task)
- `void starpu_iteration_push` (unsigned long iteration)
- `void starpu_iteration_pop` (void)
- `void starpu_create_sync_task` (`starpu_tag_t` sync_tag, unsigned ndeps, `starpu_tag_t` *deps, void(*callback)(void *), void *callback_arg)

28.13.1 Detailed Description

This section describes the interface to manipulate codelets and tasks.

28.13.2 Data Structure Documentation

28.13.2.1 struct `starpu_codelet`

The codelet structure describes a kernel that is possibly implemented on various targets. For compatibility, make sure to initialize the whole structure to zero, either by using explicit `memset`, or the function `starpu_codelet_init()`, or by letting the compiler implicitly do it in e.g. static storage case.

Data Fields

- `uint32_t where`
- `int(* can_execute)` (unsigned workerid, struct `starpu_task` *task, unsigned nimpl)
- `enum starpu_codelet_type type`
- `int max_parallelism`
- `starpu_cpu_func_t cpu_func`
- `starpu_cuda_func_t cuda_func`
- `starpu_opencil_func_t opencil_func`
- `starpu_cpu_func_t cpu_funcs` [STARPU_MAXIMPLEMENTATIONS]
- `starpu_cuda_func_t cuda_funcs` [STARPU_MAXIMPLEMENTATIONS]
- `char cuda_flags` [STARPU_MAXIMPLEMENTATIONS]
- `starpu_opencil_func_t opencil_funcs` [STARPU_MAXIMPLEMENTATIONS]
- `char opencil_flags` [STARPU_MAXIMPLEMENTATIONS]
- `starpu_mic_func_t mic_funcs` [STARPU_MAXIMPLEMENTATIONS]
- `starpu_scc_func_t scc_funcs` [STARPU_MAXIMPLEMENTATIONS]
- `const char * cpu_funcs_name` [STARPU_MAXIMPLEMENTATIONS]
- `int nbuffers`
- `enum starpu_data_access_mode modes` [STARPU_NMAXBUFS]
- `enum starpu_data_access_mode * dyn_modes`
- `unsigned specific_nodes`
- `int nodes` [STARPU_NMAXBUFS]
- `int * dyn_nodes`
- `struct starpu_perfmodel * model`
- `struct starpu_perfmodel * energy_model`
- `unsigned long per_worker_stats` [STARPU_NMAXWORKERS]
- `const char * name`
- `unsigned color`
- `int flags`

28.13.2.1.1 Field Documentation

28.13.2.1.1.1 where

```
uint32_t starpu_codelet::where
```

Optional field to indicate which types of processing units are able to execute the codelet. The different values [STARPU_CPU](#), [STARPU_CUDA](#), [STARPU_OPENCL](#) can be combined to specify on which types of processing units the codelet can be executed. [STARPU_CPU|STARPU_CUDA](#) for instance indicates that the codelet is implemented for both CPU cores and CUDA devices while [STARPU_OPENCL](#) indicates that it is only available on OpenCL devices. If the field is unset, its value will be automatically set based on the availability of the `XXX_funcs` fields defined below. It can also be set to [STARPU_NOWHERE](#) to specify that no computation has to be actually done.

28.13.2.1.1.2 can_execute

```
int(* starpu_codelet::can_execute)(unsigned workerid, struct starpu_task *task, unsigned nimpl)
```

Define a function which should return 1 if the worker designated by `workerid` can execute the `nimplth` implementation of the given task, 0 otherwise.

28.13.2.1.1.3 type

```
enum starpu_codelet_type starpu_codelet::type
```

Optional field to specify the type of the codelet. The default is [STARPU_SEQ](#), i.e. usual sequential implementation. Other values ([STARPU_SPMD](#) or [STARPU_FORKJOIN](#) declare that a parallel implementation is also available. See [Parallel Tasks](#) for details.

28.13.2.1.1.4 max_parallelism

```
int starpu_codelet::max_parallelism
```

Optional field. If a parallel implementation is available, this denotes the maximum combined worker size that StarPU will use to execute parallel tasks for this codelet.

28.13.2.1.1.5 cpu_func

```
starpu_cpu_func_t starpu_codelet::cpu_func
```

Deprecated Optional field which has been made deprecated. One should use instead the field [starpu_codelet::cpu_funcs](#).

28.13.2.1.1.6 cuda_func

```
starpu_cuda_func_t starpu_codelet::cuda_func
```

Deprecated Optional field which has been made deprecated. One should use instead the [starpu_codelet::cuda_funcs](#) field.

28.13.2.1.1.7 `openc1_func`

```
starpu_openc1_func_t starpu_codelet::openc1_func
```

Deprecated Optional field which has been made deprecated. One should use instead the `starpu_codelet::openc1_funcs` field.

28.13.2.1.1.8 `cpu_funcs`

```
starpu_cpu_func_t starpu_codelet::cpu_funcs[STARPU_MAXIMPLEMENTATIONS]
```

Optional array of function pointers to the CPU implementations of the codelet. The functions prototype must be:

```
void cpu_func(void *buffers[], void *cl_arg)
```

The first argument being the array of data managed by the data management library, and the second argument is a pointer to the argument passed from the field `starpu_task::cl_arg`. If the field `starpu_codelet::where` is set, then the field `starpu_codelet::cpu_funcs` is ignored if `STARPU_CPU` does not appear in the field `starpu_codelet::where`, it must be non-null otherwise.

28.13.2.1.1.9 `cuda_funcs`

```
starpu_cuda_func_t starpu_codelet::cuda_funcs[STARPU_MAXIMPLEMENTATIONS]
```

Optional array of function pointers to the CUDA implementations of the codelet. The functions must be host-functions written in the CUDA runtime API. Their prototype must be:

```
void cuda_func(void *buffers[], void *cl_arg)
```

If the field `starpu_codelet::where` is set, then the field `starpu_codelet::cuda_funcs` is ignored if `STARPU_CUDA` does not appear in the field `starpu_codelet::where`, it must be non-null otherwise.

28.13.2.1.1.10 `cuda_flags`

```
char starpu_codelet::cuda_flags[STARPU_MAXIMPLEMENTATIONS]
```

Optional array of flags for CUDA execution. They specify some semantic details about CUDA kernel execution, such as asynchronous execution.

28.13.2.1.1.11 `openc1_funcs`

```
starpu_openc1_func_t starpu_codelet::openc1_funcs[STARPU_MAXIMPLEMENTATIONS]
```

Optional array of function pointers to the OpenCL implementations of the codelet. The functions prototype must be:

```
void openc1_func(void *buffers[], void *cl_arg)
```

If the field `starpu_codelet::where` field is set, then the field `starpu_codelet::openc1_funcs` is ignored if `STARPU_OPENCL` does not appear in the field `starpu_codelet::where`, it must be non-null otherwise.

28.13.2.1.1.12 `openccl_flags`

```
char starpu_codelet::openccl_flags[STARPU_MAXIMPLEMENTATIONS]
```

Optional array of flags for OpenCL execution. They specify some semantic details about OpenCL kernel execution, such as asynchronous execution.

28.13.2.1.1.13 `mic_funcs`

```
starpu_mic_func_t starpu_codelet::mic_funcs[STARPU_MAXIMPLEMENTATIONS]
```

Optional array of function pointers to a function which returns the MIC implementation of the codelet. The functions prototype must be:

```
starpu_mic_kernel_t mic_func(struct starpu_codelet *cl, unsigned nimpl)
```

If the field `starpu_codelet::where` is set, then the field `starpu_codelet::mic_funcs` is ignored if `STARPU_MIC` does not appear in the field `starpu_codelet::where`. It can be null if `starpu_codelet::cpu_funcs_name` is non-NULL, in which case StarPU will simply make a symbol lookup to get the implementation.

28.13.2.1.1.14 `scc_funcs`

```
starpu_scc_func_t starpu_codelet::scc_funcs[STARPU_MAXIMPLEMENTATIONS]
```

Optional array of function pointers to a function which returns the SCC implementation of the codelet. The functions prototype must be:

```
starpu_scc_kernel_t scc_func(struct starpu_codelet *cl, unsigned nimpl)
```

If the field `starpu_codelet::where` is set, then the field `starpu_codelet::scc_funcs` is ignored if `STARPU_SCC` does not appear in the field `starpu_codelet::where`. It can be null if `starpu_codelet::cpu_funcs_name` is non-NULL, in which case StarPU will simply make a symbol lookup to get the implementation.

28.13.2.1.1.15 `cpu_funcs_name`

```
char * starpu_codelet::cpu_funcs_name[STARPU_MAXIMPLEMENTATIONS]
```

Optional array of strings which provide the name of the CPU functions referenced in the array `starpu_codelet::cpu_funcs`. This can be used when running on MIC devices or the SCC platform, for StarPU to simply look up the MIC function implementation through its name.

28.13.2.1.1.16 `nbuffers`

```
int starpu_codelet::nbuffers
```

Specify the number of arguments taken by the codelet. These arguments are managed by the DSM and are accessed from the `void *buffers[]` array. The constant argument passed with the field `starpu_task::cl_arg` is not counted in this number. This value should not be above `STARPU_NMAXBUFS`. It may be set to `STARPU_VARIABLE_NBUFFERS` to specify that the number of buffers and their access modes will be set in `starpu_task::nbuffers` and `starpu_task::modes` or `starpu_task::dyn_modes`, which thus permits to define codelets with a varying number of data.

28.13.2.1.17 modes

```
enum starpu_data_access_mode starpu_codelet::modes[STARPU_NMAXBUFS]
```

Is an array of [starpu_data_access_mode](#). It describes the required access modes to the data needed by the codelet (e.g. [STARPU_RW](#)). The number of entries in this array must be specified in the field [starpu_codelet::nbuffers](#), and should not exceed [STARPU_NMAXBUFS](#). If insufficient, this value can be set with the configure option `--enable-maxbuffers`.

28.13.2.1.18 dyn_modes

```
enum starpu_data_access_mode * starpu_codelet::dyn_modes
```

Is an array of [starpu_data_access_mode](#). It describes the required access modes to the data needed by the codelet (e.g. [STARPU_RW](#)). The number of entries in this array must be specified in the field [starpu_codelet::nbuffers](#). This field should be used for codelets having a number of datas greater than [STARPU_NMAXBUFS](#) (see [Setting Many Data Handles For a Task](#)). When defining a codelet, one should either define this field or the field [starpu_codelet::modes](#) defined above.

28.13.2.1.19 specific_nodes

```
unsigned starpu_codelet::specific_nodes
```

Default value is 0. If this flag is set, StarPU will not systematically send all data to the memory node where the task will be executing, it will read the [starpu_codelet::nodes](#) or [starpu_codelet::dyn_nodes](#) array to determine, for each data, whether to send it on the memory node where the task will be executing (-1), or on a specific node (!= -1).

28.13.2.1.20 nodes

```
int starpu_codelet::nodes[STARPU_NMAXBUFS]
```

Optional field. When [starpu_codelet::specific_nodes](#) is 1, this specifies the memory nodes where each data should be sent to for task execution. The number of entries in this array is [starpu_codelet::nbuffers](#), and should not exceed [STARPU_NMAXBUFS](#).

28.13.2.1.21 dyn_nodes

```
int * starpu_codelet::dyn_nodes
```

Optional field. When [starpu_codelet::specific_nodes](#) is 1, this specifies the memory nodes where each data should be sent to for task execution. The number of entries in this array is [starpu_codelet::nbuffers](#). This field should be used for codelets having a number of datas greater than [STARPU_NMAXBUFS](#) (see [Setting Many Data Handles For a Task](#)). When defining a codelet, one should either define this field or the field [starpu_codelet::nodes](#) defined above.

28.13.2.1.22 model

```
struct starpu_perfmodel * starpu_codelet::model
```

Optional pointer to the task duration performance model associated to this codelet. This optional field is ignored when set to `NULL` or when its field [starpu_perfmodel::symbol](#) is not set.

28.13.2.1.1.23 energy_model

```
struct starpu\_perfmodel * starpu_codelet::energy_model
```

Optional pointer to the task energy consumption performance model associated to this codelet. This optional field is ignored when set to `NULL` or when its field `starpu_perfmodel::field` is not set. In the case of parallel codelets, this has to account for all processing units involved in the parallel execution.

28.13.2.1.1.24 per_worker_stats

```
unsigned long starpu_codelet::per_worker_stats[STARPU\_NMAXWORKERS]
```

Optional array for statistics collected at runtime: this is filled by StarPU and should not be accessed directly, but for example by calling the function [starpu_codelet_display_stats\(\)](#) (See [starpu_codelet_display_stats\(\)](#) for details).

28.13.2.1.1.25 name

```
const char * starpu_codelet::name
```

Optional name of the codelet. This can be useful for debugging purposes.

28.13.2.1.1.26 color

```
unsigned starpu_codelet::color
```

Optional color of the codelet. This can be useful for debugging purposes.

28.13.2.1.1.27 flags

```
const char * starpu_codelet::flags
```

Various flags for the codelet.

28.13.2.2 struct starpu_data_descr

This type is used to describe a data handle along with an access mode.

Data Fields

starpu_data_handle_t	handle	describes a data
enum starpu_data_access_mode	mode	describes its access mode

28.13.2.3 struct starpu_task

The structure describes a task that can be offloaded on the various processing units managed by StarPU. It instantiates a codelet. It can either be allocated dynamically with the function [starpu_task_create\(\)](#), or declared statically. In the latter case, the programmer has to zero the structure [starpu_task](#) and to fill the different fields properly. The indicated default values correspond to the configuration of a task allocated with [starpu_task_create\(\)](#).

Data Fields

- const char * `name`
- struct `starpu_codelet` * `cl`
- int `nbuffers`
- `starpu_data_handle_t` `handles` [`STARPU_NMAXBUFS`]
- void * `interfaces` [`STARPU_NMAXBUFS`]
- enum `starpu_data_access_mode` `modes` [`STARPU_NMAXBUFS`]
- `starpu_data_handle_t` * `dyn_handles`
- void ** `dyn_interfaces`
- enum `starpu_data_access_mode` * `dyn_modes`
- void * `cl_arg`
- size_t `cl_arg_size`
- void(* `callback_func`)(void *)
- void * `callback_arg`
- void(* `prologue_callback_func`)(void *)
- void * `prologue_callback_arg`
- void(* `prologue_callback_pop_func`)(void *)
- void * `prologue_callback_pop_arg`
- `starpu_tag_t` `tag_id`
- unsigned `cl_arg_free`:1
- unsigned `callback_arg_free`:1
- unsigned `prologue_callback_arg_free`:1
- unsigned `prologue_callback_pop_arg_free`:1
- unsigned `use_tag`:1
- unsigned `sequential_consistency`:1
- unsigned `synchronous`:1
- unsigned `execute_on_a_specific_worker`:1
- unsigned `detach`:1
- unsigned `destroy`:1
- unsigned `regenerate`:1
- unsigned int `mf_skip`:1
- unsigned `scheduled`:1
- unsigned `prefetched`:1
- unsigned `workerid`
- unsigned `workerorder`
- int `priority`
- enum `starpu_task_status` `status`
- int `magic`
- unsigned `type`
- unsigned `color`
- unsigned `sched_ctx`
- int `hypervisor_tag`
- unsigned `possibly_parallel`
- `starpu_task_bundle_t` `bundle`
- struct `starpu_profiling_task_info` * `profiling_info`
- double `flops`
- double `predicted`
- double `predicted_transfer`
- struct `starpu_task` * `prev`
- struct `starpu_task` * `next`
- void * `starpu_private`
- struct `starpu_omp_task` * `omp_task`

28.13.2.3.1 Field Documentation

28.13.2.3.1.1 name

```
const char * starpu_task::name
```

Optional name of the task. This can be useful for debugging purposes.

28.13.2.3.1.2 cl

```
struct starpu\_codelet * starpu_task::cl
```

Is a pointer to the corresponding structure [starpu_codelet](#). This describes where the kernel should be executed, and supplies the appropriate implementations. When set to NULL, no code is executed during the tasks, such empty tasks can be useful for synchronization purposes. This field has been made deprecated. One should use instead the field [starpu_task::handles](#) to specify the data handles accessed by the task. The access modes are now defined in the field [starpu_codelet::modes](#).

28.13.2.3.1.3 nbuffers

```
int starpu_task::nbuffers
```

Specifies the number of buffers. This is only used when [starpu_codelet::nbuffers](#) is STARPU_VARIABLE_NBUFFERS.

28.13.2.3.1.4 handles

```
starpu\_data\_handle\_t starpu_task::handles[STARPU_NMAXBUFS]
```

Is an array of [starpu_data_handle_t](#). It specifies the handles to the different pieces of data accessed by the task. The number of entries in this array must be specified in the field [starpu_codelet::nbuffers](#), and should not exceed STARPU_NMAXBUFS. If insufficient, this value can be set with the configure option `--enable-maxbuffers`.

28.13.2.3.1.5 interfaces

```
void * starpu_task::interfaces[STARPU_NMAXBUFS]
```

The actual data pointers to the memory node where execution will happen, managed by the DSM.

28.13.2.3.1.6 modes

```
enum starpu\_data\_access\_mode starpu_task::modes[STARPU_NMAXBUFS]
```

Is used only when [starpu_codelet::nbuffers](#) is STARPU_VARIABLE_NBUFFERS. It is an array of [starpu_data_access_mode](#). It describes the required access modes to the data needed by the codelet (e.g. STARPU_RW). The number of entries in this array must be specified in the field [starpu_task::nbuffers](#), and should not exceed STARPU_NMAXBUFS. If insufficient, this value can be set with the configure option `--enable-maxbuffers`.

28.13.2.3.1.7 `dyn_handles`

```
starpu_data_handle_t * starpu_task::dyn_handles
```

Is an array of `starpu_data_handle_t`. It specifies the handles to the different pieces of data accessed by the task. The number of entries in this array must be specified in the field `starpu_codelet::nbuffers`. This field should be used for tasks having a number of datas greater than `STARPU_NMAXBUFS` (see [Setting Many Data Handles For a Task](#)). When defining a task, one should either define this field or the field `starpu_task::handles` defined above.

28.13.2.3.1.8 `dyn_interfaces`

```
void ** starpu_task::dyn_interfaces
```

The actual data pointers to the memory node where execution will happen, managed by the DSM. Is used when the field `starpu_task::dyn_handles` is defined.

28.13.2.3.1.9 `dyn_modes`

```
enum starpu_data_access_mode * starpu_task::dyn_modes
```

Is used only when `starpu_codelet::nbuffers` is `STARPU_VARIABLE_NBUFFERS`. It is an array of `starpu_data_access_mode`. It describes the required access modes to the data needed by the codelet (e.g. `STARPU_RW`). The number of entries in this array must be specified in the field `starpu_codelet::nbuffers`. This field should be used for codelets having a number of datas greater than `STARPU_NMAXBUFS` (see [Setting Many Data Handles For a Task](#)). When defining a codelet, one should either define this field or the field `starpu_task::modes` defined above.

28.13.2.3.1.10 `cl_arg`

```
void * starpu_task::cl_arg
```

Optional pointer which is passed to the codelet through the second argument of the codelet implementation (e.g. `starpu_codelet::cpu_func` or `starpu_codelet::cuda_func`). The default value is `NULL`. `starpu_codelet_pack_args()` and `starpu_codelet_unpack_args()` are helpers that can be used to respectively pack and unpack data into and from it, but the application can manage it any way, the only requirement is that the size of the data must be set in `starpu_task::cl_arg_size`.

28.13.2.3.1.11 `cl_arg_size`

```
size_t starpu_task::cl_arg_size
```

Optional field. For some specific drivers, the pointer `starpu_task::cl_arg` cannot not be directly given to the driver function. A buffer of size `starpu_task::cl_arg_size` needs to be allocated on the driver. This buffer is then filled with the `starpu_task::cl_arg_size` bytes starting at address `starpu_task::cl_arg`. In this case, the argument given to the codelet is therefore not the `starpu_task::cl_arg` pointer, but the address of the buffer in local store (LS) instead. This field is ignored for CPU, CUDA and OpenCL codelets, where the `starpu_task::cl_arg` pointer is given as such.

28.13.2.3.1.12 `callback_func`

```
void(* starpu_task::callback_func)(void *)
```

Optional field, the default value is `NULL`. This is a function pointer of prototype `void (*f)(void *)` which specifies a possible callback. If this pointer is non-null, the callback function is executed on the host after the execution of the task. Tasks which depend on it might already be executing. The callback is passed the value contained in the `starpu_task::callback_arg` field. No callback is executed if the field is set to `NULL`.

28.13.2.3.1.13 callback_arg

```
void * starpu_task::callback_arg
```

Optional field, the default value is `NULL`. This is the pointer passed to the callback function. This field is ignored if the field `starpu_task::callback_func` is set to `NULL`.

28.13.2.3.1.14 prologue_callback_func

```
void(* starpu_task::prologue_callback_func)(void *)
```

Optional field, the default value is `NULL`. This is a function pointer of prototype `void (*f)(void *)` which specifies a possible callback. If this pointer is non-null, the callback function is executed on the host when the task becomes ready for execution, before getting scheduled. The callback is passed the value contained in the `starpu_task::prologue_callback_arg` field. No callback is executed if the field is set to `NULL`.

28.13.2.3.1.15 prologue_callback_arg

```
void * starpu_task::prologue_callback_arg
```

Optional field, the default value is `NULL`. This is the pointer passed to the prologue callback function. This field is ignored if the field `starpu_task::prologue_callback_func` is set to `NULL`.

28.13.2.3.1.16 tag_id

```
starpu_tag_t starpu_task::tag_id
```

This optional field contains the tag associated to the task if the field `starpu_task::use_tag` is set, it is ignored otherwise.

28.13.2.3.1.17 cl_arg_free

```
unsigned starpu_task::cl_arg_free
```

Optional field. In case `starpu_task::cl_arg` was allocated by the application through `malloc()`, setting `starpu_task::cl_arg_free` to 1 makes StarPU automatically call `free(cl_arg)` when destroying the task. This saves the user from defining a callback just for that. This is mostly useful when targeting MIC or SCC, where the codelet does not execute in the same memory space as the main thread.

28.13.2.3.1.18 callback_arg_free

```
unsigned starpu_task::callback_arg_free
```

Optional field. In case `starpu_task::callback_arg` was allocated by the application through `malloc()`, setting `starpu_task::callback_arg_free` to 1 makes StarPU automatically call `free(callback_arg)` when destroying the task.

28.13.2.3.1.19 prologue_callback_arg_free

```
unsigned starpu_task::prologue_callback_arg_free
```

Optional field. In case `starpu_task::prologue_callback_arg` was allocated by the application through `malloc()`, setting `starpu_task::prologue_callback_arg_free` to 1 makes StarPU automatically call `free(prologue_callback_arg)` when destroying the task.

28.13.2.3.1.20 use_tag

```
unsigned starpu_task::use_tag
```

Optional field, the default value is 0. If set, this flag indicates that the task should be associated with the tag contained in the `starpu_task::tag_id` field. Tag allow the application to synchronize with the task and to express task dependencies easily.

28.13.2.3.1.21 sequential_consistency

```
unsigned starpu_task::sequential_consistency
```

If this flag is set (which is the default), sequential consistency is enforced for the data parameters of this task for which sequential consistency is enabled. Clearing this flag permits to disable sequential consistency for this task, even if data have it enabled.

28.13.2.3.1.22 synchronous

```
unsigned starpu_task::synchronous
```

If this flag is set, the function `starpu_task_submit()` is blocking and returns only when the task has been executed (or if no worker is able to process the task). Otherwise, `starpu_task_submit()` returns immediately.

28.13.2.3.1.23 execute_on_a_specific_worker

```
unsigned starpu_task::execute_on_a_specific_worker
```

Default value is 0. If this flag is set, StarPU will bypass the scheduler and directly affect this task to the worker specified by the field `starpu_task::workerid`.

28.13.2.3.1.24 detach

```
unsigned starpu_task::detach
```

Optional field, default value is 1. If this flag is set, it is not possible to synchronize with the task by the means of `starpu_task_wait()` later on. Internal data structures are only guaranteed to be freed once `starpu_task_wait()` is called if the flag is not set.

28.13.2.3.1.25 destroy

```
unsigned starpu_task::destroy
```

Optional value. Default value is 0 for `starpu_task_init()`, and 1 for `starpu_task_create()`. If this flag is set, the task structure will automatically be freed, either after the execution of the callback if the task is detached, or during `starpu_task_wait()` otherwise. If this flag is not set, dynamically allocated data structures will not be freed until `starpu_task_destroy()` is called explicitly. Setting this flag for a statically allocated task structure will result in undefined behaviour. The flag is set to 1 when the task is created by calling `starpu_task_create()`. Note that `starpu_task_wait_for_all()` will not free any task.

28.13.2.3.1.26 regenerate

```
unsigned starpu_task::regenerate
```

Optional field. If this flag is set, the task will be re-submitted to StarPU once it has been executed. This flag must not be set if the flag `starpu_task::destroy` is set. This flag must be set before making another task depend on this one.

28.13.2.3.1.27 mf_skip

```
unsigned int starpu_task::mf_skip
```

This is only used for tasks that use multifragment handle. This should only be used by StarPU.

28.13.2.3.1.28 scheduled

```
unsigned starpu_task::scheduled
```

Whether the scheduler has pushed the task on some queue

28.13.2.3.1.29 workerid

```
unsigned starpu_task::workerid
```

Optional field. If the field [starpu_task::execute_on_a_specific_worker](#) is set, this field indicates the identifier of the worker that should process this task (as returned by [starpu_worker_get_id\(\)](#)). This field is ignored if the field [starpu_task::execute_on_a_specific_worker](#) is set to 0.

28.13.2.3.1.30 workerorder

```
unsigned starpu_task::workerorder
```

Optional field. If the field [starpu_task::execute_on_a_specific_worker](#) is set, this field indicates the per-worker consecutive order in which tasks should be executed on the worker. Tasks will be executed in consecutive [starpu_task::workerorder](#) values, thus ignoring the availability order or task priority. See [Static Scheduling](#) for more details. This field is ignored if the field [starpu_task::execute_on_a_specific_worker](#) is set to 0.

28.13.2.3.1.31 priority

```
int starpu_task::priority
```

Optional field, the default value is [STARPU_DEFAULT_PRIO](#). This field indicates a level of priority for the task. This is an integer value that must be set between the return values of the function [starpu_sched_get_min_priority\(\)](#) for the least important tasks, and that of the function [starpu_sched_get_max_priority\(\)](#) for the most important tasks (included). The [STARPU_MIN_PRIO](#) and [STARPU_MAX_PRIO](#) macros are provided for convenience and respectively returns the value of [starpu_sched_get_min_priority\(\)](#) and [starpu_sched_get_max_priority\(\)](#). Default priority is [STARPU_DEFAULT_PRIO](#), which is always defined as 0 in order to allow static task initialization. Scheduling strategies that take priorities into account can use this parameter to take better scheduling decisions, but the scheduling policy may also ignore it.

28.13.2.3.1.32 status

```
enum starpu_task_status starpu_task::status
```

Optional field. Current state of the task.

28.13.2.3.1.33 magic

```
int starpu_task::magic
```

This field is set when initializing a task. The function [starpu_task_submit\(\)](#) will fail if the field does not have the right value. This will hence avoid submitting tasks which have not been properly initialised.

28.13.2.3.1.34 type

```
unsigned starpu_task::type
```

This field allows to specify the type of task, for filtering out tasks in profiling outputs, whether it is really internal to StarPU (::STARPU_TASK_TYPE_INTERNAL), a data acquisition synchronization task (STARPU_TASK_TYPE←_DATA_ACQUIRE), or a normal task (::STARPU_TASK_TYPE_NORMAL)

28.13.2.3.1.35 color

```
int starpu_task::color
```

This field allows to specify the color of the task to be used in dag.dot.

28.13.2.3.1.36 sched_ctx

```
unsigned starpu_task::sched_ctx
```

Scheduling context.

28.13.2.3.1.37 hypervisor_tag

```
int starpu_task::hypervisor_tag
```

Helps the hypervisor monitor the execution of this task.

28.13.2.3.1.38 bundle

```
starpu_task_bundle_t starpu_task::bundle
```

Optional field. The bundle that includes this task. If no bundle is used, this should be NULL.

28.13.2.3.1.39 profiling_info

```
struct starpu_profiling_task_info * starpu_task::profiling_info
```

Optional field. Profiling information for the task.

28.13.2.3.1.40 flops

```
double starpu_task::flops
```

This can be set to the number of floating points operations that the task will have to achieve. This is useful for easily getting GFlops curves from the tool `starpu_perfmodel_plot`, and for the hypervisor load balancing.

28.13.2.3.1.41 predicted

```
double starpu_task::predicted
```

Output field. Predicted duration of the task. This field is only set if the scheduling strategy uses performance models.

28.13.2.3.1.42 predicted_transfer

```
double starpu_task::predicted_transfer
```

Optional field. Predicted data transfer duration for the task in microseconds. This field is only valid if the scheduling strategy uses performance models.

28.13.2.3.1.43 prev

```
struct starpu_task * starpu_task::prev
```

A pointer to the previous task. This should only be used by StarPU.

28.13.2.3.1.44 next

```
struct starpu_task * starpu_task::next
```

A pointer to the next task. This should only be used by StarPU.

28.13.2.3.1.45 starpu_private

```
void * starpu_task::starpu_private
```

This is private to StarPU, do not modify. If the task is allocated by hand (without `starpu_task_create()`), this field should be set to NULL.

28.13.3 Macro Definition Documentation**28.13.3.1 STARPU_NOWHERE**

```
#define STARPU_NOWHERE
```

This macro is used when setting the field `starpu_codelet::where` to specify that the codelet has no computation part, and thus does not need to be scheduled, and data does not need to be actually loaded. This is thus essentially used for synchronization tasks.

28.13.3.2 STARPU_CPU

```
#define STARPU_CPU
```

This macro is used when setting the field `starpu_codelet::where` to specify the codelet may be executed on a CPU processing unit.

28.13.3.3 STARPU_CUDA

```
#define STARPU_CUDA
```

This macro is used when setting the field `starpu_codelet::where` to specify the codelet may be executed on a CUDA processing unit.

28.13.3.4 STARPU_OPENCL

```
#define STARPU_OPENCL
```

This macro is used when setting the field `starpu_codelet::where` to specify the codelet may be executed on a OpenCL processing unit.

28.13.3.5 STARPU_MIC

```
#define STARPU_MIC
```

This macro is used when setting the field `starpu_codelet::where` to specify the codelet may be executed on a MIC processing unit.

28.13.3.6 STARPU_SCC

```
#define STARPU_SCC
```

This macro is used when setting the field `starpu_codelet::where` to specify the codelet may be executed on an SCC processing unit.

28.13.3.7 STARPU_MAIN_RAM

```
#define STARPU_MAIN_RAM
```

This macro is used when the RAM memory node is specified.

28.13.3.8 STARPU_MULTIPLE_CPU_IMPLEMENTATIONS

```
#define STARPU_MULTIPLE_CPU_IMPLEMENTATIONS
```

Deprecated Setting the field `starpu_codelet::cpu_func` with this macro indicates the codelet will have several implementations. The use of this macro is deprecated. One should always only define the field `starpu_codelet::cpu_funcs`.

28.13.3.9 STARPU_MULTIPLE_CUDA_IMPLEMENTATIONS

```
#define STARPU_MULTIPLE_CUDA_IMPLEMENTATIONS
```

Deprecated Setting the field `starpu_codelet::cuda_func` with this macro indicates the codelet will have several implementations. The use of this macro is deprecated. One should always only define the field `starpu_codelet::cuda_funcs`.

28.13.3.10 STARPU_MULTIPLE_OPENCL_IMPLEMENTATIONS

```
#define STARPU_MULTIPLE_OPENCL_IMPLEMENTATIONS
```

Deprecated Setting the field `starpu_codelet::openccl_func` with this macro indicates the codelet will have several implementations. The use of this macro is deprecated. One should always only define the field `starpu_codelet::openccl_funcs`.

28.13.3.11 STARPU_NMAXBUFS

```
#define STARPU_NMAXBUFS
```

Defines the maximum number of buffers that tasks will be able to take as parameters. The default value is 8, it can be changed by using the configure option `--enable-maxbuffers`.

28.13.3.12 STARPU_VARIABLE_NBUFFERS

```
#define STARPU_VARIABLE_NBUFFERS
```

Value to set in `starpu_codelet::nbuffers` to specify that the codelet can accept a variable number of buffers, specified in `starpu_task::nbuffers`.

28.13.3.13 STARPU_TASK_INITIALIZER

```
#define STARPU_TASK_INITIALIZER
```

It is possible to initialize statically allocated tasks with this value. This is equivalent to initializing a structure `starpu_task` with the function `starpu_task_init()` function.

28.13.3.14 STARPU_TASK_GET_NBUFFERS

```
#define STARPU_TASK_GET_NBUFFERS(  
    task )
```

Return the number of buffers for this task, i.e. `starpu_codelet::nbuffers`, or `starpu_task::nbuffers` if the former is `STARPU_VARIABLE_NBUFFERS`.

28.13.3.15 STARPU_TASK_GET_HANDLE

```
#define STARPU_TASK_GET_HANDLE(  
    task,  
    i )
```

Return the `i` th data handle of the given task. If the task is defined with a static or dynamic number of handles, will either return the `i` th element of the field `starpu_task::handles` or the `i` th element of the field `starpu_task::dyn_handles` (see [Setting Many Data Handles For a Task](#))

28.13.3.16 STARPU_TASK_SET_HANDLE

```
#define STARPU_TASK_SET_HANDLE(  
    task,  
    handle,  
    i )
```

Set the *i* th data handle of the given task with the given dat handle. If the task is defined with a static or dynamic number of handles, will either set the *i* th element of the field `starpu_task::handles` or the *i* th element of the field `starpu_task::dyn_handles` (see [Setting Many Data Handles For a Task](#))

28.13.3.17 STARPU_CODELET_GET_MODE

```
#define STARPU_CODELET_GET_MODE(  
    codelet,  
    i )
```

Return the access mode of the *i* th data handle of the given codelet. If the codelet is defined with a static or dynamic number of handles, will either return the *i* th element of the field `starpu_codelet::modes` or the *i* th element of the field `starpu_codelet::dyn_modes` (see [Setting Many Data Handles For a Task](#))

28.13.3.18 STARPU_CODELET_SET_MODE

```
#define STARPU_CODELET_SET_MODE(  
    codelet,  
    mode,  
    i )
```

Set the access mode of the *i* th data handle of the given codelet. If the codelet is defined with a static or dynamic number of handles, will either set the *i* th element of the field `starpu_codelet::modes` or the *i* th element of the field `starpu_codelet::dyn_modes` (see [Setting Many Data Handles For a Task](#))

28.13.3.19 STARPU_TASK_GET_MODE

```
#define STARPU_TASK_GET_MODE(  
    task,  
    i )
```

Return the access mode of the *i* th data handle of the given task. If the task is defined with a static or dynamic number of handles, will either return the *i* th element of the field `starpu_task::modes` or the *i* th element of the field `starpu_task::dyn_modes` (see [Setting Many Data Handles For a Task](#))

28.13.3.20 STARPU_TASK_SET_MODE

```
#define STARPU_TASK_SET_MODE(  
    task,  
    mode,  
    i )
```

Set the access mode of the *i* th data handle of the given task. If the task is defined with a static or dynamic number of handles, will either set the *i* th element of the field `starpu_task::modes` or the *i* th element of the field `starpu_task::dyn_modes` (see [Setting Many Data Handles For a Task](#))

28.13.3.21 STARPU_CODELET_GET_NODE

```
#define STARPU_CODELET_GET_NODE(  
    codelet,  
    i )
```

Return the target node of the *i* -th data handle of *codelet*. If *codelet* is defined with a static or dynamic number of handles, will either return the *i* -th element of the field [starpu_codelet::nodes](#) or the *i* -th element of the field [starpu_codelet::dyn_nodes](#) (see [Setting Many Data Handles For a Task](#))

28.13.3.22 STARPU_CODELET_SET_NODE

```
#define STARPU_CODELET_SET_NODE(  
    codelet,  
    __node,  
    i )
```

Set the target node of the *i* -th data handle of *codelet*. If *codelet* is defined with a static or dynamic number of handles, will either set the *i* -th element of the field [starpu_codelet::nodes](#) or the *i* -th element of the field [starpu_codelet::dyn_nodes](#) (see [Setting Many Data Handles For a Task](#))

28.13.3.23 STARPU_TASK_INVALID

```
starpu_task_status::STARPU_TASK_INVALID
```

The task has just been initialized.

28.13.4 Typedef Documentation

28.13.4.1 starpu_cpu_func_t

```
starpu_cpu_func_t
```

CPU implementation of a codelet.

28.13.4.2 starpu_cuda_func_t

```
starpu_cuda_func_t
```

CUDA implementation of a codelet.

28.13.4.3 starpu_opengl_func_t

```
starpu_opengl_func_t
```

OpenCL implementation of a codelet.

28.13.4.4 starpu_mic_func_t

```
starpu_mic_func_t
```

MIC implementation of a codelet.

28.13.4.5 starpu_scc_func_t

```
starpu_scc_func_t
```

SCC implementation of a codelet.

28.13.4.6 starpu_mic_kernel_t

```
starpu_mic_kernel_t
```

MIC kernel for a codelet

28.13.4.7 starpu_scc_kernel_t

```
starpu_scc_kernel_t
```

SCC kernel for a codelet

28.13.5 Enumeration Type Documentation**28.13.5.1 starpu_codelet_type**

```
enum starpu_codelet_type
```

Describes the type of parallel task. See [Parallel Tasks](#) for details.

Enumerator

STARPU_SEQ	(default) for classical sequential tasks.
STARPU_SPMD	for a parallel task whose threads are handled by StarPU, the code has to use starpu_combined_worker_get_size() and starpu_combined_worker_get_rank() to distribute the work.
STARPU_FORKJOIN	for a parallel task whose threads are started by the codelet function, which has to use starpu_combined_worker_get_size() to determine how many threads should be started.

28.13.5.2 starpu_task_status

enum [starpu_task_status](#)

Task status

Enumerator

STARPU_TASK_BLOCKED	The task has just been submitted, and its dependencies has not been checked yet.
STARPU_TASK_READY	The task is ready for execution.
STARPU_TASK_RUNNING	The task is running on some worker.
STARPU_TASK_FINISHED	The task is finished executing.
STARPU_TASK_BLOCKED_ON_TAG	The task is waiting for a tag.
STARPU_TASK_BLOCKED_ON_TASK	The task is waiting for a task.
STARPU_TASK_BLOCKED_ON_DATA	The task is waiting for some data.

28.13.6 Function Documentation

28.13.6.1 starpu_codelet_init()

```
void starpu_codelet_init (
    struct starpu\_codelet * cl )
```

Initialize `cl` with default values. Codelets should preferably be initialized statically as shown in [Defining A Codelet](#). However such a initialisation is not always possible, e.g. when using C++.

28.13.6.2 starpu_task_init()

```
void starpu_task_init (
    struct starpu\_task * task )
```

Initialize task with default values. This function is implicitly called by [starpu_task_create\(\)](#). By default, tasks initialized with [starpu_task_init\(\)](#) must be deinitialized explicitly with [starpu_task_clean\(\)](#). Tasks can also be initialized statically, using [STARPU_TASK_INITIALIZER](#).

28.13.6.3 starpu_task_create()

```
struct starpu\_task * starpu_task_create (
    void )
```

Allocate a task structure and initialize it with default values. Tasks allocated dynamically with [starpu_task_create\(\)](#) are automatically freed when the task is terminated. This means that the task pointer can not be used any more once the task is submitted, since it can be executed at any time (unless dependencies make it wait) and thus freed at any time. If the field [starpu_task::destroy](#) is explicitly unset, the resources used by the task have to be freed by calling [starpu_task_destroy\(\)](#).

28.13.6.4 `starpu_task_dup()`

```
struct starpu_task * starpu_task_dup (
    struct starpu_task * task )
```

Allocate a task structure which is the exact duplicate of the given task.

28.13.6.5 `starpu_task_clean()`

```
void starpu_task_clean (
    struct starpu_task * task )
```

Release all the structures automatically allocated to execute task, but not the task structure itself and values set by the user remain unchanged. It is thus useful for statically allocated tasks for instance. It is also useful when users want to execute the same operation several times with as least overhead as possible. It is called automatically by `starpu_task_destroy()`. It has to be called only after explicitly waiting for the task or after `starpu_shutdown()` (waiting for the callback is not enough, since StarPU still manipulates the task after calling the callback).

28.13.6.6 `starpu_task_destroy()`

```
void starpu_task_destroy (
    struct starpu_task * task )
```

Free the resource allocated during `starpu_task_create()` and associated with task. This function is already called automatically after the execution of a task when the field `starpu_task::destroy` is set, which is the default for tasks created by `starpu_task_create()`. Calling this function on a statically allocated task results in an undefined behaviour.

28.13.6.7 `starpu_task_wait()`

```
int starpu_task_wait (
    struct starpu_task * task )
```

This function blocks until `task` has been executed. It is not possible to synchronize with a task more than once. It is not possible to wait for synchronous or detached tasks. Upon successful completion, this function returns 0. Otherwise, `-EINVAL` indicates that the specified task was either synchronous or detached.

28.13.6.8 `starpu_task_submit()`

```
int starpu_task_submit (
    struct starpu_task * task )
```

This function submits task to StarPU. Calling this function does not mean that the task will be executed immediately as there can be data or task (tag) dependencies that are not fulfilled yet: StarPU will take care of scheduling this task with respect to such dependencies. This function returns immediately if the field `starpu_task::synchronous` is set to 0, and block until the termination of the task otherwise. It is also possible to synchronize the application with asynchronous tasks by the means of tags, using the function `starpu_tag_wait()` function for instance. In case of success, this function returns 0, a return value of `-ENODEV` means that there is no worker able to process this task (e.g. there is no GPU available and this task is only implemented for CUDA devices). `starpu_task_submit()` can be called from anywhere, including codelet functions and callbacks, provided that the field `starpu_task::synchronous` is set to 0.

28.13.6.9 `starpu_task_submit_to_ctx()`

```
int starpu_task_submit_to_ctx (
    struct starpu_task * task,
    unsigned sched_ctx_id )
```

This function submits a task to StarPU to the context `sched_ctx_id` . By default `starpu_task_submit` submits the task to a global context that is created automatically by StarPU.

28.13.6.10 `starpu_task_wait_for_all()`

```
int starpu_task_wait_for_all (
    void )
```

This function blocks until all the tasks that were submitted (to the current context or the global one if there aren't any) are terminated. It does not destroy these tasks.

28.13.6.11 `starpu_task_wait_for_all_in_ctx()`

```
int starpu_task_wait_for_all_in_ctx (
    unsigned sched_ctx_id )
```

This function waits until all the tasks that were already submitted to the context `sched_ctx_id` have been executed.

28.13.6.12 `starpu_task_wait_for_n_submitted()`

```
int starpu_task_wait_for_n_submitted (
    unsigned n )
```

This function blocks until there are `n` submitted tasks left (to the current context or the global one if there aren't any) to be executed. It does not destroy these tasks.

28.13.6.13 `starpu_task_wait_for_n_submitted_in_ctx()`

```
int starpu_task_wait_for_n_submitted_in_ctx (
    unsigned sched_ctx_id,
    unsigned n )
```

This function waits until there are `n` tasks submitted left to be executed that were already submitted to the context `sched_ctx_id` .

28.13.6.14 `starpu_task_nready()`

```
int starpu_task_nready (
    void )
```

TODO

Return the number of submitted tasks which are ready for execution are already executing. It thus does not include tasks waiting for dependencies.

28.13.6.15 starpu_task_nsubmitted()

```
int starpu_task_nsubmitted (
    void )
```

Return the number of submitted tasks which have not completed yet.

28.13.6.16 starpu_task_get_current()

```
struct starpu_task * starpu_task_get_current (
    void )
```

This function returns the task currently executed by the worker, or `NULL` if it is called either from a thread that is not a task or simply because there is no task being executed at the moment.

28.13.6.17 starpu_task_get_name()

```
const char * starpu_task_get_name (
    struct starpu_task * task )
```

This function returns the name of `task`, i.e. either its `task->name` field, or the name of the corresponding performance model.

28.13.6.18 starpu_task_get_model_name()

```
const char * starpu_task_get_model_name (
    struct starpu_task * task )
```

This function returns the name of the performance model of `task`.

28.13.6.19 starpu_codelet_display_stats()

```
void starpu_codelet_display_stats (
    struct starpu_codelet * cl )
```

Output on `stderr` some statistics on the codelet `cl`.

28.13.6.20 starpu_task_wait_for_no_ready()

```
int starpu_task_wait_for_no_ready (
    void )
```

This function waits until there is no more ready task.

28.13.6.21 starpu_task_set_implementation()

```
void starpu_task_set_implementation (
    struct starpu\_task * task,
    unsigned impl )
```

This function should be called by schedulers to specify the codelet implementation to be executed when executing the task.

28.13.6.22 starpu_task_get_implementation()

```
unsigned starpu_task_get_implementation (
    struct starpu\_task * task )
```

This function return the codelet implementation to be executed when executing the task.

28.13.6.23 starpu_iteration_push()

```
void starpu_iteration_push (
    unsigned long iteration )
```

Sets the iteration number for all the tasks to be submitted after this call. This is typically called at the beginning of a task submission loop. This number will then show up in tracing tools. A corresponding [starpu_iteration_pop\(\)](#) call must be made to match the call to [starpu_iteration_push\(\)](#), at the end of the same task submission loop, typically.

Nested calls to [starpu_iteration_push](#) and [starpu_iteration_pop](#) are allowed, to describe a loop nest for instance, provided that they match properly.

28.13.6.24 starpu_iteration_pop()

```
void starpu_iteration_pop (
    void )
```

Drops the iteration number for submitted tasks. This must match a previous call to [starpu_iteration_push\(\)](#), and is typically called at the end of a task submission loop.

28.13.6.25 starpu_create_sync_task()

```
void starpu_create_sync_task (
    starpu\_tag\_t sync_tag,
    unsigned ndeps,
    starpu\_tag\_t * deps,
    void(*) (void *) callback,
    void * callback_arg )
```

This creates (and submits) an empty task that unlocks a tag once all its dependencies are fulfilled.

28.14 Insert_Task

Macros

- `#define STARPU_VALUE`
- `#define STARPU_CL_ARGS`
- `#define STARPU_CALLBACK`
- `#define STARPU_CALLBACK_WITH_ARG`
- `#define STARPU_CALLBACK_ARG`
- `#define STARPU_PRIORITY`
- `#define STARPU_DATA_ARRAY`
- `#define STARPU_DATA_MODE_ARRAY`
- `#define STARPU_EXECUTE_ON_WORKER`
- `#define STARPU_WORKER_ORDER`
- `#define STARPU_TAG`
- `#define STARPU_TAG_ONLY`
- `#define STARPU_NAME`
- `#define STARPU_FLOPS`
- `#define STARPU_SCHED_CTX`
- `#define STARPU_TASK_COLOR`

Functions

- `int starpu_insert_task` (struct `starpu_codelet` *cl,...)
- `int starpu_task_insert` (struct `starpu_codelet` *cl,...)
- `void starpu_task_insert_data_make_room` (struct `starpu_codelet` *cl, struct `starpu_task` *task, int *allocated_buffers, int current_buffer, int room)
- `void starpu_task_insert_data_process_arg` (struct `starpu_codelet` *cl, struct `starpu_task` *task, int *allocated_buffers, int *current_buffer, int arg_type, `starpu_data_handle_t` handle)
- `void starpu_task_insert_data_process_array_arg` (struct `starpu_codelet` *cl, struct `starpu_task` *task, int *allocated_buffers, int *current_buffer, int nb_handles, `starpu_data_handle_t` *handles)
- `void starpu_task_insert_data_process_mode_array_arg` (struct `starpu_codelet` *cl, struct `starpu_task` *task, int *allocated_buffers, int *current_buffer, int nb_descrs, struct `starpu_data_descr` *descrs)
- `void starpu_codelet_pack_args` (void **arg_buffer, size_t *arg_buffer_size,...)
- `void starpu_codelet_pack_arg_init` (struct `starpu_codelet_pack_arg_data` *state)
- `void starpu_codelet_pack_arg_fini` (struct `starpu_codelet_pack_arg_data` *state, void **cl_arg, size_t *cl_arg_size)
- `void starpu_codelet_unpack_args` (void *cl_arg,...)
- `void starpu_codelet_unpack_args_and_copyleft` (void *cl_arg, void *buffer, size_t buffer_size,...)
- `struct starpu_task * starpu_task_build` (struct `starpu_codelet` *cl,...)

28.14.1 Detailed Description

28.14.2 Macro Definition Documentation

28.14.2.1 STARPU_VALUE

```
#define STARPU_VALUE
```

this macro is used when calling `starpu_task_insert()`, and must be followed by a pointer to a constant value and the size of the constant

28.14.2.2 STARPU_CL_ARGS

```
#define STARPU_CL_ARGS
```

this macro is used when calling [starpu_task_insert\(\)](#), and must be followed by a memory buffer containing the arguments to be given to the task, and by the size of the arguments. The memory buffer should be the result of a previous call to [starpu_codelet_pack_args\(\)](#), and will be freed (i.e. [starpu_task::cl_arg_free](#) will be set to 1)

28.14.2.3 STARPU_CALLBACK

```
#define STARPU_CALLBACK
```

this macro is used when calling [starpu_task_insert\(\)](#), and must be followed by a pointer to a callback function

28.14.2.4 STARPU_CALLBACK_WITH_ARG

```
#define STARPU_CALLBACK_WITH_ARG
```

this macro is used when calling [starpu_task_insert\(\)](#), and must be followed by two pointers: one to a callback function, and the other to be given as an argument to the callback function; this is equivalent to using both [STARPU_CALLBACK](#) and [STARPU_CALLBACK_WITH_ARG](#).

28.14.2.5 STARPU_CALLBACK_ARG

```
#define STARPU_CALLBACK_ARG
```

this macro is used when calling [starpu_task_insert\(\)](#), and must be followed by a pointer to be given as an argument to the callback function

28.14.2.6 STARPU_PRIORITY

```
#define STARPU_PRIORITY
```

this macro is used when calling [starpu_task_insert\(\)](#), and must be followed by a integer defining a priority level

28.14.2.7 STARPU_DATA_ARRAY

```
#define STARPU_DATA_ARRAY
```

TODO

28.14.2.8 STARPU_DATA_MODE_ARRAY

```
#define STARPU_DATA_MODE_ARRAY
```

TODO

28.14.2.9 STARPU_EXECUTE_ON_WORKER

```
#define STARPU_EXECUTE_ON_WORKER
```

this macro is used when calling [starpu_task_insert\(\)](#), and must be followed by an integer value specifying the worker on which to execute the task (as specified by [starpu_task::execute_on_a_specific_worker](#))

28.14.2.10 STARPU_WORKER_ORDER

```
#define STARPU_WORKER_ORDER
```

this macro is used when calling [starpu_task_insert\(\)](#), and must be followed by an integer value specifying the worker order in which to execute the tasks (as specified by [starpu_task::workerorder](#))

28.14.2.11 STARPU_TAG

```
#define STARPU_TAG
```

this macro is used when calling [starpu_task_insert\(\)](#), and must be followed by a tag.

28.14.2.12 STARPU_TAG_ONLY

```
#define STARPU_TAG_ONLY
```

this macro is used when calling [starpu_task_insert\(\)](#), and must be followed by a tag. It sets [starpu_task::tag_id](#), but leaves [starpu_task::use_tag](#) as 0.

28.14.2.13 STARPU_NAME

```
#define STARPU_NAME
```

this macro is used when calling [starpu_task_insert\(\)](#), and must be followed by a char *. It sets [starpu_task::name](#) to it.

28.14.2.14 STARPU_FLOPS

```
#define STARPU_FLOPS
```

this macro is used when calling [starpu_task_insert\(\)](#), and must be followed by an amount of floating point operations, as a double. Users **MUST** explicitly cast into double, otherwise parameter passing will not work.

28.14.2.15 STARPU_SCHED_CTX

```
#define STARPU_SCHED_CTX
```

this macro is used when calling [starpu_task_insert\(\)](#), and must be followed by the id of the scheduling context to which we want to submit the task.

28.14.2.16 STARPU_TASK_COLOR

```
#define STARPU_TASK_COLOR
```

Used when calling [starpu_task_insert\(\)](#), must be followed by an integer representing a color

28.14.3 Function Documentation

28.14.3.1 starpu_insert_task()

```
int starpu_insert_task (
    struct starpu_codelet * cl,
    ... )
```

This function does the same as the function [starpu_task_insert\(\)](#). It has been kept to avoid breaking old codes.

28.14.3.2 starpu_task_insert()

```
int starpu_task_insert (
    struct starpu_codelet * cl,
    ... )
```

Create and submit a task corresponding to `cl` with the following arguments. The argument list must be zero-terminated.

The arguments following the codelet can be of the following types:

- [STARPU_R](#), [STARPU_W](#), [STARPU_RW](#), [STARPU_SCRATCH](#), [STARPU_REDUX](#) an access mode followed by a data handle;
- [STARPU_DATA_ARRAY](#) followed by an array of data handles and its number of elements;
- [STARPU_DATA_MODE_ARRAY](#) followed by an array of struct [starpu_data_descr](#), i.e data handles with their associated access modes, and its number of elements;
- [STARPU_EXECUTE_ON_WORKER](#), [STARPU_WORKER_ORDER](#) followed by an integer value specifying the worker on which to execute the task (as specified by [starpu_task::execute_on_a_specific_worker](#))
- the specific values [STARPU_VALUE](#), [STARPU_CALLBACK](#), [STARPU_CALLBACK_ARG](#), [STARPU_CALLBACK_WITH_ARG](#), [STARPU_PRIORITY](#), [STARPU_TAG](#), [STARPU_TAG_ONLY](#), [STARPU_FLOPS](#), [STARPU_SCHED_CTX](#), [STARPU_CL_ARGS](#), [STARPU_TASK_COLOR](#) followed by the appropriated objects as defined elsewhere.

When using [STARPU_DATA_ARRAY](#), the access mode of the data handles is not defined, it will be taken from the codelet [starpu_codelet::modes](#) or [starpu_codelet::dyn_modes](#) field. One should use [STARPU_DATA_MODE_ARRAY](#) to define the data handles along with the access modes.

Parameters to be passed to the codelet implementation are defined through the type [STARPU_VALUE](#). The function [starpu_codelet_unpack_args\(\)](#) must be called within the codelet implementation to retrieve them.

28.14.3.3 `starpu_task_insert_data_make_room()`

```
void starpu_task_insert_data_make_room (
    struct starpu_codelet * cl,
    struct starpu_task * task,
    int * allocated_buffers,
    int current_buffer,
    int room )
```

Assuming that there are already `current_buffer` data handles passed to the task, and if `*allocated_buffers` is not 0, the `task->dyn_handles` array has size `*allocated_buffers`, this function makes room for `room` other data handles, allocating or reallocating `task->dyn_handles` as necessary and updating `*allocated_buffers` accordingly. One can thus start with `*allocated_buffers` equal to 0 and `current_buffer` equal to 0, then make room by calling this function, then store handles with `STARPU_TASK_SET_HANDLE()`, make room again with this function, store yet more handles, etc.

28.14.3.4 `starpu_task_insert_data_process_arg()`

```
void starpu_task_insert_data_process_arg (
    struct starpu_codelet * cl,
    struct starpu_task * task,
    int * allocated_buffers,
    int * current_buffer,
    int arg_type,
    starpu_data_handle_t handle )
```

Store data handle `handle` into task `task` with mode `arg_type`, updating `*allocated_buffers` and `*current_buffer` accordingly.

28.14.3.5 `starpu_task_insert_data_process_array_arg()`

```
void starpu_task_insert_data_process_array_arg (
    struct starpu_codelet * cl,
    struct starpu_task * task,
    int * allocated_buffers,
    int * current_buffer,
    int nb_handles,
    starpu_data_handle_t * handles )
```

Store `nb_handles` data handles `handles` into task `task`, updating `allocated_buffers` and `*current_buffer` accordingly.

28.14.3.6 `starpu_task_insert_data_process_mode_array_arg()`

```
void starpu_task_insert_data_process_mode_array_arg (
    struct starpu_codelet * cl,
    struct starpu_task * task,
    int * allocated_buffers,
    int * current_buffer,
    int nb_descrs,
    struct starpu_data_descr * descrs )
```

Store `nb_descrs` data handles described by `descrs` into task `task`, updating `*allocated_buffers` and `*current_buffer` accordingly.

28.14.3.7 `starpu_codelet_pack_args()`

```
void starpu_codelet_pack_args (
    void ** arg_buffer,
    size_t * arg_buffer_size,
    ... )
```

Pack arguments of type `STARPU_VALUE` into a buffer which can be given to a codelet and later unpacked with the function `starpu_codelet_unpack_args()`.

Instead of calling `starpu_codelet_pack_args()`, one can also call `starpu_codelet_pack_arg_init()`, then `starpu_codelet_pack_arg()` for each data, then `starpu_codelet_pack_arg_fini()`.

28.14.3.8 `starpu_codelet_pack_arg_init()`

```
void starpu_codelet_pack_arg_init (
    struct starpu_codelet_pack_arg_data * state )
```

Initialize struct `starpu_codelet_pack_arg` before calling `starpu_codelet_pack_arg()` and `starpu_codelet_pack_arg_fini()`. This will simply initialize the content of the structure.

28.14.3.9 `starpu_codelet_pack_arg_fini()`

```
void starpu_codelet_pack_arg_fini (
    struct starpu_codelet_pack_arg_data * state,
    void ** cl_arg,
    size_t * cl_arg_size )
```

Finish packing data, after calling `starpu_codelet_pack_arg_init()` once and `starpu_codelet_pack_arg()` several times.

28.14.3.10 `starpu_codelet_unpack_args()`

```
void starpu_codelet_unpack_args (
    void * cl_arg,
    ... )
```

Retrieve the arguments of type `STARPU_VALUE` associated to a task automatically created using the function `starpu_task_insert()`. If any parameter's value is 0, unpacking will stop there and ignore the remaining parameters.

28.14.3.11 `starpu_codelet_unpack_args_and_copyleft()`

```
void starpu_codelet_unpack_args_and_copyleft (
    void * cl_arg,
    void * buffer,
    size_t buffer_size,
    ... )
```

Similar to `starpu_codelet_unpack_args()`, but if any parameter is 0, copy the part of `cl_arg` that has not been read in buffer which can then be used in a later call to one of the unpack functions.

28.14.3.12 `starpu_task_build()`

```
struct starpu\_task * starpu_task_build (
    struct starpu\_codelet * cl,
    ... )
```

Create a task corresponding to `cl` with the following arguments. The argument list must be zero-terminated. The arguments following the codelet are the same as the ones for the function [starpu_task_insert\(\)](#). If some arguments of type [STARPU_VALUE](#) are given, the parameter `starpu_task::cl_arg_free` will be set to 1.

28.15 Explicit Dependencies

Typedefs

- typedef uint64_t [starpu_tag_t](#)

Functions

- void [starpu_task_declare_deps_array](#) (struct [starpu_task](#) *task, unsigned ndeps, struct [starpu_task](#) *task_array[])
- int [starpu_task_get_task_succs](#) (struct [starpu_task](#) *task, unsigned ndeps, struct [starpu_task](#) *task_array[])
- int [starpu_task_get_task_scheduled_succs](#) (struct [starpu_task](#) *task, unsigned ndeps, struct [starpu_task](#) *task_array[])
- void [starpu_tag_declare_deps](#) ([starpu_tag_t](#) id, unsigned ndeps,...)
- void [starpu_tag_declare_deps_array](#) ([starpu_tag_t](#) id, unsigned ndeps, [starpu_tag_t](#) *array)
- int [starpu_tag_wait](#) ([starpu_tag_t](#) id)
- int [starpu_tag_wait_array](#) (unsigned ntags, [starpu_tag_t](#) *id)
- void [starpu_tag_restart](#) ([starpu_tag_t](#) id)
- void [starpu_tag_remove](#) ([starpu_tag_t](#) id)
- void [starpu_tag_notify_from_apps](#) ([starpu_tag_t](#) id)

28.15.1 Detailed Description

28.15.2 Typedef Documentation

28.15.2.1 `starpu_tag_t`

[starpu_tag_t](#)

This type defines a task logical identifier. It is possible to associate a task with a unique *tag* chosen by the application, and to express dependencies between tasks by the means of those tags. To do so, fill the field `starpu_task::tag_id` with a tag number (can be arbitrary) and set the field `starpu_task::use_tag` to 1. If [starpu_tag_declare_deps\(\)](#) is called with this tag number, the task will not be started until the tasks which holds the declared dependency tags are completed.

28.15.3 Function Documentation

28.15.3.1 `starpu_task_declare_deps_array()`

```
void starpu_task_declare_deps_array (
    struct starpu\_task * task,
    unsigned ndeps,
    struct starpu\_task * task_array[] )
```

Declare task dependencies between a `task` and an array of tasks of length `ndeps`. This function must be called prior to the submission of the task, but it may called after the submission or the execution of the tasks in the array, provided the tasks are still valid (i.e. they were not automatically destroyed). Calling this function on a task that was already submitted or with an entry of `task_array` that is no longer a valid task results in an undefined behaviour. If `ndeps` is 0, no dependency is added. It is possible to call [starpu_task_declare_deps_array\(\)](#) several times on the same task, in this case, the dependencies are added. It is possible to have redundancy in the task dependencies.

28.15.3.2 `starpu_task_get_task_succs()`

```
int starpu_task_get_task_succs (
    struct starpu\_task * task,
    unsigned ndeps,
    struct starpu\_task * task_array[] )
```

Fills `task_array` with the list of tasks which are direct children of `task`. `ndeps` is the size of `task_array`. This function returns the number of direct children. `task_array` can be set to NULL if `ndeps` is 0, which allows to compute the number of children before allocating an array to store them. This function can only be called if `task` has not completed yet, otherwise the results are undefined. The result may also be outdated if some additional dependency has been added in the meanwhile.

28.15.3.3 `starpu_task_get_task_scheduled_succs()`

```
int starpu_task_get_task_scheduled_succs (
    struct starpu\_task * task,
    unsigned ndeps,
    struct starpu\_task * task_array[] )
```

This behaves like [starpu_task_get_task_succs\(\)](#), except that it only reports tasks which will go through the scheduler, thus avoiding tasks with not codelet, or with explicit placement.

28.15.3.4 `starpu_tag_declare_deps()`

```
void starpu_tag_declare_deps (
    starpu_tag_t id,
    unsigned ndeps,
    ... )
```

Specify the dependencies of the task identified by tag `id`. The first argument specifies the tag which is configured, the second argument gives the number of tag(s) on which `id` depends. The following arguments are the tags which have to be terminated to unlock the task. This function must be called before the associated task is submitted to StarPU with `starpu_task_submit()`.

WARNING! Use with caution. Because of the variable arity of `starpu_tag_declare_deps()`, note that the last arguments must be of type `starpu_tag_t`: constant values typically need to be explicitly casted. Otherwise, due to integer sizes and argument passing on the stack, the C compiler might consider the tag `0x200000003` instead of `0x2` and `0x3` when calling `starpu_tag_declare_deps(0x1, 2, 0x2, 0x3)`. Using the `starpu_tag_declare_deps_array()` function avoids this hazard.

```
/* Tag 0x1 depends on tags 0x32 and 0x52 */
starpu_tag_declare_deps((starpu_tag_t)0x1, 2, (starpu_tag_t)
    0x32, (starpu_tag_t)0x52);
```

28.15.3.5 `starpu_tag_declare_deps_array()`

```
void starpu_tag_declare_deps_array (
    starpu_tag_t id,
    unsigned ndeps,
    starpu_tag_t * array )
```

This function is similar to `starpu_tag_declare_deps()`, except that it does not take a variable number of arguments but an array of tags of size `ndeps`.

```
/* Tag 0x1 depends on tags 0x32 and 0x52 */
starpu_tag_t tag_array[2] = {0x32, 0x52};
starpu_tag_declare_deps_array((starpu_tag_t)0x1, 2, tag_array);
```

28.15.3.6 `starpu_tag_wait()`

```
int starpu_tag_wait (
    starpu_tag_t id )
```

This function blocks until the task associated to tag `id` has been executed. This is a blocking call which must therefore not be called within tasks or callbacks, but only from the application directly. It is possible to synchronize with the same tag multiple times, as long as the `starpu_tag_remove()` function is not called. Note that it is still possible to synchronize with a tag associated to a task for which the structure `starpu_task` was freed (e.g. if the field `starpu_task::destroy` was enabled).

28.15.3.7 `starpu_tag_wait_array()`

```
int starpu_tag_wait_array (
    unsigned ntags,
    starpu_tag_t * id )
```

This function is similar to [starpu_tag_wait\(\)](#) except that it blocks until all the `ntags` tags contained in the array `id` are terminated.

28.15.3.8 `starpu_tag_restart()`

```
void starpu_tag_restart (
    starpu_tag_t id )
```

This function can be used to clear the *already notified* status of a tag which is not associated with a task. Before that, calling [starpu_tag_notify_from_apps\(\)](#) again will not notify the successors. After that, the next call to [starpu_tag_notify_from_apps\(\)](#) will notify the successors.

28.15.3.9 `starpu_tag_remove()`

```
void starpu_tag_remove (
    starpu_tag_t id )
```

This function releases the resources associated to tag `id`. It can be called once the corresponding task has been executed and when there is no other tag that depend on this tag anymore.

28.15.3.10 `starpu_tag_notify_from_apps()`

```
void starpu_tag_notify_from_apps (
    starpu_tag_t id )
```

This function explicitly unlocks tag `id`. It may be useful in the case of applications which execute part of their computation outside StarPU tasks (e.g. third-party libraries). It is also provided as a convenient tool for the programmer, for instance to entirely construct the task DAG before actually giving StarPU the opportunity to execute the tasks. When called several times on the same tag, notification will be done only on first call, thus implementing "OR" dependencies, until the tag is restarted using [starpu_tag_restart\(\)](#).

28.16 Implicit Data Dependencies

In this section, we describe how StarPU makes it possible to insert implicit task dependencies in order to enforce sequential data consistency. When this data consistency is enabled on a specific data handle, any data access will appear as sequentially consistent from the application. For instance, if the application submits two tasks that access the same piece of data in read-only mode, and then a third task that access it in write mode, dependencies will be added between the two first tasks and the third one. Implicit data dependencies are also inserted in the case of data accesses from the application.

Functions

- void [starpu_data_set_default_sequential_consistency_flag](#) (unsigned flag)
- unsigned [starpu_data_get_default_sequential_consistency_flag](#) (void)
- void [starpu_data_set_sequential_consistency_flag](#) ([starpu_data_handle_t](#) handle, unsigned flag)
- unsigned [starpu_data_get_sequential_consistency_flag](#) ([starpu_data_handle_t](#) handle)

28.16.1 Detailed Description

In this section, we describe how StarPU makes it possible to insert implicit task dependencies in order to enforce sequential data consistency. When this data consistency is enabled on a specific data handle, any data access will appear as sequentially consistent from the application. For instance, if the application submits two tasks that access the same piece of data in read-only mode, and then a third task that access it in write mode, dependencies will be added between the two first tasks and the third one. Implicit data dependencies are also inserted in the case of data accesses from the application.

28.16.2 Function Documentation

28.16.2.1 [starpu_data_set_default_sequential_consistency_flag\(\)](#)

```
void starpu_data_set_default_sequential_consistency_flag (  
    unsigned flag )
```

Set the default sequential consistency flag. If a non-zero value is passed, a sequential data consistency will be enforced for all handles registered after this function call, otherwise it is disabled. By default, StarPU enables sequential data consistency. It is also possible to select the data consistency mode of a specific data handle with the function [starpu_data_set_sequential_consistency_flag\(\)](#).

28.16.2.2 [starpu_data_get_default_sequential_consistency_flag\(\)](#)

```
unsigned starpu_data_get_default_sequential_consistency_flag (  
    void )
```

Return the default sequential consistency flag

28.16.2.3 [starpu_data_set_sequential_consistency_flag\(\)](#)

```
void starpu_data_set_sequential_consistency_flag (  
    starpu\_data\_handle\_t handle,  
    unsigned flag )
```

Set the data consistency mode associated to a data handle. The consistency mode set using this function has the priority over the default mode which can be set with [starpu_data_set_default_sequential_consistency_flag\(\)](#).

28.16.2.4 starpu_data_get_sequential_consistency_flag()

```
unsigned starpu_data_get_sequential_consistency_flag (
    starpu_data_handle_t handle )
```

Get the data consistency mode associated to the data handle `handle`

28.17 Performance Model

Data Structures

- struct [starpu_perfmodel_device](#)
- struct [starpu_perfmodel_arch](#)
- struct [starpu_perfmodel](#)
- struct [starpu_perfmodel_regression_model](#)
- struct [starpu_perfmodel_per_arch](#)
- struct [starpu_perfmodel_history_list](#)
- struct [starpu_perfmodel_history_entry](#)

Enumerations

- enum [starpu_perfmodel_type](#) {
STARPU_PERFMODEL_INVALID, **STARPU_PER_ARCH**, **STARPU_COMMON**, **STARPU_HISTORY_B↵**
ASED,
STARPU_REGRESSION_BASED, **STARPU_NL_REGRESSION_BASED** }

Functions

- void [starpu_perfmodel_init](#) (struct [starpu_perfmodel](#) *model)
- void [starpu_perfmodel_free_sampling_directories](#) (void)
- int [starpu_perfmodel_load_file](#) (const char *filename, struct [starpu_perfmodel](#) *model)
- int [starpu_perfmodel_load_symbol](#) (const char *symbol, struct [starpu_perfmodel](#) *model)
- int [starpu_perfmodel_unload_model](#) (struct [starpu_perfmodel](#) *model)
- void [starpu_perfmodel_debugfilepath](#) (struct [starpu_perfmodel](#) *model, struct [starpu_perfmodel_arch](#) *arch, char *path, size_t maxlen, unsigned nimpl)
- char * [starpu_perfmodel_get_archtype_name](#) (enum [starpu_worker_archtype](#) archtype)
- void [starpu_perfmodel_get_arch_name](#) (struct [starpu_perfmodel_arch](#) *arch, char *archname, size_t ↵
maxlen, unsigned nimpl)
- struct [starpu_perfmodel_arch](#) * [starpu_worker_get_perf_archtype](#) (int workerid, unsigned sched_ctx_id)
- void [starpu_perfmodel_initialize](#) (void)
- int [starpu_perfmodel_list](#) (FILE *output)
- void [starpu_perfmodel_directory](#) (FILE *output)
- void [starpu_perfmodel_print](#) (struct [starpu_perfmodel](#) *model, struct [starpu_perfmodel_arch](#) *arch, unsigned
nimpl, char *parameter, uint32_t *footprint, FILE *output)
- int [starpu_perfmodel_print_all](#) (struct [starpu_perfmodel](#) *model, char *arch, char *parameter, uint32_t ↵
t *footprint, FILE *output)
- int [starpu_perfmodel_print_estimations](#) (struct [starpu_perfmodel](#) *model, uint32_t footprint, FILE *output)
- void [starpu_bus_print_bandwidth](#) (FILE *f)
- void [starpu_bus_print_affinity](#) (FILE *f)
- void [starpu_bus_print_filenames](#) (FILE *f)
- void [starpu_perfmodel_update_history](#) (struct [starpu_perfmodel](#) *model, struct [starpu_task](#) *task, struct
[starpu_perfmodel_arch](#) *arch, unsigned cpuid, unsigned nimpl, double measured)
- double [starpu_transfer_bandwidth](#) (unsigned src_node, unsigned dst_node)
- double [starpu_transfer_latency](#) (unsigned src_node, unsigned dst_node)
- double [starpu_transfer_predict](#) (unsigned src_node, unsigned dst_node, size_t size)
- double [starpu_perfmodel_history_based_expected_perf](#) (struct [starpu_perfmodel](#) *model, struct [starpu_↵](#)
[perfmodel_arch](#) *arch, uint32_t footprint)

28.17.1 Detailed Description

28.17.2 Data Structure Documentation

28.17.2.1 struct starpu_perfmodel_device

todo

Data Fields

enum starpu_worker_archtype	type	is the type of the device
int	devid	is the identifier of the precise device
int	ncores	

28.17.2.2 struct starpu_perfmodel_arch

todo

Data Fields

int	ndevices	is the number of the devices for the given arch
struct starpu_perfmodel_device *	devices	is the list of the devices for the given arch

28.17.2.3 struct starpu_perfmodel

Contains all information about a performance model. At least the type and symbol fields have to be filled when defining a performance model for a codelet. For compatibility, make sure to initialize the whole structure to zero, either by using explicit memset, or by letting the compiler implicitly do it in e.g. static storage case. If not provided, other fields have to be zero.

Data Fields

- enum [starpu_perfmodel_type](#) type
- double(* [cost_function](#))(struct [starpu_task](#) *, unsigned nimpl)
- double(* [arch_cost_function](#))(struct [starpu_task](#) *, struct [starpu_perfmodel_arch](#) *arch, unsigned nimpl)
- size_t(* [size_base](#))(struct [starpu_task](#) *, unsigned nimpl)
- uint32_t(* [footprint](#))(struct [starpu_task](#) *)
- const char * [symbol](#)
- unsigned [is_loaded](#)
- unsigned **benchmarking**
- unsigned [is_init](#)
- starpu_perfmodel_state_t **state**

28.17.2.3.1 Field Documentation

28.17.2.3.1.1 type

```
enum starpu_perfmodel_type starpu_perfmodel::type
```

is the type of performance model

- [STARPU_HISTORY_BASED](#), [STARPU_REGRESSION_BASED](#), [STARPU_NL_REGRESSION_BASED](#)↵: No other fields needs to be provided, this is purely history-based.
- [STARPU_PER_ARCH](#): either field [starpu_perfmodel::arch_cost_function](#) has to be filled with a function that returns the cost in micro-seconds on the arch given as parameter, or field [starpu_perfmodel::per_arch](#) has to be filled with functions which return the cost in micro-seconds.
- [STARPU_COMMON](#): field [starpu_perfmodel::cost_function](#) has to be filled with a function that returns the cost in micro-seconds on a CPU, timing on other archs will be determined by multiplying by an arch-specific factor.

28.17.2.3.1.2 cost_function

```
double(* starpu_perfmodel::cost_function)(struct starpu_task *, unsigned nimpl)
```

Used by [STARPU_COMMON](#): takes a task and implementation number, and must return a task duration estimation in micro-seconds.

28.17.2.3.1.3 arch_cost_function

```
double(* starpu_perfmodel::arch_cost_function)(struct starpu_task *, struct starpu_perfmodel_↵
arch *arch, unsigned nimpl)
```

Used by [STARPU_COMMON](#): takes a task, an arch and implementation number, and must return a task duration estimation in micro-seconds on that arch.

28.17.2.3.1.4 size_base

```
size_t(* starpu_perfmodel::size_base)(struct starpu_task *, unsigned nimpl)
```

Used by [STARPU_HISTORY_BASED](#), [STARPU_REGRESSION_BASED](#) and [STARPU_NL_REGRESSION_B↵ASED](#). If not NULL, takes a task and implementation number, and returns the size to be used as index to distinguish histories and as a base for regressions.

28.17.2.3.1.5 footprint

```
uint32_t(* starpu_perfmodel::footprint)(struct starpu_task *)
```

Used by [STARPU_HISTORY_BASED](#). If not NULL, takes a task and returns the footprint to be used as index to distinguish histories. The default is to use the `starpu_task_data_footprint` function.

28.17.2.3.1.6 symbol

```
const char * starpu_perfmodel::symbol
```

is the symbol name for the performance model, which will be used as file name to store the model. It must be set otherwise the model will be ignored.

28.17.2.3.1.7 is_loaded

```
unsigned starpu_perfmodel::is_loaded
```

Whether the performance model is already loaded from the disk.

28.17.2.3.1.8 is_init

```
unsigned starpu_perfmodel::is_init
```

todo

28.17.2.4 struct starpu_perfmodel_regression_model

...

Data Fields

double	sumlny	sum of $\ln(\text{measured})$
double	sumlnx	sum of $\ln(\text{size})$
double	sumlnx2	sum of $\ln(\text{size})^2$
unsigned long	minx	minimum size
unsigned long	maxx	maximum size
double	sumlnxlny	sum of $\ln(\text{size}) * \ln(\text{measured})$
double	alpha	estimated = $\alpha * \text{size}^\beta$
double	beta	estimated = $\alpha * \text{size}^\beta$
unsigned	valid	whether the linear regression model is valid (i.e. enough measures)
double	a	estimated = $a * \text{size}^b + c$
double	b	estimated = $a * \text{size}^b + c$
double	c	estimated = $a * \text{size}^b + c$
unsigned	nl_valid	whether the non-linear regression model is valid (i.e. enough measures)
unsigned	nsample	number of sample values for non-linear regression

28.17.2.5 struct starpu_perfmodel_per_arch

contains information about the performance model of a given arch.

Data Fields

starpu_perfmodel_per_arch_cost_function	cost_function	Used by STARPU_PER_ARCH , must point to functions which take a task, the target arch and implementation number (as mere convenience, since the array is already indexed by these), and must return a task duration estimation in micro-seconds.
starpu_perfmodel_per_arch_size_base	size_base	Same as in structure starpu_perfmodel , but per-arch, in case it depends on the architecture-specific implementation.

Data Fields

struct starpu_perfmodel_history_table *	history	The history of performance measurements.
struct starpu_perfmodel_history_list *	list	Used by STARPU_HISTORY_BASED and STARPU_NL_REGRESSION_BASED , records all execution history measures.
struct starpu_perfmodel_regression_model	regression	Used by STARPU_REGRESSION_BASED and STARPU_NL_REGRESSION_BASED , contains the estimated factors of the regression.
char	debug_path[256]	

28.17.2.6 struct starpu_perfmodel_history_list

todo

Data Fields

struct starpu_perfmodel_history_list *	next	todo
struct starpu_perfmodel_history_entry *	entry	todo

28.17.2.7 struct starpu_perfmodel_history_entry

todo

Data Fields

double	mean	mean_n = 1/n sum
double	deviation	n dev_n = sum2 - 1/n (sum)^2
double	sum	sum of samples (in μ s)
double	sum2	sum of samples^2
unsigned	nsample	number of samples
unsigned	nerror	
uint32_t	footprint	data footprint
size_t	size	in bytes
double	flops	Provided by the application

28.17.3 Enumeration Type Documentation

28.17.3.1 `starpu_perfmodel_type`

```
enum starpu_perfmodel_type
```

TODO

Enumerator

STARPU_PER_ARCH	Application-provided per-arch cost model function
STARPU_COMMON	Application-provided common cost model function, with per-arch factor
STARPU_HISTORY_BASED	Automatic history-based cost model
STARPU_REGRESSION_BASED	Automatic linear regression-based cost model ($\alpha * \text{size}^\beta$)
STARPU_NL_REGRESSION_BASED	Automatic non-linear regression-based cost model ($a * \text{size}^b + c$)

28.17.4 Function Documentation

28.17.4.1 `starpu_perfmodel_init()`

```
void starpu_perfmodel_init (
    struct starpu_perfmodel * model )
```

todo

28.17.4.2 `starpu_perfmodel_free_sampling_directories()`

```
void starpu_perfmodel_free_sampling_directories (
    void )
```

this function frees internal memory used for sampling directory management. It should only be called by an application which is not calling `starpu_shutdown` as this function already calls it. See for example `tools/starpu_perfmodel_display.c`.

28.17.4.3 `starpu_perfmodel_load_file()`

```
int starpu_perfmodel_load_file (
    const char * filename,
    struct starpu_perfmodel * model )
```

loads the performance model found in the given file. The model structure has to be completely zero, and will be filled with the information stored in the given file.

28.17.4.4 `starpu_perfmodel_load_symbol()`

```
int starpu_perfmodel_load_symbol (
    const char * symbol,
    struct starpu_perfmodel * model )
```

loads a given performance model. The model structure has to be completely zero, and will be filled with the information saved in `$STARPU_HOME/.starpu`. The function is intended to be used by external tools that should read the performance model files.

28.17.4.5 `starpu_perfmodel_unload_model()`

```
int starpu_perfmodel_unload_model (
    struct starpu_perfmodel * model )
```

unloads the given model which has been previously loaded through the function `starpu_perfmodel_load_symbol()`

28.17.4.6 `starpu_perfmodel_debugfilepath()`

```
void starpu_perfmodel_debugfilepath (
    struct starpu_perfmodel * model,
    struct starpu_perfmodel_arch * arch,
    char * path,
    size_t maxlen,
    unsigned nimpl )
```

returns the path to the debugging information for the performance model.

28.17.4.7 `starpu_perfmodel_get_archtype_name()`

```
char * starpu_perfmodel_get_archtype_name (
    enum starpu_worker_archtype archtype )
```

todo

28.17.4.8 `starpu_perfmodel_get_arch_name()`

```
void starpu_perfmodel_get_arch_name (
    struct starpu_perfmodel_arch * arch,
    char * archname,
    size_t maxlen,
    unsigned nimpl )
```

returns the architecture name for `arch`

28.17.4.9 `starpu_worker_get_perf_archtype()`

```
struct starpu_perfmodel_arch * starpu_worker_get_perf_archtype (
    int workerid,
    unsigned sched_ctx_id )
```

returns the architecture type of a given worker.

28.17.4.10 starpu_perfmodel_initialize()

```
void starpu_perfmodel_initialize (
    void )
```

If `starpu_init` is not used, `starpu_perfmodel_initialize` should be used before calling `starpu_perfmodel_*` functions.

28.17.4.11 starpu_perfmodel_list()

```
int starpu_perfmodel_list (
    FILE * output )
```

prints a list of all performance models on `output`

28.17.4.12 starpu_perfmodel_directory()

```
void starpu_perfmodel_directory (
    FILE * output )
```

prints the directory name storing performance models on `output`

28.17.4.13 starpu_perfmodel_print()

```
void starpu_perfmodel_print (
    struct starpu_perfmodel * model,
    struct starpu_perfmodel_arch * arch,
    unsigned nimpl,
    char * parameter,
    uint32_t * footprint,
    FILE * output )
```

todo

28.17.4.14 starpu_perfmodel_print_all()

```
int starpu_perfmodel_print_all (
    struct starpu_perfmodel * model,
    char * arch,
    char * parameter,
    uint32_t * footprint,
    FILE * output )
```

todo

28.17.4.15 starpu_perfmodel_print_estimations()

```
int starpu_perfmodel_print_estimations (
    struct starpu_perfmodel * model,
    uint32_t footprint,
    FILE * output )
```

todo

28.17.4.16 starpu_bus_print_bandwidth()

```
void starpu_bus_print_bandwidth (
    FILE * f )
```

prints a matrix of bus bandwidths on *f*.

28.17.4.17 starpu_bus_print_affinity()

```
void starpu_bus_print_affinity (
    FILE * f )
```

prints the affinity devices on *f*.

28.17.4.18 starpu_bus_print_filenames()

```
void starpu_bus_print_filenames (
    FILE * f )
```

prints on *f* the name of the files containing the matrix of bus bandwidths, the affinity devices and the latency.

28.17.4.19 starpu_perfmodel_update_history()

```
void starpu_perfmodel_update_history (
    struct starpu_perfmodel * model,
    struct starpu_task * task,
    struct starpu_perfmodel_arch * arch,
    unsigned cpuid,
    unsigned nimpl,
    double measured )
```

This feeds the performance model *model* with an explicit measurement *measured* (in μ s), in addition to measurements done by StarPU itself. This can be useful when the application already has an existing set of measurements done in good conditions, that StarPU could benefit from instead of doing on-line measurements. And example of use can be seen in [Performance Model Example](#).

28.17.4.20 starpu_transfer_bandwidth()

```
double starpu_transfer_bandwidth (
    unsigned src_node,
    unsigned dst_node )
```

Return the bandwidth of data transfer between two memory nodes

28.17.4.21 starpu_transfer_latency()

```
double starpu_transfer_latency (
    unsigned src_node,
    unsigned dst_node )
```

Return the latency of data transfer between two memory nodes

28.17.4.22 starpu_transfer_predict()

```
double starpu_transfer_predict (
    unsigned src_node,
    unsigned dst_node,
    size_t size )
```

Return the estimated time to transfer a given size between two memory nodes.

28.17.4.23 starpu_perfmodel_history_based_expected_perf()

```
double starpu_perfmodel_history_based_expected_perf (
    struct starpu_perfmodel * model,
    struct starpu_perfmodel_arch * arch,
    uint32_t footprint )
```

Return the estimated time of a task whose model is named `and` and whose footprint is `footprint`

28.18 Profiling

Data Structures

- struct [starpu_profiling_task_info](#)
- struct [starpu_profiling_worker_info](#)
- struct [starpu_profiling_bus_info](#)

Macros

- `#define` [STARPU_PROFILING_DISABLE](#)
- `#define` [STARPU_PROFILING_ENABLE](#)

Functions

- int [starpu_profiling_status_set](#) (int status)
- int [starpu_profiling_status_get](#) (void)
- void [starpu_profiling_init](#) (void)
- void [starpu_profiling_set_id](#) (int new_id)
- int [starpu_profiling_worker_get_info](#) (int workerid, struct [starpu_profiling_worker_info](#) *worker_info)
- int [starpu_bus_get_profiling_info](#) (int busid, struct [starpu_profiling_bus_info](#) *bus_info)
- int [starpu_bus_get_count](#) (void)
- int [starpu_bus_get_id](#) (int src, int dst)
- int [starpu_bus_get_src](#) (int busid)
- int [starpu_bus_get_dst](#) (int busid)
- double [starpu_timing_timespec_delay_us](#) (struct timespec *start, struct timespec *end)
- double [starpu_timing_timespec_to_us](#) (struct timespec *ts)
- void [starpu_profiling_bus_helper_display_summary](#) (void)
- void [starpu_profiling_worker_helper_display_summary](#) (void)
- void [starpu_data_display_memory_stats](#) ()

28.18.1 Detailed Description

28.18.2 Data Structure Documentation

28.18.2.1 `struct starpu_profiling_task_info`

This structure contains information about the execution of a task. It is accessible from the field [starpu_task↔::profiling_info](#) if profiling was enabled.

Data Fields

struct timespec	submit_time	Date of task submission (relative to the initialization of StarPU).
struct timespec	push_start_time	Time when the task was submitted to the scheduler.
struct timespec	push_end_time	Time when the scheduler finished with the task submission.
struct timespec	pop_start_time	Time when the scheduler started to be requested for a task, and eventually gave that task.
struct timespec	pop_end_time	Time when the scheduler finished providing the task for execution.
struct timespec	acquire_data_start_time	Time when the worker started fetching input data.
struct timespec	acquire_data_end_time	Time when the worker finished fetching input data.
struct timespec	start_time	Date of task execution beginning (relative to the initialization of StarPU).
struct timespec	end_time	Date of task execution termination (relative to the initialization of StarPU).
struct timespec	release_data_start_time	Time when the worker started releasing data.
struct timespec	release_data_end_time	Time when the worker finished releasing data.
struct timespec	callback_start_time	Time when the worker started the application callback for the task.
struct timespec	callback_end_time	Time when the worker finished the application callback for the task.
int	workerid	Identifier of the worker which has executed the task.
uint64_t	used_cycles	Number of cycles used by the task, only available in the MoviSim
uint64_t	stall_cycles	Number of cycles stalled within the task, only available in the MoviSim
double	energy_consumed	Energy consumed by the task, in Joules

28.18.2.2 struct starpu_profiling_worker_info

This structure contains the profiling information associated to a worker. The timing is provided since the previous call to [starpu_profiling_worker_get_info\(\)](#)

Data Fields

struct timespec	start_time	Starting date for the reported profiling measurements.
struct timespec	total_time	Duration of the profiling measurement interval.
struct timespec	executing_time	Time spent by the worker to execute tasks during the profiling measurement interval.
struct timespec	sleeping_time	Time spent idling by the worker during the profiling measurement interval.
int	executed_tasks	Number of tasks executed by the worker during the profiling measurement interval.
uint64_t	used_cycles	Number of cycles used by the worker, only available in the MoviSim
uint64_t	stall_cycles	Number of cycles stalled within the worker, only available in the MoviSim
double	energy_consumed	Energy consumed by the worker, in Joules

28.18.2.3 struct starpu_profiling_bus_info

todo

Data Fields

struct timespec	start_time	Time of bus profiling startup.
struct timespec	total_time	Total time of bus profiling.
int long long	transferred_bytes	Number of bytes transferred during profiling.
int	transfer_count	Number of transfers during profiling.

28.18.3 Macro Definition Documentation

28.18.3.1 STARPU_PROFILING_DISABLE

STARPU_PROFILING_DISABLE

This value is used when calling the function [starpu_profiling_status_set\(\)](#) to disable profiling.

28.18.3.2 STARPU_PROFILING_ENABLE

STARPU_PROFILING_ENABLE

This value is used when calling the function [starpu_profiling_status_set\(\)](#) to enable profiling.

28.18.4 Function Documentation

28.18.4.1 starpu_profiling_status_set()

```
int starpu_profiling_status_set (
    int status )
```

This function sets the profiling status. Profiling is activated by passing [STARPU_PROFILING_ENABLE](#) in status. Passing [STARPU_PROFILING_DISABLE](#) disables profiling. Calling this function resets all profiling measurements. When profiling is enabled, the field [starpu_task::profiling_info](#) points to a valid structure [starpu_profiling_task_info](#) containing information about the execution of the task. Negative return values indicate an error, otherwise the previous status is returned.

28.18.4.2 starpu_profiling_status_get()

```
int starpu_profiling_status_get (
    void )
```

Return the current profiling status or a negative value in case there was an error.

28.18.4.3 `starpu_profiling_init()`

```
void starpu_profiling_init (
    void )
```

This function resets performance counters and enable profiling if the environment variable `STARPU_PROFILING` is set to a positive value.

28.18.4.4 `starpu_profiling_set_id()`

```
void starpu_profiling_set_id (
    int new_id )
```

This function sets the ID used for profiling trace filename. It needs to be called before `starpu_init()`.

28.18.4.5 `starpu_profiling_worker_get_info()`

```
int starpu_profiling_worker_get_info (
    int workerid,
    struct starpu_profiling_worker_info * worker_info )
```

Get the profiling info associated to the worker identified by `workerid`, and reset the profiling measurements. If the argument `worker_info` is NULL, only reset the counters associated to worker `workerid`. Upon successful completion, this function returns 0. Otherwise, a negative value is returned.

28.18.4.6 `starpu_bus_get_profiling_info()`

```
int starpu_bus_get_profiling_info (
    int busid,
    struct starpu_profiling_bus_info * bus_info )
```

todo

28.18.4.7 `starpu_bus_get_count()`

```
int starpu_bus_get_count (
    void )
```

Return the number of buses in the machine

28.18.4.8 `starpu_bus_get_id()`

```
int starpu_bus_get_id (
    int src,
    int dst )
```

Return the identifier of the bus between `src` and `dst`

28.18.4.9 `starpu_bus_get_src()`

```
int starpu_bus_get_src (
    int busid )
```

Return the source point of bus `busid`

28.18.4.10 `starpu_bus_get_dst()`

```
int starpu_bus_get_dst (
    int busid )
```

Return the destination point of bus `busid`

28.18.4.11 `starpu_timing_timespec_delay_us()`

```
double starpu_timing_timespec_delay_us (
    struct timespec * start,
    struct timespec * end )
```

Returns the time elapsed between `start` and `end` in microseconds.

28.18.4.12 `starpu_timing_timespec_to_us()`

```
double starpu_timing_timespec_to_us (
    struct timespec * ts )
```

Converts the given timespec `ts` into microseconds

28.18.4.13 `starpu_profiling_bus_helper_display_summary()`

```
void starpu_profiling_bus_helper_display_summary (
    void )
```

Displays statistics about the bus on stderr. if the environment variable `STARPU_BUS_STATS` is defined. The function is called automatically by `starpu_shutdown()`.

28.18.4.14 `starpu_profiling_worker_helper_display_summary()`

```
void starpu_profiling_worker_helper_display_summary (
    void )
```

Displays statistics about the workers on stderr if the environment variable `STARPU_WORKER_STATS` is defined. The function is called automatically by `starpu_shutdown()`.

28.18.4.15 `starpu_data_display_memory_stats()`

```
void starpu_data_display_memory_stats ( )
```

Display statistics about the current data handles registered within StarPU. StarPU must have been configured with the configure option `--enable-memory-stats` (see [Memory Feedback](#)).

28.19 Theoretical Lower Bound on Execution Time

Compute theoretical upper computation efficiency bound corresponding to some actual execution.

Functions

- void `starpu_bound_start` (int *deps*, int *prio*)
- void `starpu_bound_stop` (void)
- void `starpu_bound_print_dot` (FILE **output*)
- void `starpu_bound_compute` (double **res*, double **integer_res*, int *integer*)
- void `starpu_bound_print_lp` (FILE **output*)
- void `starpu_bound_print_mps` (FILE **output*)
- void `starpu_bound_print` (FILE **output*, int *integer*)

28.19.1 Detailed Description

Compute theoretical upper computation efficiency bound corresponding to some actual execution.

28.19.2 Function Documentation

28.19.2.1 `starpu_bound_start()`

```
void starpu_bound_start (
    int deps,
    int prio )
```

Start recording tasks (resets stats). *deps* tells whether dependencies should be recorded too (this is quite expensive)

28.19.2.2 `starpu_bound_stop()`

```
void starpu_bound_stop (
    void )
```

Stop recording tasks

28.19.2.3 `starpu_bound_print_dot()`

```
void starpu_bound_print_dot (
    FILE * output )
```

Print the DAG that was recorded

28.19.2.4 `starpu_bound_compute()`

```
void starpu_bound_compute (
    double * res,
    double * integer_res,
    int integer )
```

Get theoretical upper bound (in ms) (needs glpk support detected by configure script). It returns 0 if some performance models are not calibrated.

28.19.2.5 `starpu_bound_print_lp()`

```
void starpu_bound_print_lp (
    FILE * output )
```

Emit the Linear Programming system on `output` for the recorded tasks, in the lp format

28.19.2.6 `starpu_bound_print_mps()`

```
void starpu_bound_print_mps (
    FILE * output )
```

Emit the Linear Programming system on `output` for the recorded tasks, in the mps format

28.19.2.7 `starpu_bound_print()`

```
void starpu_bound_print (
    FILE * output,
    int integer )
```

Emit statistics of actual execution vs theoretical upper bound. `integer` permits to choose between integer solving (which takes a long time but is correct), and relaxed solving (which provides an approximate solution).

28.20 CUDA Extensions

Macros

- `#define STARPU_USE_CUDA`
- `#define STARPU_MAXCUDADEVS`
- `#define STARPU_CUDA_REPORT_ERROR(status)`
- `#define STARPU_CUBLAS_REPORT_ERROR(status)`

Functions

- `cudaStream_t starpu_cuda_get_local_stream` (void)
- `const struct cudaDeviceProp * starpu_cuda_get_device_properties` (unsigned workerid)
- `void starpu_cuda_report_error` (const char *func, const char *file, int line, cudaError_t status)
- `int starpu_cuda_copy_async_sync` (void *src_ptr, unsigned src_node, void *dst_ptr, unsigned dst_node, size_t ssize, cudaStream_t stream, enum cudaMemcpyKind kind)
- `void starpu_cuda_set_device` (unsigned devid)
- `void starpu_cublas_init` (void)
- `void starpu_cublas_shutdown` (void)
- `void starpu_cublas_report_error` (const char *func, const char *file, int line, int status)

28.20.1 Detailed Description

28.20.2 Macro Definition Documentation

28.20.2.1 STARPU_USE_CUDA

```
#define STARPU_USE_CUDA
```

This macro is defined when StarPU has been installed with CUDA support. It should be used in your code to detect the availability of CUDA as shown in [Full source code for the 'Scaling a Vector' example](#).

28.20.2.2 STARPU_MAXCUDADEVs

```
#define STARPU_MAXCUDADEVs
```

This macro defines the maximum number of CUDA devices that are supported by StarPU.

28.20.2.3 STARPU_CUDA_REPORT_ERROR

```
#define STARPU_CUDA_REPORT_ERROR(  
    status )
```

Calls [starpu_cuda_report_error\(\)](#), passing the current function, file and line position.

28.20.2.4 STARPU_CUBLAS_REPORT_ERROR

```
#define STARPU_CUBLAS_REPORT_ERROR(  
    status )
```

Calls [starpu_cublas_report_error\(\)](#), passing the current function, file and line position.

28.20.3 Function Documentation

28.20.3.1 `starpu_cuda_get_local_stream()`

```
cudaStream_t starpu_cuda_get_local_stream (
    void )
```

This function gets the current worker's CUDA stream. StarPU provides a stream for every CUDA device controlled by StarPU. This function is only provided for convenience so that programmers can easily use asynchronous operations within codelets without having to create a stream by hand. Note that the application is not forced to use the stream provided by [starpu_cuda_get_local_stream\(\)](#) and may also create its own streams. Synchronizing with `cudaThreadSynchronize()` is allowed, but will reduce the likelihood of having all transfers overlapped.

28.20.3.2 `starpu_cuda_get_device_properties()`

```
const struct cudaDeviceProp * starpu_cuda_get_device_properties (
    unsigned workerid )
```

This function returns a pointer to device properties for worker `workerid` (assumed to be a CUDA worker).

28.20.3.3 `starpu_cuda_report_error()`

```
void starpu_cuda_report_error (
    const char * func,
    const char * file,
    int line,
    cudaError_t status )
```

Report a CUDA error.

28.20.3.4 `starpu_cuda_copy_async_sync()`

```
int starpu_cuda_copy_async_sync (
    void * src_ptr,
    unsigned src_node,
    void * dst_ptr,
    unsigned dst_node,
    size_t ssize,
    cudaStream_t stream,
    enum cudaMemcpyKind kind )
```

Copy `ssize` bytes from the pointer `src_ptr` on `src_node` to the pointer `dst_ptr` on `dst_node`. The function first tries to copy the data asynchronously (unless `stream` is `NULL`). If the asynchronous copy fails or if `stream` is `NULL`, it copies the data synchronously. The function returns `-EAGAIN` if the asynchronous launch was successful. It returns 0 if the synchronous copy was successful, or fails otherwise.

28.20.3.5 `starpu_cuda_set_device()`

```
void starpu_cuda_set_device (
    unsigned devid )
```

Calls `cudaSetDevice(devid)` or `cudaGLSetGLDevice(devid)`, according to whether `devid` is among the field `starpu_conf::cuda_opengl_interoperability`.

28.20.3.6 `starpu_cublas_init()`

```
void starpu_cublas_init (
    void )
```

This function initializes CUBLAS on every CUDA device. The CUBLAS library must be initialized prior to any CUBLAS call. Calling `starpu_cublas_init()` will initialize CUBLAS on every CUDA device controlled by StarPU. This call blocks until CUBLAS has been properly initialized on every device.

28.20.3.7 `starpu_cublas_shutdown()`

```
void starpu_cublas_shutdown (
    void )
```

This function synchronously deinitializes the CUBLAS library on every CUDA device.

28.20.3.8 `starpu_cublas_report_error()`

```
void starpu_cublas_report_error (
    const char * func,
    const char * file,
    int line,
    int status )
```

Report a cublas error.

28.21 OpenCL Extensions

Data Structures

- struct `starpu_opengl_program`

Macros

- `#define STARPU_USE_OPENCL`
- `#define STARPU_MAXOPENCLDEVS`
- `#define STARPU_OPENCL_DATADIR`

Writing OpenCL kernels

- void [starpu_opengl_get_context](#) (int devid, cl_context *context)
- void [starpu_opengl_get_device](#) (int devid, cl_device_id *device)
- void [starpu_opengl_get_queue](#) (int devid, cl_command_queue *queue)
- void [starpu_opengl_get_current_context](#) (cl_context *context)
- void [starpu_opengl_get_current_queue](#) (cl_command_queue *queue)
- int [starpu_opengl_set_kernel_args](#) (cl_int *err, cl_kernel *kernel,...)

Compiling OpenCL kernels

Source codes for OpenCL kernels can be stored in a file or in a string. StarPU provides functions to build the program executable for each available OpenCL device as a cl_program object. This program executable can then be loaded within a specific queue as explained in the next section. These are only helpers, Applications can also fill a [starpu_opengl_program](#) array by hand for more advanced use (e.g. different programs on the different OpenCL devices, for relocation purpose for instance).

- int [starpu_opengl_load_opengl_from_file](#) (const char *source_file_name, struct [starpu_opengl_program](#) *opengl_programs, const char *build_options)
- int [starpu_opengl_load_opengl_from_string](#) (const char *opengl_program_source, struct [starpu_opengl_program](#) *opengl_programs, const char *build_options)
- int [starpu_opengl_unload_opengl](#) (struct [starpu_opengl_program](#) *opengl_programs)
- void [starpu_opengl_load_program_source](#) (const char *source_file_name, char *located_file_name, char *located_dir_name, char *opengl_program_source)
- void [starpu_opengl_load_program_source_malloc](#) (const char *source_file_name, char **located_file_name, char **located_dir_name, char **opengl_program_source)
- int [starpu_opengl_compile_opengl_from_file](#) (const char *source_file_name, const char *build_options)
- int [starpu_opengl_compile_opengl_from_string](#) (const char *opengl_program_source, const char *file_name, const char *build_options)
- int [starpu_opengl_load_binary_opengl](#) (const char *kernel_id, struct [starpu_opengl_program](#) *opengl_programs)

Loading OpenCL kernels

- int [starpu_opengl_load_kernel](#) (cl_kernel *kernel, cl_command_queue *queue, struct [starpu_opengl_program](#) *opengl_programs, const char *kernel_name, int devid)
- int [starpu_opengl_release_kernel](#) (cl_kernel kernel)

OpenCL statistics

- int [starpu_opengl_collect_stats](#) (cl_event event)

OpenCL utilities

- `#define STARPU_OPENCL_DISPLAY_ERROR(status)`
- `#define STARPU_OPENCL_REPORT_ERROR(status)`
- `#define STARPU_OPENCL_REPORT_ERROR_WITH_MSG(msg, status)`
- `const char * starpu_openccl_error_string (cl_int status)`
- `void starpu_openccl_display_error (const char *func, const char *file, int line, const char *msg, cl_int status)`
- `static __starpu_inline void starpu_openccl_report_error (const char *func, const char *file, int line, const char *msg, cl_int status)`
- `cl_int starpu_openccl_allocate_memory (int devid, cl_mem *addr, size_t size, cl_mem_flags flags)`
- `cl_int starpu_openccl_copy_ram_to_openccl (void *ptr, unsigned src_node, cl_mem buffer, unsigned dst_node, size_t size, size_t offset, cl_event *event, int *ret)`
- `cl_int starpu_openccl_copy_openccl_to_ram (cl_mem buffer, unsigned src_node, void *ptr, unsigned dst_node, size_t size, size_t offset, cl_event *event, int *ret)`
- `cl_int starpu_openccl_copy_openccl_to_openccl (cl_mem src, unsigned src_node, size_t src_offset, cl_mem dst, unsigned dst_node, size_t dst_offset, size_t size, cl_event *event, int *ret)`
- `cl_int starpu_openccl_copy_async_sync (uintptr_t src, size_t src_offset, unsigned src_node, uintptr_t dst, size_t dst_offset, unsigned dst_node, size_t size, cl_event *event)`

28.21.1 Detailed Description

28.21.2 Data Structure Documentation

28.21.2.1 struct starpu_openccl_program

Stores the OpenCL programs as compiled for the different OpenCL devices.

Data Fields

<code>cl_program</code>	<code>programs[STARPU_MAXOPENCLDEVS]</code>	Stores each program for each OpenCL device.
-------------------------	---	---

28.21.3 Macro Definition Documentation

28.21.3.1 STARPU_USE_OPENCL

```
#define STARPU_USE_OPENCL
```

This macro is defined when StarPU has been installed with OpenCL support. It should be used in your code to detect the availability of OpenCL as shown in [Full source code for the 'Scaling a Vector' example](#).

28.21.3.2 STARPU_MAXOPENCLDEVS

```
#define STARPU_MAXOPENCLDEVS
```

This macro defines the maximum number of OpenCL devices that are supported by StarPU.

28.21.3.3 STARPU_OPENCL_DATADIR

```
#define STARPU_OPENCL_DATADIR
```

This macro defines the directory in which the OpenCL codelets of the applications provided with StarPU have been installed.

28.21.3.4 STARPU_OPENCL_DISPLAY_ERROR

```
#define STARPU_OPENCL_DISPLAY_ERROR(  
    status )
```

Call the function [starpu_openccl_display_error\(\)](#) with the given error *status*, the current function name, current file and line number, and a empty message.

28.21.3.5 STARPU_OPENCL_REPORT_ERROR

```
#define STARPU_OPENCL_REPORT_ERROR(  
    status )
```

Call the function [starpu_openccl_report_error\(\)](#) with the given error *status*, with the current function name, current file and line number, and a empty message.

28.21.3.6 STARPU_OPENCL_REPORT_ERROR_WITH_MSG

```
#define STARPU_OPENCL_REPORT_ERROR_WITH_MSG(  
    msg,  
    status )
```

Call the function [starpu_openccl_report_error\(\)](#) with the given *msg* and the given error *status*, with the current function name, current file and line number.

28.21.4 Function Documentation

28.21.4.1 starpu_openccl_get_context()

```
void starpu_openccl_get_context (  
    int devid,  
    cl_context * context )
```

Places the OpenCL context of the device designated by *devid* into *context*.

28.21.4.2 `starpu_opengl_get_device()`

```
void starpu_opengl_get_device (
    int devid,
    cl_device_id * device )
```

Places the `cl_device_id` corresponding to `devid` in `device`.

28.21.4.3 `starpu_opengl_get_queue()`

```
void starpu_opengl_get_queue (
    int devid,
    cl_command_queue * queue )
```

Places the command queue of the device designated by `devid` into `queue`.

28.21.4.4 `starpu_opengl_get_current_context()`

```
void starpu_opengl_get_current_context (
    cl_context * context )
```

Return the context of the current worker.

28.21.4.5 `starpu_opengl_get_current_queue()`

```
void starpu_opengl_get_current_queue (
    cl_command_queue * queue )
```

Return the computation kernel command queue of the current worker.

28.21.4.6 `starpu_opengl_set_kernel_args()`

```
int starpu_opengl_set_kernel_args (
    cl_int * err,
    cl_kernel * kernel,
    ... )
```

Sets the arguments of a given kernel. The list of arguments must be given as `(size_t size_of_the_argument, cl_mem * pointer_to_the_argument)`. The last argument must be 0. Returns the number of arguments that were successfully set. In case of failure, returns the id of the argument that could not be set and `err` is set to the error returned by OpenCL. Otherwise, returns the number of arguments that were set.

Here an example:

```
int n;
cl_int err;
cl_kernel kernel;
n = starpu_opengl_set_kernel_args(&err, 2, &kernel,
                                sizeof(foo), &foo,
                                sizeof(bar), &bar,
                                0);
if (n != 2)
    fprintf(stderr, "Error : %d\n", err);
```

28.21.4.7 starpu_opengl_load_opengl_from_file()

```
int starpu_opengl_load_opengl_from_file (
    const char * source_file_name,
    struct starpu\_opengl\_program * opengl_programs,
    const char * build_options )
```

This function compiles an OpenGL source code stored in a file.

28.21.4.8 starpu_opengl_load_opengl_from_string()

```
int starpu_opengl_load_opengl_from_string (
    const char * opengl_program_source,
    struct starpu\_opengl\_program * opengl_programs,
    const char * build_options )
```

This function compiles an OpenGL source code stored in a string.

28.21.4.9 starpu_opengl_unload_opengl()

```
int starpu_opengl_unload_opengl (
    struct starpu\_opengl\_program * opengl_programs )
```

This function unloads an OpenGL compiled code.

28.21.4.10 starpu_opengl_load_program_source()

```
void starpu_opengl_load_program_source (
    const char * source_file_name,
    char * located_file_name,
    char * located_dir_name,
    char * opengl_program_source )
```

Store the contents of the file `source_file_name` in the buffer `opengl_program_source`. The file `source_file_name` can be located in the current directory, or in the directory specified by the environment variable [STARPU_OPENGL_PROGRAM_DIR](#), or in the directory `share/starpu/opengl` of the installation directory of StarPU, or in the source directory of StarPU. When the file is found, `located_file_name` is the full name of the file as it has been located on the system, `located_dir_name` the directory where it has been located. Otherwise, they are both set to the empty string.

28.21.4.11 starpu_opengl_load_program_source_malloc()

```
void starpu_opengl_load_program_source_malloc (
    const char * source_file_name,
    char ** located_file_name,
    char ** located_dir_name,
    char ** opengl_program_source )
```

Similar to function [starpu_opengl_load_program_source\(\)](#) but it allocates the buffers `located_file_name`, `located_dir_name` and `opengl_program_source`.

28.21.4.12 starpu_opengl_compile_opengl_from_file()

```
int starpu_opengl_compile_opengl_from_file (
    const char * source_file_name,
    const char * build_options )
```

Compile the OpenCL kernel stored in the file `source_file_name` with the given options `build_options` and stores the result in the directory `$STARPU_HOME/.starpu/opengl` with the same filename as `source_file_name`. The compilation is done for every OpenCL device, and the filename is suffixed with the vendor id and the device id of the OpenCL device.

28.21.4.13 starpu_opengl_compile_opengl_from_string()

```
int starpu_opengl_compile_opengl_from_string (
    const char * opengl_program_source,
    const char * file_name,
    const char * build_options )
```

Compile the OpenCL kernel in the string `opengl_program_source` with the given options `build_options` and stores the result in the directory `$STARPU_HOME/.starpu/opengl` with the filename `file_name`. The compilation is done for every OpenCL device, and the filename is suffixed with the vendor id and the device id of the OpenCL device.

28.21.4.14 starpu_opengl_load_binary_opengl()

```
int starpu_opengl_load_binary_opengl (
    const char * kernel_id,
    struct starpu_opengl_program * opengl_programs )
```

Compile the binary OpenCL kernel identified with `kernel_id`. For every OpenCL device, the binary OpenCL kernel will be loaded from the file `$STARPU_HOME/.starpu/opengl/<kernel_id>.<device_type>.vendor_id_<vendor_id>_device_id_<device_id>`.

28.21.4.15 starpu_opengl_load_kernel()

```
int starpu_opengl_load_kernel (
    cl_kernel * kernel,
    cl_command_queue * queue,
    struct starpu_opengl_program * opengl_programs,
    const char * kernel_name,
    int devid )
```

Create a kernel `kernel` for device `devid`, on its computation command queue returned in `queue`, using program `opengl_programs` and name `kernel_name`.

28.21.4.16 starpu_opengl_release_kernel()

```
int starpu_opengl_release_kernel (
    cl_kernel kernel )
```

Release the given `kernel`, to be called after kernel execution.

28.21.4.17 starpu_opengl_collect_stats()

```
int starpu_opengl_collect_stats (
    cl_event event )
```

This function allows to collect statistics on a kernel execution. After termination of the kernels, the OpenCL codelet should call this function to pass it the even returned by `clEnqueueNDRangeKernel`, to let StarPU collect statistics about the kernel execution (used cycles, consumed energy).

28.21.4.18 starpu_opengl_error_string()

```
const char * starpu_opengl_error_string (
    cl_int status )
```

Return the error message in English corresponding to `status`, an OpenCL error code.

28.21.4.19 starpu_opengl_display_error()

```
void starpu_opengl_display_error (
    const char * func,
    const char * file,
    int line,
    const char * msg,
    cl_int status )
```

Given a valid error status, prints the corresponding error message on stdout, along with the given function name `func`, the given filename `file`, the given line number `line` and the given message `msg`.

28.21.4.20 starpu_opengl_report_error()

```
void starpu_opengl_report_error (
    const char * func,
    const char * file,
    int line,
    const char * msg,
    cl_int status ) [static]
```

Call the function [starpu_opengl_display_error\(\)](#) and abort.

28.21.4.21 starpu_opengl_allocate_memory()

```
cl_int starpu_opengl_allocate_memory (
    int devid,
    cl_mem * addr,
    size_t size,
    cl_mem_flags flags )
```

Allocate `size` bytes of memory, stored in `addr`. `flags` must be a valid combination of `cl_mem_flags` values.

28.21.4.22 starpu_opengl_copy_ram_to_opengl()

```
cl_int starpu_opengl_copy_ram_to_opengl (
    void * ptr,
    unsigned src_node,
    cl_mem buffer,
    unsigned dst_node,
    size_t size,
    size_t offset,
    cl_event * event,
    int * ret )
```

Copy `size` bytes from the given `ptr` on RAM `src_node` to the given `buffer` on OpenCL `dst_node`. `offset` is the offset, in bytes, in `buffer`. if `event` is `NULL`, the copy is synchronous, i.e the queue is synchronised before returning. If not `NULL`, `event` can be used after the call to wait for this particular copy to complete. This function returns `CL_SUCCESS` if the copy was successful, or a valid OpenCL error code otherwise. The integer pointed to by `ret` is set to `-EAGAIN` if the asynchronous launch was successful, or to 0 if `event` was `NULL`.

28.21.4.23 starpu_opengl_copy_opengl_to_ram()

```
cl_int starpu_opengl_copy_opengl_to_ram (
    cl_mem buffer,
    unsigned src_node,
    void * ptr,
    unsigned dst_node,
    size_t size,
    size_t offset,
    cl_event * event,
    int * ret )
```

Copy `size` bytes asynchronously from the given `buffer` on OpenCL `src_node` to the given `ptr` on RAM `dst_node`. `offset` is the offset, in bytes, in `buffer`. if `event` is `NULL`, the copy is synchronous, i.e the queue is synchronised before returning. If not `NULL`, `event` can be used after the call to wait for this particular copy to complete. This function returns `CL_SUCCESS` if the copy was successful, or a valid OpenCL error code otherwise. The integer pointed to by `ret` is set to `-EAGAIN` if the asynchronous launch was successful, or to 0 if `event` was `NULL`.

28.21.4.24 starpu_opengl_copy_opengl_to_opengl()

```
cl_int starpu_opengl_copy_opengl_to_opengl (
    cl_mem src,
    unsigned src_node,
    size_t src_offset,
    cl_mem dst,
    unsigned dst_node,
    size_t dst_offset,
    size_t size,
    cl_event * event,
    int * ret )
```

Copy `size` bytes asynchronously from byte offset `src_offset` of `src` on OpenCL `src_node` to byte offset `dst_offset` of `dst` on OpenCL `dst_node`. if `event` is `NULL`, the copy is synchronous, i.e. the queue is synchronised before returning. If not `NULL`, `event` can be used after the call to wait for this particular copy to complete. This function returns `CL_SUCCESS` if the copy was successful, or a valid OpenCL error code otherwise. The integer pointed to by `ret` is set to `-EAGAIN` if the asynchronous launch was successful, or to 0 if `event` was `NULL`.

28.21.4.25 starpu_opencil_copy_async_sync()

```
cl_int starpu_opencil_copy_async_sync (
    uintptr_t src,
    size_t src_offset,
    unsigned src_node,
    uintptr_t dst,
    size_t dst_offset,
    unsigned dst_node,
    size_t size,
    cl_event * event )
```

Copy size bytes from byte offset `src_offset` of `src` on `src_node` to byte offset `dst_offset` of `dst` on `dst_node`. if `event` is `NULL`, the copy is synchronous, i.e. the queue is synchronised before returning. If not `NULL`, `event` can be used after the call to wait for this particular copy to complete. The function returns `-EAGAIN` if the asynchronous launch was successful. It returns 0 if the synchronous copy was successful, or fails otherwise.

28.22 OpenMP Runtime Support

This section describes the interface provided for implementing OpenMP runtimes on top of StarPU.

Data Structures

- struct [starpu_omp_lock_t](#)
- struct [starpu_omp_nest_lock_t](#)
- struct [starpu_omp_parallel_region_attr](#)
- struct [starpu_omp_task_region_attr](#)

Enumerations

- enum [starpu_omp_sched_value](#) {
[starpu_omp_sched_undefined](#), [starpu_omp_sched_static](#), [starpu_omp_sched_dynamic](#), [starpu_omp_↔
sched_guided](#),
[starpu_omp_sched_auto](#), [starpu_omp_sched_runtime](#) }
- enum [starpu_omp_proc_bind_value](#) {
[starpu_omp_proc_bind_undefined](#), [starpu_omp_proc_bind_false](#), [starpu_omp_proc_bind_true](#), [starpu_↔
omp_proc_bind_master](#),
[starpu_omp_proc_bind_close](#), [starpu_omp_proc_bind_spread](#) }

Initialisation

- `#define` [STARPU_OPENMP](#)
- int [starpu_omp_init](#) (void) [__STARPU_OMP_NOTHROW](#)
- void [starpu_omp_shutdown](#) (void) [__STARPU_OMP_NOTHROW](#)

Parallel

- void [starpu_omp_parallel_region](#) (const struct [starpu_omp_parallel_region_attr](#) *attr) [__STARPU_OMP_↔
NOTHROW](#)
- void [starpu_omp_master](#) (void(*f)(void *arg), void *arg) [__STARPU_OMP_NOTHROW](#)
- int [starpu_omp_master_inline](#) (void) [__STARPU_OMP_NOTHROW](#)

Synchronization

- void [starpu_omp_barrier](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_critical](#) (void(*)(void *arg), void *arg, const char *name) __STARPU_OMP_NOTHROW
- void [starpu_omp_critical_inline_begin](#) (const char *name) __STARPU_OMP_NOTHROW
- void [starpu_omp_critical_inline_end](#) (const char *name) __STARPU_OMP_NOTHROW

Worksharing

- void [starpu_omp_single](#) (void(*)(void *arg), void *arg, int nowait) __STARPU_OMP_NOTHROW
- int [starpu_omp_single_inline](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_single_copyprivate](#) (void(*)(void *arg, void *data, unsigned long long data_size), void *arg, void *data, unsigned long long data_size) __STARPU_OMP_NOTHROW
- void * [starpu_omp_single_copyprivate_inline_begin](#) (void *data) __STARPU_OMP_NOTHROW
- void [starpu_omp_single_copyprivate_inline_end](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_for](#) (void(*)(unsigned long long _first_i, unsigned long long _nb_i, void *arg), void *arg, unsigned long long nb_iterations, unsigned long long chunk, int schedule, int ordered, int nowait) __STARPU_OMP_NOTHROW
- int [starpu_omp_for_inline_first](#) (unsigned long long nb_iterations, unsigned long long chunk, int schedule, int ordered, unsigned long long *_first_i, unsigned long long *_nb_i) __STARPU_OMP_NOTHROW
- int [starpu_omp_for_inline_next](#) (unsigned long long nb_iterations, unsigned long long chunk, int schedule, int ordered, unsigned long long *_first_i, unsigned long long *_nb_i) __STARPU_OMP_NOTHROW
- void [starpu_omp_for_alt](#) (void(*)(unsigned long long _begin_i, unsigned long long _end_i, void *arg), void *arg, unsigned long long nb_iterations, unsigned long long chunk, int schedule, int ordered, int nowait) __STARPU_OMP_NOTHROW
- int [starpu_omp_for_inline_first_alt](#) (unsigned long long nb_iterations, unsigned long long chunk, int schedule, int ordered, unsigned long long *_begin_i, unsigned long long *_end_i) __STARPU_OMP_NOTHROW
- int [starpu_omp_for_inline_next_alt](#) (unsigned long long nb_iterations, unsigned long long chunk, int schedule, int ordered, unsigned long long *_begin_i, unsigned long long *_end_i) __STARPU_OMP_NOTHROW
- void [starpu_omp_ordered](#) (void(*)(void *arg), void *arg) __STARPU_OMP_NOTHROW
- void [starpu_omp_ordered_inline_begin](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_ordered_inline_end](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_sections](#) (unsigned long long nb_sections, void(**section_f)(void *arg), void **section_arg, int nowait) __STARPU_OMP_NOTHROW
- void [starpu_omp_sections_combined](#) (unsigned long long nb_sections, void(*section_f)(unsigned long long section_num, void *arg), void *section_arg, int nowait) __STARPU_OMP_NOTHROW

Task

- void [starpu_omp_task_region](#) (const struct [starpu_omp_task_region_attr](#) *attr) __STARPU_OMP_NOTHROW
- void [starpu_omp_taskwait](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_taskgroup](#) (void(*)(void *arg), void *arg) __STARPU_OMP_NOTHROW
- void [starpu_omp_taskgroup_inline_begin](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_taskgroup_inline_end](#) (void) __STARPU_OMP_NOTHROW

API

- void [starpu_omp_set_num_threads](#) (int threads) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_num_threads](#) () __STARPU_OMP_NOTHROW
- int [starpu_omp_get_thread_num](#) () __STARPU_OMP_NOTHROW
- int [starpu_omp_get_max_threads](#) () __STARPU_OMP_NOTHROW
- int [starpu_omp_get_num_procs](#) (void) __STARPU_OMP_NOTHROW
- int [starpu_omp_in_parallel](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_set_dynamic](#) (int dynamic_threads) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_dynamic](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_set_nested](#) (int nested) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_nested](#) (void) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_cancellation](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_set_schedule](#) (enum [starpu_omp_sched_value](#) kind, int modifier) __STARPU_OMP_NOTHROW
- void [starpu_omp_get_schedule](#) (enum [starpu_omp_sched_value](#) *kind, int *modifier) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_thread_limit](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_set_max_active_levels](#) (int max_levels) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_max_active_levels](#) (void) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_level](#) (void) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_ancestor_thread_num](#) (int level) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_team_size](#) (int level) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_active_level](#) (void) __STARPU_OMP_NOTHROW
- int [starpu_omp_in_final](#) (void) __STARPU_OMP_NOTHROW
- enum [starpu_omp_proc_bind_value](#) [starpu_omp_get_proc_bind](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_set_default_device](#) (int device_num) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_default_device](#) (void) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_num_devices](#) (void) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_num_teams](#) (void) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_team_num](#) (void) __STARPU_OMP_NOTHROW
- int [starpu_omp_is_initial_device](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_init_lock](#) ([starpu_omp_lock_t](#) *lock) __STARPU_OMP_NOTHROW
- void [starpu_omp_destroy_lock](#) ([starpu_omp_lock_t](#) *lock) __STARPU_OMP_NOTHROW
- void [starpu_omp_set_lock](#) ([starpu_omp_lock_t](#) *lock) __STARPU_OMP_NOTHROW
- void [starpu_omp_unset_lock](#) ([starpu_omp_lock_t](#) *lock) __STARPU_OMP_NOTHROW
- int [starpu_omp_test_lock](#) ([starpu_omp_lock_t](#) *lock) __STARPU_OMP_NOTHROW
- void [starpu_omp_init_nest_lock](#) ([starpu_omp_nest_lock_t](#) *lock) __STARPU_OMP_NOTHROW
- void [starpu_omp_destroy_nest_lock](#) ([starpu_omp_nest_lock_t](#) *lock) __STARPU_OMP_NOTHROW
- void [starpu_omp_set_nest_lock](#) ([starpu_omp_nest_lock_t](#) *lock) __STARPU_OMP_NOTHROW
- void [starpu_omp_unset_nest_lock](#) ([starpu_omp_nest_lock_t](#) *lock) __STARPU_OMP_NOTHROW
- int [starpu_omp_test_nest_lock](#) ([starpu_omp_nest_lock_t](#) *lock) __STARPU_OMP_NOTHROW
- void [starpu_omp_atomic_fallback_inline_begin](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_atomic_fallback_inline_end](#) (void) __STARPU_OMP_NOTHROW
- double [starpu_omp_get_wtime](#) (void) __STARPU_OMP_NOTHROW
- double [starpu_omp_get_wtick](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_vector_annotate](#) ([starpu_data_handle_t](#) handle, uint32_t slice_base) __STARPU_OMP_NOTHROW

28.22.1 Detailed Description

This section describes the interface provided for implementing OpenMP runtimes on top of StarPU.

28.22.2 Data Structure Documentation

28.22.2.1 struct starpu_omp_lock_t

Opaque Simple Lock object ([Simple Locks](#)) for inter-task synchronization operations.

See also

[starpu_omp_init_lock\(\)](#)
[starpu_omp_destroy_lock\(\)](#)
[starpu_omp_set_lock\(\)](#)
[starpu_omp_unset_lock\(\)](#)
[starpu_omp_test_lock\(\)](#)

Data Fields

void *	internal	Is an opaque pointer for internal use.
--------	----------	--

28.22.2.2 struct starpu_omp_nest_lock_t

Opaque Nestable Lock object ([Nestable Locks](#)) for inter-task synchronization operations.

See also

[starpu_omp_init_nest_lock\(\)](#)
[starpu_omp_destroy_nest_lock\(\)](#)
[starpu_omp_set_nest_lock\(\)](#)
[starpu_omp_unset_nest_lock\(\)](#)
[starpu_omp_test_nest_lock\(\)](#)

Data Fields

void *	internal	Is an opaque pointer for internal use.
--------	----------	--

28.22.2.3 struct starpu_omp_parallel_region_attr

Set of attributes used for creating a new parallel region.

See also

[starpu_omp_parallel_region\(\)](#)

Data Fields

struct starpu_codelet	cl	Is a starpu_codelet (Codelet And Tasks) to use for the parallel region implicit tasks. The codelet must provide a CPU implementation function.
---------------------------------------	----	--

Data Fields

starpu_data_handle_t *	handles	Is an array of zero or more starpu_data_handle_t data handle to be passed to the parallel region implicit tasks.
void *	cl_arg	Is an optional pointer to an inline argument to be passed to the region implicit tasks.
size_t	cl_arg_size	Is the size of the optional inline argument to be passed to the region implicit tasks, or 0 if unused.
unsigned	cl_arg_free	Is a boolean indicating whether the optional inline argument should be automatically freed (true), or not (false).
int	if_clause	Is a boolean indicating whether the if clause of the corresponding <code>pragma omp parallel</code> is true or false.
int	num_threads	Is an integer indicating the requested number of threads in the team of the newly created parallel region, or 0 to let the runtime choose the number of threads alone. This attribute may be ignored by the runtime system if the requested number of threads is higher than the number of threads that the runtime can create.

28.22.2.4 struct starpu_omp_task_region_attr

Set of attributes used for creating a new task region.

See also

[starpu_omp_task_region\(\)](#)

Data Fields

struct starpu_codelet	cl	Is a starpu_codelet (Codelet And Tasks) to use for the task region explicit task. The codelet must provide a CPU implementation function or an accelerator implementation for offloaded target regions.
starpu_data_handle_t *	handles	Is an array of zero or more starpu_data_handle_t data handle to be passed to the task region explicit tasks.
void *	cl_arg	Is an optional pointer to an inline argument to be passed to the region implicit tasks.
size_t	cl_arg_size	Is the size of the optional inline argument to be passed to the region implicit tasks, or 0 if unused.
unsigned	cl_arg_free	Is a boolean indicating whether the optional inline argument should be automatically freed (true), or not (false).
int	priority	
int	if_clause	Is a boolean indicating whether the if clause of the corresponding <code>pragma omp task</code> is true or false.
int	final_clause	Is a boolean indicating whether the final clause of the corresponding <code>pragma omp task</code> is true or false.
int	untied_clause	Is a boolean indicating whether the untied clause of the corresponding <code>pragma omp task</code> is true or false.
int	mergeable_clause	Is a boolean indicating whether the mergeable clause of the corresponding <code>pragma omp task</code> is true or false.

28.22.3 Macro Definition Documentation

28.22.3.1 STARPU_OPENMP

```
#define STARPU_OPENMP
```

This macro is defined when StarPU has been installed with OpenMP Runtime support. It should be used in your code to detect the availability of the runtime support for OpenMP.

28.22.4 Enumeration Type Documentation

28.22.4.1 starpu_omp_sched_value

```
enum starpu_omp_sched_value
```

Set of constants for selecting the for loop iteration scheduling algorithm ([Parallel For](#)) as defined by the OpenMP specification.

Enumerator

starpu_omp_sched_undefined	Undefined iteration scheduling algorithm.
starpu_omp_sched_static	Static iteration scheduling algorithm.
starpu_omp_sched_dynamic	Dynamic iteration scheduling algorithm.
starpu_omp_sched_guided	Guided iteration scheduling algorithm.
starpu_omp_sched_auto	Automatically choosen iteration scheduling algorithm.
starpu_omp_sched_runtime	Choice of iteration scheduling algorithm deferred at runtime . See also starpu_omp_for() starpu_omp_for_inline_first() starpu_omp_for_inline_next() starpu_omp_for_alt() starpu_omp_for_inline_first_alt() starpu_omp_for_inline_next_alt()

28.22.4.2 starpu_omp_proc_bind_value

```
enum starpu_omp_proc_bind_value
```

Set of constants for selecting the processor binding method, as defined in the OpenMP specification.

Enumerator

<code>starpu_omp_proc_bind_undefined</code>	Undefined processor binding method.
<code>starpu_omp_proc_bind_false</code>	Team threads may be moved between places at any time.
<code>starpu_omp_proc_bind_true</code>	Team threads may not be moved between places.
<code>starpu_omp_proc_bind_master</code>	Assign every thread in the team to the same place as the master thread.
<code>starpu_omp_proc_bind_close</code>	Assign every thread in the team to a place close to the parent thread.
<code>starpu_omp_proc_bind_spread</code>	Assign team threads as a sparse distribution over the selected places. See also starpu_omp_get_proc_bind()

28.22.5 Function Documentation

28.22.5.1 `starpu_omp_init()`

```
int starpu_omp_init (
    void )
```

Initializes StarPU and its OpenMP Runtime support.

28.22.5.2 `starpu_omp_shutdown()`

```
void starpu_omp_shutdown (
    void )
```

Shutdown StarPU and its OpenMP Runtime support.

28.22.5.3 `starpu_omp_parallel_region()`

```
void starpu_omp_parallel_region (
    const struct starpu\_omp\_parallel\_region\_attr * attr )
```

Generates and launch an OpenMP parallel region and return after its completion. `attr` specifies the attributes for the generated parallel region. If this function is called from inside another, generating, parallel region, the generated parallel region is nested within the generating parallel region.

This function can be used to implement `#pragma omp parallel`.

28.22.5.4 `starpu_omp_master()`

```
void starpu_omp_master (
    void(*) (void *arg) f,
    void * arg )
```

Executes a function only on the master thread of the OpenMP parallel region it is called from. When called from a thread that is not the master of the parallel region it is called from, this function does nothing. `f` is the function to be called. `arg` is an argument passed to function `f`.

This function can be used to implement `#pragma omp master`.

28.22.5.5 `starpu_omp_master_inline()`

```
int starpu_omp_master_inline (
    void )
```

Determines whether the calling thread is the master of the OpenMP parallel region it is called from or not.

This function can be used to implement `#pragma omp master` without code outlining.

Returns

- ! 0 if called by the region's master thread.
- 0 if not called by the region's master thread.

28.22.5.6 `starpu_omp_barrier()`

```
void starpu_omp_barrier (
    void )
```

Waits until each participating thread of the innermost OpenMP parallel region has reached the barrier and each explicit OpenMP task bound to this region has completed its execution.

This function can be used to implement `#pragma omp barrier`.

28.22.5.7 `starpu_omp_critical()`

```
void starpu_omp_critical (
    void(*) (void *arg) f,
    void * arg,
    const char * name )
```

Waits until no other thread is executing within the context of the selected critical section, then proceeds to the exclusive execution of a function within the critical section. `f` is the function to be executed in the critical section. `arg` is an argument passed to function `f`. `name` is the name of the selected critical section. If `name == NULL`, the selected critical section is the unique anonymous critical section.

This function can be used to implement `#pragma omp critical`.

28.22.5.8 `starpu_omp_critical_inline_begin()`

```
void starpu_omp_critical_inline_begin (
    const char * name )
```

Waits until execution can proceed exclusively within the context of the selected critical section. `name` is the name of the selected critical section. If `name == NULL`, the selected critical section is the unique anonymous critical section.

This function together with [starpu_omp_critical_inline_end](#) can be used to implement `#pragma omp critical` without code outlining.

28.22.5.9 starpu_omp_critical_inline_end()

```
void starpu_omp_critical_inline_end (
    const char * name )
```

Ends the exclusive execution within the context of the selected critical section. `name` is the name of the selected critical section. If `name==NULL`, the selected critical section is the unique anonymous critical section.

This function together with [starpu_omp_critical_inline_begin](#) can be used to implement `#pragma omp critical` without code outlining.

28.22.5.10 starpu_omp_single()

```
void starpu_omp_single (
    void(*) (void *arg) f,
    void * arg,
    int nowait )
```

Ensures that a single participating thread of the innermost OpenMP parallel region executes a function. `f` is the function to be executed by a single thread. `arg` is an argument passed to function `f`. `nowait` is a flag indicating whether an implicit barrier is requested after the single section (`nowait==0`) or not (`nowait==!0`).

This function can be used to implement `#pragma omp single`.

28.22.5.11 starpu_omp_single_inline()

```
int starpu_omp_single_inline (
    void )
```

Decides whether the current thread is elected to run the following single section among the participating threads of the innermost OpenMP parallel region.

This function can be used to implement `#pragma omp single` without code outlining.

Returns

- !0 if the calling thread has won the election.
- 0 if the calling thread has lost the election.

28.22.5.12 starpu_omp_single_copyprivate()

```
void starpu_omp_single_copyprivate (
    void(*) (void *arg, void *data, unsigned long long data_size) f,
    void * arg,
    void * data,
    unsigned long long data_size )
```

This function executes `f` on a single task of the current parallel region task, and then broadcast the contents of the memory block pointed by the copyprivate pointer `data` and of size `data_size` to the corresponding `data` pointed memory blocks of all the other participating region tasks. This function can be used to implement `#pragma omp single` with a copyprivate clause.

See also

[starpu_omp_single_copyprivate_inline](#)
[starpu_omp_single_copyprivate_inline_begin](#)
[starpu_omp_single_copyprivate_inline_end](#)

28.22.5.13 starpu_omp_single_copyprivate_inline_begin()

```
void * starpu_omp_single_copyprivate_inline_begin (
    void * data )
```

This function elects one task among the tasks of the current parallel region task to execute the following single section, and then broadcast the copyprivate pointer `data` to all the other participating region tasks. This function can be used to implement `#pragma omp single` with a copyprivate clause without code outlining.

See also

[starpu_omp_single_copyprivate_inline](#)
[starpu_omp_single_copyprivate_inline_end](#)

28.22.5.14 starpu_omp_single_copyprivate_inline_end()

```
void starpu_omp_single_copyprivate_inline_end (
    void )
```

This function completes the execution of a single section and returns the broadcasted copyprivate pointer for tasks that lost the election and NULL for the task that won the election. This function can be used to implement `#pragma omp single` with a copyprivate clause without code outlining.

Returns

the copyprivate pointer for tasks that lost the election and therefore did not execute the code of the single section.

NULL for the task that won the election and executed the code of the single section.

See also

[starpu_omp_single_copyprivate_inline](#)
[starpu_omp_single_copyprivate_inline_begin](#)

28.22.5.15 starpu_omp_for()

```
void starpu_omp_for (
    void(*) (unsigned long long _first_i, unsigned long long _nb_i, void *arg) f,
    void * arg,
    unsigned long long nb_iterations,
    unsigned long long chunk,
    int schedule,
    int ordered,
    int nowait )
```

Executes a parallel loop together with the other threads participating to the innermost parallel region. `f` is the function to be executed iteratively. `arg` is an argument passed to function `f`. `nb_iterations` is the number of iterations to be performed by the parallel loop. `chunk` is the number of consecutive iterations that should be affected to the same thread when scheduling the loop workshares, it follows the semantics of the `modifier` argument in OpenMP `#pragma omp for` specification. `schedule` is the scheduling mode according to the OpenMP specification. `ordered` is a flag indicating whether the loop region may contain an ordered section (`ordered==!0`) or not (`ordered==0`). `nowait` is a flag indicating whether an implicit barrier is requested after the for section (`nowait==0`) or not (`nowait==!0`).

The function `f` will be called with arguments `_first_i`, the first iteration to perform, `_nb_i`, the number of consecutive iterations to perform before returning, `arg`, the free `arg` argument.

This function can be used to implement `#pragma omp for`.

28.22.5.16 `starpu_omp_for_inline_first()`

```
int starpu_omp_for_inline_first (
    unsigned long long nb_iterations,
    unsigned long long chunk,
    int schedule,
    int ordered,
    unsigned long long * _first_i,
    unsigned long long * _nb_i )
```

Decides whether the current thread should start to execute a parallel loop section. See [starpu_omp_for](#) for the argument description.

This function together with [starpu_omp_for_inline_next](#) can be used to implement `#pragma omp for` without code outlining.

Returns

!0 if the calling thread participates to the loop region and should execute a first chunk of iterations. In that case, **_first_i* will be set to the first iteration of the chunk to perform and **_nb_i* will be set to the number of iterations of the chunk to perform.

0 if the calling thread does not participate to the loop region because all the available iterations have been affected to the other threads of the parallel region.

See also

[starpu_omp_for](#)

28.22.5.17 `starpu_omp_for_inline_next()`

```
int starpu_omp_for_inline_next (
    unsigned long long nb_iterations,
    unsigned long long chunk,
    int schedule,
    int ordered,
    unsigned long long * _first_i,
    unsigned long long * _nb_i )
```

Decides whether the current thread should continue to execute a parallel loop section. See [starpu_omp_for](#) for the argument description.

This function together with [starpu_omp_for_inline_first](#) can be used to implement `#pragma omp for` without code outlining.

Returns

!0 if the calling thread should execute a next chunk of iterations. In that case, **_first_i* will be set to the first iteration of the chunk to perform and **_nb_i* will be set to the number of iterations of the chunk to perform.

0 if the calling thread does not participate anymore to the loop region because all the available iterations have been affected to the other threads of the parallel region.

See also

[starpu_omp_for](#)

28.22.5.18 `starpu_omp_for_alt()`

```
void starpu_omp_for_alt (
    void(*) (unsigned long long _begin_i, unsigned long long _end_i, void *arg) f,
    void * arg,
    unsigned long long nb_iterations,
    unsigned long long chunk,
    int schedule,
    int ordered,
    int nowait )
```

Alternative implementation of a parallel loop. This function differs from [starpu_omp_for](#) in the expected arguments of the loop function `f`.

The function `f` will be called with arguments `_begin_i`, the first iteration to perform, `_end_i`, the first iteration not to perform before returning, `arg`, the free `arg` argument.

This function can be used to implement `#pragma omp for`.

See also

[starpu_omp_for](#)

28.22.5.19 `starpu_omp_for_inline_first_alt()`

```
int starpu_omp_for_inline_first_alt (
    unsigned long long nb_iterations,
    unsigned long long chunk,
    int schedule,
    int ordered,
    unsigned long long * _begin_i,
    unsigned long long * _end_i )
```

Inline version of the alternative implementation of a parallel loop.

This function together with [starpu_omp_for_inline_next_alt](#) can be used to implement `#pragma omp for` without code outlining.

See also

[starpu_omp_for](#)
[starpu_omp_for_alt](#)
[starpu_omp_for_inline_first](#)

28.22.5.20 starpu_omp_for_inline_next_alt()

```
int starpu_omp_for_inline_next_alt (
    unsigned long long nb_iterations,
    unsigned long long chunk,
    int schedule,
    int ordered,
    unsigned long long * _begin_i,
    unsigned long long * _end_i )
```

Inline version of the alternative implementation of a parallel loop.

This function together with [starpu_omp_for_inline_first_alt](#) can be used to implement `#pragma omp for` without code outlining.

See also

[starpu_omp_for](#)
[starpu_omp_for_alt](#)
[starpu_omp_for_inline_next](#)

28.22.5.21 starpu_omp_ordered()

```
void starpu_omp_ordered (
    void(*) (void *arg) f,
    void * arg )
```

Ensures that a function is sequentially executed once for each iteration in order within a parallel loop, by the thread that own the iteration. *f* is the function to be executed by the thread that own the current iteration. *arg* is an argument passed to function *f*.

This function can be used to implement `#pragma omp ordered`.

28.22.5.22 starpu_omp_ordered_inline_begin()

```
void starpu_omp_ordered_inline_begin (
    void )
```

Waits until all the iterations of a parallel loop below the iteration owned by the current thread have been executed.

This function together with [starpu_omp_ordered_inline_end](#) can be used to implement `#pragma omp ordered` without code code outlining.

28.22.5.23 starpu_omp_ordered_inline_end()

```
void starpu_omp_ordered_inline_end (
    void )
```

Notifies that the ordered section for the current iteration has been completed.

This function together with [starpu_omp_ordered_inline_begin](#) can be used to implement `#pragma omp ordered` without code code outlining.

28.22.5.24 `starpu_omp_sections()`

```
void starpu_omp_sections (
    unsigned long long nb_sections,
    void(**)(void *arg) section_f,
    void ** section_arg,
    int nowait )
```

Ensures that each function of a given array of functions is executed by one and only one thread. `nb_sections` is the number of functions in the array `section_f`. `section_f` is the array of functions to be executed as sections. `section_arg` is an array of arguments to be passed to the corresponding function. `nowait` is a flag indicating whether an implicit barrier is requested after the execution of all the sections (`nowait==0`) or not (`nowait==!0`).

This function can be used to implement `#pragma omp sections` and `#pragma omp section`.

28.22.5.25 `starpu_omp_sections_combined()`

```
void starpu_omp_sections_combined (
    unsigned long long nb_sections,
    void(*) (unsigned long long section_num, void *arg) section_f,
    void * section_arg,
    int nowait )
```

Alternative implementation of sections. This function differs from [starpu_omp_sections](#) in that all the sections are combined within a single function in this version. `section_f` is the function implementing the combined sections.

The function `section_f` will be called with arguments `section_num`, the section number to be executed, `arg`, the entry of `section_arg` corresponding to this section.

This function can be used to implement `#pragma omp sections` and `#pragma omp section`.

See also

[starpu_omp_sections](#)

28.22.5.26 `starpu_omp_task_region()`

```
void starpu_omp_task_region (
    const struct starpu\_omp\_task\_region\_attr * attr )
```

Generates an explicit child task. The execution of the generated task is asynchronous with respect to the calling code unless specified otherwise. `attr` specifies the attributes for the generated task region.

This function can be used to implement `#pragma omp task`.

28.22.5.27 `starpu_omp_taskwait()`

```
void starpu_omp_taskwait (
    void )
```

Waits for the completion of the tasks generated by the current task. This function does not wait for the descendants of the tasks generated by the current task.

This function can be used to implement `#pragma omp taskwait`.

28.22.5.28 `starpu_omp_taskgroup()`

```
void starpu_omp_taskgroup (
    void(*) (void *arg) f,
    void * arg )
```

Launches a function and wait for the completion of every descendant task generated during the execution of the function.

This function can be used to implement `#pragma omp taskgroup`.

See also

[starpu_omp_taskgroup_inline_begin](#)
[starpu_omp_taskgroup_inline_end](#)

28.22.5.29 `starpu_omp_taskgroup_inline_begin()`

```
void starpu_omp_taskgroup_inline_begin (
    void )
```

Launches a function and gets ready to wait for the completion of every descendant task generated during the dynamic scope of the taskgroup.

This function can be used to implement `#pragma omp taskgroup` without code outlining.

See also

[starpu_omp_taskgroup](#)
[starpu_omp_taskgroup_inline_end](#)

28.22.5.30 `starpu_omp_taskgroup_inline_end()`

```
void starpu_omp_taskgroup_inline_end (
    void )
```

Waits for the completion of every descendant task generated during the dynamic scope of the taskgroup.

This function can be used to implement `#pragma omp taskgroup` without code outlining.

See also

[starpu_omp_taskgroup](#)
[starpu_omp_taskgroup_inline_begin](#)

28.22.5.31 `starpu_omp_set_num_threads()`

```
void starpu_omp_set_num_threads (
    int threads )
```

This function sets ICVS `nthreads_var` for the parallel regions to be created with the current region.

Note: The StarPU OpenMP runtime support currently ignores this setting for nested parallel regions.

See also

[starpu_omp_get_num_threads](#)
[starpu_omp_get_thread_num](#)
[starpu_omp_get_max_threads](#)
[starpu_omp_get_num_procs](#)

28.22.5.32 `starpu_omp_get_num_threads()`

```
int starpu_omp_get_num_threads ( )
```

This function returns the number of threads of the current region.

Returns

the number of threads of the current region.

See also

[starpu_omp_set_num_threads](#)
[starpu_omp_get_thread_num](#)
[starpu_omp_get_max_threads](#)
[starpu_omp_get_num_procs](#)

28.22.5.33 starpu_omp_get_thread_num()

```
int starpu_omp_get_thread_num ( )
```

This function returns the rank of the current thread among the threads of the current region.

Returns

the rank of the current thread in the current region.

See also

[starpu_omp_set_num_threads](#)
[starpu_omp_get_num_threads](#)
[starpu_omp_get_max_threads](#)
[starpu_omp_get_num_procs](#)

28.22.5.34 starpu_omp_get_max_threads()

```
int starpu_omp_get_max_threads ( )
```

This function returns the maximum number of threads that can be used to create a region from the current region.

Returns

the maximum number of threads that can be used to create a region from the current region.

See also

[starpu_omp_set_num_threads](#)
[starpu_omp_get_num_threads](#)
[starpu_omp_get_thread_num](#)
[starpu_omp_get_num_procs](#)

28.22.5.35 starpu_omp_get_num_procs()

```
int starpu_omp_get_num_procs (
    void )
```

This function returns the number of StarPU CPU workers.

Returns

the number of StarPU CPU workers.

See also

[starpu_omp_set_num_threads](#)
[starpu_omp_get_num_threads](#)
[starpu_omp_get_thread_num](#)
[starpu_omp_get_max_threads](#)

28.22.5.36 starpu_omp_in_parallel()

```
int starpu_omp_in_parallel (
    void )
```

This function returns whether it is called from the scope of a parallel region or not.

Returns

! 0 if called from a parallel region scope.
0 otherwise.

28.22.5.37 starpu_omp_set_dynamic()

```
void starpu_omp_set_dynamic (
    int dynamic_threads )
```

This function enables (1) or disables (0) dynamically adjusting the number of parallel threads.

Note: The StarPU OpenMP runtime support currently ignores the argument of this function.

See also

[starpu_omp_get_dynamic](#)

28.22.5.38 starpu_omp_get_dynamic()

```
int starpu_omp_get_dynamic (
    void )
```

This function returns the state of dynamic thread number adjustment.

Returns

! 0 if dynamic thread number adjustment is enabled.
0 otherwise.

See also

[starpu_omp_set_dynamic](#)

28.22.5.39 `starpu_omp_set_nested()`

```
void starpu_omp_set_nested (  
    int nested )
```

This function enables (1) or disables (0) nested parallel regions.

Note: The StarPU OpenMP runtime support currently ignores the argument of this function.

See also

[starpu_omp_get_nested](#)
[starpu_omp_get_max_active_levels](#)
[starpu_omp_set_max_active_levels](#)
[starpu_omp_get_level](#)
[starpu_omp_get_active_level](#)

28.22.5.40 `starpu_omp_get_nested()`

```
int starpu_omp_get_nested (  
    void )
```

This function returns whether nested parallel sections are enabled or not.

Returns

! 0 if nested parallel sections are enabled.
0 otherwise.

See also

[starpu_omp_set_nested](#)
[starpu_omp_get_max_active_levels](#)
[starpu_omp_set_max_active_levels](#)
[starpu_omp_get_level](#)
[starpu_omp_get_active_level](#)

28.22.5.41 `starpu_omp_get_cancellation()`

```
int starpu_omp_get_cancellation (  
    void )
```

This function returns the state of the cancel ICVS var.

28.22.5.42 `starpu_omp_set_schedule()`

```
void starpu_omp_set_schedule (
    enum starpu_omp_sched_value kind,
    int modifier )
```

This function sets the default scheduling kind for upcoming loops within the current parallel section. `kind` is the scheduler kind, `modifier` complements the scheduler kind with informations such as the chunk size, in accordance with the OpenMP specification.

See also

[starpu_omp_get_schedule](#)

28.22.5.43 `starpu_omp_get_schedule()`

```
void starpu_omp_get_schedule (
    enum starpu_omp_sched_value * kind,
    int * modifier )
```

This function returns the current selected default loop scheduler.

Returns

the kind and the modifier of the current default loop scheduler.

See also

[starpu_omp_set_schedule](#)

28.22.5.44 `starpu_omp_get_thread_limit()`

```
int starpu_omp_get_thread_limit (
    void )
```

This function returns the number of StarPU CPU workers.

Returns

the number of StarPU CPU workers.

28.22.5.45 starpu_omp_set_max_active_levels()

```
void starpu_omp_set_max_active_levels (
    int max_levels )
```

This function sets the maximum number of allowed active parallel section levels.

Note: The StarPU OpenMP runtime support currently ignores the argument of this function and assume `max_levels` equals 1 instead.

See also

[starpu_omp_set_nested](#)
[starpu_omp_get_nested](#)
[starpu_omp_get_max_active_levels](#)
[starpu_omp_get_level](#)
[starpu_omp_get_active_level](#)

28.22.5.46 starpu_omp_get_max_active_levels()

```
int starpu_omp_get_max_active_levels (
    void )
```

This function returns the current maximum number of allowed active parallel section levels

Returns

the current maximum number of allowed active parallel section levels.

See also

[starpu_omp_set_nested](#)
[starpu_omp_get_nested](#)
[starpu_omp_set_max_active_levels](#)
[starpu_omp_get_level](#)
[starpu_omp_get_active_level](#)

28.22.5.47 starpu_omp_get_level()

```
int starpu_omp_get_level (
    void )
```

This function returns the nesting level of the current parallel section.

Returns

the nesting level of the current parallel section.

See also

[starpu_omp_set_nested](#)
[starpu_omp_get_nested](#)
[starpu_omp_get_max_active_levels](#)
[starpu_omp_set_max_active_levels](#)
[starpu_omp_get_active_level](#)

28.22.5.48 starpu_omp_get_ancestor_thread_num()

```
int starpu_omp_get_ancestor_thread_num (
    int level )
```

This function returns the number of the ancestor of the current parallel section.

Returns

the number of the ancestor of the current parallel section.

28.22.5.49 starpu_omp_get_team_size()

```
int starpu_omp_get_team_size (
    int level )
```

This function returns the size of the team of the current parallel section.

Returns

the size of the team of the current parallel section.

28.22.5.50 starpu_omp_get_active_level()

```
int starpu_omp_get_active_level (
    void )
```

This function returns the nestinglevel of the current innermost active parallel section.

Returns

the nestinglevel of the current innermost active parallel section.

See also

[starpu_omp_set_nested](#)
[starpu_omp_get_nested](#)
[starpu_omp_get_max_active_levels](#)
[starpu_omp_set_max_active_levels](#)
[starpu_omp_get_level](#)

28.22.5.51 starpu_omp_in_final()

```
int starpu_omp_in_final (
    void )
```

This function checks whether the current task is final or not.

Returns

! 0 if called from a final task.
0 otherwise.

28.22.5.52 starpu_omp_get_proc_bind()

```
enum starpu_omp_proc_bind_value starpu_omp_get_proc_bind (
    void )
```

This function returns the `proc_bind` setting of the current parallel region.

Returns

the `proc_bind` setting of the current parallel region.

28.22.5.53 starpu_omp_set_default_device()

```
void starpu_omp_set_default_device (
    int device_num )
```

This function sets the number of the device to use as default.

Note: The StarPU OpenMP runtime support currently ignores the argument of this function.

See also

[starpu_omp_get_default_device](#)
[starpu_omp_is_initial_device](#)

28.22.5.54 starpu_omp_get_default_device()

```
int starpu_omp_get_default_device (  
    void )
```

This function returns the number of the device used as default.

Returns

the number of the device used as default.

See also

[starpu_omp_set_default_device](#)
[starpu_omp_is_initial_device](#)

28.22.5.55 starpu_omp_get_num_devices()

```
int starpu_omp_get_num_devices (  
    void )
```

This function returns the number of the devices.

Returns

the number of the devices.

28.22.5.56 starpu_omp_get_num_teams()

```
int starpu_omp_get_num_teams (  
    void )
```

This function returns the number of teams in the current teams region.

Returns

the number of teams in the current teams region.

See also

[starpu_omp_get_num_teams](#)

28.22.5.57 `starpu_omp_get_team_num()`

```
int starpu_omp_get_team_num (
    void )
```

This function returns the team number of the calling thread.

Returns

the team number of the calling thread.

See also

[starpu_omp_get_num_teams](#)

28.22.5.58 `starpu_omp_is_initial_device()`

```
int starpu_omp_is_initial_device (
    void )
```

This function checks whether the current device is the initial device or not.

Returns

! 0 if called from the host device.
0 otherwise.

See also

[starpu_omp_set_default_device](#)
[starpu_omp_get_default_device](#)

28.22.5.59 `starpu_omp_init_lock()`

```
void starpu_omp_init_lock (
    starpu_omp_lock_t * lock )
```

This function initializes an opaque lock object.

See also

[starpu_omp_destroy_lock](#)
[starpu_omp_set_lock](#)
[starpu_omp_unset_lock](#)
[starpu_omp_test_lock](#)

28.22.5.60 starpu_omp_destroy_lock()

```
void starpu_omp_destroy_lock (
    starpu_omp_lock_t * lock )
```

This function destroys an opaque lock object.

See also

[starpu_omp_init_lock](#)
[starpu_omp_set_lock](#)
[starpu_omp_unset_lock](#)
[starpu_omp_test_lock](#)

28.22.5.61 starpu_omp_set_lock()

```
void starpu_omp_set_lock (
    starpu_omp_lock_t * lock )
```

This function locks an opaque lock object. If the lock is already locked, the function will block until it succeeds in exclusively acquiring the lock.

See also

[starpu_omp_init_lock](#)
[starpu_omp_destroy_lock](#)
[starpu_omp_unset_lock](#)
[starpu_omp_test_lock](#)

28.22.5.62 starpu_omp_unset_lock()

```
void starpu_omp_unset_lock (
    starpu_omp_lock_t * lock )
```

This function unlocks a previously locked lock object. The behaviour of this function is unspecified if it is called on an unlocked lock object.

See also

[starpu_omp_init_lock](#)
[starpu_omp_destroy_lock](#)
[starpu_omp_set_lock](#)
[starpu_omp_test_lock](#)

28.22.5.63 `starpu_omp_test_lock()`

```
int starpu_omp_test_lock (
    starpu_omp_lock_t * lock )
```

This function unblockingly attempts to lock a lock object and returns whether it succeeded or not.

Returns

! 0 if the function succeeded in acquiring the lock.
0 if the lock was already locked.

See also

[starpu_omp_init_lock](#)
[starpu_omp_destroy_lock](#)
[starpu_omp_set_lock](#)
[starpu_omp_unset_lock](#)

28.22.5.64 `starpu_omp_init_nest_lock()`

```
void starpu_omp_init_nest_lock (
    starpu_omp_nest_lock_t * lock )
```

This function initializes an opaque lock object supporting nested locking operations.

See also

[starpu_omp_destroy_nest_lock](#)
[starpu_omp_set_nest_lock](#)
[starpu_omp_unset_nest_lock](#)
[starpu_omp_test_nest_lock](#)

28.22.5.65 `starpu_omp_destroy_nest_lock()`

```
void starpu_omp_destroy_nest_lock (
    starpu_omp_nest_lock_t * lock )
```

This function destroys an opaque lock object supporting nested locking operations.

See also

[starpu_omp_init_nest_lock](#)
[starpu_omp_set_nest_lock](#)
[starpu_omp_unset_nest_lock](#)
[starpu_omp_test_nest_lock](#)

28.22.5.66 starpu_omp_set_nest_lock()

```
void starpu_omp_set_nest_lock (
    starpu_omp_nest_lock_t * lock )
```

This function locks an opaque lock object supporting nested locking operations. If the lock is already locked by another task, the function will block until it succeeds in exclusively acquiring the lock. If the lock is already taken by the current task, the function will increase the nested locking level of the lock object.

See also

[starpu_omp_init_nest_lock](#)
[starpu_omp_destroy_nest_lock](#)
[starpu_omp_unset_nest_lock](#)
[starpu_omp_test_nest_lock](#)

28.22.5.67 starpu_omp_unset_nest_lock()

```
void starpu_omp_unset_nest_lock (
    starpu_omp_nest_lock_t * lock )
```

This function unlocks a previously locked lock object supporting nested locking operations. If the lock has been locked multiple times in nested fashion, the nested locking level is decreased and the lock remains locked. Otherwise, if the lock has only been locked once, it becomes unlocked. The behaviour of this function is unspecified if it is called on an unlocked lock object. The behaviour of this function is unspecified if it is called from a different task than the one that locked the lock object.

See also

[starpu_omp_init_nest_lock](#)
[starpu_omp_destroy_nest_lock](#)
[starpu_omp_set_nest_lock](#)
[starpu_omp_test_nest_lock](#)

28.22.5.68 starpu_omp_test_nest_lock()

```
int starpu_omp_test_nest_lock (
    starpu_omp_nest_lock_t * lock )
```

This function unblocking attempts to lock an opaque lock object supporting nested locking operations and returns whether it succeeded or not. If the lock is already locked by another task, the function will return without having acquired the lock. If the lock is already taken by the current task, the function will increase the nested locking level of the lock object.

Returns

!0 if the function succeeded in acquiring the lock.
0 if the lock was already locked.

See also

[starpu_omp_init_nest_lock](#)
[starpu_omp_destroy_nest_lock](#)
[starpu_omp_set_nest_lock](#)
[starpu_omp_unset_nest_lock](#)

28.22.5.69 starpu_omp_atomic_fallback_inline_begin()

```
void starpu_omp_atomic_fallback_inline_begin (
    void )
```

This function implements the entry point of a fallback global atomic region. It blocks until it succeeds in acquiring exclusive access to the global atomic region.

See also

[starpu_omp_atomic_fallback_inline_end](#)

28.22.5.70 starpu_omp_atomic_fallback_inline_end()

```
void starpu_omp_atomic_fallback_inline_end (
    void )
```

This function implements the exit point of a fallback global atomic region. It release the exclusive access to the global atomic region.

See also

[starpu_omp_atomic_fallback_inline_begin](#)

28.22.5.71 starpu_omp_get_wtime()

```
double starpu_omp_get_wtime (
    void )
```

This function returns the elapsed wallclock time in seconds.

Returns

the elapsed wallclock time in seconds.

See also

[starpu_omp_get_wtick](#)

28.22.5.72 `starpu_omp_get_wtick()`

```
double starpu_omp_get_wtick (
    void )
```

This function returns the precision of the time used by `starpu_omp_get_wtime`.

Returns

the precision of the time used by `starpu_omp_get_wtime`.

See also

[starpu_omp_get_wtime](#)

28.22.5.73 `starpu_omp_vector_annotate()`

```
void starpu_omp_vector_annotate (
    starpu_data_handle_t handle,
    uint32_t slice_base )
```

This function enables setting additional vector metadata needed by the OpenMP Runtime Support.

`handle` is vector data handle. `slice_base` is the base of an array slice, expressed in number of vector elements from the array base.

See also

[STARPU_VECTOR_GET_SLICE_BASE](#)

28.23 MIC Extensions

Macros

- `#define` [STARPU_USE_MIC](#)
- `#define` [STARPU_MAXMICDEVS](#)

Typedefs

- `typedef void *` [starpu_mic_func_symbol_t](#)

Functions

- `int` [starpu_mic_register_kernel](#) ([starpu_mic_func_symbol_t](#) *symbol, const char *func_name)
- [starpu_mic_kernel_t](#) [starpu_mic_get_kernel](#) ([starpu_mic_func_symbol_t](#) symbol)

28.23.1 Detailed Description

28.23.2 Macro Definition Documentation

28.23.2.1 STARPU_USE_MIC

```
#define STARPU_USE_MIC
```

This macro is defined when StarPU has been installed with MIC support. It should be used in your code to detect the availability of MIC.

28.23.2.2 STARPU_MAXMICDEVS

```
#define STARPU_MAXMICDEVS
```

This macro defines the maximum number of MIC devices that are supported by StarPU.

28.23.3 Typedef Documentation

28.23.3.1 starpu_mic_func_symbol_t

```
starpu_mic_func_symbol_t
```

Type for MIC function symbols

28.23.4 Function Documentation

28.23.4.1 starpu_mic_register_kernel()

```
int starpu_mic_register_kernel (
    starpu_mic_func_symbol_t * symbol,
    const char * func_name )
```

Initiate a lookup on each MIC device to find the adress of the function named `func_name`, store them in the global array `kernels` and return the index in the array through `symbol`.

28.23.4.2 starpu_mic_get_kernel()

```
starpu_mic_kernel_t starpu_mic_get_kernel (
    starpu_mic_func_symbol_t symbol )
```

If success, return the pointer to the function defined by `symbol` on the device linked to the called device. This can for instance be used in a `starpu_mic_func_t` implementation.

28.24 SCC Extensions

Macros

- `#define STARPU_USE_SCC`
- `#define STARPU_MAXSCCDEVS`

Typedefs

- `typedef void * starpu_scc_func_symbol_t`

Functions

- `int starpu_scc_register_kernel (starpu_scc_func_symbol_t *symbol, const char *func_name)`
- `starpu_scc_kernel_t starpu_scc_get_kernel (starpu_scc_func_symbol_t symbol)`

28.24.1 Detailed Description

28.24.2 Macro Definition Documentation

28.24.2.1 STARPU_USE_SCC

```
#define STARPU_USE_SCC
```

This macro is defined when StarPU has been installed with SCC support. It should be used in your code to detect the availability of SCC.

28.24.2.2 STARPU_MAXSCCDEVS

```
#define STARPU_MAXSCCDEVS
```

This macro defines the maximum number of SCC devices that are supported by StarPU.

28.24.3 Typedef Documentation

28.24.3.1 `starpu_scc_func_symbol_t`

`starpu_scc_func_symbol_t`

Type for SCC function symbols

28.24.4 Function Documentation

28.24.4.1 `starpu_scc_register_kernel()`

```
int starpu_scc_register_kernel (
    starpu_scc_func_symbol_t * symbol,
    const char * func_name )
```

Initiate a lookup on each SCC device to find the adress of the function named `func_name`, store them in the global array `kernels` and return the index in the array through `symbol`.

28.24.4.2 `starpu_scc_get_kernel()`

```
starpu_scc_kernel_t starpu_scc_get_kernel (
    starpu_scc_func_symbol_t symbol )
```

If success, return the pointer to the function defined by `symbol` on the device linked to the called device. This can for instance be used in a `starpu_scc_func_t` implementation.

28.25 Miscellaneous Helpers

Functions

- int `starpu_data_cpy` (`starpu_data_handle_t` dst_handle, `starpu_data_handle_t` src_handle, int asynchronous, void(*callback_func)(void *), void *callback_arg)
- void `starpu_execute_on_each_worker` (void(*func)(void *), void *arg, uint32_t where)
- void `starpu_execute_on_each_worker_ex` (void(*func)(void *), void *arg, uint32_t where, const char *name)
- void `starpu_execute_on_specific_workers` (void(*func)(void *), void *arg, unsigned num_workers, unsigned *workers, const char *name)
- double `starpu_timing_now` (void)

28.25.1 Detailed Description

28.25.2 Function Documentation

28.25.2.1 `starpu_data_cpy()`

```
int starpu_data_cpy (
    starpu_data_handle_t dst_handle,
    starpu_data_handle_t src_handle,
    int asynchronous,
    void(*) (void *) callback_func,
    void * callback_arg )
```

Copy the content of `src_handle` into `dst_handle`. The parameter `asynchronous` indicates whether the function should block or not. In the case of an asynchronous call, it is possible to synchronize with the termination of this operation either by the means of implicit dependencies (if enabled) or by calling [starpu_task_wait_for_all\(\)](#). If `callback_func` is not NULL, this callback function is executed after the handle has been copied, and it is given the pointer `callback_arg` as argument.

28.25.2.2 `starpu_execute_on_each_worker()`

```
void starpu_execute_on_each_worker (
    void(*) (void *) func,
    void * arg,
    uint32_t where )
```

This function executes the given function on a subset of workers. When calling this method, the offloaded function `func` is executed by every StarPU worker that may execute the function. The argument `arg` is passed to the offloaded function. The argument `where` specifies on which types of processing units the function should be executed. Similarly to the field [starpu_codelet::where](#), it is possible to specify that the function should be executed on every CUDA device and every CPU by passing [STARPU_CPU|STARPU_CUDA](#). This function blocks until the function has been executed on every appropriate processing units, so that it may not be called from a callback function for instance.

28.25.2.3 `starpu_execute_on_each_worker_ex()`

```
void starpu_execute_on_each_worker_ex (
    void(*) (void *) func,
    void * arg,
    uint32_t where,
    const char * name )
```

Same as [starpu_execute_on_each_worker\(\)](#), except that the task name is specified in the argument `name`.

28.25.2.4 `starpu_execute_on_specific_workers()`

```
void starpu_execute_on_specific_workers (
    void(*) (void *) func,
    void * arg,
    unsigned num_workers,
    unsigned * workers,
    const char * name )
```

Call `func(arg)` on every worker in the `workers` array. `num_workers` indicates the number of workers in this array. This function is synchronous, but the different workers may execute the function in parallel.

28.25.2.5 `starpu_timing_now()`

```
double starpu_timing_now (
    void )
```

Return the current date in micro-seconds.

28.26 FxT Support

Data Structures

- struct [starpu_fxt_codelet_event](#)
- struct [starpu_fxt_options](#)

Functions

- void [starpu_fxt_options_init](#) (struct [starpu_fxt_options](#) *options)
- void [starpu_fxt_generate_trace](#) (struct [starpu_fxt_options](#) *options)
- void [starpu_fxt_start_profiling](#) (void)
- void [starpu_fxt_stop_profiling](#) (void)
- void [starpu_fxt_autostart_profiling](#) (int autostart)
- void [starpu_fxt_write_data_trace](#) (char *filename_in)
- void [starpu_fxt_trace_user_event](#) (unsigned long code)
- void [starpu_fxt_trace_user_event_string](#) (const char *s)

28.26.1 Detailed Description

28.26.2 Data Structure Documentation

28.26.2.1 struct `starpu_fxt_codelet_event`

todo

Data Fields

char	symbol[256]	name of the codelet
int	workerid	
char	perfmodel_archname[256]	
uint32_t	hash	
size_t	size	
float	time	

28.26.2.2 struct starpu_fxt_options

todo

Data Fields

	unsigned	per_task_colour	
	unsigned	no_events	
	unsigned	no_counter	
	unsigned	no_bus	
	unsigned	no_flops	
	unsigned	ninputfiles	
	unsigned	no_acquire	
	unsigned	internal	
	char *	filenames[STARPU_FXT_MAX_FILES]	
	char *	out_paje_path	
	char *	distrib_time_path	
	char *	activity_path	
	char *	dag_path	
	char *	tasks_path	
	char *	data_path	
	char *	anim_path	
	char *	file_prefix	In case we are going to gather multiple traces (e.g in the case of MPI processes), we may need to prefix the name of the containers.
	uint64_t	file_offset	In case we are going to gather multiple traces (e.g in the case of MPI processes), we may need to prefix the name of the containers.
	int	file_rank	In case we are going to gather multiple traces (e.g in the case of MPI processes), we may need to prefix the name of the containers.
	char	worker_names[STARPU_NMAXWORKERS][256]	Output parameters
struct starpu_perfmodel_arch		worker_archtypes[STARPU_NMAXWORKERS]	Output parameters
	int	nworkers	Output parameters
struct starpu_fxt_codelet_event **		dumped_codelets	In case we want to dump the list of codelets to an external tool
	long	dumped_codelets_count	In case we want to dump the list of codelets to an external tool

28.26.3 Function Documentation

28.26.3.1 `starpu_fxt_options_init()`

```
void starpu_fxt_options_init (
    struct starpu_fxt_options * options )
```

todo

28.26.3.2 `starpu_fxt_generate_trace()`

```
void starpu_fxt_generate_trace (
    struct starpu_fxt_options * options )
```

todo

28.26.3.3 `starpu_fxt_start_profiling()`

```
void starpu_fxt_start_profiling (
    void )
```

Start recording the trace. The trace is by default started from `starpu_init()` call, but can be paused by using `starpu_fxt_stop_profiling()`, in which case `starpu_fxt_start_profiling()` should be called to resume recording events.

28.26.3.4 `starpu_fxt_stop_profiling()`

```
void starpu_fxt_stop_profiling (
    void )
```

Stop recording the trace. The trace is by default stopped when calling `starpu_shutdown()`. `starpu_fxt_stop_profiling()` can however be used to stop it earlier. `starpu_fxt_start_profiling()` can then be called to start recording it again, etc.

28.26.3.5 `starpu_fxt_autostart_profiling()`

```
void starpu_fxt_autostart_profiling (
    int autostart )
```

Determines whether profiling should be started by `starpu_init`, or only when `starpu_fxt_start_profiling` is called. *autostart* should be 1 to do so, or 0 to prevent it.

28.26.3.6 `starpu_fxt_write_data_trace()`

```
void starpu_fxt_write_data_trace (
    char * filename_in )
```

todo

28.26.3.7 `starpu_fxt_trace_user_event()`

```
void starpu_fxt_trace_user_event (
    unsigned long code )
```

Add an event in the execution trace if FxT is enabled.

28.26.3.8 `starpu_fxt_trace_user_event_string()`

```
void starpu_fxt_trace_user_event_string (
    const char * s )
```

Add a string event in the execution trace if FxT is enabled.

28.27 FFT Support

Functions

- void * `starpufft_malloc` (size_t n)
- void `starpufft_free` (void *p)
- starpufft_plan `starpufft_plan_dft_1d` (int n, int sign, unsigned flags)
- starpufft_plan `starpufft_plan_dft_2d` (int n, int m, int sign, unsigned flags)
- struct `starpu_task` * `starpufft_start` (starpufft_plan p, void *in, void *out)
- struct `starpu_task` * `starpufft_start_handle` (starpufft_plan p, `starpu_data_handle_t` in, `starpu_data_handle_t` out)
- int `starpufft_execute` (starpufft_plan p, void *in, void *out)
- int `starpufft_execute_handle` (starpufft_plan p, `starpu_data_handle_t` in, `starpu_data_handle_t` out)
- void `starpufft_cleanup` (starpufft_plan p)
- void `starpufft_destroy_plan` (starpufft_plan p)

28.27.1 Detailed Description

28.27.2 Function Documentation

28.27.2.1 `starpufft_malloc()`

```
void * starpufft_malloc (
    size_t n )
```

Allocates memory for n bytes. This is preferred over malloc(), since it allocates pinned memory, which allows overlapped transfers.

28.27.2.2 starpufft_free()

```
void * starpufft_free (
    void * p )
```

Release memory previously allocated.

28.27.2.3 starpufft_plan_dft_1d()

```
struct starpufft_plan * starpufft_plan_dft_1d (
    int n,
    int sign,
    unsigned flags )
```

Initializes a plan for 1D FFT of size *n*. *sign* can be `STARPUFFT_FORWARD` or `STARPUFFT_INVERSE`. *flags* must be 0.

28.27.2.4 starpufft_plan_dft_2d()

```
struct starpufft_plan * starpufft_plan_dft_2d (
    int n,
    int m,
    int sign,
    unsigned flags )
```

Initializes a plan for 2D FFT of size (*n*, *m*). *sign* can be `STARPUFFT_FORWARD` or `STARPUFFT_INVERSE`. *flags* must be 0.

28.27.2.5 starpufft_start()

```
struct starpu_task * starpufft_start (
    starpufft_plan p,
    void * in,
    void * out )
```

Start an FFT previously planned as *p*, using *in* and *out* as input and output. This only submits the task and does not wait for it. The application should call [starpufft_cleanup\(\)](#) to unregister the

28.27.2.6 starpufft_start_handle()

```
struct starpu_task * starpufft_start_handle (
    starpufft_plan p,
    starpu_data_handle_t in,
    starpu_data_handle_t out )
```

Start an FFT previously planned as *p*, using data handles *in* and *out* as input and output (assumed to be vectors of elements of the expected types). This only submits the task and does not wait for it.

28.27.2.7 starpufft_execute()

```
void starpufft_execute (
    starpufft_plan p,
    void * in,
    void * out )
```

Execute an FFT previously planned as `p`, using `in` and `out` as input and output. This submits and waits for the task.

28.27.2.8 starpufft_execute_handle()

```
void starpufft_execute_handle (
    starpufft_plan p,
    starpu_data_handle_t in,
    starpu_data_handle_t out )
```

Execute an FFT previously planned as `p`, using data handles `in` and `out` as input and output (assumed to be vectors of elements of the expected types). This submits and waits for the task.

28.27.2.9 starpufft_cleanup()

```
void starpufft_cleanup (
    starpufft_plan p )
```

Releases data for plan `p`, in the [starpufft_start\(\)](#) case.

28.27.2.10 starpufft_destroy_plan()

```
void starpufft_destroy_plan (
    starpufft_plan p )
```

Destroys plan `p`, i.e. release all CPU (fftw) and GPU (cufft) resources.

28.28 MPI Support

Initialisation

- `#define STARPU_USE_MPI`
- `int starpu_mpi_init_comm (int *argc, char ***argv, int initialize_mpi, MPI_Comm comm)`
- `int starpu_mpi_init (int *argc, char ***argv, int initialize_mpi)`
- `int starpu_mpi_initialize (void)`
- `int starpu_mpi_initialize_extended (int *rank, int *world_size)`
- `int starpu_mpi_shutdown (void)`
- `void starpu_mpi_comm_amounts_retrieve (size_t *comm_amounts)`
- `int starpu_mpi_comm_size (MPI_Comm comm, int *size)`
- `int starpu_mpi_comm_rank (MPI_Comm comm, int *rank)`
- `int starpu_mpi_world_rank (void)`
- `int starpu_mpi_world_size (void)`

Communication

- `#define STARPU_MPI_TAG_UB`
- `int starpu_mpi_send (starpu_data_handle_t data_handle, int dest, int mpi_tag, MPI_Comm comm)`
- `int starpu_mpi_recv (starpu_data_handle_t data_handle, int source, int mpi_tag, MPI_Comm comm, MPI_Status *status)`
- `int starpu_mpi_isend (starpu_data_handle_t data_handle, starpu_mpi_req *req, int dest, int mpi_tag, MPI_Comm comm)`
- `int starpu_mpi_irecv (starpu_data_handle_t data_handle, starpu_mpi_req *req, int source, int mpi_tag, MPI_Comm comm)`
- `int starpu_mpi_isend_detached (starpu_data_handle_t data_handle, int dest, int mpi_tag, MPI_Comm comm, void(*callback)(void *), void *arg)`
- `int starpu_mpi_irecv_detached (starpu_data_handle_t data_handle, int source, int mpi_tag, MPI_Comm comm, void(*callback)(void *), void *arg)`
- `int starpu_mpi_irecv_detached_sequential_consistency (starpu_data_handle_t data_handle, int source, int mpi_tag, MPI_Comm comm, void(*callback)(void *), void *arg, int sequential_consistency)`
- `int starpu_mpi_issend (starpu_data_handle_t data_handle, starpu_mpi_req *req, int dest, int mpi_tag, MPI_Comm comm)`
- `int starpu_mpi_issend_detached (starpu_data_handle_t data_handle, int dest, int mpi_tag, MPI_Comm comm, void(*callback)(void *), void *arg)`
- `int starpu_mpi_wait (starpu_mpi_req *req, MPI_Status *status)`
- `int starpu_mpi_test (starpu_mpi_req *req, int *flag, MPI_Status *status)`
- `int starpu_mpi_barrier (MPI_Comm comm)`
- `int starpu_mpi_wait_for_all (MPI_Comm comm)`
- `int starpu_mpi_isend_detached_unlock_tag (starpu_data_handle_t data_handle, int dest, int mpi_tag, MPI_Comm comm, starpu_tag_t tag)`
- `int starpu_mpi_irecv_detached_unlock_tag (starpu_data_handle_t data_handle, int source, int mpi_tag, MPI_Comm comm, starpu_tag_t tag)`
- `int starpu_mpi_isend_array_detached_unlock_tag (unsigned array_size, starpu_data_handle_t *data_handle, int *dest, int *mpi_tag, MPI_Comm *comm, starpu_tag_t tag)`
- `int starpu_mpi_irecv_array_detached_unlock_tag (unsigned array_size, starpu_data_handle_t *data_handle, int *source, int *mpi_tag, MPI_Comm *comm, starpu_tag_t tag)`
- `int starpu_mpi_get_communication_tag (void)`
- `void starpu_mpi_set_communication_tag (int tag)`
- `int starpu_mpi_datatype_register (starpu_data_handle_t handle, starpu_mpi_datatype_allocate_func_t allocate_datatype_func, starpu_mpi_datatype_free_func_t free_datatype_func)`
- `int starpu_mpi_datatype_unregister (starpu_data_handle_t handle)`
- `int starpu_mpi_comm_get_attr (MPI_Comm comm, int keyval, void *attribute_val, int *flag)`

Communication Cache

- `int starpu_mpi_cache_is_enabled ()`
- `int starpu_mpi_cache_set (int enabled)`
- `void starpu_mpi_cache_flush (MPI_Comm comm, starpu_data_handle_t data_handle)`
- `void starpu_mpi_cache_flush_all_data (MPI_Comm comm)`
- `int starpu_mpi_cached_receive (starpu_data_handle_t data_handle)`
- `int starpu_mpi_cached_send (starpu_data_handle_t data_handle, int dest)`

MPI Insert Task

- `#define starpu_mpi_data_register(data_handle, tag, rank)`
- `#define starpu_data_set_tag`
- `#define starpu_mpi_data_set_rank(handle, rank)`
- `#define starpu_data_set_rank`
- `#define starpu_data_get_rank`
- `#define starpu_data_get_tag`
- `#define STARPU_MPI_PER_NODE`
- `#define STARPU_EXECUTE_ON_NODE`
- `#define STARPU_EXECUTE_ON_DATA`
- `#define STARPU_NODE_SELECTION_POLICY`
- `void starpu_mpi_data_register_comm (starpu_data_handle_t data_handle, int tag, int rank, MPI_Comm comm)`
- `void starpu_mpi_data_set_tag (starpu_data_handle_t handle, int tag)`
- `void starpu_mpi_data_set_rank_comm (starpu_data_handle_t handle, int rank, MPI_Comm comm)`
- `int starpu_mpi_data_get_rank (starpu_data_handle_t handle)`
- `int starpu_mpi_data_get_tag (starpu_data_handle_t handle)`
- `void starpu_mpi_data_migrate (MPI_Comm comm, starpu_data_handle_t handle, int new_rank)`
- `int starpu_mpi_insert_task (MPI_Comm comm, struct starpu_codelet *codelet,...)`
- `int starpu_mpi_task_insert (MPI_Comm comm, struct starpu_codelet *codelet,...)`
- `struct starpu_task * starpu_mpi_task_build (MPI_Comm comm, struct starpu_codelet *codelet,...)`
- `int starpu_mpi_task_post_build (MPI_Comm comm, struct starpu_codelet *codelet,...)`
- `void starpu_mpi_get_data_on_node (MPI_Comm comm, starpu_data_handle_t data_handle, int node)`
- `void starpu_mpi_get_data_on_node_detached (MPI_Comm comm, starpu_data_handle_t data_handle, int node, void(*callback)(void *), void *arg)`
- `void starpu_mpi_get_data_on_all_nodes_detached (MPI_Comm comm, starpu_data_handle_t data_handle)`

Node Selection Policy

- `int starpu_mpi_node_selection_get_current_policy ()`
- `int starpu_mpi_node_selection_set_current_policy (int policy)`
- `int starpu_mpi_node_selection_register_policy (starpu_mpi_select_node_policy_func_t policy_func)`
- `int starpu_mpi_node_selection_unregister_policy (int policy)`

Collective Operations

- `void starpu_mpi_redux_data (MPI_Comm comm, starpu_data_handle_t data_handle)`
- `int starpu_mpi_scatter_detached (starpu_data_handle_t *data_handles, int count, int root, MPI_Comm comm, void(*scallback)(void *), void *sarg, void(*rcallback)(void *), void *rarg)`
- `int starpu_mpi_gather_detached (starpu_data_handle_t *data_handles, int count, int root, MPI_Comm comm, void(*scallback)(void *), void *sarg, void(*rcallback)(void *), void *rarg)`

28.28.1 Detailed Description

28.28.2 Macro Definition Documentation

28.28.2.1 STARPU_USE_MPI

```
#define STARPU_USE_MPI
```

This macro is defined when StarPU has been installed with MPI support. It should be used in your code to detect the availability of MPI.

28.28.2.2 STARPU_MPI_TAG_UB

```
#define STARPU_MPI_TAG_UB
```

When given to the function [starpu_mpi_comm_get_attr\(\)](#), retrieve the value for the upper bound for tag value.

28.28.2.3 starpu_mpi_data_register

```
#define starpu_mpi_data_register(  
    data_handle,  
    tag,  
    rank )
```

Register to MPI a StarPU data handle with the given tag, rank and the MPI communicator MPI_COMM_WORLD. It also automatically clears the MPI communication cache when unregistering the data.

28.28.2.4 starpu_data_set_tag

```
#define starpu_data_set_tag
```

Symbol kept for backward compatibility. Calling function [starpu_mpi_data_set_tag](#)

28.28.2.5 starpu_mpi_data_set_rank

```
#define starpu_mpi_data_set_rank(  
    handle,  
    rank )
```

Register to MPI a StarPU data handle with the given rank and the MPI communicator MPI_COMM_WORLD. No tag will be defined. It also automatically clears the MPI communication cache when unregistering the data. Symbol kept for backward compatibility. Calling function [starpu_mpi_data_set_rank](#)

28.28.2.6 starpu_data_set_rank

```
#define starpu_data_set_rank
```

Register to MPI a StarPU data handle with the given rank and the MPI communicator MPI_COMM_WORLD. No tag will be defined. It also automatically clears the MPI communication cache when unregistering the data. Symbol kept for backward compatibility. Calling function [starpu_mpi_data_set_rank](#)

28.28.2.7 `starpu_data_get_rank`

```
#define starpu_data_get_rank
```

Return the rank of the given data. Symbol kept for backward compatibility. Calling function `starpu_mpi_data_get_rank`

28.28.2.8 `starpu_data_get_tag`

```
#define starpu_data_get_tag
```

Return the tag of the given data. Symbol kept for backward compatibility. Calling function `starpu_mpi_data_get_tag`

28.28.2.9 `STARPU_MPI_PER_NODE`

```
#define STARPU_MPI_PER_NODE
```

Can be used as rank when calling `starpu_mpi_data_register()` and alike, to specify that the data is per-node: each node will have its own value. Tasks writing to such data will be replicated on all nodes (and all parameters then have to be per-node). Tasks not writing to such data will just take the node-local value without any MPI communication.

28.28.2.10 `STARPU_EXECUTE_ON_NODE`

```
#define STARPU_EXECUTE_ON_NODE
```

this macro is used when calling `starpu_mpi_task_insert()`, and must be followed by a integer value which specified the node on which to execute the codelet.

28.28.2.11 `STARPU_EXECUTE_ON_DATA`

```
#define STARPU_EXECUTE_ON_DATA
```

this macro is used when calling `starpu_mpi_task_insert()`, and must be followed by a data handle to specify that the node owning the given data will execute the codelet.

28.28.2.12 `STARPU_NODE_SELECTION_POLICY`

```
#define STARPU_NODE_SELECTION_POLICY
```

this macro is used when calling `starpu_mpi_task_insert()`, and must be followed by a identifier to a node selection policy. This is needed when several nodes own data in `STARPU_W` mode.

28.28.3 Function Documentation

28.28.3.1 starpu_mpi_init_comm()

```
int starpu_mpi_init_comm (
    int * argc,
    char *** argv,
    int initialize_mpi,
    MPI_Comm comm )
```

Initializes the starpumpi library with the given communicator. `initialize_mpi` indicates if MPI should be initialized or not by StarPU. If the value is not 0, MPI will be initialized by calling `MPI_Init_Thread(argc, argv, MPI_THREAD_SERIALIZED, ...)`. [starpu_init\(\)](#) must be called before [starpu_mpi_init_comm\(\)](#).

28.28.3.2 starpu_mpi_init()

```
int starpu_mpi_init (
    int * argc,
    char *** argv,
    int initialize_mpi )
```

Call [starpu_mpi_init_comm\(\)](#) with the MPI communicator `MPI_COMM_WORLD`.

28.28.3.3 starpu_mpi_initialize()

```
int starpu_mpi_initialize (
    void )
```

Deprecated This function has been made deprecated. One should use instead the function [starpu_mpi_init\(\)](#). This function does not call `MPI_Init()`, it should be called beforehand.

28.28.3.4 starpu_mpi_initialize_extended()

```
int starpu_mpi_initialize_extended (
    int * rank,
    int * world_size )
```

Deprecated This function has been made deprecated. One should use instead the function [starpu_mpi_init\(\)](#). MPI will be initialized by starpumpi by calling `MPI_Init_Thread(argc, argv, MPI_THREAD_SERIALIZED, ...)`.

28.28.3.5 starpu_mpi_shutdown()

```
int starpu_mpi_shutdown (
    void )
```

Cleans the starpumpi library. This must be called between calling starpu_mpi functions and [starpu_shutdown\(\)](#). `MPI_Finalize()` will be called if StarPU-MPI has been initialized by [starpu_mpi_init\(\)](#).

28.28.3.6 starpu_mpi_comm_amounts_retrieve()

```
void starpu_mpi_comm_amounts_retrieve (
    size_t * comm_amounts )
```

Retrieve the current amount of communications from the current node in the array `comm_amounts` which must have a size greater or equal to the world size. Communications statistics must be enabled (see [STARPU_COMM_STATS](#)).

28.28.3.7 starpu_mpi_comm_size()

```
int starpu_mpi_comm_size (
    MPI_Comm comm,
    int * size )
```

Return in `size` the size of the communicator `comm`

28.28.3.8 starpu_mpi_comm_rank()

```
int starpu_mpi_comm_rank (
    MPI_Comm comm,
    int * rank )
```

Return in `rank` the rank of the calling process in the communicator `comm`

28.28.3.9 starpu_mpi_world_rank()

```
int starpu_mpi_world_rank (
    void )
```

Return the rank of the calling process in the communicator `MPI_COMM_WORLD`

28.28.3.10 starpu_mpi_world_size()

```
int starpu_mpi_world_size (
    void )
```

Return the size of the communicator `MPI_COMM_WORLD`

28.28.3.11 starpu_mpi_send()

```
int starpu_mpi_send (
    starpu_data_handle_t data_handle,
    int dest,
    int mpi_tag,
    MPI_Comm comm )
```

Performs a standard-mode, blocking send of `data_handle` to the node `dest` using the message tag `mpi_tag` within the communicator `comm`.

28.28.3.12 starpu_mpi_recv()

```
int starpu_mpi_recv (
    starpu_data_handle_t data_handle,
    int source,
    int mpi_tag,
    MPI_Comm comm,
    MPI_Status * status )
```

Performs a standard-mode, blocking receive in `data_handle` from the node `source` using the message tag `mpi_tag` within the communicator `comm`.

28.28.3.13 starpu_mpi_isend()

```
int starpu_mpi_isend (
    starpu_data_handle_t data_handle,
    starpu_mpi_req * req,
    int dest,
    int mpi_tag,
    MPI_Comm comm )
```

Posts a standard-mode, non blocking send of `data_handle` to the node `dest` using the message tag `mpi_tag` within the communicator `comm`. After the call, the pointer to the request `req` can be used to test or to wait for the completion of the communication.

28.28.3.14 starpu_mpi_irecv()

```
int starpu_mpi_irecv (
    starpu_data_handle_t data_handle,
    starpu_mpi_req * req,
    int source,
    int mpi_tag,
    MPI_Comm comm )
```

Posts a nonblocking receive in `data_handle` from the node `source` using the message tag `mpi_tag` within the communicator `comm`. After the call, the pointer to the request `req` can be used to test or to wait for the completion of the communication.

28.28.3.15 starpu_mpi_isend_detached()

```
int starpu_mpi_isend_detached (
    starpu_data_handle_t data_handle,
    int dest,
    int mpi_tag,
    MPI_Comm comm,
    void(*) (void *) callback,
    void * arg )
```

Posts a standard-mode, non blocking send of `data_handle` to the node `dest` using the message tag `mpi_tag` within the communicator `comm`. On completion, the `callback` function is called with the argument `arg`. Similarly to the pthread detached functionality, when a detached communication completes, its resources are automatically released back to the system, there is no need to test or to wait for the completion of the request.

28.28.3.16 starpu_mpi_irecv_detached()

```
int starpu_mpi_irecv_detached (
    starpu_data_handle_t data_handle,
    int source,
    int mpi_tag,
    MPI_Comm comm,
    void(*) (void *) callback,
    void * arg )
```

Posts a nonblocking receive in `data_handle` from the node `source` using the message tag `mpi_tag` within the communicator `comm`. On completion, the `callback` function is called with the argument `arg`. Similarly to the pthread detached functionality, when a detached communication completes, its resources are automatically released back to the system, there is no need to test or to wait for the completion of the request.

28.28.3.17 starpu_mpi_irecv_detached_sequential_consistency()

```
int starpu_mpi_irecv_detached_sequential_consistency (
    starpu_data_handle_t data_handle,
    int source,
    int mpi_tag,
    MPI_Comm comm,
    void(*) (void *) callback,
    void * arg,
    int sequential_consistency )
```

Posts a nonblocking receive in `data_handle` from the node `source` using the message tag `mpi_tag` within the communicator `comm`. On completion, the `callback` function is called with the argument `arg`. The parameter `sequential_consistency` allows to enable or disable the sequential consistency for data handle (sequential consistency will be enabled or disabled based on the value of the parameter `sequential_consistency` and the value of the sequential consistency defined for `data_handle`). Similarly to the pthread detached functionality, when a detached communication completes, its resources are automatically released back to the system, there is no need to test or to wait for the completion of the request.

28.28.3.18 starpu_mpi_issend()

```
int starpu_mpi_issend (
    starpu_data_handle_t data_handle,
    starpu_mpi_req * req,
    int dest,
    int mpi_tag,
    MPI_Comm comm )
```

Performs a synchronous-mode, non-blocking send of `data_handle` to the node `dest` using the message tag `mpi_tag` within the communicator `comm`.

28.28.3.19 starpu_mpi_issend_detached()

```
int starpu_mpi_issend_detached (
    starpu_data_handle_t data_handle,
    int dest,
    int mpi_tag,
    MPI_Comm comm,
    void(*) (void *) callback,
    void * arg )
```

Performs a synchronous-mode, non-blocking send of `data_handle` to the node `dest` using the message tag `mpi_tag` within the communicator `comm`. On completion, the `callback` function is called with the argument `arg`. Similarly to the pthread detached functionality, when a detached communication completes, its resources are automatically released back to the system, there is no need to test or to wait for the completion of the request.

28.28.3.20 starpu_mpi_wait()

```
int starpu_mpi_wait (
    starpu_mpi_req * req,
    MPI_Status * status )
```

Returns when the operation identified by request `req` is complete.

28.28.3.21 starpu_mpi_test()

```
int starpu_mpi_test (
    starpu_mpi_req * req,
    int * flag,
    MPI_Status * status )
```

If the operation identified by `req` is complete, set `flag` to 1. The `status` object is set to contain information on the completed operation.

28.28.3.22 starpu_mpi_barrier()

```
int starpu_mpi_barrier (
    MPI_Comm comm )
```

Blocks the caller until all group members of the communicator `comm` have called it.

28.28.3.23 starpu_mpi_wait_for_all()

```
int starpu_mpi_wait_for_all (
    MPI_Comm comm )
```

Wait until all StarPU tasks and communications for the given communicator are completed.

28.28.3.24 starpu_mpi_isend_detached_unlock_tag()

```
int starpu_mpi_isend_detached_unlock_tag (
    starpu_data_handle_t data_handle,
    int dest,
    int mpi_tag,
    MPI_Comm comm,
    starpu_tag_t tag )
```

Posts a standard-mode, non blocking send of `data_handle` to the node `dest` using the message tag `mpi_tag` within the communicator `comm`. On completion, `tag` is unlocked.

28.28.3.25 starpu_mpi_irecv_detached_unlock_tag()

```
int starpu_mpi_irecv_detached_unlock_tag (
    starpu_data_handle_t data_handle,
    int source,
    int mpi_tag,
    MPI_Comm comm,
    starpu_tag_t tag )
```

Posts a nonblocking receive in `data_handle` from the node `source` using the message tag `mpi_tag` within the communicator `comm`. On completion, `tag` is unlocked.

28.28.3.26 starpu_mpi_isend_array_detached_unlock_tag()

```
int starpu_mpi_isend_array_detached_unlock_tag (
    unsigned array_size,
    starpu_data_handle_t * data_handle,
    int * dest,
    int * mpi_tag,
    MPI_Comm * comm,
    starpu_tag_t tag )
```

Posts `array_size` standard-mode, non blocking send. Each post sends the `n`-th data of the array `data_handle` to the `n`-th node of the array `dest` using the `n`-th message tag of the array `mpi_tag` within the `n`-th communicator of the array `comm`. On completion of the all the requests, `tag` is unlocked.

28.28.3.27 starpu_mpi_irecv_array_detached_unlock_tag()

```
int starpu_mpi_irecv_array_detached_unlock_tag (
    unsigned array_size,
    starpu_data_handle_t * data_handle,
    int * source,
    int * mpi_tag,
    MPI_Comm * comm,
    starpu_tag_t tag )
```

Posts `array_size` nonblocking receive. Each post receives in the `n`-th data of the array `data_handle` from the `n`-th node of the array `source` using the `n`-th message tag of the array `mpi_tag` within the `n`-th communicator of the array `comm`. On completion of the all the requests, `tag` is unlocked.

28.28.3.28 starpu_mpi_get_communication_tag()

```
int starpu_mpi_get_communication_tag (
    void )
```

todo

28.28.3.29 starpu_mpi_set_communication_tag()

```
void starpu_mpi_set_communication_tag (
    int tag )
```

todo

28.28.3.30 starpu_mpi_datatype_register()

```
int starpu_mpi_datatype_register (
    starpu_data_handle_t handle,
    starpu_mpi_datatype_allocate_func_t allocate_datatype_func,
    starpu_mpi_datatype_free_func_t free_datatype_func )
```

Register functions to create and free a MPI datatype for the given handle. It is important that the function is called before any communication can take place for a data with the given handle. See [Exchanging User Defined Data Interface](#) for an example.

28.28.3.31 starpu_mpi_datatype_unregister()

```
int starpu_mpi_datatype_unregister (
    starpu_data_handle_t handle )
```

Unregister the MPI datatype functions stored for the interface of the given handle.

28.28.3.32 starpu_mpi_comm_get_attr()

```
int starpu_mpi_comm_get_attr (
    MPI_Comm comm,
    int keyval,
    void * attribute_val,
    int * flag )
```

Retrieve an attribute value by key, similarly to the MPI function `MPI_comm_get_attr()`, except that the value is a pointer to `int64_t` instead of `int`. If an attribute is attached on `comm` to `keyval`, then the call returns `flag` equal to 1, and the attribute value in `attribute_val`. Otherwise, `flag` is set to 0.

28.28.3.33 starpu_mpi_cache_is_enabled()

```
int starpu_mpi_cache_is_enabled ( )
```

Return 1 if the communication cache is enabled, 0 otherwise

28.28.3.34 starpu_mpi_cache_set()

```
int starpu_mpi_cache_set (
    int enabled )
```

If `enabled` is 1, enable the communication cache. Otherwise, clean the cache if it was enabled and disable it.

28.28.3.35 starpu_mpi_cache_flush()

```
void starpu_mpi_cache_flush (
    MPI_Comm comm,
    starpu_data_handle_t data_handle )
```

Clear the send and receive communication cache for the data `data_handle` and invalidate the value. The function has to be called at the same point of task graph submission by all the MPI nodes on which the handle was registered. The function does nothing if the cache mechanism is disabled (see [STARPU_MPI_CACHE](#)).

28.28.3.36 starpu_mpi_cache_flush_all_data()

```
void starpu_mpi_cache_flush_all_data (
    MPI_Comm comm )
```

Clear the send and receive communication cache for all data and invalidate their values. The function has to be called at the same point of task graph submission by all the MPI nodes. The function does nothing if the cache mechanism is disabled (see [STARPU_MPI_CACHE](#)).

28.28.3.37 starpu_mpi_cached_receive()

```
int starpu_mpi_cached_receive (
    starpu_data_handle_t data_handle )
```

Test whether `data_handle` is cached for reception, i.e. the value was previously received from the owner node, and not flushed since then.

28.28.3.38 starpu_mpi_cached_send()

```
int starpu_mpi_cached_send (
    starpu_data_handle_t data_handle,
    int dest )
```

Test whether `data_handle` is cached for emission to node `dest`, i.e. the value was previously sent to `dest`, and not flushed since then.

28.28.3.39 starpu_mpi_data_register_comm()

```
void starpu_mpi_data_register_comm (
    starpu_data_handle_t data_handle,
    int tag,
    int rank,
    MPI_Comm comm )
```

Register to MPI a StarPU data handle with the given tag, rank and MPI communicator. It also automatically clears the MPI communication cache when unregistering the data.

28.28.3.40 starpu_mpi_data_set_tag()

```
void starpu_mpi_data_set_tag (
    starpu_data_handle_t handle,
    int tag )
```

Register to MPI a StarPU data handle with the given tag. No rank will be defined. It also automatically clears the MPI communication cache when unregistering the data.

28.28.3.41 starpu_mpi_data_set_rank_comm()

```
void starpu_mpi_data_set_rank_comm (
    starpu_data_handle_t handle,
    int rank,
    MPI_Comm comm )
```

Register to MPI a StarPU data handle with the given rank and given communicator. No tag will be defined. It also automatically clears the MPI communication cache when unregistering the data.

28.28.3.42 starpu_mpi_data_get_rank()

```
int starpu_mpi_data_get_rank (
    starpu_data_handle_t handle )
```

Return the rank of the given data.

28.28.3.43 starpu_mpi_data_get_tag()

```
int starpu_mpi_data_get_tag (
    starpu_data_handle_t handle )
```

Return the tag of the given data.

28.28.3.44 starpu_mpi_data_migrate()

```
void starpu_mpi_data_migrate (
    MPI_Comm comm,
    starpu_data_handle_t handle,
    int new_rank )
```

Submits migration of the data onto the `new_rank` MPI node. This means both submitting the transfer of the data to node `new_rank` if it hasn't been submitted already, and setting the home node of the data to the new node. Further data transfers submitted by [starpu_mpi_task_insert\(\)](#) will be done from that new node. This function thus needs to be called on all nodes which have registered the data at the same point of tasks submissions. This also flushes the cache for this data to avoid incoherencies.

28.28.3.45 starpu_mpi_insert_task()

```
int starpu_mpi_insert_task (
    MPI_Comm comm,
    struct starpu_codelet * codelet,
    ... )
```

This function does the same as the function [starpu_mpi_task_insert\(\)](#). It has been kept to avoid breaking old codes.

28.28.3.46 starpu_mpi_task_insert()

```
int starpu_mpi_task_insert (
    MPI_Comm comm,
    struct starpu_codelet * codelet,
    ... )
```

Create and submit a task corresponding to codelet with the following arguments. The argument list must be zero-terminated.

The arguments following the codelet are the same types as for the function [starpu_task_insert\(\)](#). Access modes for data can also be set with [STARPU_SSEND](#) to specify the data has to be sent using a synchronous and non-blocking mode (see [starpu_mpi_issend\(\)](#)). The extra argument [STARPU_EXECUTE_ON_NODE](#) followed by an integer allows to specify the MPI node to execute the codelet. It is also possible to specify that the node owning a specific data will execute the codelet, by using [STARPU_EXECUTE_ON_DATA](#) followed by a data handle.

The internal algorithm is as follows:

1. Find out which MPI node is going to execute the codelet.
 - If there is only one node owning data in [STARPU_W](#) mode, it will be selected;
 - If there is several nodes owning data in [STARPU_W](#) mode, a node will be selected according to a given node selection policy (see [STARPU_NODE_SELECTION_POLICY](#) or [starpu_mpi_node_selection_↵set_current_policy\(\)](#));
 - The argument [STARPU_EXECUTE_ON_NODE](#) followed by an integer can be used to specify the node;
 - The argument [STARPU_EXECUTE_ON_DATA](#) followed by a data handle can be used to specify that the node owning the given data will execute the codelet.
2. Send and receive data as requested. Nodes owning data which need to be read by the task are sending them to the MPI node which will execute it. The latter receives them.
3. Execute the codelet. This is done by the MPI node selected in the 1st step of the algorithm.
4. If several MPI nodes own data to be written to, send written data back to their owners.

The algorithm also includes a communication cache mechanism that allows not to send data twice to the same MPI node, unless the data has been modified. The cache can be disabled (see [STARPU_MPI_CACHE](#)).

28.28.3.47 starpu_mpi_task_build()

```
struct starpu_task * starpu_mpi_task_build (
    MPI_Comm comm,
    struct starpu_codelet * codelet,
    ... )
```

Create a task corresponding to codelet with the following arguments. The argument list must be zero-terminated. The function performs the first two steps of the function [starpu_mpi_task_insert\(\)](#), i.e. submitting the MPI communications needed before the execution of the task, and the creation of the task on one node. Only the MPI node selected in the first step of the algorithm will return a valid task structure which can then be submitted, others will return NULL. The function [starpu_mpi_task_post_build\(\)](#) MUST be called after that on all nodes, and after the submission of the task on the node which creates it, with the SAME list of arguments.

28.28.3.48 starpu_mpi_task_post_build()

```
int starpu_mpi_task_post_build (
    MPI_Comm comm,
    struct starpu_codelet * codelet,
    ... )
```

This function MUST be called after a call to [starpu_mpi_task_build\(\)](#), with the SAME list of arguments. It performs the fourth – last – step of the algorithm described in [starpu_mpi_task_insert\(\)](#).

28.28.3.49 starpu_mpi_get_data_on_node()

```
void starpu_mpi_get_data_on_node (
    MPI_Comm comm,
    starpu_data_handle_t data_handle,
    int node )
```

Transfer data `data_handle` to MPI node `node`, sending it from its owner if needed. At least the target node and the owner have to call the function.

28.28.3.50 starpu_mpi_get_data_on_node_detached()

```
void starpu_mpi_get_data_on_node_detached (
    MPI_Comm comm,
    starpu_data_handle_t data_handle,
    int node,
    void(*) (void *) callback,
    void * arg )
```

Transfer data `data_handle` to MPI node `node`, sending it from its owner if needed. At least the target node and the owner have to call the function. On reception, the `callback` function is called with the argument `arg`.

28.28.3.51 starpu_mpi_get_data_on_all_nodes_detached()

```
void starpu_mpi_get_data_on_all_nodes_detached (
    MPI_Comm comm,
    starpu_data_handle_t data_handle )
```

Transfer data `data_handle` to all MPI nodes, sending it from its owner if needed. All nodes have to call the function.

28.28.3.52 starpu_mpi_node_selection_get_current_policy()

```
int starpu_mpi_node_selection_get_current_policy ( )
```

Return the current policy used to select the node which will execute the codelet

28.28.3.53 starpu_mpi_node_selection_set_current_policy()

```
int starpu_mpi_node_selection_set_current_policy (
    int policy )
```

Set the current policy used to select the node which will execute the codelet. The policy STARPU_MPI_NODE_SELECTION_MOST_R_DATA selects the node having the most data in R mode so as to minimize the amount of data to be transferred.

28.28.3.54 starpu_mpi_node_selection_register_policy()

```
int starpu_mpi_node_selection_register_policy (
    starpu_mpi_select_node_policy_func_t policy_func )
```

Register a new policy which can then be used when there is several nodes owning data in W mode. Here an example of function defining a node selection policy. The codelet will be executed on the node owing the first data with a size bigger than 1M, or on the node 0 if no data fits the given size.

```
int my_node_selection_policy(int me, int nb_nodes, struct starpu_data_descr *descr, int
    nb_data)
{
    // me is the current MPI rank
    // nb_nodes is the number of MPI nodes
    // descr is the description of the data specified when calling starpu_mpi_task_insert
    // nb_data is the number of data in descr
    int i;
    for(i= 0 ; i<nb_data ; i++)
    {
        starpu_data_handle_t data = descr[i].handle;
        enum starpu_data_access_mode mode = descr[i].mode;
        if (mode & STARPU_R)
        {
            int rank = starpu_data_get_rank(data);
            size_t size = starpu_data_get_size(data);
            if (size > 1024*1024) return rank;
        }
    }
    return 0;
}
```

28.28.3.55 starpu_mpi_node_selection_unregister_policy()

```
int starpu_mpi_node_selection_unregister_policy (
    int policy )
```

Unregister a previously registered policy.

28.28.3.56 starpu_mpi_redux_data()

```
void starpu_mpi_redux_data (
    MPI_Comm comm,
    starpu_data_handle_t data_handle )
```

Perform a reduction on the given data. All nodes send the data to its owner node which will perform a reduction.

28.28.3.57 starpu_mpi_scatter_detached()

```
int starpu_mpi_scatter_detached (
    starpu_data_handle_t * data_handles,
    int count,
    int root,
    MPI_Comm comm,
    void(*) (void *) scallback,
    void * sarg,
    void(*) (void *) rcallback,
    void * rarg )
```

Scatter data among processes of the communicator based on the ownership of the data. For each data of the array `data_handles`, the process `root` sends the data to the process owning this data. Processes receiving data must have valid data handles to receive them. On completion of the collective communication, the `scallback` function is called with the argument `sarg` on the process `root`, the `rcallback` function is called with the argument `rarg` on any other process.

28.28.3.58 starpu_mpi_gather_detached()

```
int starpu_mpi_gather_detached (
    starpu_data_handle_t * data_handles,
    int count,
    int root,
    MPI_Comm comm,
    void(*) (void *) scallback,
    void * sarg,
    void(*) (void *) rcallback,
    void * rarg )
```

Gather data from the different processes of the communicator onto the process `root`. Each process owning data handle in the array `data_handles` will send them to the process `root`. The process `root` must have valid data handles to receive the data. On completion of the collective communication, the `rcallback` function is called with the argument `rarg` on the process `root`, the `scallback` function is called with the argument `sarg` on any other process.

28.29 Task Bundles**Typedefs**

- typedef struct `_starpu_task_bundle` * `starpu_task_bundle_t`

Functions

- void `starpu_task_bundle_create` (`starpu_task_bundle_t` *bundle)
- int `starpu_task_bundle_insert` (`starpu_task_bundle_t` bundle, struct `starpu_task` *task)
- int `starpu_task_bundle_remove` (`starpu_task_bundle_t` bundle, struct `starpu_task` *task)
- void `starpu_task_bundle_close` (`starpu_task_bundle_t` bundle)
- double `starpu_task_bundle_expected_length` (`starpu_task_bundle_t` bundle, struct `starpu_perfmodel_arch` *arch, unsigned nimpl)
- double `starpu_task_bundle_expected_energy` (`starpu_task_bundle_t` bundle, struct `starpu_perfmodel_arch` *arch, unsigned nimpl)
- double `starpu_task_bundle_expected_data_transfer_time` (`starpu_task_bundle_t` bundle, unsigned memory_node)

28.29.1 Detailed Description

28.29.2 Typedef Documentation

28.29.2.1 `starpu_task_bundle_t`

`starpu_task_bundle_t`

Opaque structure describing a list of tasks that should be scheduled on the same worker whenever it's possible. It must be considered as a hint given to the scheduler as there is no guarantee that they will be executed on the same worker.

28.29.3 Function Documentation

28.29.3.1 `starpu_task_bundle_create()`

```
void starpu_task_bundle_create (
    starpu_task_bundle_t * bundle )
```

Factory function creating and initializing `bundle`, when the call returns, memory needed is allocated and `bundle` is ready to use.

28.29.3.2 `starpu_task_bundle_insert()`

```
int starpu_task_bundle_insert (
    starpu_task_bundle_t bundle,
    struct starpu_task * task )
```

Insert `task` in `bundle`. Until `task` is removed from `bundle` its expected length and data transfer time will be considered along those of the other tasks of `bundle`. This function must not be called if `bundle` is already closed and/or `task` is already submitted. On success, it returns 0. There are two cases of error : if `bundle` is already closed it returns `-EPERM`, if `task` was already submitted it returns `-EINVAL`.

28.29.3.3 `starpu_task_bundle_remove()`

```
int starpu_task_bundle_remove (
    starpu_task_bundle_t bundle,
    struct starpu_task * task )
```

Remove `task` from `bundle`. Of course `task` must have been previously inserted in `bundle`. This function must not be called if `bundle` is already closed and/or `task` is already submitted. Doing so would result in undefined behaviour. On success, it returns 0. If `bundle` is already closed it returns `-ENOENT`.

28.29.3.4 `starpu_task_bundle_close()`

```
void starpu_task_bundle_close (
    starpu_task_bundle_t bundle )
```

Inform the runtime that the user will not modify `bundle` anymore, it means no more inserting or removing task. Thus the runtime can destroy it when possible.

28.29.3.5 `starpu_task_bundle_expected_length()`

```
double starpu_task_bundle_expected_length (
    starpu_task_bundle_t bundle,
    struct starpu_perfmodel_arch * arch,
    unsigned nimpl )
```

Return the expected duration of `bundle` in micro-seconds.

28.29.3.6 `starpu_task_bundle_expected_energy()`

```
double starpu_task_bundle_expected_energy (
    starpu_task_bundle_t bundle,
    struct starpu_perfmodel_arch * arch,
    unsigned nimpl )
```

Return the expected energy consumption of `bundle` in J.

28.29.3.7 `starpu_task_bundle_expected_data_transfer_time()`

```
double starpu_task_bundle_expected_data_transfer_time (
    starpu_task_bundle_t bundle,
    unsigned memory_node )
```

Return the time (in micro-seconds) expected to transfer all data used within `bundle`.

28.30 Task Lists

Data Structures

- struct [starpu_task_list](#)

Functions

- static STARPU_INLINE void [starpu_task_list_init](#) (struct [starpu_task_list](#) *list)
- static STARPU_INLINE void [starpu_task_list_push_front](#) (struct [starpu_task_list](#) *list, struct [starpu_task](#) *task)
- static STARPU_INLINE void [starpu_task_list_push_back](#) (struct [starpu_task_list](#) *list, struct [starpu_task](#) *task)
- static STARPU_INLINE struct [starpu_task](#) * [starpu_task_list_front](#) (struct [starpu_task_list](#) *list)
- static STARPU_INLINE struct [starpu_task](#) * [starpu_task_list_back](#) (struct [starpu_task_list](#) *list)
- static STARPU_INLINE int [starpu_task_list_empty](#) (struct [starpu_task_list](#) *list)
- static STARPU_INLINE void [starpu_task_list_erase](#) (struct [starpu_task_list](#) *list, struct [starpu_task](#) *task)
- static STARPU_INLINE struct [starpu_task](#) * [starpu_task_list_pop_front](#) (struct [starpu_task_list](#) *list)
- static STARPU_INLINE struct [starpu_task](#) * [starpu_task_list_pop_back](#) (struct [starpu_task_list](#) *list)
- static STARPU_INLINE struct [starpu_task](#) * [starpu_task_list_begin](#) (struct [starpu_task_list](#) *list)
- static STARPU_INLINE struct [starpu_task](#) * [starpu_task_list_next](#) (struct [starpu_task](#) *task)
- static STARPU_INLINE int [starpu_task_list_ismember](#) (struct [starpu_task_list](#) *list, struct [starpu_task](#) *look)

28.30.1 Detailed Description

28.30.2 Data Structure Documentation

28.30.2.1 struct starpu_task_list

Stores a double-chained list of tasks

Data Fields

struct starpu_task *	head	head of the list
struct starpu_task *	tail	tail of the list

28.30.3 Function Documentation

28.30.3.1 starpu_task_list_init()

```
void starpu_task_list_init (
    struct starpu\_task\_list * list ) [static]
```

Initialize a list structure

28.30.3.2 starpu_task_list_push_front()

```
void starpu_task_list_push_front (
    struct starpu\_task\_list * list,
    struct starpu\_task * task ) [static]
```

Push task at the front of list

28.30.3.3 starpu_task_list_push_back()

```
void starpu_task_list_push_back (
    struct starpu\_task\_list * list,
    struct starpu\_task * task ) [static]
```

Push task at the back of list

28.30.3.4 starpu_task_list_front()

```
struct starpu\_task * starpu_task_list_front (
    struct starpu\_task\_list * list ) [static]
```

Get the front of list (without removing it)

28.30.3.5 starpu_task_list_back()

```
struct starpu_task * starpu_task_list_back (
    struct starpu_task_list * list ) [static]
```

Get the back of `list` (without removing it)

28.30.3.6 starpu_task_list_empty()

```
int starpu_task_list_empty (
    struct starpu_task_list * list ) [static]
```

Test if `list` is empty

28.30.3.7 starpu_task_list_erase()

```
void starpu_task_list_erase (
    struct starpu_task_list * list,
    struct starpu_task * task ) [static]
```

Remove `task` from `list`

28.30.3.8 starpu_task_list_pop_front()

```
struct starpu_task * starpu_task_list_pop_front (
    struct starpu_task_list * list ) [static]
```

Remove the element at the front of `list`

28.30.3.9 starpu_task_list_pop_back()

```
struct starpu_task * starpu_task_list_pop_back (
    struct starpu_task_list * list ) [static]
```

Remove the element at the back of `list`

28.30.3.10 starpu_task_list_begin()

```
struct starpu_task * starpu_task_list_begin (
    struct starpu_task_list * list ) [static]
```

Get the first task of `list`.

28.30.3.11 starpu_task_list_next()

```
struct starpu_task * starpu_task_list_next (
    struct starpu_task * task ) [static]
```

Get the next task of `list`. This is not erase-safe.

28.30.3.12 `starpu_task_list_ismember()`

```
int starpu_task_list_ismember (
    struct starpu_task_list * list,
    struct starpu_task * look ) [static]
```

Test whether the given task `look` is contained in the `list`.

28.31 Parallel Tasks

Functions

- int `starpu_combined_worker_get_size` (void)
- int `starpu_combined_worker_get_rank` (void)
- unsigned `starpu_combined_worker_get_count` (void)
- int `starpu_combined_worker_get_id` (void)
- int `starpu_combined_worker_assign_workerid` (int nworkers, int workerid_array[])
- int `starpu_combined_worker_get_description` (int workerid, int *worker_size, int **combined_workerid)
- int `starpu_combined_worker_can_execute_task` (unsigned workerid, struct `starpu_task` *task, unsigned nimpl)
- void `starpu_parallel_task_barrier_init` (struct `starpu_task` *task, int workerid)
- void `starpu_parallel_task_barrier_init_n` (struct `starpu_task` *task, int worker_size)

28.31.1 Detailed Description

28.31.2 Function Documentation

28.31.2.1 `starpu_combined_worker_get_size()`

```
int starpu_combined_worker_get_size (
    void )
```

Return the size of the current combined worker, i.e. the total number of cpus running the same task in the case of `STARPU_SPMD` parallel tasks, or the total number of threads that the task is allowed to start in the case of `STARPU_FORKJOIN` parallel tasks.

28.31.2.2 `starpu_combined_worker_get_rank()`

```
int starpu_combined_worker_get_rank (
    void )
```

Return the rank of the current thread within the combined worker. Can only be used in `STARPU_FORKJOIN` parallel tasks, to know which part of the task to work on.

28.31.2.3 `starpu_combined_worker_get_count()`

```
unsigned starpu_combined_worker_get_count (
    void )
```

Return the number of different combined workers.

28.31.2.4 `starpu_combined_worker_get_id()`

```
int starpu_combined_worker_get_id (
    void )
```

Return the identifier of the current combined worker.

28.31.2.5 `starpu_combined_worker_assign_workerid()`

```
int starpu_combined_worker_assign_workerid (
    int nworkers,
    int workerid_array[] )
```

Register a new combined worker and get its identifier

28.31.2.6 `starpu_combined_worker_get_description()`

```
int starpu_combined_worker_get_description (
    int workerid,
    int * worker_size,
    int ** combined_workerid )
```

Get the description of a combined worker

28.31.2.7 `starpu_combined_worker_can_execute_task()`

```
int starpu_combined_worker_can_execute_task (
    unsigned workerid,
    struct starpu\_task * task,
    unsigned nimpl )
```

Variant of [starpu_worker_can_execute_task\(\)](#) compatible with combined workers

28.31.2.8 `starpu_parallel_task_barrier_init()`

```
void starpu_parallel_task_barrier_init (
    struct starpu\_task * task,
    int workerid )
```

Initialise the barrier for the parallel task, and dispatch the task between the different workers of the given combined worker.

28.31.2.9 `starpu_parallel_task_barrier_init_n()`

```
void starpu_parallel_task_barrier_init_n (
    struct starpu\_task * task,
    int worker_size )
```

Initialise the barrier for the parallel task, to be pushed to *worker_size* workers (without having to explicit a given combined worker).

28.32 Running Drivers

Functions

- int [starpu_driver_run](#) (struct [starpu_driver](#) *d)
- int [starpu_driver_init](#) (struct [starpu_driver](#) *d)
- int [starpu_driver_run_once](#) (struct [starpu_driver](#) *d)
- int [starpu_driver_deinit](#) (struct [starpu_driver](#) *d)
- void [starpu_drivers_request_termination](#) (void)

28.32.1 Detailed Description

28.32.2 Function Documentation

28.32.2.1 `starpu_driver_run()`

```
int starpu_driver_run (
    struct starpu\_driver * d )
```

Initialize the given driver, run it until it receives a request to terminate, deinitialize it and return 0 on success. It returns `-EINVAL` if `d->type` is not a valid StarPU device type ([STARPU_CPU_WORKER](#), [STARPU_CUDA_WORKER](#) or [STARPU_OPENCL_WORKER](#)). This is the same as using the following functions: calling [starpu_driver_init\(\)](#), then calling [starpu_driver_run_once\(\)](#) in a loop, and eventually [starpu_driver_deinit\(\)](#).

28.32.2.2 `starpu_driver_init()`

```
int starpu_driver_init (
    struct starpu\_driver * d )
```

Initialize the given driver. Returns 0 on success, `-EINVAL` if `d->type` is not a valid [starpu_worker_archtype](#).

28.32.2.3 `starpu_driver_run_once()`

```
int starpu_driver_run_once (
    struct starpu\_driver * d )
```

Run the driver once, then returns 0 on success, `-EINVAL` if `d->type` is not a valid [starpu_worker_archtype](#).

28.32.2.4 `starpu_driver_deinit()`

```
int starpu_driver_deinit (
    struct starpu\_driver * d )
```

Deinitialize the given driver. Returns 0 on success, `-EINVAL` if `d->type` is not a valid [starpu_worker_archtype](#).

28.32.2.5 `starpu_drivers_request_termination()`

```
void starpu_drivers_request_termination (
    void )
```

Notify all running drivers they should terminate.

28.33 Expert Mode

Functions

- void [starpu_wake_all_blocked_workers](#) (void)
- int [starpu_progression_hook_register](#) (unsigned(*func)(void *arg), void *arg)
- void [starpu_progression_hook_deregister](#) (int hook_id)

28.33.1 Detailed Description

28.33.2 Function Documentation

28.33.2.1 `starpu_wake_all_blocked_workers()`

```
void starpu_wake_all_blocked_workers (
    void )
```

Wake all the workers, so they can inspect data requests and task submissions again.

28.33.2.2 `starpu_progression_hook_register()`

```
int starpu_progression_hook_register (
    unsigned(*) (void *arg) func,
    void * arg )
```

Register a progression hook, to be called when workers are idle.

28.33.2.3 `starpu_progression_hook_deregister()`

```
void starpu_progression_hook_deregister (
    int hook_id )
```

Unregister a given progression hook.

28.34 StarPU-Top Interface

Data Structures

- struct [starpu_top_data](#)
- struct [starpu_top_param](#)

Enumerations

- enum [starpu_top_data_type](#) { [STARPU_TOP_DATA_BOOLEAN](#), [STARPU_TOP_DATA_INTEGER](#), [STARPU_TOP_DATA_FLOAT](#) }
- enum [starpu_top_param_type](#) { [STARPU_TOP_PARAM_BOOLEAN](#), [STARPU_TOP_PARAM_INTEGER](#), [STARPU_TOP_PARAM_FLOAT](#), [STARPU_TOP_PARAM_ENUM](#) }
- enum [starpu_top_message_type](#) { [TOP_TYPE_GO](#), [TOP_TYPE_SET](#), [TOP_TYPE_CONTINUE](#), [TOP_TYPE_ENABLE](#), [TOP_TYPE_DISABLE](#), [TOP_TYPE_DEBUG](#), [TOP_TYPE_UNKNOW](#) }

Functions to call before the initialisation

- struct [starpu_top_data](#) * [starpu_top_add_data_boolean](#) (const char *data_name, int active)
- struct [starpu_top_data](#) * [starpu_top_add_data_integer](#) (const char *data_name, int minimum_value, int maximum_value, int active)
- struct [starpu_top_data](#) * [starpu_top_add_data_float](#) (const char *data_name, double minimum_value, double maximum_value, int active)
- struct [starpu_top_param](#) * [starpu_top_register_parameter_boolean](#) (const char *param_name, int *parameter_field, void(*callback)(struct [starpu_top_param](#) *))
- struct [starpu_top_param](#) * [starpu_top_register_parameter_float](#) (const char *param_name, double *parameter_field, double minimum_value, double maximum_value, void(*callback)(struct [starpu_top_param](#) *))
- struct [starpu_top_param](#) * [starpu_top_register_parameter_integer](#) (const char *param_name, int *parameter_field, int minimum_value, int maximum_value, void(*callback)(struct [starpu_top_param](#) *))
- struct [starpu_top_param](#) * [starpu_top_register_parameter_enum](#) (const char *param_name, int *parameter_field, char **values, int nb_values, void(*callback)(struct [starpu_top_param](#) *))

Initialisation

- void [starpu_top_init_and_wait](#) (const char *server_name)

To call after initialisation

- void [starpu_top_update_parameter](#) (const struct [starpu_top_param](#) *param)
- void [starpu_top_update_data_boolean](#) (const struct [starpu_top_data](#) *data, int value)
- void [starpu_top_update_data_integer](#) (const struct [starpu_top_data](#) *data, int value)
- void [starpu_top_update_data_float](#) (const struct [starpu_top_data](#) *data, double value)
- void [starpu_top_task_prevision](#) (struct [starpu_task](#) *task, int devid, unsigned long long start, unsigned long long end)
- void [starpu_top_debug_log](#) (const char *message)
- void [starpu_top_debug_lock](#) (const char *message)

28.34.1 Detailed Description

28.34.2 Data Structure Documentation

28.34.2.1 struct starpu_top_data

todo

Data Fields

unsigned int	id	todo
const char *	name	todo
int	int_min_value	todo
int	int_max_value	todo
double	double_min_value	todo
double	double_max_value	todo
int	active	todo
enum starpu_top_data_type	type	todo
struct starpu_top_data *	next	todo

28.34.2.2 struct starpu_top_param

todo

Data Fields

- unsigned int [id](#)
- const char * [name](#)
- enum [starpu_top_param_type](#) type
- void * [value](#)
- char ** [enum_values](#)
- int [nb_values](#)
- void(* [callback](#))(struct [starpu_top_param](#) *)
- int [int_min_value](#)
- int [int_max_value](#)
- double [double_min_value](#)
- double [double_max_value](#)
- struct [starpu_top_param](#) * [next](#)

28.34.2.2.1 Field Documentation

28.34.2.2.1.1 id

```
unsigned int starpu_top_param::id
```

todo

28.34.2.2.1.2 name

```
const char * starpu_top_param::name
```

todo

28.34.2.2.1.3 type

```
enum starpu_top_param_type starpu_top_param::type
```

todo

28.34.2.2.1.4 value

```
void * starpu_top_param::value
```

todo

28.34.2.2.1.5 enum_values

```
char ** starpu_top_param::enum_values
```

only for enum type can be NULL

28.34.2.2.1.6 nb_values

```
int starpu_top_param::nb_values
```

todo

28.34.2.2.1.7 callback

```
void(* starpu_top_param::callback)(struct starpu_top_param *)
```

todo

28.34.2.2.1.8 int_min_value

```
int starpu_top_param::int_min_value
```

only for integer type

28.34.2.2.1.9 int_max_value

```
int starpu_top_param::int_max_value
```

todo

28.34.2.2.1.10 double_min_value

```
double starpu_top_param::double_min_value
```

only for double type

28.34.2.2.1.11 double_max_value

```
double starpu_top_param::double_max_value
```

todo

28.34.2.2.1.12 next

```
struct starpu_top_param * starpu_top_param::next
```

todo

28.34.3 Enumeration Type Documentation

28.34.3.1 starpu_top_data_type

```
enum starpu_top_data_type
```

StarPU-Top Data type

Enumerator

STARPU_TOP_DATA_BOOLEAN	todo
STARPU_TOP_DATA_INTEGER	todo
STARPU_TOP_DATA_FLOAT	todo

28.34.3.2 starpu_top_param_type

```
enum starpu_top_param_type
```

StarPU-Top Parameter type

Enumerator

STARPU_TOP_PARAM_BOOLEAN	todo
STARPU_TOP_PARAM_INTEGER	todo
STARPU_TOP_PARAM_FLOAT	todo
STARPU_TOP_PARAM_ENUM	todo

28.34.3.3 starpu_top_message_type

```
enum starpu_top_message_type
```

StarPU-Top Message type

Enumerator

TOP_TYPE_GO	todo
TOP_TYPE_SET	todo
TOP_TYPE_CONTINUE	todo
TOP_TYPE_ENABLE	todo
TOP_TYPE_DISABLE	todo
TOP_TYPE_DEBUG	todo
TOP_TYPE_UNKNOW	todo

28.34.4 Function Documentation

28.34.4.1 starpu_top_add_data_boolean()

```
struct starpu_top_data * starpu_top_add_data_boolean (
    const char * data_name,
    int active )
```

This function register a data named `data_name` of type boolean. If `active=0`, the value will NOT be displayed to user by default. Any other value will make the value displayed by default.

28.34.4.2 starpu_top_add_data_integer()

```
struct starpu_top_data * starpu_top_add_data_integer (
    const char * data_name,
    int minimum_value,
    int maximum_value,
    int active )
```

This fonction register a data named `data_name` of type integer. The minimum and maximum value will be usefull to define the scale in UI. If `active=0`, the value will NOT be displayed to user by default. Any other value will make the value displayed by default.

28.34.4.3 `starpu_top_add_data_float()`

```
struct starpu_top_data * starpu_top_add_data_float (
    const char * data_name,
    double minimum_value,
    double maximum_value,
    int active )
```

This fonction register a data named `data_name` of type float. The minimum and maximum value will be usefull to define the scale in UI. If `active=0`, the value will NOT be displayed to user by default. Any other value will make the value displayed by default.

28.34.4.4 `starpu_top_register_parameter_boolean()`

```
struct starpu_top_param * starpu_top_register_parameter_boolean (
    const char * param_name,
    int * parameter_field,
    void(*) (struct starpu_top_param *) callback )
```

This fonction register a parameter named `parameter_name`, of type boolean. The `callback` fonction will be called when the parameter is modified by UI, and can be null.

28.34.4.5 `starpu_top_register_parameter_float()`

```
struct starpu_top_param * starpu_top_register_parameter_float (
    const char * param_name,
    double * parameter_field,
    double minimum_value,
    double maximum_value,
    void(*) (struct starpu_top_param *) callback )
```

his fonction register a parameter named `param_name`, of type integer. Minimum and maximum value will be used to prevent user seting incorrect value. The `callback` fonction will be called when the parameter is modified by UI, and can be null.

28.34.4.6 `starpu_top_register_parameter_integer()`

```
struct starpu_top_param * starpu_top_register_parameter_integer (
    const char * param_name,
    int * parameter_field,
    int minimum_value,
    int maximum_value,
    void(*) (struct starpu_top_param *) callback )
```

This fonction register a parameter named `param_name`, of type float. Minimum and maximum value will be used to prevent user seting incorrect value. The `callback` fonction will be called when the parameter is modified by UI, and can be null.

28.34.4.7 `starpu_top_register_parameter_enum()`

```
struct starpu\_top\_param * starpu_top_register_parameter_enum (
    const char * param_name,
    int * parameter_field,
    char ** values,
    int nb_values,
    void(*) (struct starpu\_top\_param *) callback )
```

This function register a parameter named `param_name`, of type `enum`. Minimum and maximum value will be used to prevent user setting incorrect value. The `callback` function will be called when the parameter is modified by UI, and can be null.

28.34.4.8 `starpu_top_init_and_wait()`

```
void starpu_top_init_and_wait (
    const char * server_name )
```

This function must be called when all parameters and data have been registered AND initialised (for parameters). This function will wait for a TOP to connect, send initialisation sentences, and wait for the GO message.

28.34.4.9 `starpu_top_update_parameter()`

```
void starpu_top_update_parameter (
    const struct starpu\_top\_param * param )
```

This function should be called after every modification of a parameter from something other than `starpu_top`. This function notice UI that the configuration changed.

28.34.4.10 `starpu_top_update_data_boolean()`

```
void starpu_top_update_data_boolean (
    const struct starpu\_top\_data * data,
    int value )
```

This function updates the value of the [starpu_top_data](#) on UI.

28.34.4.11 `starpu_top_update_data_integer()`

```
void starpu_top_update_data_integer (
    const struct starpu\_top\_data * data,
    int value )
```

This function updates the value of the [starpu_top_data](#) on UI.

28.34.4.12 `starpu_top_update_data_float()`

```
void starpu_top_update_data_float (
    const struct starpu\_top\_data * data,
    double value )
```

This function updates the value of the [starpu_top_data](#) on UI.

28.34.4.13 `starpu_top_task_prevision()`

```
void starpu_top_task_prevision (
    struct starpu\_task * task,
    int devid,
    unsigned long long start,
    unsigned long long end )
```

This function notifies UI than the task have been planed to run from start to end, on computation-core.

28.34.4.14 `starpu_top_debug_log()`

```
void starpu_top_debug_log (
    const char * message )
```

This function is useful in debug mode. The starpu developper doesn't need to check if the debug mode is active. This is checked by `starpu_top` itsefl. It just send a message to display by UI.

28.34.4.15 `starpu_top_debug_lock()`

```
void starpu_top_debug_lock (
    const char * message )
```

This function is useful in debug mode. The starpu developper doesn't need to check if the debug mode is active. This is checked by `starpu_top` itsefl. It send a message and wait for a continue message from UI to return. The lock (wich create a stop-point) should be called only by the main thread. Calling it from more than one thread is not supported.

28.35 Scheduling Contexts

StarPU permits on one hand grouping workers in combined workers in order to execute a parallel task and on the other hand grouping tasks in bundles that will be executed by a single specified worker. In contrast when we group workers in scheduling contexts we submit starpu tasks to them and we schedule them with the policy assigned to the context. Scheduling contexts can be created, deleted and modified dynamically.

Data Structures

- struct [starpu_sched_ctx_performance_counters](#)

Scheduling Contexts Basic API

- `#define STARPU_SCHED_CTX_POLICY_NAME`
- `#define STARPU_SCHED_CTX_POLICY_STRUCT`
- `#define STARPU_SCHED_CTX_POLICY_MIN_PRIO`
- `#define STARPU_SCHED_CTX_POLICY_MAX_PRIO`
- `unsigned starpu_sched_ctx_create (int *workerids_ctx, int nworkers_ctx, const char *sched_ctx_name,...)`
- `unsigned starpu_sched_ctx_create_inside_interval (const char *policy_name, const char *sched_ctx_name, int min_ncpus, int max_ncpus, int min_ngpus, int max_ngpus, unsigned allow_overlap)`
- `void starpu_sched_ctx_register_close_callback (unsigned sched_ctx_id, void(*close_callback)(unsigned sched_ctx_id, void *args), void *args)`
- `void starpu_sched_ctx_add_workers (int *workerids_ctx, int nworkers_ctx, unsigned sched_ctx_id)`
- `void starpu_sched_ctx_remove_workers (int *workerids_ctx, int nworkers_ctx, unsigned sched_ctx_id)`
- `void starpu_sched_ctx_display_workers (unsigned sched_ctx_id, FILE *f)`
- `void starpu_sched_ctx_delete (unsigned sched_ctx_id)`
- `void starpu_sched_ctx_set_inheritor (unsigned sched_ctx_id, unsigned inheritor)`
- `void starpu_sched_ctx_set_context (unsigned *sched_ctx_id)`
- `unsigned starpu_sched_ctx_get_context (void)`
- `void starpu_sched_ctx_stop_task_submission (void)`
- `void starpu_sched_ctx_finished_submit (unsigned sched_ctx_id)`
- `unsigned starpu_sched_ctx_get_workers_list (unsigned sched_ctx_id, int **workerids)`
- `unsigned starpu_sched_ctx_get_workers_list_raw (unsigned sched_ctx_id, int **workerids)`
- `unsigned starpu_sched_ctx_get_nworkers (unsigned sched_ctx_id)`
- `unsigned starpu_sched_ctx_get_nshared_workers (unsigned sched_ctx_id, unsigned sched_ctx_id2)`
- `unsigned starpu_sched_ctx_contains_worker (int workerid, unsigned sched_ctx_id)`
- `unsigned starpu_sched_ctx_worker_get_id (unsigned sched_ctx_id)`
- `unsigned starpu_sched_ctx_overlapping_ctxs_on_worker (int workerid)`

Scheduling Context Priorities

- `#define STARPU_MIN_PRIO`
- `#define STARPU_MAX_PRIO`
- `#define STARPU_DEFAULT_PRIO`
- `int starpu_sched_ctx_set_min_priority (unsigned sched_ctx_id, int min_prio)`
- `int starpu_sched_ctx_set_max_priority (unsigned sched_ctx_id, int max_prio)`
- `int starpu_sched_ctx_get_min_priority (unsigned sched_ctx_id)`
- `int starpu_sched_ctx_get_max_priority (unsigned sched_ctx_id)`
- `int starpu_sched_ctx_min_priority_is_set (unsigned sched_ctx_id)`
- `int starpu_sched_ctx_max_priority_is_set (unsigned sched_ctx_id)`

Scheduling Context Worker Collection

- `struct starpu_worker_collection * starpu_sched_ctx_create_worker_collection (unsigned sched_ctx_id, enum starpu_worker_collection_type type) STARPU_ATTRIBUTE_MALLOC`
- `void starpu_sched_ctx_delete_worker_collection (unsigned sched_ctx_id)`
- `struct starpu_worker_collection * starpu_sched_ctx_get_worker_collection (unsigned sched_ctx_id)`

Scheduling Context Link with Hypervisor

- void [starpu_sched_ctx_set_perf_counters](#) (unsigned sched_ctx_id, void *perf_counters)
- void [starpu_sched_ctx_call_pushed_task_cb](#) (int workerid, unsigned sched_ctx_id)
- void [starpu_sched_ctx_notify_hypervisor_exists](#) (void)
- unsigned [starpu_sched_ctx_check_if_hypervisor_exists](#) (void)
- void [starpu_sched_ctx_set_policy_data](#) (unsigned sched_ctx_id, void *policy_data)
- void * [starpu_sched_ctx_get_policy_data](#) (unsigned sched_ctx_id)
- void * [starpu_sched_ctx_exec_parallel_code](#) (void *(*func)(void *), void *param, unsigned sched_ctx_id)
- int [starpu_sched_ctx_get_nready_tasks](#) (unsigned sched_ctx_id)
- double [starpu_sched_ctx_get_nready_flops](#) (unsigned sched_ctx_id)

28.35.1 Detailed Description

StarPU permits on one hand grouping workers in combined workers in order to execute a parallel task and on the other hand grouping tasks in bundles that will be executed by a single specified worker. In contrast when we group workers in scheduling contexts we submit starpu tasks to them and we schedule them with the policy assigned to the context. Scheduling contexts can be created, deleted and modified dynamically.

28.35.2 Data Structure Documentation

28.35.2.1 struct starpu_sched_ctx_performance_counters

Performance counters used by the starpu to indicate the hypervisor how the application and the resources are executing.

Data Fields

- void(* [notify_idle_cycle](#))(unsigned sched_ctx_id, int worker, double idle_time)
- void(* [notify_poped_task](#))(unsigned sched_ctx_id, int worker)
- void(* [notify_pushed_task](#))(unsigned sched_ctx_id, int worker)
- void(* [notify_post_exec_task](#))(struct [starpu_task](#) *task, size_t data_size, uint32_t footprint, int hypervisor↔_tag, double flops)
- void(* [notify_submitted_job](#))(struct [starpu_task](#) *task, uint32_t footprint, size_t data_size)
- void(* [notify_empty_ctx](#))(unsigned sched_ctx_id, struct [starpu_task](#) *task)
- void(* [notify_delete_context](#))(unsigned sched_ctx)

28.35.2.1.1 Field Documentation

28.35.2.1.1.1 notify_idle_cycle

```
void(* starpu_sched_ctx_performance_counters::notify_idle_cycle)(unsigned sched_ctx_id, int worker, double idle_time)
```

Inform the hypervisor for how long a worker has been idle in the specified context

28.35.2.1.1.2 notify_poped_task

```
void(* starpu_sched_ctx_performance_counters::notify_poped_task)(unsigned sched_ctx_id, int worker)
```

Notifies the hypervisor that a task executing a specified number of instructions has been popped from the worker

28.35.2.1.1.3 notify_pushed_task

```
void(* starpu_sched_ctx_performance_counters::notify_pushed_task)(unsigned sched_ctx_id, int worker)
```

Notifies the hypervisor that a task has been scheduled on the queue of the worker corresponding to the specified context

28.35.2.1.1.4 notify_post_exec_task

```
void(* starpu_sched_ctx_performance_counters::notify_post_exec_task)(struct starpu_task *task, size_t data_size, uint32_t footprint, int hypervisor_tag, double flops)
```

Notifies the hypervisor that a task has just been executed

28.35.2.1.1.5 notify_submitted_job

```
void(* starpu_sched_ctx_performance_counters::notify_submitted_job)(struct starpu_task *task, uint32_t footprint, size_t data_size)
```

Notifies the hypervisor that a task has just been submitted

28.35.2.1.1.6 notify_delete_context

```
void(* starpu_sched_ctx_performance_counters::notify_delete_context)(unsigned sched_ctx)
```

Notifies the hypervisor that the context was deleted

28.35.3 Macro Definition Documentation**28.35.3.1 STARPU_SCHED_CTX_POLICY_NAME**

```
#define STARPU_SCHED_CTX_POLICY_NAME
```

This macro is used when calling [starpu_sched_ctx_create\(\)](#) to specify a name for a scheduling policy

28.35.3.2 STARPU_SCHED_CTX_POLICY_STRUCT

```
#define STARPU_SCHED_CTX_POLICY_STRUCT
```

This macro is used when calling [starpu_sched_ctx_create\(\)](#) to specify a pointer to a scheduling policy

28.35.3.3 STARPU_SCHED_CTX_POLICY_MIN_PRIO

```
#define STARPU_SCHED_CTX_POLICY_MIN_PRIO
```

This macro is used when calling [starpu_sched_ctx_create\(\)](#) to specify a minimum scheduler priority value.

28.35.3.4 STARPU_SCHED_CTX_POLICY_MAX_PRIO

```
#define STARPU_SCHED_CTX_POLICY_MAX_PRIO
```

This macro is used when calling [starpu_sched_ctx_create\(\)](#) to specify a maximum scheduler priority value.

28.35.3.5 STARPU_MIN_PRIO

```
#define STARPU_MIN_PRIO
```

Provided for legacy reasons.

28.35.3.6 STARPU_MAX_PRIO

```
#define STARPU_MAX_PRIO
```

Provided for legacy reasons.

28.35.3.7 STARPU_DEFAULT_PRIO

```
#define STARPU_DEFAULT_PRIO
```

By convention, the default priority level should be 0 so that we can statically allocate tasks with a default priority.

28.35.4 Function Documentation**28.35.4.1 starpu_sched_ctx_create()**

```
unsigned starpu_sched_ctx_create (
    int * workerids_ctx,
    int nworkers_ctx,
    const char * sched_ctx_name,
    ... )
```

This function creates a scheduling context with the given parameters (see below) and assigns the workers in `workerids_ctx` to execute the tasks submitted to it. The return value represents the identifier of the context that has just been created. It will be further used to indicate the context the tasks will be submitted to. The return value should be at most [STARPU_NMAX_SCHED_CTXS](#).

The arguments following the name of the scheduling context can be of the following types:

- [STARPU_SCHED_CTX_POLICY_NAME](#), followed by the name of a predefined scheduling policy. Use an empty string to create the context with the default scheduling policy.
- [STARPU_SCHED_CTX_POLICY_STRUCT](#), followed by a pointer to a custom scheduling policy (struct [starpu_sched_policy](#) *)
- [STARPU_SCHED_CTX_POLICY_MIN_PRIO](#), followed by a integer representing the minimum priority value to be defined for the scheduling policy.
- [STARPU_SCHED_CTX_POLICY_MAX_PRIO](#), followed by a integer representing the maximum priority value to be defined for the scheduling policy.

28.35.4.2 starpu_sched_ctx_create_inside_interval()

```
unsigned starpu_sched_ctx_create_inside_interval (
    const char * policy_name,
    const char * sched_ctx_name,
    int min_ncpus,
    int max_ncpus,
    int min_ngpus,
    int max_ngpus,
    unsigned allow_overlap )
```

Create a context indicating an approximate interval of resources

28.35.4.3 starpu_sched_ctx_register_close_callback()

```
void starpu_sched_ctx_register_close_callback (
    unsigned sched_ctx_id,
    void(*) (unsigned sched_ctx_id, void *args) close_callback,
    void * args )
```

Execute the callback whenever the last task of the context finished executing, it is called with the parameters: `sched_ctx_id` and any other parameter needed by the application (packed in a `void*`)

28.35.4.4 starpu_sched_ctx_add_workers()

```
void starpu_sched_ctx_add_workers (
    int * workerids_ctx,
    int nworkers_ctx,
    unsigned sched_ctx_id )
```

This function adds dynamically the workers in `workerids_ctx` to the context `sched_ctx_id`. The last argument cannot be greater than [STARPU_NMAX_SCHED_CTXS](#).

28.35.4.5 starpu_sched_ctx_remove_workers()

```
void starpu_sched_ctx_remove_workers (
    int * workerids_ctx,
    int nworkers_ctx,
    unsigned sched_ctx_id )
```

This function removes the workers in `workerids_ctx` from the context `sched_ctx_id`. The last argument cannot be greater than `STARPU_NMAX_SCHED_CTXS`.

28.35.4.6 starpu_sched_ctx_display_workers()

```
void starpu_sched_ctx_display_workers (
    unsigned sched_ctx_id,
    FILE * f )
```

This function prints on the file `f` the worker names belonging to the context `sched_ctx_id`

28.35.4.7 `starpu_sched_ctx_delete()`

```
void starpu_sched_ctx_delete (
    unsigned sched_ctx_id )
```

Delete scheduling context `sched_ctx_id` and transfer remaining workers to the inheritor scheduling context.

28.35.4.8 `starpu_sched_ctx_set_inheritor()`

```
void starpu_sched_ctx_set_inheritor (
    unsigned sched_ctx_id,
    unsigned inheritor )
```

Indicate which context will inherit the resources of this context when he will be deleted.

28.35.4.9 `starpu_sched_ctx_set_context()`

```
void starpu_sched_ctx_set_context (
    unsigned * sched_ctx_id )
```

Set the scheduling context the subsequent tasks will be submitted to

28.35.4.10 `starpu_sched_ctx_get_context()`

```
unsigned starpu_sched_ctx_get_context (
    void )
```

Return the scheduling context the tasks are currently submitted to, or `STARPU_NMAX_SCHED_CTXS` if no default context has been defined by calling the function `starpu_sched_ctx_set_context()`.

28.35.4.11 `starpu_sched_ctx_stop_task_submission()`

```
void starpu_sched_ctx_stop_task_submission (
    void )
```

Stop submitting tasks from the empty context list until the next time the context has time to check the empty context list

28.35.4.12 `starpu_sched_ctx_finished_submit()`

```
void starpu_sched_ctx_finished_submit (
    unsigned sched_ctx_id )
```

Indicate starpu that the application finished submitting to this context in order to move the workers to the inheritor as soon as possible.

28.35.4.13 starpu_sched_ctx_get_workers_list()

```
unsigned starpu_sched_ctx_get_workers_list (
    unsigned sched_ctx_id,
    int ** workerids )
```

Returns the list of workers in the array `workerids`, the returned value is the number of workers. The user should free the `workerids` table after finishing using it (it is allocated inside the function with the proper size)

28.35.4.14 starpu_sched_ctx_get_workers_list_raw()

```
unsigned starpu_sched_ctx_get_workers_list_raw (
    unsigned sched_ctx_id,
    int ** workerids )
```

Returns the list of workers in the array `workerids`, the returned value is the number of workers. This list is provided in raw order, i.e. not sorted by tree or list order, and the user should not free the `workerids` table. This function is thus much less costly than `starpu_sched_ctx_get_workers_list`.

28.35.4.15 starpu_sched_ctx_get_nworkers()

```
unsigned starpu_sched_ctx_get_nworkers (
    unsigned sched_ctx_id )
```

Return the number of workers managed by the specified contexts (Usually needed to verify if it manages any workers or if it should be blocked)

28.35.4.16 starpu_sched_ctx_get_nshared_workers()

```
unsigned starpu_sched_ctx_get_nshared_workers (
    unsigned sched_ctx_id,
    unsigned sched_ctx_id2 )
```

Return the number of workers shared by two contexts.

28.35.4.17 starpu_sched_ctx_contains_worker()

```
unsigned starpu_sched_ctx_contains_worker (
    int workerid,
    unsigned sched_ctx_id )
```

Return 1 if the worker belongs to the context and 0 otherwise

28.35.4.18 starpu_sched_ctx_worker_get_id()

```
unsigned starpu_sched_ctx_worker_get_id (
    unsigned sched_ctx_id )
```

Return the workerid if the worker belongs to the context and -1 otherwise. If the thread calling this function is not a worker the function returns -1 as it calls the function [starpu_worker_get_id\(\)](#).

28.35.4.19 starpu_sched_ctx_overlapping_ctxs_on_worker()

```
unsigned starpu_sched_ctx_overlapping_ctxs_on_worker (
    int workerid )
```

Check if a worker is shared between several contexts

28.35.4.20 starpu_sched_ctx_set_min_priority()

```
int starpu_sched_ctx_set_min_priority (
    unsigned sched_ctx_id,
    int min_prio )
```

Defines the minimum task priority level supported by the scheduling policy of the given scheduler context. The default minimum priority level is the same as the default priority level which is 0 by convention. The application may access that value by calling the function [starpu_sched_ctx_get_min_priority\(\)](#). This function should only be called from the initialization method of the scheduling policy, and should not be used directly from the application.

28.35.4.21 starpu_sched_ctx_set_max_priority()

```
int starpu_sched_ctx_set_max_priority (
    unsigned sched_ctx_id,
    int max_prio )
```

Defines the maximum priority level supported by the scheduling policy of the given scheduler context. The default maximum priority level is 1. The application may access that value by calling the [starpu_sched_ctx_get_max↵_priority](#) function. This function should only be called from the initialization method of the scheduling policy, and should not be used directly from the application.

28.35.4.22 starpu_sched_ctx_get_min_priority()

```
int starpu_sched_ctx_get_min_priority (
    unsigned sched_ctx_id )
```

Returns the current minimum priority level supported by the scheduling policy of the given scheduler context.

28.35.4.23 starpu_sched_ctx_get_max_priority()

```
int starpu_sched_ctx_get_max_priority (
    unsigned sched_ctx_id )
```

Returns the current maximum priority level supported by the scheduling policy of the given scheduler context.

28.35.4.24 starpu_sched_ctx_min_priority_is_set()

```
int starpu_sched_ctx_min_priority_is_set (
    unsigned sched_ctx_id )
```

todo

28.35.4.25 starpu_sched_ctx_max_priority_is_set()

```
int starpu_sched_ctx_max_priority_is_set (
    unsigned sched_ctx_id )
```

todo

28.35.4.26 starpu_sched_ctx_create_worker_collection()

```
struct starpu_worker_collection * starpu_sched_ctx_create_worker_collection (
    unsigned sched_ctx_id,
    enum starpu_worker_collection_type type )
```

Create a worker collection of the type indicated by the last parameter for the context specified through the first parameter.

28.35.4.27 starpu_sched_ctx_delete_worker_collection()

```
void starpu_sched_ctx_delete_worker_collection (
    unsigned sched_ctx_id )
```

Delete the worker collection of the specified scheduling context

28.35.4.28 starpu_sched_ctx_get_worker_collection()

```
struct starpu_worker_collection * starpu_sched_ctx_get_worker_collection (
    unsigned sched_ctx_id )
```

Return the worker collection managed by the indicated context

28.35.4.29 starpu_sched_ctx_set_perf_counters()

```
void starpu_sched_ctx_set_perf_counters (
    unsigned sched_ctx_id,
    void * perf_counters )
```

Indicates to starpu the pointer to the performance counter

28.35.4.30 starpu_sched_ctx_call_pushed_task_cb()

```
void starpu_sched_ctx_call_pushed_task_cb (
    int workerid,
    unsigned sched_ctx_id )
```

Callback that lets the scheduling policy tell the hypervisor that a task was pushed on a worker

28.35.4.31 starpu_sched_ctx_notify_hypervisor_exists()

```
void starpu_sched_ctx_notify_hypervisor_exists (
    void )
```

Allow the hypervisor to let starpu know he's initialised

28.35.4.32 starpu_sched_ctx_check_if_hypervisor_exists()

```
unsigned starpu_sched_ctx_check_if_hypervisor_exists (
    void )
```

Ask starpu if he is informed if the hypervisor is initialised

28.35.4.33 starpu_sched_ctx_set_policy_data()

```
void starpu_sched_ctx_set_policy_data (
    unsigned sched_ctx_id,
    void * policy_data )
```

Allocate the scheduling policy data (private information of the scheduler like queues, variables, additional condition variables) the context

28.35.4.34 starpu_sched_ctx_get_policy_data()

```
void * starpu_sched_ctx_get_policy_data (
    unsigned sched_ctx_id )
```

Return the scheduling policy data (private information of the scheduler) of the contexts previously assigned to.

28.35.4.35 starpu_sched_ctx_exec_parallel_code()

```
void * starpu_sched_ctx_exec_parallel_code (
    void (*)(void *) func,
    void * param,
    unsigned sched_ctx_id )
```

execute any parallel code on the workers of the sched_ctx (workers are blocked)

28.35.4.36 starpu_sched_ctx_get_nready_tasks()

```
int starpu_sched_ctx_get_nready_tasks (
    unsigned sched_ctx_id )
```

todo

28.35.4.37 `starpu_sched_ctx_get_nready_flops()`

```
double starpu_sched_ctx_get_nready_flops (
    unsigned sched_ctx_id )
```

todo

28.36 Scheduling Policy

TODO. While StarPU comes with a variety of scheduling policies (see [Task Scheduling Policies](#)), it may sometimes be desirable to implement custom policies to address specific problems. The API described below allows users to write their own scheduling policy.

Data Structures

- struct [starpu_sched_policy](#)

Macros

- `#define` [STARPU_MAXIMPLEMENTATIONS](#)

Functions

- struct [starpu_sched_policy](#) ** [starpu_sched_get_predefined_policies](#) ()
- void [starpu_worker_get_sched_condition](#) (int workerid, [starpu_pthread_mutex_t](#) **[sched_mutex](#), [starpu_pthread_cond_t](#) **[sched_cond](#))
- int [starpu_wake_worker](#) (int workerid)
- int [starpu_sched_set_min_priority](#) (int min_prio)
- int [starpu_sched_set_max_priority](#) (int max_prio)
- int [starpu_sched_get_min_priority](#) (void)
- int [starpu_sched_get_max_priority](#) (void)
- int [starpu_push_local_task](#) (int workerid, struct [starpu_task](#) *task, int back)
- int [starpu_push_task_end](#) (struct [starpu_task](#) *task)
- int [starpu_worker_can_execute_task](#) (unsigned workerid, struct [starpu_task](#) *task, unsigned nimpl)
- int [starpu_worker_can_execute_task_impl](#) (unsigned workerid, struct [starpu_task](#) *task, unsigned *impl ↵ mask)
- int [starpu_worker_can_execute_task_first_impl](#) (unsigned workerid, struct [starpu_task](#) *task, unsigned *nimpl)
- uint32_t [starpu_task_footprint](#) (struct [starpu_perfmodel](#) *model, struct [starpu_task](#) *task, struct [starpu_perfmodel_arch](#) *arch, unsigned nimpl)
- uint32_t [starpu_task_data_footprint](#) (struct [starpu_task](#) *task)
- double [starpu_task_expected_length](#) (struct [starpu_task](#) *task, struct [starpu_perfmodel_arch](#) *arch, unsigned nimpl)
- double [starpu_worker_get_relative_speedup](#) (struct [starpu_perfmodel_arch](#) *perf_arch)
- double [starpu_task_expected_data_transfer_time](#) (unsigned memory_node, struct [starpu_task](#) *task)
- double [starpu_data_expected_transfer_time](#) ([starpu_data_handle_t](#) handle, unsigned memory_node, enum [starpu_data_access_mode](#) mode)
- double [starpu_task_expected_energy](#) (struct [starpu_task](#) *task, struct [starpu_perfmodel_arch](#) *arch, unsigned nimpl)
- double [starpu_task_expected_conversion_time](#) (struct [starpu_task](#) *task, struct [starpu_perfmodel_arch](#) *arch, unsigned nimpl)
- int [starpu_get_prefetch_flag](#) (void)
- int [starpu_prefetch_task_input_on_node](#) (struct [starpu_task](#) *task, unsigned node)
- int [starpu_idle_prefetch_task_input_on_node](#) (struct [starpu_task](#) *task, unsigned node)
- void [starpu_sched_ctx_worker_shares_tasks_lists](#) (int workerid, int sched_ctx_id)

Scheduling Contexts Basic API

- `#define STARPU_NMAX_SCHED_CTXS`

28.36.1 Detailed Description

TODO. While StarPU comes with a variety of scheduling policies (see [Task Scheduling Policies](#)), it may sometimes be desirable to implement custom policies to address specific problems. The API described below allows users to write their own scheduling policy.

28.36.2 Data Structure Documentation

28.36.2.1 struct starpu_sched_policy

This structure contains all the methods that implement a scheduling policy. An application may specify which scheduling strategy in the field `starpu_conf::sched_policy` passed to the function `starpu_init()`.

For each task going through the scheduler, the following methods get called in the given order:

- `starpu_sched_policy::submit_hook` when the task is submitted
- `starpu_sched_policy::push_task` when the task becomes ready. The scheduler is here **given** the task
- `starpu_sched_policy::pop_task` when a worker is idle. The scheduler here **gives** back the task to the core
- `starpu_sched_policy::pre_exec_hook` right before the worker actually starts the task computation (after transferring any missing data).
- `starpu_sched_policy::post_exec_hook` right after the worker actually completed the task computation.

For each task not going through the scheduler (because `starpu_task::execute_on_a_specific_worker` was set), these get called:

- `starpu_sched_policy::submit_hook` when the task is submitted
- `starpu_sched_policy::push_task_notify` when the task becomes ready. This is just a notification, the scheduler does not have to do anything about the task.
- `starpu_sched_policy::pre_exec_hook` right before the worker actually starts the task computation (after transferring any missing data).
- `starpu_sched_policy::post_exec_hook` right after the worker actually completed the task computation.

Data Fields

- `void(* init_sched)(unsigned sched_ctx_id)`
- `void(* deinit_sched)(unsigned sched_ctx_id)`
- `int(* push_task)(struct starpu_task *)`
- `double(* simulate_push_task)(struct starpu_task *)`
- `void(* push_task_notify)(struct starpu_task *, int workerid, int perf_workerid, unsigned sched_ctx_id)`
- `struct starpu_task *(* pop_task)(unsigned sched_ctx_id)`
- `struct starpu_task *(* pop_every_task)(unsigned sched_ctx_id)`
- `void(* submit_hook)(struct starpu_task *task)`
- `void(* pre_exec_hook)(struct starpu_task *)`
- `void(* post_exec_hook)(struct starpu_task *)`
- `void(* do_schedule)(unsigned sched_ctx_id)`
- `void(* add_workers)(unsigned sched_ctx_id, int *workerids, unsigned nworkers)`
- `void(* remove_workers)(unsigned sched_ctx_id, int *workerids, unsigned nworkers)`
- `const char * policy_name`
- `const char * policy_description`

28.36.2.1.1 Field Documentation

28.36.2.1.1.1 `init_sched`

```
void(* starpu_sched_policy::init_sched)(unsigned sched_ctx_id)
```

Initialize the scheduling policy, called before any other method.

28.36.2.1.1.2 `deinit_sched`

```
void(* starpu_sched_policy::deinit_sched)(unsigned sched_ctx_id)
```

Cleanup the scheduling policy, called before any other method.

28.36.2.1.1.3 `push_task`

```
int(* starpu_sched_policy::push_task)(struct starpu_task *)
```

Insert a task into the scheduler, called when the task becomes ready for execution.

28.36.2.1.1.4 `push_task_notify`

```
void(* starpu_sched_policy::push_task_notify)(struct starpu_task *, int workerid, int perf_←  
workerid, unsigned sched_ctx_id)
```

Notify the scheduler that a task was pushed on a given worker. This method is called when a task that was explicitly assigned to a worker becomes ready and is about to be executed by the worker. This method therefore permits to keep the state of the scheduler coherent even when StarPU bypasses the scheduling strategy.

28.36.2.1.1.5 `pop_task`

```
struct starpu_task *(* starpu_sched_policy::pop_task)(unsigned sched_ctx_id)
```

Get a task from the scheduler. If this method returns `NULL`, the worker will start sleeping. If later on some task are pushed for this worker, `starpu_wake_worker()` must be called to wake the worker so it can call the `pop_task()` method again.

The mutex associated to the worker is already taken when this method is called. This method may release it (e.g. for scalability reasons when doing work stealing), but it must acquire it again before taking the decision whether to return a task or `NULL`, so the atomicity of deciding to return `NULL` and making the worker actually sleep is preserved. Otherwise in simgrid or blocking driver mode the worker might start sleeping while a task has just been pushed for it.

If this method is defined as `NULL`, the worker will only execute tasks from its local queue. In this case, the `push_task` method should use the `starpu_push_local_task` method to assign tasks to the different workers.

28.36.2.1.1.6 `pop_every_task`

```
struct starpu_task *(* starpu_sched_policy::pop_every_task)(unsigned sched_ctx_id)
```

Remove all available tasks from the scheduler (tasks are chained by the means of the field `starpu_task::prev` and `starpu_task::next`). The mutex associated to the worker is already taken when this method is called. This is currently not used and can be discarded.

28.36.2.1.1.7 submit_hook

```
void(* starpu_sched_policy::submit_hook)(struct starpu_task *)
```

Optional field. This method is called when a task is submitted.

28.36.2.1.1.8 pre_exec_hook

```
void(* starpu_sched_policy::pre_exec_hook)(struct starpu_task *)
```

Optional field. This method is called every time a task is starting.

28.36.2.1.1.9 post_exec_hook

```
void(* starpu_sched_policy::post_exec_hook)(struct starpu_task *)
```

Optional field. This method is called every time a task has been executed.

28.36.2.1.1.10 do_schedule

```
void(* starpu_sched_policy::do_schedule)(unsigned sched_ctx_id)
```

Optional field. This method is called when it is a good time to start scheduling tasks. This is notably called when the application calls `starpu_task_wait_for_all` or `starpu_do_schedule` explicitly.

28.36.2.1.1.11 add_workers

```
void(* starpu_sched_policy::add_workers)(unsigned sched_ctx_id, int *workerids, unsigned nworkers)
```

Initialize scheduling structures corresponding to each worker used by the policy.

28.36.2.1.1.12 remove_workers

```
void(* starpu_sched_policy::remove_workers)(unsigned sched_ctx_id, int *workerids, unsigned nworkers)
```

Deinitialize scheduling structures corresponding to each worker used by the policy.

28.36.2.1.1.13 policy_name

```
const char * starpu_sched_policy::policy_name
```

Optional field. Name of the policy.

28.36.2.1.1.14 policy_description

```
const char * starpu_sched_policy::policy_description
```

Optional field. Human readable description of the policy.

28.36.3 Macro Definition Documentation

28.36.3.1 STARPU_NMAX_SCHED_CTXS

```
#define STARPU_NMAX_SCHED_CTXS
```

Define the maximum number of scheduling contexts managed by StarPU. The default value can be modified at configure by using the option `--enable-max-sched-ctxs`.

28.36.3.2 STARPU_MAXIMPLEMENTATIONS

```
#define STARPU_MAXIMPLEMENTATIONS
```

Define the maximum number of implementations per architecture. The default value can be modified at configure by using the option `--enable-maximplementations`.

28.36.4 Function Documentation

28.36.4.1 starpu_sched_get_predefined_policies()

```
struct starpu_sched_policy ** starpu_sched_get_predefined_policies ( )
```

Return an NULL-terminated array of all the predefined scheduling policies.

28.36.4.2 starpu_worker_get_sched_condition()

```
void starpu_worker_get_sched_condition (
    int workerid,
    starpu_pthread_mutex_t ** sched_mutex,
    starpu_pthread_cond_t ** sched_cond )
```

When there is no available task for a worker, StarPU blocks this worker on a condition variable. This function specifies which condition variable (and the associated mutex) should be used to block (and to wake up) a worker. Note that multiple workers may use the same condition variable. For instance, in the case of a scheduling strategy with a single task queue, the same condition variable would be used to block and wake up all workers.

28.36.4.3 starpu_wake_worker()

```
int starpu_wake_worker (
    int workerid )
```

In simgrid or blocking driver mode, this should be called by push functions to wake the potential workers that are supposed to pick up the tasks which just have been pushed, otherwise they may remain sleeping.

28.36.4.4 starpu_sched_set_min_priority()

```
int starpu_sched_set_min_priority (
    int min_prio )
```

TODO: check if this is correct Defines the minimum task priority level supported by the scheduling policy. The default minimum priority level is the same as the default priority level which is 0 by convention. The application may access that value by calling the function [starpu_sched_get_min_priority\(\)](#). This function should only be called from the initialization method of the scheduling policy, and should not be used directly from the application.

28.36.4.5 starpu_sched_set_max_priority()

```
int starpu_sched_set_max_priority (
    int max_prio )
```

TODO: check if this is correct Defines the maximum priority level supported by the scheduling policy. The default maximum priority level is 1. The application may access that value by calling the function [starpu_sched_get_max_priority\(\)](#). This function should only be called from the initialization method of the scheduling policy, and should not be used directly from the application.

28.36.4.6 starpu_sched_get_min_priority()

```
int starpu_sched_get_min_priority (
    void )
```

TODO: check if this is correct Returns the current minimum priority level supported by the scheduling policy

28.36.4.7 starpu_sched_get_max_priority()

```
int starpu_sched_get_max_priority (
    void )
```

TODO: check if this is correct Returns the current maximum priority level supported by the scheduling policy

28.36.4.8 starpu_push_local_task()

```
int starpu_push_local_task (
    int workerid,
    struct starpu_task * task,
    int back )
```

The scheduling policy may put tasks directly into a worker's local queue so that it is not always necessary to create its own queue when the local queue is sufficient. If `back` is not 0, `task` is put at the back of the queue where the worker will pop tasks first. Setting `back` to 0 therefore ensures a FIFO ordering.

28.36.4.9 starpu_push_task_end()

```
int starpu_push_task_end (
    struct starpu_task * task )
```

This function must be called by a scheduler to notify that the given task has just been pushed.

28.36.4.10 starpu_worker_can_execute_task()

```
int starpu_worker_can_execute_task (
    unsigned workerid,
    struct starpu_task * task,
    unsigned nimpl )
```

Check if the worker specified by workerid can execute the codelet. Schedulers need to call it before assigning a task to a worker, otherwise the task may fail to execute.

28.36.4.11 starpu_worker_can_execute_task_impl()

```
int starpu_worker_can_execute_task_impl (
    unsigned workerid,
    struct starpu_task * task,
    unsigned * impl_mask )
```

Check if the worker specified by workerid can execute the codelet and returns which implementation numbers can be used. Schedulers need to call it before assigning a task to a worker, otherwise the task may fail to execute. This should be preferred rather than calling starpu_worker_can_execute_task for each and every implementation. It can also be used with impl_mask == NULL to check for at least one implementation without determining which.

28.36.4.12 starpu_worker_can_execute_task_first_impl()

```
int starpu_worker_can_execute_task_first_impl (
    unsigned workerid,
    struct starpu_task * task,
    unsigned * nimpl )
```

Check if the worker specified by workerid can execute the codelet and returns the first implementation which can be used. Schedulers need to call it before assigning a task to a worker, otherwise the task may fail to execute. This should be preferred rather than calling starpu_worker_can_execute_task for each and every implementation. It can also be used with impl_mask == NULL to check for at least one implementation without determining which.

28.36.4.13 starpu_task_footprint()

```
uint32_t starpu_task_footprint (
    struct starpu_perfmodel * model,
    struct starpu_task * task,
    struct starpu_perfmodel_arch * arch,
    unsigned nimpl )
```

Returns the footprint for a given task, taking into account user-provided perfmodel footprint or size_base functions.

28.36.4.14 starpu_task_data_footprint()

```
uint32_t starpu_task_data_footprint (
    struct starpu_task * task )
```

Returns the raw footprint for the data of a given task (without taking into account user-provided functions).

28.36.4.15 starpu_task_expected_length()

```
double starpu_task_expected_length (
    struct starpu_task * task,
    struct starpu_perfmodel_arch * arch,
    unsigned nimpl )
```

Returns expected task duration in micro-seconds.

28.36.4.16 starpu_worker_get_relative_speedup()

```
double starpu_worker_get_relative_speedup (
    struct starpu_perfmodel_arch * perf_arch )
```

Returns an estimated speedup factor relative to CPU speed

28.36.4.17 starpu_task_expected_data_transfer_time()

```
double starpu_task_expected_data_transfer_time (
    unsigned memory_node,
    struct starpu_task * task )
```

Returns expected data transfer time in micro-seconds.

28.36.4.18 starpu_data_expected_transfer_time()

```
double starpu_data_expected_transfer_time (
    starpu_data_handle_t handle,
    unsigned memory_node,
    enum starpu_data_access_mode mode )
```

Predict the transfer time (in micro-seconds) to move handle to a memory node

28.36.4.19 starpu_task_expected_energy()

```
double starpu_task_expected_energy (
    struct starpu_task * task,
    struct starpu_perfmodel_arch * arch,
    unsigned nimpl )
```

Returns expected energy consumption in J

28.36.4.20 starpu_task_expected_conversion_time()

```
double starpu_task_expected_conversion_time (
    struct starpu_task * task,
    struct starpu_perfmodel_arch * arch,
    unsigned nimpl )
```

Returns expected conversion time in ms (multiformat interface only)

28.36.4.21 starpu_get_prefetch_flag()

```
int starpu_get_prefetch_flag (
    void )
```

Whether `STARPU_PREFETCH` was set

28.36.4.22 starpu_prefetch_task_input_on_node()

```
int starpu_prefetch_task_input_on_node (
    struct starpu_task * task,
    unsigned node )
```

Prefetch data for a given task on a given node

28.36.4.23 starpu_idle_prefetch_task_input_on_node()

```
int starpu_idle_prefetch_task_input_on_node (
    struct starpu_task * task,
    unsigned node )
```

Prefetch data for a given task on a given node when the bus is idle

28.36.4.24 starpu_sched_ctx_worker_shares_tasks_lists()

```
void starpu_sched_ctx_worker_shares_tasks_lists (
    int workerid,
    int sched_ctx_id )
```

The scheduling policies indicates if the worker may pop tasks from the list of other workers or if there is a central list with task for all the workers

28.37 Tree

This section describes the tree facilities provided by StarPU.

Data Structures

- struct `starpu_tree`

Functions

- void `starpu_tree_reset_visited` (struct `starpu_tree` *tree, char *visited)
- void `starpu_tree_insert` (struct `starpu_tree` *tree, int id, int level, int is_pu, int arity, struct `starpu_tree` *father)
- struct `starpu_tree` * `starpu_tree_get` (struct `starpu_tree` *tree, int id)
- struct `starpu_tree` * `starpu_tree_get_neighbour` (struct `starpu_tree` *tree, struct `starpu_tree` *node, char *visited, char *present)
- void `starpu_tree_free` (struct `starpu_tree` *tree)

28.37.1 Detailed Description

This section describes the tree facilities provided by StarPU.

28.37.2 Data Structure Documentation

28.37.2.1 `struct starpu_tree`

Data Fields

struct starpu_tree *	nodes	todo
struct starpu_tree *	father	todo
int	arity	todo
int	id	todo
int	level	todo
int	is_pu	todo

28.37.3 Function Documentation

28.37.3.1 [starpu_tree_reset_visited\(\)](#)

```
void starpu_tree_reset_visited (
    struct starpu\_tree * tree,
    char * visited )
```

todo

28.37.3.2 [starpu_tree_insert\(\)](#)

```
void starpu_tree_insert (
    struct starpu\_tree * tree,
    int id,
    int level,
    int is_pu,
    int arity,
    struct starpu\_tree * father )
```

todo

28.37.3.3 [starpu_tree_get\(\)](#)

```
struct starpu\_tree * starpu_tree_get (
    struct starpu\_tree * tree,
    int id )
```

todo

28.37.3.4 [starpu_tree_get_neighbour\(\)](#)

```
struct starpu\_tree * starpu_tree_get_neighbour (
    struct starpu\_tree * tree,
    struct starpu\_tree * node,
    char * visited,
    char * present )
```

todo

28.37.3.5 starpu_tree_free()

```
void starpu_tree_free (
    struct starpu_tree * tree )
```

todo

28.38 Scheduling Context Hypervisor - Regular usage

Macros

- `#define SC_HYPERVISOR_MAX_IDLE`
- `#define SC_HYPERVISOR_PRIORITY`
- `#define SC_HYPERVISOR_MIN_WORKERS`
- `#define SC_HYPERVISOR_MAX_WORKERS`
- `#define SC_HYPERVISOR_GRANULARITY`
- `#define SC_HYPERVISOR_FIXED_WORKERS`
- `#define SC_HYPERVISOR_MIN_TASKS`
- `#define SC_HYPERVISOR_NEW_WORKERS_MAX_IDLE`
- `#define SC_HYPERVISOR_TIME_TO_APPLY`
- `#define SC_HYPERVISOR_ISPEED_W_SAMPLE`
- `#define SC_HYPERVISOR_ISPEED_CTX_SAMPLE`
- `#define SC_HYPERVISOR_NULL`

Functions

- `void * sc_hypervisor_init (struct sc_hypervisor_policy *policy)`
- `void sc_hypervisor_shutdown (void)`
- `void sc_hypervisor_register_ctx (unsigned sched_ctx, double total_flops)`
- `void sc_hypervisor_unregister_ctx (unsigned sched_ctx)`
- `void sc_hypervisor_resize_ctxs (unsigned *sched_ctxs, int nsched_ctxs, int *workers, int nworkers)`
- `void sc_hypervisor_stop_resize (unsigned sched_ctx)`
- `void sc_hypervisor_start_resize (unsigned sched_ctx)`
- `const char * sc_hypervisor_get_policy ()`
- `void sc_hypervisor_add_workers_to_sched_ctx (int *workers_to_add, unsigned nworkers_to_add, unsigned sched_ctx)`
- `void sc_hypervisor_remove_workers_from_sched_ctx (int *workers_to_remove, unsigned nworkers_to_remove, unsigned sched_ctx, unsigned now)`
- `void sc_hypervisor_move_workers (unsigned sender_sched_ctx, unsigned receiver_sched_ctx, int *workers_to_move, unsigned nworkers_to_move, unsigned now)`
- `void sc_hypervisor_size_ctxs (unsigned *sched_ctxs, int nsched_ctxs, int *workers, int nworkers)`
- `void sc_hypervisor_set_type_of_task (struct starpu_codelet *cl, unsigned sched_ctx, uint32_t footprint, size_t data_size)`
- `void sc_hypervisor_update_diff_total_flops (unsigned sched_ctx, double diff_total_flops)`
- `void sc_hypervisor_update_diff_elapsed_flops (unsigned sched_ctx, double diff_task_flops)`
- `void sc_hypervisor_ctl (unsigned sched_ctx,...)`

28.38.1 Detailed Description

28.38.2 Macro Definition Documentation

28.38.2.1 SC_HYPERVISOR_MAX_IDLE

```
#define SC_HYPERVISOR_MAX_IDLE
```

This macro is used when calling [sc_hypervisor_ctl\(\)](#) and must be followed by 3 arguments: an array of int for the workerids to apply the condition, an int to indicate the size of the array, and a double value indicating the maximum idle time allowed for a worker before the resizing process should be triggered

28.38.2.2 SC_HYPERVISOR_PRIORITY

```
#define SC_HYPERVISOR_PRIORITY
```

This macro is used when calling [sc_hypervisor_ctl\(\)](#) and must be followed by 3 arguments: an array of int for the workerids to apply the condition, an int to indicate the size of the array, and an int value indicating the priority of the workers previously mentioned. The workers with the smallest priority are moved the first.

28.38.2.3 SC_HYPERVISOR_MIN_WORKERS

```
#define SC_HYPERVISOR_MIN_WORKERS
```

This macro is used when calling [sc_hypervisor_ctl\(\)](#) and must be followed by 1 argument(int) indicating the minimum number of workers a context should have, underneath this limit the context cannot execute.

28.38.2.4 SC_HYPERVISOR_MAX_WORKERS

```
#define SC_HYPERVISOR_MAX_WORKERS
```

This macro is used when calling [sc_hypervisor_ctl\(\)](#) and must be followed by 1 argument(int) indicating the maximum number of workers a context should have, above this limit the context would not be able to scale

28.38.2.5 SC_HYPERVISOR_GRANULARITY

```
#define SC_HYPERVISOR_GRANULARITY
```

This macro is used when calling [sc_hypervisor_ctl\(\)](#) and must be followed by 1 argument(int) indicating the granularity of the resizing process (the number of workers should be moved from the context once it is resized) This parameter is ignore for the Gflops rate based strategy (see [Resizing Strategies](#)), the number of workers that have to be moved is calculated by the strategy.

28.38.2.6 SC_HYPERVISOR_FIXED_WORKERS

```
#define SC_HYPERVISOR_FIXED_WORKERS
```

This macro is used when calling [sc_hypervisor_ctl\(\)](#) and must be followed by 2 arguments: an array of int for the workerids to apply the condition and an int to indicate the size of the array. These workers are not allowed to be moved from the context.

28.38.2.7 SC_HYPERVISOR_MIN_TASKS

```
#define SC_HYPERVISOR_MIN_TASKS
```

This macro is used when calling [sc_hypervisor_ctl\(\)](#) and must be followed by 1 argument (int) that indicated the minimum number of tasks that have to be executed before the context could be resized. This parameter is ignored for the Application Driven strategy (see [Resizing Strategies](#)) where the user indicates exactly when the resize should be done.

28.38.2.8 SC_HYPERVISOR_NEW_WORKERS_MAX_IDLE

```
#define SC_HYPERVISOR_NEW_WORKERS_MAX_IDLE
```

This macro is used when calling [sc_hypervisor_ctl\(\)](#) and must be followed by 1 argument, a double value indicating the maximum idle time allowed for workers that have just been moved from other contexts in the current context.

28.38.2.9 SC_HYPERVISOR_TIME_TO_APPLY

```
#define SC_HYPERVISOR_TIME_TO_APPLY
```

This macro is used when calling [sc_hypervisor_ctl\(\)](#) and must be followed by 1 argument (int) indicating the tag an executed task should have such that this configuration should be taken into account.

28.38.2.10 SC_HYPERVISOR_ISPEED_W_SAMPLE

```
#define SC_HYPERVISOR_ISPEED_W_SAMPLE
```

This macro is used when calling [sc_hypervisor_ctl\(\)](#) and must be followed by 1 argument, a double, that indicates the number of flops needed to be executed before computing the speed of a worker

28.38.2.11 SC_HYPERVISOR_ISPEED_CTX_SAMPLE

```
#define SC_HYPERVISOR_ISPEED_CTX_SAMPLE
```

This macro is used when calling [sc_hypervisor_ctl\(\)](#) and must be followed by 1 argument, a double, that indicates the number of flops needed to be executed before computing the speed of a context

28.38.2.12 SC_HYPERVISOR_NULL

```
#define SC_HYPERVISOR_NULL
```

This macro is used when calling [sc_hypervisor_ctl\(\)](#) and must be followed by 1 arguments

28.38.3 Function Documentation

28.38.3.1 `sc_hypervisor_init()`

```
void * sc_hypervisor_init (
    struct sc\_hypervisor\_policy * policy )
```

There is a single hypervisor that is in charge of resizing contexts and the resizing strategy is chosen at the initialization of the hypervisor. A single resize can be done at a time.

The Scheduling Context Hypervisor Plugin provides a series of performance counters to StarPU. By incrementing them, StarPU can help the hypervisor in the resizing decision making process.

This function initializes the hypervisor to use the strategy provided as parameter and creates the performance counters (see [starpu_sched_ctx_performance_counters](#)). These performance counters represent actually some callbacks that will be used by the contexts to notify the information needed by the hypervisor.

Note: The Hypervisor is actually a worker that takes this role once certain conditions trigger the resizing process (there is no additional thread assigned to the hypervisor).

28.38.3.2 `sc_hypervisor_shutdown()`

```
void sc_hypervisor_shutdown (
    void )
```

The hypervisor and all information concerning it is cleaned. There is no synchronization between this function and [starpu_shutdown\(\)](#). Thus, this should be called after [starpu_shutdown\(\)](#), because the performance counters will still need allocated callback functions.

28.38.3.3 `sc_hypervisor_register_ctx()`

```
void sc_hypervisor_register_ctx (
    unsigned sched_ctx,
    double total_flops )
```

Scheduling Contexts that have to be resized by the hypervisor must be first registered to the hypervisor. This function registers the context to the hypervisor, and indicate the number of flops the context will execute (used for Gflops rate based strategy or any other custom strategy needing it, for the others we can pass 0.0)

28.38.3.4 `sc_hypervisor_unregister_ctx()`

```
void sc_hypervisor_unregister_ctx (
    unsigned sched_ctx )
```

Whenever we want to exclude contexts from the resizing process we have to unregister them from the hypervisor.

28.38.3.5 `sc_hypervisor_resize_ctxs()`

```
void sc_hypervisor_resize_ctxs (
    unsigned * sched_ctxs,
    int nsched_ctxs,
    int * workers,
    int nworkers )
```

Requires reconsidering the distribution of ressources over the indicated scheduling contexts

28.38.3.6 `sc_hypervisor_stop_resize()`

```
void sc_hypervisor_stop_resize (
    unsigned sched_ctx )
```

The user can totally forbid the resizing of a certain context or can then change his mind and allow it (in this case the resizing is managed by the hypervisor, that can forbid it or allow it)

28.38.3.7 `sc_hypervisor_start_resize()`

```
void sc_hypervisor_start_resize (
    unsigned sched_ctx )
```

Allow resizing of a context. The user can then provide information to the hypervisor concerning the conditions of resizing.

28.38.3.8 `sc_hypervisor_get_policy()`

```
char * sc_hypervisor_get_policy ( )
```

Returns the name of the resizing policy the hypervisor uses

28.38.3.9 `sc_hypervisor_add_workers_to_sched_ctx()`

```
void sc_hypervisor_add_workers_to_sched_ctx (
    int * workers_to_add,
    unsigned nworkers_to_add,
    unsigned sched_ctx )
```

Ask the hypervisor to add workers to a sched_ctx

28.38.3.10 `sc_hypervisor_remove_workers_from_sched_ctx()`

```
void sc_hypervisor_remove_workers_from_sched_ctx (
    int * workers_to_remove,
    unsigned nworkers_to_remove,
    unsigned sched_ctx,
    unsigned now )
```

Ask the hypervisor to remove workers from a sched_ctx

28.38.3.11 `sc_hypervisor_move_workers()`

```
void sc_hypervisor_move_workers (
    unsigned sender_sched_ctx,
    unsigned receiver_sched_ctx,
    int * workers_to_move,
    unsigned nworkers_to_move,
    unsigned now )
```

Moves workers from one context to another

28.38.3.12 sc_hypervisor_size_ctxs()

```
void sc_hypervisor_size_ctxs (
    unsigned * sched_ctxs,
    int nsched_ctxs,
    int * workers,
    int nworkers )
```

Ask the hypervisor to chose a distribution of workers in the required contexts

28.38.3.13 sc_hypervisor_set_type_of_task()

```
void sc_hypervisor_set_type_of_task (
    struct starpu_codelet * cl,
    unsigned sched_ctx,
    uint32_t footprint,
    size_t data_size )
```

Indicate the types of tasks a context will execute in order to better decide the sizing of ctxs

28.38.3.14 sc_hypervisor_update_diff_total_flops()

```
void sc_hypervisor_update_diff_total_flops (
    unsigned sched_ctx,
    double diff_total_flops )
```

Change dynamically the total number of flops of a context, move the deadline of the finishing time of the context

28.38.3.15 sc_hypervisor_update_diff_elapsed_flops()

```
void sc_hypervisor_update_diff_elapsed_flops (
    unsigned sched_ctx,
    double diff_task_flops )
```

Change dynamically the number of the elapsed flops in a context, modify the past in order to better compute the speed

28.38.3.16 sc_hypervisor_ctl()

```
void sc_hypervisor_ctl (
    unsigned sched_ctx,
    ... )
```

Inputs conditions to the context sched_ctx with the following arguments. The argument list must be zero-terminated.

28.39 Scheduling Context Hypervisor - Building a new resizing policy

Data Structures

- struct [sc_hypervisor_policy](#)
- struct [sc_hypervisor_policy_config](#)
- struct [sc_hypervisor_wrapper](#)
- struct [sc_hypervisor_resize_ack](#)
- struct [sc_hypervisor_policy_task_pool](#)

Macros

- `#define` [STARPU_HYPERVISOR_TAG](#)

Functions

- void [sc_hypervisor_post_resize_request](#) (unsigned sched_ctx, int task_tag)
- unsigned [sc_hypervisor_get_size_req](#) (unsigned **sched_ctxs, int *nsched_ctxs, int **workers, int *nworkers)
- void [sc_hypervisor_save_size_req](#) (unsigned *sched_ctxs, int nsched_ctxs, int *workers, int nworkers)
- void [sc_hypervisor_free_size_req](#) (void)
- unsigned [sc_hypervisor_can_resize](#) (unsigned sched_ctx)
- struct [sc_hypervisor_policy_config](#) * [sc_hypervisor_get_config](#) (unsigned sched_ctx)
- void [sc_hypervisor_set_config](#) (unsigned sched_ctx, void *config)
- unsigned * [sc_hypervisor_get_sched_ctxs](#) ()
- int [sc_hypervisor_get_nsched_ctxs](#) ()
- struct [sc_hypervisor_wrapper](#) * [sc_hypervisor_get_wrapper](#) (unsigned sched_ctx)
- double [sc_hypervisor_get_elapsed_flops_per_sched_ctx](#) (struct [sc_hypervisor_wrapper](#) *sc_w)

28.39.1 Detailed Description

28.39.2 Data Structure Documentation

28.39.2.1 struct [sc_hypervisor_policy](#)

This structure contains all the methods that implement a hypervisor resizing policy.

Data Fields

- const char * [name](#)
- unsigned [custom](#)
- void(* [size_ctxs](#))(unsigned *sched_ctxs, int nsched_ctxs, int *workers, int nworkers)
- void(* [resize_ctxs](#))(unsigned *sched_ctxs, int nsched_ctxs, int *workers, int nworkers)
- void(* [handle_idle_cycle](#))(unsigned sched_ctx, int worker)
- void(* [handle_pushed_task](#))(unsigned sched_ctx, int worker)
- void(* [handle_poped_task](#))(unsigned sched_ctx, int worker, struct [starpu_task](#) *task, uint32_t footprint)
- void(* [handle_idle_end](#))(unsigned sched_ctx, int worker)
- void(* [handle_post_exec_hook](#))(unsigned sched_ctx, int task_tag)
- void(* [handle_submitted_job](#))(struct [starpu_codelet](#) *cl, unsigned sched_ctx, uint32_t footprint, size_t data↔_size)
- void(* [end_ctx](#))(unsigned sched_ctx)

28.39.2.1.1 Field Documentation

28.39.2.1.1.1 name

```
sc_hypervisor_policy::name
```

Indicates the name of the policy, if there is not a custom policy, the policy corresponding to this name will be used by the hypervisor

28.39.2.1.1.2 custom

```
sc_hypervisor_policy::custom
```

Indicates whether the policy is custom or not

28.39.2.1.1.3 size_ctxs

```
sc_hypervisor_policy::size_ctxs
```

Distribute workers to contexts even at the beginning of the program

28.39.2.1.1.4 resize_ctxs

```
sc_hypervisor_policy::resize_ctxs
```

Require explicit resizing

28.39.2.1.1.5 handle_idle_cycle

```
sc_hypervisor_policy::handle_idle_cycle
```

It is called whenever the indicated worker executes another idle cycle in sched_ctx

28.39.2.1.1.6 handle_pushed_task

```
sc_hypervisor_policy::handle_pushed_task
```

It is called whenever a task is pushed on the worker's queue corresponding to the context sched_ctx

28.39.2.1.1.7 handle_poped_task

```
sc_hypervisor_policy::handle_poped_task
```

It is called whenever a task is popped from the worker's queue corresponding to the context sched_ctx

The hypervisor takes a decision when another task was popped from this worker in this ctx

28.39.2.1.1.8 handle_idle_end

```
sc_hypervisor_policy::handle_idle_end
```

It is called whenever a task is executed on the indicated worker and context after a long period of idle time

28.39.2.1.1.9 handle_post_exec_hook

```
sc_hypervisor_policy::handle_post_exec_hook
```

It is called whenever a tag task has just been executed. The table of resize requests is provided as well as the tag

28.39.2.1.1.10 handle_submitted_job

```
sc_hypervisor_policy::handle_submitted_job
```

The hypervisor takes a decision when a job was submitted in this ctx

28.39.2.1.1.11 end_ctx

```
sc_hypervisor_policy::end_ctx
```

The hypervisor takes a decision when a certain ctx was deleted

28.39.2.2 struct sc_hypervisor_policy_config

This structure contains all configuration information of a context. It contains configuration information for each context, which can be used to construct new resize strategies.

Data Fields

int	min_nworkers	Indicates the minimum number of workers needed by the context
int	max_nworkers	Indicates the maximum number of workers needed by the context
int	granularity	Indicates the workers granularity of the context
int	priority[STARPU_NMAXWORKERS]	Indicates the priority of each worker in the context
double	max_idle[STARPU_NMAXWORKERS]	Indicates the maximum idle time accepted before a resize is triggered
double	min_working[STARPU_NMAXWORKERS]	Indicates that underneath this limit the priority of the worker is reduced
int	fixed_workers[STARPU_NMAXWORKERS]	Indicates which workers can be moved and which ones are fixed
double	new_workers_max_idle	Indicates the maximum idle time accepted before a resize is triggered for the workers that just arrived in the new context
double	ispeed_w_sample[STARPU_NMAXWORKERS]	Indicates the sample used to compute the instant speed per worker
double	ispeed_ctx_sample	Indicates the sample used to compute the instant speed per ctxs
double	time_sample	todo

28.39.2.3 struct sc_hypervisor_wrapper

This structure is a wrapper of the contexts available in StarPU and contains all information about a context obtained by incrementing the performance counters.

Data Fields

unsigned	sched_ctx	The context wrapped
struct sc_hypervisor_policy_config *	config	The corresponding resize configuration
double	start_time_w[STARPU_NMAXWORKERS]	
double	current_idle_time[STARPU_NMAXWORKERS]	The idle time counter of each worker of the context
double	idle_time[STARPU_NMAXWORKERS]	The time the workers were idle from the last resize
double	idle_start_time[STARPU_NMAXWORKERS]	The moment when the workers started being idle
double	exec_time[STARPU_NMAXWORKERS]	
double	exec_start_time[STARPU_NMAXWORKERS]	
int	worker_to_be_removed[STARPU_NMAXWORKERS]	The list of workers that will leave this contexts (lazy resizing process)
int	pushed_tasks[STARPU_NMAXWORKERS]	The number of pushed tasks of each worker of the context
int	popped_tasks[STARPU_NMAXWORKERS]	The number of popped tasks of each worker of the context
double	total_flops	The total number of flops to execute by the context
double	total_elapsed_flops[STARPU_NMAXWORKERS]	The number of flops executed by each workers of the context
double	elapsed_flops[STARPU_NMAXWORKERS]	The number of flops executed by each worker of the context from last resize
size_t	elapsed_data[STARPU_NMAXWORKERS]	The quantity of data (in bytes) used to execute tasks on each worker in this ctx
int	elapsed_tasks[STARPU_NMAXWORKERS]	The nr of tasks executed on each worker in this ctx
double	ref_speed[2]	The average speed of the workers (type of workers) when they belonged to this context 0 - cuda 1 - cpu
double	submitted_flops	The number of flops submitted to this ctx
double	remaining_flops	The number of flops that still have to be executed by the workers in the context
double	start_time	The time when he started executed
double	real_start_time	The first time a task was pushed to this context
double	hyp_react_start_time	
struct sc_hypervisor_resize_ack	resize_ack	The structure confirming the last resize finished and a new one can be done

Data Fields

starpu_pthread_mutex_t	mutex	The mutex needed to synchronize the acknowledgment of the workers into the receiver context
unsigned	total_flops_available	A boolean indicating if the hypervisor can use the flops corresponding to the entire execution of the context
unsigned	to_be_sized	
unsigned	compute_idle[STARPU_NMAXWORKERS]	
unsigned	compute_partial_idle[STARPU_NMAXWORKERS]	
unsigned	consider_max	

28.39.2.4 struct sc_hypervisor_resize_ack

This structures checks if the workers moved to another context are actually taken into account in that context.

Data Fields

int	receiver_sched_ctx	The context receiving the new workers
int *	moved_workers	The workers moved to the receiver context
int	nmoved_workers	The number of workers moved
int *	acked_workers	If the value corresponding to a worker is 1, this one is taken into account in the new context if 0 not yet

28.39.2.5 struct sc_hypervisor_policy_task_pool

task wrapper linked list

Data Fields

struct starpu_codelet *	cl	Which codelet has been executed
uint32_t	footprint	Task footprint key
unsigned	sched_ctx_id	Context the task belongs to
unsigned long	n	Number of tasks of this kind
size_t	data_size	The quantity of data(in bytes) needed by the task to execute
struct sc_hypervisor_policy_task_pool *	next	Other task kinds

28.39.3 Macro Definition Documentation

28.39.3.1 STARPU_HYPERVISOR_TAG

```
#define STARPU_HYPERVISOR_TAG
```

```
todo
```

28.39.4 Function Documentation

28.39.4.1 `sc_hypervisor_post_resize_request()`

```
void sc_hypervisor_post_resize_request (
    unsigned sched_ctx,
    int task_tag )
```

Requires resizing the context `sched_ctx` whenever a task tagged with the id `task_tag` finished executing

28.39.4.2 `sc_hypervisor_get_size_req()`

```
unsigned sc_hypervisor_get_size_req (
    unsigned ** sched_ctxs,
    int * nsched_ctxs,
    int ** workers,
    int * nworkers )
```

Check if there are pending demands of resizing

28.39.4.3 `sc_hypervisor_save_size_req()`

```
void sc_hypervisor_save_size_req (
    unsigned * sched_ctxs,
    int nsched_ctxs,
    int * workers,
    int nworkers )
```

Save a demand of resizing

28.39.4.4 `sc_hypervisor_free_size_req()`

```
void sc_hypervisor_free_size_req (
    void )
```

Clear the list of pending demands of resizing

28.39.4.5 `sc_hypervisor_can_resize()`

```
unsigned sc_hypervisor_can_resize (
    unsigned sched_ctx )
```

Check out if a context can be resized

28.39.4.6 `sc_hypervisor_get_config()`

```
struct sc_hypervisor_policy_config * sc_hypervisor_get_config (
    unsigned sched_ctx )
```

Returns the configuration structure of a context

28.39.4.7 `sc_hypervisor_set_config()`

```
void sc_hypervisor_set_config (
    unsigned sched_ctx,
    void * config )
```

Set a certain configuration to a contexts

28.39.4.8 `sc_hypervisor_get_sched_ctxs()`

```
unsigned * sc_hypervisor_get_sched_ctxs ( )
```

Gets the contexts managed by the hypervisor

28.39.4.9 `sc_hypervisor_get_nsched_ctxs()`

```
int sc_hypervisor_get_nsched_ctxs ( )
```

Gets the number of contexts managed by the hypervisor

28.39.4.10 `sc_hypervisor_get_wrapper()`

```
struct sc_hypervisor_wrapper * sc_hypervisor_get_wrapper (
    unsigned sched_ctx )
```

Returns the wrapper corresponding the context `sched_ctx`

28.39.4.11 `sc_hypervisor_get_elapsed_flops_per_sched_ctx()`

```
double sc_hypervisor_get_elapsed_flops_per_sched_ctx (
    struct sc_hypervisor_wrapper * sc_w )
```

Returns the flops of a context elapsed from the last resize

28.40 Modularized Scheduler Interface

Data Structures

- struct `starpu_sched_component`
- struct `starpu_sched_tree`
- struct `starpu_sched_component_fifo_data`
- struct `starpu_sched_component_prio_data`
- struct `starpu_sched_component_mct_data`
- struct `starpu_sched_component_perfmmodel_select_data`
- struct `starpu_sched_component_composed_recipe`
- struct `starpu_sched_component_specs`

Macros

- `#define STARPU_SCHED_COMPONENT_IS_HOMOGENEOUS(component)`
- `#define STARPU_SCHED_COMPONENT_IS_SINGLE_MEMORY_NODE(component)`

Enumerations

- enum `starpu_sched_component_properties` { `STARPU_SCHED_COMPONENT_HOMOGENEOUS`, `STARPU_SCHED_COMPONENT_SINGLE_MEMORY_NODE` }

Scheduling Tree API

- struct `starpu_sched_tree` * `starpu_sched_tree_create` (unsigned sched_ctx_id) `STARPU_ATTRIBUTE_MALLOC`
- void `starpu_sched_tree_destroy` (struct `starpu_sched_tree` *tree)
- void `starpu_sched_tree_update_workers` (struct `starpu_sched_tree` *t)
- void `starpu_sched_tree_update_workers_in_ctx` (struct `starpu_sched_tree` *t)
- int `starpu_sched_tree_push_task` (struct `starpu_task` *task)
- struct `starpu_task` * `starpu_sched_tree_pop_task` (unsigned sched_ctx)
- void `starpu_sched_tree_add_workers` (unsigned sched_ctx_id, int *workerids, unsigned nworkers)
- void `starpu_sched_tree_remove_workers` (unsigned sched_ctx_id, int *workerids, unsigned nworkers)
- void `starpu_sched_component_connect` (struct `starpu_sched_component` *parent, struct `starpu_sched_component` *child)

Generic Scheduling Component API

- struct `starpu_sched_component` * `starpu_sched_component_create` (struct `starpu_sched_tree` *tree, const char *name) `STARPU_ATTRIBUTE_MALLOC`
- void `starpu_sched_component_destroy` (struct `starpu_sched_component` *component)
- void `starpu_sched_component_destroy_rec` (struct `starpu_sched_component` *component)
- int `starpu_sched_component_can_execute_task` (struct `starpu_sched_component` *component, struct `starpu_task` *task)
- int `STARPU_WARN_UNUSED_RESULT` `starpu_sched_component_execute_preds` (struct `starpu_sched_component` *component, struct `starpu_task` *task, double *length)
- double `starpu_sched_component_transfer_length` (struct `starpu_sched_component` *component, struct `starpu_task` *task)

Worker Component API

- struct `starpu_sched_component` * `starpu_sched_component_worker_get` (unsigned sched_ctx, int workerid)
- int `starpu_sched_component_worker_get_workerid` (struct `starpu_sched_component` *worker_component)
- int `starpu_sched_component_is_worker` (struct `starpu_sched_component` *component)
- int `starpu_sched_component_is_simple_worker` (struct `starpu_sched_component` *component)
- int `starpu_sched_component_is_combined_worker` (struct `starpu_sched_component` *component)
- void `starpu_sched_component_worker_pre_exec_hook` (struct `starpu_task` *task)
- void `starpu_sched_component_worker_post_exec_hook` (struct `starpu_task` *task)

Flow-control Fifo Component API

- double `starpu_sched_component_estimated_load` (struct `starpu_sched_component` *component)
- double `starpu_sched_component_estimated_end_min` (struct `starpu_sched_component` *component)
- double `starpu_sched_component_estimated_end_average` (struct `starpu_sched_component` *component)
- struct `starpu_sched_component` * `starpu_sched_component_fifo_create` (struct `starpu_sched_tree` *tree, struct `starpu_sched_component_fifo_data` *fifo_data) STARPU_ATTRIBUTE_MALLOC
- int `starpu_sched_component_is_fifo` (struct `starpu_sched_component` *component)

Flow-control Prio Component API

- struct `starpu_sched_component` * `starpu_sched_component_prio_create` (struct `starpu_sched_tree` *tree, struct `starpu_sched_component_prio_data` *prio_data) STARPU_ATTRIBUTE_MALLOC
- int `starpu_sched_component_is_prio` (struct `starpu_sched_component` *component)

Resource-mapping Work-Stealing Component API

- int `starpu_sched_tree_work_stealing_push_task` (struct `starpu_task` *task)
- int `starpu_sched_component_is_work_stealing` (struct `starpu_sched_component` *component)

Resource-mapping Random Component API

- int `starpu_sched_component_is_random` (struct `starpu_sched_component` *)

Resource-mapping Eager Component API

- int `starpu_sched_component_is_eager` (struct `starpu_sched_component` *)

Resource-mapping Eager-Calibration Component API

- int `starpu_sched_component_is_eager_calibration` (struct `starpu_sched_component` *)

Resource-mapping MCT Component API

- struct `starpu_sched_component` * `starpu_sched_component_mct_create` (struct `starpu_sched_tree` *tree, struct `starpu_sched_component_mct_data` *mct_data) STARPU_ATTRIBUTE_MALLOC
- int `starpu_sched_component_is_mct` (struct `starpu_sched_component` *component)

Resource-mapping Heft Component API

- struct `starpu_sched_component` * `starpu_sched_component_heft_create` (struct `starpu_sched_tree` *tree, struct `starpu_sched_component_mct_data` *mct_data) `STARPU_ATTRIBUTE_MALLOC`
- int `starpu_sched_component_is_heft` (struct `starpu_sched_component` *component)

Special-purpose Perfmodel_Select Component API

- struct `starpu_sched_component` * `starpu_sched_component_perfmodel_select_create` (struct `starpu_sched_tree` *tree, struct `starpu_sched_component_perfmodel_select_data` *perfmodel_select_data) `STARPU_ATTRIBUTE_MALLOC`
- int `starpu_sched_component_is_perfmodel_select` (struct `starpu_sched_component` *component)

Recipe Component API

- struct `starpu_sched_component_composed_recipe` * `starpu_sched_component_composed_recipe_create` (void) `STARPU_ATTRIBUTE_MALLOC`
- struct `starpu_sched_component_composed_recipe` * `starpu_sched_component_composed_recipe_create_singleton` (struct `starpu_sched_component` *(*create_component)(struct `starpu_sched_tree` *tree, void *arg), void *arg) `STARPU_ATTRIBUTE_MALLOC`
- void `starpu_sched_component_composed_recipe_add` (struct `starpu_sched_component_composed_recipe` *recipe, struct `starpu_sched_component` *(*create_component)(struct `starpu_sched_tree` *tree, void *arg), void *arg)
- void `starpu_sched_component_composed_recipe_destroy` (struct `starpu_sched_component_composed_recipe` *)
- struct `starpu_sched_component` * `starpu_sched_component_composed_component_create` (struct `starpu_sched_tree` *tree, struct `starpu_sched_component_composed_recipe` *recipe) `STARPU_ATTRIBUTE_MALLOC`
- struct `starpu_sched_tree` * `starpu_sched_component_make_scheduler` (unsigned sched_ctx_id, struct `starpu_sched_component_specs` s)
- int `starpu_sched_component_push_task` (struct `starpu_sched_component` *from, struct `starpu_sched_component` *to, struct `starpu_task` *task)
- struct `starpu_task` * `starpu_sched_component_pull_task` (struct `starpu_sched_component` *from, struct `starpu_sched_component` *to)

28.40.1 Detailed Description

28.40.2 Data Structure Documentation

28.40.2.1 struct `starpu_sched_component`

This structure represent a scheduler module. A scheduler is a tree-like structure of them, some parts of scheduler can be shared by several contexes to perform some local optimisations, so, for all components, a list of parent is defined indexed by `sched_ctx_id`. They embed there specialised method in a pseudo object-style, so calls are like `component->push_task(component,task)`

Data Fields

- struct `starpu_sched_tree` * `tree`
- struct `starpu_bitmap` * `workers`
- struct `starpu_bitmap` * `workers_in_ctx`
- void * `data`
- char * `name`
- int `nchildren`
- struct `starpu_sched_component` ** `children`
- int `nparents`
- struct `starpu_sched_component` ** `parents`
- void(* `add_child`)(struct `starpu_sched_component` *component, struct `starpu_sched_component` *child)
- void(* `remove_child`)(struct `starpu_sched_component` *component, struct `starpu_sched_component` *child)
- void(* `add_parent`)(struct `starpu_sched_component` *component, struct `starpu_sched_component` *parent)
- void(* `remove_parent`)(struct `starpu_sched_component` *component, struct `starpu_sched_component` *parent)
- int(* `push_task`)(struct `starpu_sched_component` *, struct `starpu_task` *)
- struct `starpu_task` *(`pull_task`)(struct `starpu_sched_component` *)
- int(* `can_push`)(struct `starpu_sched_component` *component)
- void(* `can_pull`)(struct `starpu_sched_component` *component)
- double(* `estimated_load`)(struct `starpu_sched_component` *component)
- double(* `estimated_end`)(struct `starpu_sched_component` *component)
- void(* `deinit_data`)(struct `starpu_sched_component` *component)
- void(* `notify_change_workers`)(struct `starpu_sched_component` *component)
- int `properties`
- hwloc_obj_t `obj`

28.40.2.1.1 Field Documentation

28.40.2.1.1.1 `tree`

```
struct starpu_sched_tree * starpu_sched_component::tree
```

The tree containing the component

28.40.2.1.1.2 `workers`

```
struct starpu_bitmap * starpu_sched_component::workers
```

this member contain the set of underlying workers

28.40.2.1.1.3 `workers_in_ctx`

```
starpu_sched_component::workers_in_ctx
```

this member contain the subset of `starpu_sched_component::workers` that is currently available in the context The push method should take this member into account. this member is set with : `component->workers UNION tree->workers UNION component->child[i]->workers_in_ctx` iff exist x such as `component->children[i]->parents[x] == component`

28.40.2.1.1.4 data

```
void * starpu_sched_component::data
```

private data

28.40.2.1.1.5 nchildren

```
int starpu_sched_component::nchildren
```

the number of components's children

28.40.2.1.1.6 children

```
struct starpu_sched_component ** starpu_sched_component::children
```

the vector of component's children

28.40.2.1.1.7 nparents

```
int starpu_sched_component::nparents
```

the numbers of component's parents

28.40.2.1.1.8 parents

```
struct starpu_sched_component ** starpu_sched_component::parents
```

the vector of component's parents

28.40.2.1.1.9 add_child

```
void(* starpu_sched_component::add_child)(struct starpu_sched_component *component, struct  
starpu_sched_component *child)
```

add a child to component

28.40.2.1.1.10 remove_child

```
void(* starpu_sched_component::remove_child)(struct starpu_sched_component *component, struct  
starpu_sched_component *child)
```

remove a child from component

28.40.2.1.1.11 add_parent

```
void(* starpu_sched_component::add_parent)(struct starpu_sched_component *component, struct  
starpu_sched_component *parent)
```

todo

28.40.2.1.1.12 remove_parent

```
void(* starpu_sched_component::remove_parent)(struct starpu_sched_component *component, struct
starpu_sched_component *parent)
```

todo

28.40.2.1.1.13 push_task

```
int(* starpu_sched_component::push_task)(struct starpu_sched_component *, struct starpu_task *)
```

push a task in the scheduler module. this function is called to push a task on component subtree, this can either perform a recursive call on a child or store the task in the component, then it will be returned by a further pull_task call. the caller must ensure that component is able to execute task. This method must either return 0 if it the task was properly stored or passed over to a child component, or return a value different from 0 if the task could not be consumed (e.g. the queue is full).

28.40.2.1.1.14 pull_task

```
struct starpu_task *(* starpu_sched_component::pull_task)(struct starpu_sched_component *)
```

pop a task from the scheduler module. this function is called by workers to get a task from their parents. this function should first return a locally stored task or perform a recursive call on the parents. the task returned by this function is executable by the caller

28.40.2.1.1.15 can_push

```
int(* starpu_sched_component::can_push)(struct starpu_sched_component *component)
```

This function is called by a component which implements a queue, allowing it to signify to its parents that an empty slot is available in its queue. The basic implementation of this function is a recursive call to its parents, the user has to specify a personally-made function to catch those calls.

28.40.2.1.1.16 can_pull

```
void(* starpu_sched_component::can_pull)(struct starpu_sched_component *component)
```

This function allow a component to wake up a worker. It is currently called by component which implements a queue, to signify to its children that a task have been pushed in its local queue, and is available to be popped by a worker, for example. The basic implementation of this function is a recursive call to its children, until at least one worker have been woken up.

28.40.2.1.1.17 estimated_load

```
double(* starpu_sched_component::estimated_load)(struct starpu_sched_component *component)
```

is an heuristic to compute load of scheduler module. Basically the number of tasks divided by the sum of relatives speedup of workers available in context. $estimated_load(component) = \sum(estimated_load(component_children)) + nb_local_tasks / average(relative_speedup(underlying_worker))$

28.40.2.1.1.18 estimated_end

```
starpu_sched_component::estimated_end
```

return the time when a worker will enter in starvation. This function is relevant only if the task->predicted member has been set.

28.40.2.1.1.19 deinit_data

```
void(* starpu_sched_component::deinit_data)(struct starpu_sched_component *component)
```

called by starpu_sched_component_destroy. Should free data allocated during creation

28.40.2.1.1.20 notify_change_workers

```
void(* starpu_sched_component::notify_change_workers)(struct starpu_sched_component *component)
```

this function is called for each component when workers are added or removed from a context

28.40.2.1.1.21 properties

```
int starpu_sched_component::properties
```

todo

28.40.2.1.1.22 obj

```
hwloc_obj_t starpu_sched_component::obj
```

the hwloc object associated to scheduler module. points to the part of topology that is binded to this component, eg: a numa node for a ws component that would balance load between underlying sockets

28.40.2.2 struct starpu_sched_tree

The actual scheduler

Data Fields

struct starpu_sched_component *	root	this is the entry module of the scheduler
struct starpu_bitmap *	workers	this is the set of workers available in this context, this value is used to mask workers in modules
unsigned	sched_ctx_id	the context id of the scheduler
struct starpu_sched_component *	worker_components[STARPU_NMAXWORKERS]	worker components
starpu_pthread_mutex_t	lock	this lock is used to protect the scheduler, it is taken in read mode pushing a task and in write mode for adding or removing workers

28.40.2.3 struct starpu_sched_component_fifo_data**Data Fields**

unsigned	ntasks_threshold	todo
double	exp_len_threshold	todo

28.40.2.4 struct starpu_sched_component_prio_data

Data Fields

unsigned	ntasks_threshold	todo
double	exp_len_threshold	todo

28.40.2.5 struct starpu_sched_component_mct_data

Data Fields

double	alpha	todo
double	beta	todo
double	_gamma	todo
double	idle_power	todo

28.40.2.6 struct starpu_sched_component_perfmodel_select_data

Data Fields

struct starpu_sched_component *	calibrator_component	todo
struct starpu_sched_component *	no_perfmodel_component	todo
struct starpu_sched_component *	perfmodel_component	todo

28.40.2.7 struct starpu_sched_component_composed_recipe

parameters for starpu_sched_component_composed_component_create

28.40.2.8 struct starpu_sched_component_specs

Define how build a scheduler according to topology. Each level (except for hwloc_machine_composed_sched_↔ component) can be NULL, then the level is just skipped. Bugs everywhere, do not rely on.

Data Fields

- struct [starpu_sched_component_composed_recipe](#) * **hwloc_machine_composed_sched_component**
- struct [starpu_sched_component_composed_recipe](#) * **hwloc_component_composed_sched_component**
- struct [starpu_sched_component_composed_recipe](#) * **hwloc_socket_composed_sched_component**
- struct [starpu_sched_component_composed_recipe](#) * **hwloc_cache_composed_sched_component**
- struct [starpu_sched_component_composed_recipe](#) * (* **worker_composed_sched_component**)(enum [starpu_worker_archtype](#) archtype)
- int **mix_heterogeneous_workers**

28.40.3 Macro Definition Documentation

28.40.3.1 STARPU_SCHED_COMPONENT_IS_HOMOGENEOUS

```
#define STARPU_SCHED_COMPONENT_IS_HOMOGENEOUS (
    component )
```

indicate if component is homogeneous

28.40.3.2 STARPU_SCHED_COMPONENT_IS_SINGLE_MEMORY_NODE

```
#define STARPU_SCHED_COMPONENT_IS_SINGLE_MEMORY_NODE (
    component )
```

indicate if all workers have the same memory component

28.40.4 Enumeration Type Documentation

28.40.4.1 starpu_sched_component_properties

```
enum starpu_sched_component_properties
```

flags for [starpu_sched_component::properties](#)

Enumerator

STARPU_SCHED_COMPONENT_HOMOGENEOUS	indicate that all workers have the same starpu_worker_archtype
STARPU_SCHED_COMPONENT_SINGLE_MEMORY_NODE	indicate that all workers have the same memory component

28.40.5 Function Documentation

28.40.5.1 starpu_sched_tree_create()

```
struct starpu_sched_tree * starpu_sched_tree_create (
    unsigned sched_ctx_id )
```

create a empty initialized [starpu_sched_tree](#)

28.40.5.2 starpu_sched_tree_destroy()

```
void starpu_sched_tree_destroy (
    struct starpu_sched_tree * tree )
```

destroy tree and free all non shared component in it.

28.40.5.3 `starpu_sched_tree_update_workers()`

```
void starpu_sched_tree_update_workers (
    struct starpu\_sched\_tree * t )
```

recursively set all [starpu_sched_component::workers](#), do not take into account shared parts (except workers).

28.40.5.4 `starpu_sched_tree_update_workers_in_ctx()`

```
void starpu_sched_tree_update_workers_in_ctx (
    struct starpu\_sched\_tree * t )
```

recursively set all [starpu_sched_component::workers_in_ctx](#), do not take into account shared parts (except workers)

28.40.5.5 `starpu_sched_tree_push_task()`

```
int starpu_sched_tree_push_task (
    struct starpu\_task * task )
```

compatibility with [starpu_sched_policy](#) interface

28.40.5.6 `starpu_sched_tree_pop_task()`

```
struct starpu\_task * starpu_sched_tree_pop_task (
    unsigned sched_ctx )
```

compatibility with [starpu_sched_policy](#) interface

28.40.5.7 `starpu_sched_tree_add_workers()`

```
void starpu_sched_tree_add_workers (
    unsigned sched_ctx_id,
    int * workerids,
    unsigned nworkers )
```

compatibility with [starpu_sched_policy](#) interface

28.40.5.8 `starpu_sched_tree_remove_workers()`

```
void starpu_sched_tree_remove_workers (
    unsigned sched_ctx_id,
    int * workerids,
    unsigned nworkers )
```

compatibility with [starpu_sched_policy](#) interface

28.40.5.9 starpu_sched_component_connect()

```
void starpu_sched_component_connect (
    struct starpu_sched_component * parent,
    struct starpu_sched_component * child )
```

Attaches component `child` to parent `parent`. Some component may accept only one child, others accept several (e.g. MCT)

28.40.5.10 starpu_sched_component_create()

```
struct starpu_sched_component * starpu_sched_component_create (
    struct starpu_sched_tree * tree,
    const char * name )
```

allocate and initialize component field with defaults values : `.pop_task` make recursive call on father `.estimated_load` compute relative speedup and tasks in sub tree `.estimated_end` return the average of recursive call on children `.add_child` is `starpu_sched_component_add_child` `.remove_child` is `starpu_sched_component_remove_child` `.notify_change_workers` does nothing `.deinit_data` does nothing

28.40.5.11 starpu_sched_component_destroy()

```
void starpu_sched_component_destroy (
    struct starpu_sched_component * component )
```

free data allocated by `starpu_sched_component_create` and call `component->deinit_data(component)` set to null the member `starpu_sched_component::fathers[sched_ctx_id]` of all child if its equal to `component`

28.40.5.12 starpu_sched_component_destroy_rec()

```
void starpu_sched_component_destroy_rec (
    struct starpu_sched_component * component )
```

recursively destroy non shared parts of a component 's tree

28.40.5.13 starpu_sched_component_can_execute_task()

```
int starpu_sched_component_can_execute_task (
    struct starpu_sched_component * component,
    struct starpu_task * task )
```

return true iff component can execute task, this function take into account the workers available in the scheduling context

28.40.5.14 starpu_sched_component_execute_preds()

```
int starpu_sched_component_execute_preds (
    struct starpu_sched_component * component,
    struct starpu_task * task,
    double * length )
```

return a non null value if `component` can execute `task`. write the execution prediction length for the best implementation of the best worker available and write this at `length` address. this result is more relevant if `starpu_sched_component::is_homogeneous` is non null. if a worker need to be calibrated for an implementation, nan is set to `length`.

28.40.5.15 starpu_sched_component_transfer_length()

```
double starpu_sched_component_transfer_length (
    struct starpu_sched_component * component,
    struct starpu_task * task )
```

return the average time to transfer `task` data to underlying `component` workers.

28.40.5.16 starpu_sched_component_worker_get()

```
struct starpu_sched_component * starpu_sched_component_worker_get (
    unsigned sched_ctx,
    int workerid )
```

return the struct `starpu_sched_component` corresponding to `workerid`. Undefined if `workerid` is not a valid `workerid`

28.40.5.17 starpu_sched_component_worker_get_workerid()

```
int starpu_sched_component_worker_get_workerid (
    struct starpu_sched_component * worker_component )
```

return the `workerid` of `worker_component`, undefined if `starpu_sched_component_is_worker(worker_component) == 0`

28.40.5.18 starpu_sched_component_is_worker()

```
int starpu_sched_component_is_worker (
    struct starpu_sched_component * component )
```

return true iff `component` is a worker component

28.40.5.19 starpu_sched_component_is_simple_worker()

```
int starpu_sched_component_is_simple_worker (
    struct starpu_sched_component * component )
```

return true iff `component` is a simple worker component

28.40.5.20 `starpu_sched_component_is_combined_worker()`

```
int starpu_sched_component_is_combined_worker (
    struct starpu\_sched\_component * component )
```

return true iff component is a combined worker component

28.40.5.21 `starpu_sched_component_worker_pre_exec_hook()`

```
void starpu_sched_component_worker_pre_exec_hook (
    struct starpu\_task * task )
```

compatibility with [starpu_sched_policy](#) interface update predictions for workers

28.40.5.22 `starpu_sched_component_worker_post_exec_hook()`

```
void starpu_sched_component_worker_post_exec_hook (
    struct starpu\_task * task )
```

compatibility with [starpu_sched_policy](#) interface

28.40.5.23 `starpu_sched_component_estimated_load()`

```
double starpu_sched_component_estimated_load (
    struct starpu\_sched\_component * component )
```

default function for the `estimated_load` component method, just sums up the loads of the children of the component.

28.40.5.24 `starpu_sched_component_estimated_end_min()`

```
double starpu_sched_component_estimated_end_min (
    struct starpu\_sched\_component * component )
```

function that can be used for the `estimated_end` component method, which just computes the minimum completion time of the children.

28.40.5.25 `starpu_sched_component_estimated_end_average()`

```
double starpu_sched_component_estimated_end_average (
    struct starpu\_sched\_component * component )
```

default function for the `estimated_end` component method, which just computes the average completion time of the children.

28.40.5.26 starpu_sched_component_fifo_create()

```
struct starpu_sched_component * starpu_sched_component_fifo_create (
    struct starpu_sched_tree * tree,
    struct starpu_sched_component_fifo_data * fifo_data )
```

Return a struct `starpu_sched_component` with a fifo. A stable sort is performed according to tasks priorities. A `push_task` call on this component does not perform recursive calls, underlying components will have to call `pop_task` to get it. `starpu_sched_component::estimated_end` function compute the estimated length by dividing the sequential length by the number of underlying workers. Do not take into account tasks that are currently executed.

28.40.5.27 starpu_sched_component_is_fifo()

```
int starpu_sched_component_is_fifo (
    struct starpu_sched_component * component )
```

return true iff component is a fifo component

28.40.5.28 starpu_sched_component_prio_create()

```
struct starpu_sched_component * starpu_sched_component_prio_create (
    struct starpu_sched_tree * tree,
    struct starpu_sched_component_prio_data * prio_data )
```

todo

28.40.5.29 starpu_sched_component_is_prio()

```
int starpu_sched_component_is_prio (
    struct starpu_sched_component * component )
```

todo

28.40.5.30 starpu_sched_tree_work_stealing_push_task()

```
int starpu_sched_tree_work_stealing_push_task (
    struct starpu_task * task )
```

undefined if there is no work stealing component in the scheduler. If any, `task` is pushed in a default way if the caller is the application, and in the caller's fifo if its a worker.

28.40.5.31 starpu_sched_component_is_work_stealing()

```
int starpu_sched_component_is_work_stealing (
    struct starpu_sched_component * component )
```

return true iff component is a work stealing component

28.40.5.32 starpu_sched_component_is_random()

```
int starpu_sched_component_is_random (
    struct starpu_sched_component * )
```

return true iff component is a random component

28.40.5.33 starpu_sched_component_is_eager()

```
int starpu_sched_component_is_eager (
    struct starpu_sched_component * )
```

todo

28.40.5.34 starpu_sched_component_is_eager_calibration()

```
int starpu_sched_component_is_eager_calibration (
    struct starpu_sched_component * )
```

todo

28.40.5.35 starpu_sched_component_mct_create()

```
struct starpu_sched_component * starpu_sched_component_mct_create (
    struct starpu_sched_tree * tree,
    struct starpu_sched_component_mct_data * mct_data )
```

create a component with mct_data parameters. the mct component doesn't do anything but pushing tasks on no↔
_perf_model_component and calibrating_component

28.40.5.36 starpu_sched_component_is_mct()

```
int starpu_sched_component_is_mct (
    struct starpu_sched_component * component )
```

todo

28.40.5.37 starpu_sched_component_heft_create()

```
struct starpu_sched_component * starpu_sched_component_heft_create (
    struct starpu_sched_tree * tree,
    struct starpu_sched_component_mct_data * mct_data )
```

this component perform a heft scheduling

28.40.5.38 starpu_sched_component_is_heft()

```
int starpu_sched_component_is_heft (
    struct starpu_sched_component * component )
```

return true iff component is a heft component

28.40.5.39 starpu_sched_component_perfmodel_select_create()

```
struct starpu_sched_component * starpu_sched_component_perfmodel_select_create (
    struct starpu_sched_tree * tree,
    struct starpu_sched_component_perfmodel_select_data * perfmodel_select_data )
```

todo

28.40.5.40 starpu_sched_component_is_perfmodel_select()

```
int starpu_sched_component_is_perfmodel_select (
    struct starpu_sched_component * component )
```

todo

28.40.5.41 starpu_sched_component_composed_recipe_create()

```
struct starpu_sched_component_composed_recipe * starpu_sched_component_composed_recipe_create
(
    void )
```

return an empty recipe for a composed component, it should not be used without modification

28.40.5.42 starpu_sched_component_composed_recipe_create_singleton()

```
struct starpu_sched_component_composed_recipe * starpu_sched_component_composed_recipe_create↵
_singleton (
    struct starpu_sched_component *(*)(struct starpu_sched_tree *tree, void *arg)
    create_component,
    void * arg )
```

return a recipe to build a composed component with a create_component

28.40.5.43 starpu_sched_component_composed_recipe_add()

```
void starpu_sched_component_composed_recipe_add (
    struct starpu_sched_component_composed_recipe * recipe,
    struct starpu_sched_component *(*)(struct starpu_sched_tree *tree, void *arg)
    create_component,
    void * arg )
```

add create_component under all previous components in recipe

28.40.5.44 starpu_sched_component_composed_recipe_destroy()

```
void starpu_sched_component_composed_recipe_destroy (
    struct starpu_sched_component_composed_recipe * )
```

destroy composed_sched_component, this should be done after starpu_sched_component_composed_recipe_create was called

28.40.5.45 starpu_sched_component_composed_component_create()

```
struct starpu_sched_component * starpu_sched_component_composed_component_create (
    struct starpu_sched_tree * tree,
    struct starpu_sched_component_composed_recipe * recipe )
```

create a component that behave as all component of recipe where linked. Except that you cant use starpu_sched_component_is_foo function if recipe contain a single create_foo arg_foo pair, create_foo(arg_foo) is returned instead of a composed component

28.40.5.46 starpu_sched_component_make_scheduler()

```
struct starpu_sched_tree * starpu_sched_component_make_scheduler (
    unsigned sched_ctx_id,
    struct starpu_sched_component_specs s )
```

this function build a scheduler for sched_ctx_id according to s and the hwloc topology of the machine.

28.40.5.47 starpu_sched_component_push_task()

```
int starpu_sched_component_push_task (
    struct starpu_sched_component * from,
    struct starpu_sched_component * to,
    struct starpu_task * task )
```

Push a task to a component. This is a helper for component->push_task(component, task) plus tracing.

28.40.5.48 starpu_sched_component_pull_task()

```
struct starpu_task * starpu_sched_component_pull_task (
    struct starpu_sched_component * from,
    struct starpu_sched_component * to )
```

Pull a task from a component. This is a helper for component->pull_task(component) plus tracing.

Chapter 29

File Index

29.1 File List

Here is a list of all documented files with brief descriptions:

sc_hypervisor.h	523
sc_hypervisor_config.h	524
sc_hypervisor_lp.h	525
sc_hypervisor_monitoring.h	525
sc_hypervisor_policy.h	526
starpu.h	481
starpu_bitmap.h	482
starpu_bound.h	482
starpu_config.h	483
starpu_cublas.h	485
starpu_cuda.h	485
starpu_data.h	485
starpu_data_filters.h	487
starpu_data_interfaces.h	489
starpu_deprecated_api.h	494
starpu_disk.h	494
starpu_driver.h	494
starpu_expert.h	495
starpu_fxt.h	495
starpu_hash.h	496
starpu_mic.h	496
starpu_mod.f90	??
starpu_mpi.h	519
starpu_opencl.h	496
starpu_openmp.h	498
starpu_perfmodel.h	500
starpu_profiling.h	502
starpu_rand.h	503
starpu_scc.h	503
starpu_sched_component.h	??
starpu_sched_ctx.h	503
starpu_sched_ctx_hypervisor.h	505
starpu_scheduler.h	505
starpu_simgrid_wrap.h	??
starpu_sink.h	506

starpu_stdlib.h	507
starpu_task.h	507
starpu_task_bundle.h	510
starpu_task_list.h	510
starpu_task_util.h	511
starpu_thread.h	512
starpu_thread_util.h	514
starpu_top.h	515
starpu_tree.h	516
starpu_util.h	517
starpu_worker.h	518
starpufft.h	522

Chapter 30

File Documentation

30.1 starpu.h File Reference

```
#include <stdlib.h>
#include <stdint.h>
#include <starpu_config.h>
#include <starpu_opengl.h>
#include <starpu_thread.h>
#include <starpu_thread_util.h>
#include <starpu_util.h>
#include <starpu_data.h>
#include <starpu_disk.h>
#include <starpu_data_interfaces.h>
#include <starpu_data_filters.h>
#include <starpu_stdlib.h>
#include <starpu_perfmodel.h>
#include <starpu_worker.h>
#include <starpu_task.h>
#include <starpu_task_list.h>
#include <starpu_task_util.h>
#include <starpu_sched_ctx.h>
#include <starpu_expert.h>
#include <starpu_rand.h>
#include <starpu_cuda.h>
#include <starpu_cublas.h>
#include <starpu_cusparse.h>
#include <starpu_bound.h>
#include <starpu_hash.h>
#include <starpu_profiling.h>
#include <starpu_top.h>
#include <starpu_fxt.h>
#include <starpu_driver.h>
#include <starpu_tree.h>
#include <starpu_openmp.h>
#include <starpu_simgrid_wrap.h>
#include <starpu_bitmap.h>
#include "starpu_deprecated_api.h"
```

Data Structures

- struct [starpu_conf](#)

Functions

- int [starpu_conf_init](#) (struct [starpu_conf](#) *conf)
- int [starpu_init](#) (struct [starpu_conf](#) *conf) [STARPU_WARN_UNUSED_RESULT](#)
- int [starpu_initialize](#) (struct [starpu_conf](#) *user_conf, int *argc, char ***argv)
- void [starpu_pause](#) (void)
- void [starpu_resume](#) (void)
- void [starpu_shutdown](#) (void)
- void [starpu_topology_print](#) (FILE *f)
- int [starpu_asynchronous_copy_disabled](#) (void)
- int [starpu_asynchronous_cuda_copy_disabled](#) (void)
- int [starpu_asynchronous_opencl_copy_disabled](#) (void)
- int [starpu_asynchronous_mic_copy_disabled](#) (void)
- void [starpu_display_stats](#) ()
- void [starpu_get_version](#) (int *major, int *minor, int *release)

30.2 starpu_bitmap.h File Reference

Functions

- struct [starpu_bitmap](#) * [starpu_bitmap_create](#) (void) [STARPU_ATTRIBUTE_MALLOC](#)
- void [starpu_bitmap_destroy](#) (struct [starpu_bitmap](#) *b)
- void [starpu_bitmap_set](#) (struct [starpu_bitmap](#) *b, int e)
- void [starpu_bitmap_unset](#) (struct [starpu_bitmap](#) *b, int e)
- void [starpu_bitmap_unset_all](#) (struct [starpu_bitmap](#) *b)
- int [starpu_bitmap_get](#) (struct [starpu_bitmap](#) *b, int e)
- void [starpu_bitmap_unset_and](#) (struct [starpu_bitmap](#) *a, struct [starpu_bitmap](#) *b, struct [starpu_bitmap](#) *c)
- void [starpu_bitmap_or](#) (struct [starpu_bitmap](#) *a, struct [starpu_bitmap](#) *b)
- int [starpu_bitmap_and_get](#) (struct [starpu_bitmap](#) *b1, struct [starpu_bitmap](#) *b2, int e)
- int [starpu_bitmap_cardinal](#) (struct [starpu_bitmap](#) *b)
- int [starpu_bitmap_first](#) (struct [starpu_bitmap](#) *b)
- int [starpu_bitmap_last](#) (struct [starpu_bitmap](#) *b)
- int [starpu_bitmap_next](#) (struct [starpu_bitmap](#) *b, int e)
- int [starpu_bitmap_has_next](#) (struct [starpu_bitmap](#) *b, int e)

30.3 starpu_bound.h File Reference

```
#include <stdio.h>
```

Functions

- void [starpu_bound_start](#) (int deps, int prio)
- void [starpu_bound_stop](#) (void)
- void [starpu_bound_print_dot](#) (FILE *output)
- void [starpu_bound_compute](#) (double *res, double *integer_res, int integer)
- void [starpu_bound_print_lp](#) (FILE *output)
- void [starpu_bound_print_mps](#) (FILE *output)
- void [starpu_bound_print](#) (FILE *output, int integer)

30.4 starpu_config.h File Reference

```
#include <sys/types.h>
```

Macros

- #define [STARPU_MAJOR_VERSION](#)
- #define [STARPU_MINOR_VERSION](#)
- #define [STARPU_RELEASE_VERSION](#)
- #define **STARPU_USE_CPU**
- #define [STARPU_USE_CUDA](#)
- #define [STARPU_USE_OPENCL](#)
- #define [STARPU_USE_MIC](#)
- #define [STARPU_USE_SCC](#)
- #define **STARPU_SIMGRID**
- #define **STARPU_SIMGRID_HAVE_XBT_BARRIER_INIT**
- #define **STARPU_HAVE_SIMGRID_MSG_H**
- #define **STARPU_HAVE_XBT_SYNCHRO_H**
- #define **STARPU_HAVE_VALGRIND_H**
- #define **STARPU_HAVE_MEMCHECK_H**
- #define **STARPU_VALGRIND_FULL**
- #define **STARPU_SANITIZE_LEAK**
- #define **STARPU_NON_BLOCKING_DRIVERS**
- #define **STARPU_HAVE_ICC**
- #define **STARPU_ATLAS**
- #define **STARPU_GOTO**
- #define **STARPU_OPENBLAS**
- #define **STARPU_MKL**
- #define **STARPU_SYSTEM_BLAS**
- #define **STARPU_BUILD_DIR**
- #define [STARPU_OPENCL_DATADIR](#)
- #define **STARPU_HAVE_MAGMA**
- #define **STARPU_OPENGL_RENDER**
- #define **STARPU_USE_GTK**
- #define **STARPU_HAVE_X11**
- #define **STARPU_HAVE_POSIX_MEMALIGN**
- #define **STARPU_HAVE_MEMALIGN**
- #define **STARPU_HAVE_MALLOC_H**
- #define **STARPU_HAVE_SYNC_BOOL_COMPARE_AND_SWAP**
- #define **STARPU_HAVE_SYNC_VAL_COMPARE_AND_SWAP**
- #define **STARPU_HAVE_SYNC_FETCH_AND_ADD**
- #define **STARPU_HAVE_SYNC_FETCH_AND_OR**
- #define **STARPU_HAVE_SYNC_LOCK_TEST_AND_SET**
- #define **STARPU_HAVE_SYNC_SYNCHRONIZE**
- #define **STARPU_DEVEL**
- #define **STARPU_MODEL_DEBUG**
- #define **STARPU_NO_ASSERT**
- #define **STARPU_DEBUG**
- #define **STARPU_VERBOSE**
- #define **STARPU_GDB_PATH**
- #define **STARPU_HAVE_FFTW**
- #define **STARPU_HAVE_FFTWF**

- #define **STARPU_HAVE_FFTWL**
- #define **STARPU_HAVE_CUFFTDOUBLECOMPLEX**
- #define **STARPU_HAVE_CURAND**
- #define [STARPU_MAXNODES](#)
- #define [STARPU_NMAXBUFS](#)
- #define [STARPU_MAXCPUS](#)
- #define [STARPU_MAXCUDADEVs](#)
- #define [STARPU_MAXOPENCLDEVs](#)
- #define [STARPU_MAXMICDEVs](#)
- #define [STARPU_MAXSCCDEVs](#)
- #define [STARPU_NMAXWORKERS](#)
- #define [STARPU_MAXIMPLEMENTATIONS](#)
- #define **STARPU_MAXMPKERNELS**
- #define **STARPU_USE_SC_HYPERVISOR**
- #define **STARPU_SC_HYPERVISOR_DEBUG**
- #define **STARPU_HAVE_GLPK_H**
- #define **STARPU_HAVE_CUDA_MEMCPY_PEER**
- #define **STARPU_HAVE_LIBNUMA**
- #define **STARPU_HAVE_WINDOWS**
- #define **STARPU_LINUX_SYS**
- #define **STARPU_HAVE_SETENV**
- #define **STARPU_HAVE_UNSETENV**
- #define **STARPU_HAVE_UNISTD_H**
- #define **STARPU_USE_FXT**
- #define **STARPU_FXT_LOCK_TRACES**
- #define **__starpus_func__**
- #define **__starpus_inline**
- #define **STARPU_QUICK_CHECK**
- #define **STARPU_LONG_CHECK**
- #define **STARPU_USE_DRAND48**
- #define **STARPU_USE_ERAND48_R**
- #define **STARPU_HAVE_NEARBYINTF**
- #define **STARPU_HAVE_RINTF**
- #define **STARPU_USE_TOP**
- #define **STARPU_HAVE_HWLOC**
- #define **STARPU_HAVE_PTHREAD_SPIN_LOCK**
- #define **STARPU_HAVE_PTHREAD_BARRIER**
- #define **STARPU_HAVE_PTHREAD_SETNAME_NP**
- #define **STARPU_HAVE_STRUCT_TIMESPEC**
- #define **STARPU_HAVE_HELGRIND_H**
- #define **HAVE_MPI_COMM_F2C**
- #define **STARPU_HAVE_DARWIN**
- #define **STARPU_HAVE_STRERROR_R**
- #define **STARPU_HAVE_STATEMENT_EXPRESSIONS**
- #define **STARPU_PERF_MODEL_DIR**

Initialisation

- #define [STARPU_OPENMP](#)

Initialisation

- #define [STARPU_USE_MPI](#)

Scheduling Contexts Basic API

- #define [STARPU_NMAX_SCHED_CTXS](#)

Typedefs

- typedef `ssize_t` `starpu_ssize_t`

30.5 starpu_cublas.h File Reference

Functions

- void `starpu_cublas_init` (void)
- void `starpu_cublas_shutdown` (void)

30.6 starpu_cuda.h File Reference

```
#include <starpu_config.h>
#include <cuda.h>
#include <cuda_runtime.h>
#include <cuda_runtime_api.h>
```

Macros

- #define `STARPU_CUBLAS_REPORT_ERROR`(status)
- #define `STARPU_CUDA_REPORT_ERROR`(status)

Functions

- void `starpu_cublas_report_error` (const char *func, const char *file, int line, int status)
- void `starpu_cuda_report_error` (const char *func, const char *file, int line, cudaError_t status)
- `cudaStream_t` `starpu_cuda_get_local_stream` (void)
- const struct `cudaDeviceProp` * `starpu_cuda_get_device_properties` (unsigned workerid)
- int `starpu_cuda_copy_async_sync` (void *src_ptr, unsigned src_node, void *dst_ptr, unsigned dst_node, size_t ssize, `cudaStream_t` stream, enum `cudaMemcpyKind` kind)
- void `starpu_cuda_set_device` (unsigned devid)

30.7 starpu_data.h File Reference

```
#include <starpu.h>
```

Data Structures

- struct `starpu_data_descr`

Macros

- `#define starpu_data_malloc_pinned_if_possible`
- `#define starpu_data_free_pinned_if_possible`
- `#define STARPU_MAIN_RAM`

Typedefs

- `typedef struct _starpu_data_state * starpu_data_handle_t`
- `typedef struct starpu_arbiter * starpu_arbiter_t`

Enumerations

- `enum starpu_data_access_mode {`
`STARPU_NONE, STARPU_R, STARPU_W, STARPU_RW,`
`STARPU_SCRATCH, STARPU_REDUX, STARPU_COMMUTE, STARPU_SSEND,`
`STARPU_LOCALITY, STARPU_ACCESS_MODE_MAX }`
- `enum starpu_node_kind {`
`STARPU_UNUSED, STARPU_CPU_RAM, STARPU_CUDA_RAM, STARPU_OPENCL_RAM,`
`STARPU_DISK_RAM, STARPU_MIC_RAM, STARPU_SCC_RAM, STARPU_SCC_SHM }`

Functions

- `void starpu_data_display_memory_stats ()`
- `unsigned starpu_worker_get_memory_node (unsigned workerid)`
- `unsigned starpu_memory_nodes_get_count (void)`
- `enum starpu_node_kind starpu_node_get_kind (unsigned node)`
- `void starpu_data_set_sequential_consistency_flag (starpu_data_handle_t handle, unsigned flag)`
- `unsigned starpu_data_get_sequential_consistency_flag (starpu_data_handle_t handle)`
- `unsigned starpu_data_get_default_sequential_consistency_flag (void)`
- `void starpu_data_set_default_sequential_consistency_flag (unsigned flag)`
- `unsigned starpu_data_test_if_allocated_on_node (starpu_data_handle_t handle, unsigned memory_node)`
- `void starpu_memchunk_tidy (unsigned memory_node)`

Basic Data Management API

Data management is done at a high-level in StarPU: rather than accessing a mere list of contiguous buffers, the tasks may manipulate data that are described by a high-level construct which we call data interface.

An example of data interface is the "vector" interface which describes a contiguous data array on a specific memory node. This interface is a simple structure containing the number of elements in the array, the size of the elements, and the address of the array in the appropriate address space (this address may be invalid if there is no valid copy of the array in the memory node). More informations on the data interfaces provided by StarPU are given in [Data Interfaces](#).

When a piece of data managed by StarPU is used by a task, the task implementation is given a pointer to an interface describing a valid copy of the data that is accessible from the current processing unit.

Every worker is associated to a memory node which is a logical abstraction of the address space from which the processing unit gets its data. For instance, the memory node associated to the different CPU workers represents main memory (RAM), the memory node associated to a GPU is DRAM embedded on the device. Every memory node is identified by a logical index which is accessible from the function `starpu_worker_get_memory_node()`. When registering a piece of data to StarPU, the specified memory node indicates where the piece of data initially resides (we also call this memory node the home node of a piece of data).

- void [starpu_data_set_name](#) ([starpu_data_handle_t](#) handle, const char *name)
- void [starpu_data_set_coordinates_array](#) ([starpu_data_handle_t](#) handle, int dimensions, int dims[])
- void [starpu_data_set_coordinates](#) ([starpu_data_handle_t](#) handle, unsigned dimensions,...)
- void [starpu_data_unregister](#) ([starpu_data_handle_t](#) handle)
- void [starpu_data_unregister_no_coherency](#) ([starpu_data_handle_t](#) handle)
- void [starpu_data_unregister_submit](#) ([starpu_data_handle_t](#) handle)
- void [starpu_data_invalidate](#) ([starpu_data_handle_t](#) handle)
- void [starpu_data_invalidate_submit](#) ([starpu_data_handle_t](#) handle)
- void [starpu_data_advise_as_important](#) ([starpu_data_handle_t](#) handle, unsigned is_important)
- int [starpu_data_request_allocation](#) ([starpu_data_handle_t](#) handle, unsigned node)
- int [starpu_data_fetch_on_node](#) ([starpu_data_handle_t](#) handle, unsigned node, unsigned async)
- int [starpu_data_prefetch_on_node](#) ([starpu_data_handle_t](#) handle, unsigned node, unsigned async)
- int [starpu_data_idle_prefetch_on_node](#) ([starpu_data_handle_t](#) handle, unsigned node, unsigned async)
- void [starpu_data_wont_use](#) ([starpu_data_handle_t](#) handle)
- void [starpu_data_set_wt_mask](#) ([starpu_data_handle_t](#) handle, uint32_t wt_mask)
- void [starpu_data_query_status](#) ([starpu_data_handle_t](#) handle, int memory_node, int *is_allocated, int *is_valid, int *is_requested)
- void [starpu_data_set_reduction_methods](#) ([starpu_data_handle_t](#) handle, struct [starpu_codelet](#) *redu_xl, struct [starpu_codelet](#) *init_cl)
- struct [starpu_data_interface_ops](#) * [starpu_data_get_interface_ops](#) ([starpu_data_handle_t](#) handle)
- void [starpu_data_set_user_data](#) ([starpu_data_handle_t](#) handle, void *user_data)
- void * [starpu_data_get_user_data](#) ([starpu_data_handle_t](#) handle)

Access registered data from the application

- #define [STARPU_ACQUIRE_NO_NODE](#)
- #define [STARPU_ACQUIRE_ALL_NODES](#)
- #define [STARPU_DATA_ACQUIRE_CB](#)(handle, mode, code)
- int [starpu_data_acquire](#) ([starpu_data_handle_t](#) handle, enum [starpu_data_access_mode](#) mode)
- int [starpu_data_acquire_on_node](#) ([starpu_data_handle_t](#) handle, int node, enum [starpu_data_access_mode](#) mode)
- int [starpu_data_acquire_cb](#) ([starpu_data_handle_t](#) handle, enum [starpu_data_access_mode](#) mode, void(*callback)(void *), void *arg)
- int [starpu_data_acquire_on_node_cb](#) ([starpu_data_handle_t](#) handle, int node, enum [starpu_data_access_↵_mode](#) mode, void(*callback)(void *), void *arg)
- int [starpu_data_acquire_cb_sequential_consistency](#) ([starpu_data_handle_t](#) handle, enum [starpu_data_↵_access_mode](#) mode, void(*callback)(void *), void *arg, int sequential_consistency)
- int [starpu_data_acquire_on_node_cb_sequential_consistency](#) ([starpu_data_handle_t](#) handle, int node, enum [starpu_data_access_mode](#) mode, void(*callback)(void *), void *arg, int sequential_consistency)
- int [starpu_data_acquire_on_node_cb_sequential_consistency_sync_jobids](#) ([starpu_data_handle_t](#) handle, int node, enum [starpu_data_access_mode](#) mode, void(*callback)(void *), void *arg, int sequential_↵_consistency, long *pre_sync_jobid, long *post_sync_jobid)
- int [starpu_data_acquire_try](#) ([starpu_data_handle_t](#) handle, enum [starpu_data_access_mode](#) mode)
- int [starpu_data_acquire_on_node_try](#) ([starpu_data_handle_t](#) handle, int node, enum [starpu_data_access_↵_mode](#) mode)
- void [starpu_data_release](#) ([starpu_data_handle_t](#) handle)
- void [starpu_data_release_on_node](#) ([starpu_data_handle_t](#) handle, int node)
- [starpu_arbiter_t](#) [starpu_arbiter_create](#) (void) [STARPU_ATTRIBUTE_MALLOC](#)
- void [starpu_data_assign_arbiter](#) ([starpu_data_handle_t](#) handle, [starpu_arbiter_t](#) arbiter)
- void [starpu_arbiter_destroy](#) ([starpu_arbiter_t](#) arbiter)

30.8 starpu_data_filters.h File Reference

```
#include <starpu.h>
#include <stdarg.h>
```

Data Structures

- struct [starpu_data_filter](#)

Functions

Basic API

- void [starpu_data_partition](#) ([starpu_data_handle_t](#) initial_handle, struct [starpu_data_filter](#) *f)
- void [starpu_data_unpartition](#) ([starpu_data_handle_t](#) root_data, unsigned gathering_node)
- int [starpu_data_get_nb_children](#) ([starpu_data_handle_t](#) handle)
- [starpu_data_handle_t](#) [starpu_data_get_child](#) ([starpu_data_handle_t](#) handle, unsigned i)
- [starpu_data_handle_t](#) [starpu_data_get_sub_data](#) ([starpu_data_handle_t](#) root_data, unsigned depth,...)
- [starpu_data_handle_t](#) [starpu_data_vget_sub_data](#) ([starpu_data_handle_t](#) root_data, unsigned depth, va_list pa)
- void [starpu_data_map_filters](#) ([starpu_data_handle_t](#) root_data, unsigned nfilters,...)
- void [starpu_data_vmap_filters](#) ([starpu_data_handle_t](#) root_data, unsigned nfilters, va_list pa)

Asynchronous API

- void [starpu_data_partition_plan](#) ([starpu_data_handle_t](#) initial_handle, struct [starpu_data_filter](#) *f, [starpu_data_handle_t](#) *children)
- void [starpu_data_partition_submit](#) ([starpu_data_handle_t](#) initial_handle, unsigned nparts, [starpu_data_handle_t](#) *children)
- void [starpu_data_partition_readonly_submit](#) ([starpu_data_handle_t](#) initial_handle, unsigned nparts, [starpu_data_handle_t](#) *children)
- void [starpu_data_partition_readwrite_upgrade_submit](#) ([starpu_data_handle_t](#) initial_handle, unsigned nparts, [starpu_data_handle_t](#) *children)
- void [starpu_data_unpartition_submit](#) ([starpu_data_handle_t](#) initial_handle, unsigned nparts, [starpu_data_handle_t](#) *children, int gathering_node)
- void [starpu_data_unpartition_readonly_submit](#) ([starpu_data_handle_t](#) initial_handle, unsigned nparts, [starpu_data_handle_t](#) *children, int gathering_node)
- void [starpu_data_partition_clean](#) ([starpu_data_handle_t](#) root_data, unsigned nparts, [starpu_data_handle_t](#) *children)

Predefined BCSR Filter Functions

This section gives a partial list of the predefined partitioning functions for BCSR data. Examples on how to use them are shown in [Partitioning Data](#). The complete list can be found in the file [starpu_data_filters.h](#).

- void [starpu_bcsr_filter_canonical_block](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_csr_filter_vertical_block](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)

Predefined Matrix Filter Functions

This section gives a partial list of the predefined partitioning functions for matrix data. Examples on how to use them are shown in [Partitioning Data](#). The complete list can be found in the file [starpu_data_filters.h](#).

- void [starpu_matrix_filter_block](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_matrix_filter_block_shadow](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_matrix_filter_vertical_block](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_matrix_filter_vertical_block_shadow](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)

Predefined Vector Filter Functions

This section gives a partial list of the predefined partitioning functions for vector data. Examples on how to use them are shown in [Partitioning Data](#). The complete list can be found in the file [starpu_data_filters.h](#).

- void [starpu_vector_filter_block](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_vector_filter_block_shadow](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_vector_filter_list_long](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_vector_filter_list](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_vector_filter_divide_in_2](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)

Predefined Block Filter Functions

This section gives a partial list of the predefined partitioning functions for block data. Examples on how to use them are shown in [Partitioning Data](#). The complete list can be found in the file [starpu_data_filters.h](#). A usage example is available in [examples/filters/shadow3d.c](#)

- void [starpu_block_filter_block](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_block_filter_block_shadow](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_block_filter_vertical_block](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_block_filter_vertical_block_shadow](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_block_filter_depth_block](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)
- void [starpu_block_filter_depth_block_shadow](#) (void *father_interface, void *child_interface, struct [starpu_data_filter](#) *f, unsigned id, unsigned nparts)

30.9 starpu_data_interfaces.h File Reference

```
#include <starpu.h>
#include <cuda_runtime.h>
```

Data Structures

- struct [starpu_data_copy_methods](#)
- struct [starpu_data_interface_ops](#)
- struct [starpu_matrix_interface](#)
- struct [starpu_coo_interface](#)
- struct [starpu_block_interface](#)
- struct [starpu_vector_interface](#)
- struct [starpu_variable_interface](#)
- struct [starpu_csr_interface](#)
- struct [starpu_bcsr_interface](#)
- struct [starpu_multiformat_data_interface_ops](#)
- struct [starpu_multiformat_interface](#)

Macros

- `#define STARPU_MULTIFORMAT_GET_CPU_PTR(interface)`
- `#define STARPU_MULTIFORMAT_GET_CUDA_PTR(interface)`
- `#define STARPU_MULTIFORMAT_GET_OPENCL_PTR(interface)`
- `#define STARPU_MULTIFORMAT_GET_MIC_PTR(interface)`
- `#define STARPU_MULTIFORMAT_GET_NX(interface)`

Accessing COO Data Interfaces

- `#define STARPU_COO_GET_COLUMNS(interface)`
- `#define STARPU_COO_GET_COLUMNS_DEV_HANDLE(interface)`
- `#define STARPU_COO_GET_ROWS(interface)`
- `#define STARPU_COO_GET_ROWS_DEV_HANDLE(interface)`
- `#define STARPU_COO_GET_VALUES(interface)`
- `#define STARPU_COO_GET_VALUES_DEV_HANDLE(interface)`
- `#define STARPU_COO_GET_OFFSET`
- `#define STARPU_COO_GET_NX(interface)`
- `#define STARPU_COO_GET_NY(interface)`
- `#define STARPU_COO_GET_NVALUES(interface)`
- `#define STARPU_COO_GET_ELEMSIZE(interface)`

Typedefs

- `typedef cudaStream_t starpu_cudaStream_t`

Enumerations

- `enum starpu_data_interface_id {`
`STARPU_UNKNOWN_INTERFACE_ID, STARPU_MATRIX_INTERFACE_ID, STARPU_BLOCK_INTER-`
`FACE_ID, STARPU_VECTOR_INTERFACE_ID,`
`STARPU_CSR_INTERFACE_ID, STARPU_BCSR_INTERFACE_ID, STARPU_VARIABLE_INTERFACE-`
`_ID, STARPU_VOID_INTERFACE_ID,`
`STARPU_MULTIFORMAT_INTERFACE_ID, STARPU_COO_INTERFACE_ID, STARPU_MAX_INTERF-`
`ACE_ID }`

Functions

- `void starpu_multiformat_data_register (starpu_data_handle_t *handle, int home_node, void *ptr, uint32_t nobjects, struct starpu_multiformat_data_interface_ops *format_ops)`

Defining Interface

Applications can provide their own interface as shown in [Defining A New Data Interface](#).

- `int starpu_interface_copy (uintptr_t src, size_t src_offset, unsigned src_node, uintptr_t dst, size_t dst_offset, unsigned dst_node, size_t size, void *async_data)`
- `uintptr_t starpu_malloc_on_node_flags (unsigned dst_node, size_t size, int flags)`
- `uintptr_t starpu_malloc_on_node (unsigned dst_node, size_t size)`
- `void starpu_free_on_node_flags (unsigned dst_node, uintptr_t addr, size_t size, int flags)`
- `void starpu_free_on_node (unsigned dst_node, uintptr_t addr, size_t size)`
- `void starpu_malloc_on_node_set_default_flags (unsigned node, int flags)`
- `int starpu_data_interface_get_next_id (void)`

Basic Data Management API

Data management is done at a high-level in StarPU: rather than accessing a mere list of contiguous buffers, the tasks may manipulate data that are described by a high-level construct which we call data interface.

An example of data interface is the "vector" interface which describes a contiguous data array on a specific memory node. This interface is a simple structure containing the number of elements in the array, the size of the elements, and the address of the array in the appropriate address space (this address may be invalid if there is no valid copy of the array in the memory node). More informations on the data interfaces provided by StarPU are given in [Data Interfaces](#).

When a piece of data managed by StarPU is used by a task, the task implementation is given a pointer to an interface describing a valid copy of the data that is accessible from the current processing unit.

Every worker is associated to a memory node which is a logical abstraction of the address space from which the processing unit gets its data. For instance, the memory node associated to the different CPU workers represents main memory (RAM), the memory node associated to a GPU is DRAM embedded on the device. Every memory node is identified by a logical index which is accessible from the function [starpu_worker_get_memory_node\(\)](#). When registering a piece of data to StarPU, the specified memory node indicates where the piece of data initially resides (we also call this memory node the home node of a piece of data).

- void [starpu_data_register](#) ([starpu_data_handle_t](#) *handleptr, int home_node, void *data_interface, struct [starpu_data_interface_ops](#) *ops)
- void [starpu_data_ptr_register](#) ([starpu_data_handle_t](#) handle, unsigned node)
- void [starpu_data_register_same](#) ([starpu_data_handle_t](#) *handledst, [starpu_data_handle_t](#) handlesrc)
- [starpu_data_handle_t](#) [starpu_data_lookup](#) (const void *ptr)

Accessing Data Interfaces

Each data interface is provided with a set of field access functions. The ones using a void * parameter aimed to be used in codelet implementations (see for example the code in [Vector Scaling Using StarPU's API](#)).

- void * [starpu_data_handle_to_pointer](#) ([starpu_data_handle_t](#) handle, unsigned node)
- int [starpu_data_pointer_is_inside](#) ([starpu_data_handle_t](#) handle, unsigned node, void *ptr)
- void * [starpu_data_get_local_ptr](#) ([starpu_data_handle_t](#) handle)
- enum [starpu_data_interface_id](#) [starpu_data_get_interface_id](#) ([starpu_data_handle_t](#) handle)
- int [starpu_data_pack](#) ([starpu_data_handle_t](#) handle, void **ptr, [starpu_ssize_t](#) *count)
- int [starpu_data_unpack](#) ([starpu_data_handle_t](#) handle, void *ptr, [size_t](#) count)
- [size_t](#) [starpu_data_get_size](#) ([starpu_data_handle_t](#) handle)

Registering Data

There are several ways to register a memory region so that it can be managed by StarPU. The functions below allow the registration of vectors, 2D matrices, 3D matrices as well as BCSR and CSR sparse matrices.

- void * [starpu_data_get_interface_on_node](#) ([starpu_data_handle_t](#) handle, unsigned memory_node)
- void [starpu_matrix_data_register](#) ([starpu_data_handle_t](#) *handle, int home_node, [uintptr_t](#) ptr, [uint32_t](#) ld, [uint32_t](#) nx, [uint32_t](#) ny, [size_t](#) elemsize)
- void [starpu_matrix_ptr_register](#) ([starpu_data_handle_t](#) handle, unsigned node, [uintptr_t](#) ptr, [uintptr_t](#) dev↵_handle, [size_t](#) offset, [uint32_t](#) ld)
- void [starpu_coo_data_register](#) ([starpu_data_handle_t](#) *handleptr, int home_node, [uint32_t](#) nx, [uint32_t](#) ny, [uint32_t](#) n_values, [uint32_t](#) *columns, [uint32_t](#) *rows, [uintptr_t](#) values, [size_t](#) elemsize)
- void [starpu_block_data_register](#) ([starpu_data_handle_t](#) *handle, int home_node, [uintptr_t](#) ptr, [uint32_t](#) ld, [uint32_t](#) ldz, [uint32_t](#) nx, [uint32_t](#) ny, [uint32_t](#) nz, [size_t](#) elemsize)
- void [starpu_block_ptr_register](#) ([starpu_data_handle_t](#) handle, unsigned node, [uintptr_t](#) ptr, [uintptr_t](#) dev↵_handle, [size_t](#) offset, [uint32_t](#) ld, [uint32_t](#) ldz)
- void [starpu_vector_data_register](#) ([starpu_data_handle_t](#) *handle, int home_node, [uintptr_t](#) ptr, [uint32_t](#) nx, [size_t](#) elemsize)
- void [starpu_vector_ptr_register](#) ([starpu_data_handle_t](#) handle, unsigned node, [uintptr_t](#) ptr, [uintptr_t](#) dev↵_handle, [size_t](#) offset)
- void [starpu_variable_data_register](#) ([starpu_data_handle_t](#) *handle, int home_node, [uintptr_t](#) ptr, [size_t](#) size)
- void [starpu_variable_ptr_register](#) ([starpu_data_handle_t](#) handle, unsigned node, [uintptr_t](#) ptr, [uintptr_t](#) ↵_dev_handle, [size_t](#) offset)

- void [starpu_void_data_register](#) ([starpu_data_handle_t](#) *handle)
- void [starpu_csr_data_register](#) ([starpu_data_handle_t](#) *handle, int home_node, uint32_t nnz, uint32_t nrow, uintptr_t nzval, uint32_t *colind, uint32_t *rowptr, uint32_t firstentry, size_t elemsize)
- void [starpu_bcsr_data_register](#) ([starpu_data_handle_t](#) *handle, int home_node, uint32_t nnz, uint32_t nrow, uintptr_t nzval, uint32_t *colind, uint32_t *rowptr, uint32_t firstentry, uint32_t r, uint32_t c, size_t elemsize)

Variables

- struct [starpu_data_interface_ops](#) **starpu_interface_matrix_ops**
- struct [starpu_data_interface_ops](#) **starpu_interface_coo_ops**
- struct [starpu_data_interface_ops](#) **starpu_interface_block_ops**
- struct [starpu_data_interface_ops](#) **starpu_interface_vector_ops**
- struct [starpu_data_interface_ops](#) **starpu_interface_variable_ops**
- struct [starpu_data_interface_ops](#) **starpu_interface_void_ops**
- struct [starpu_data_interface_ops](#) **starpu_interface_csr_ops**
- struct [starpu_data_interface_ops](#) **starpu_interface_bcsr_ops**

Accessing Variable Data Interfaces

- #define [STARPU_VARIABLE_GET_PTR](#)(interface)
- #define [STARPU_VARIABLE_GET_OFFSET](#)(interface)
- #define [STARPU_VARIABLE_GET_ELEMSIZE](#)(interface)
- #define [STARPU_VARIABLE_GET_DEV_HANDLE](#)(interface)
- size_t [starpu_variable_get_elemsize](#) ([starpu_data_handle_t](#) handle)
- uintptr_t [starpu_variable_get_local_ptr](#) ([starpu_data_handle_t](#) handle)

Accessing Vector Data Interfaces

- #define [STARPU_VECTOR_GET_PTR](#)(interface)
- #define [STARPU_VECTOR_GET_DEV_HANDLE](#)(interface)
- #define [STARPU_VECTOR_GET_OFFSET](#)(interface)
- #define [STARPU_VECTOR_GET_NX](#)(interface)
- #define [STARPU_VECTOR_GET_ELEMSIZE](#)(interface)
- #define [STARPU_VECTOR_GET_SLICE_BASE](#)(interface)
- uint32_t [starpu_vector_get_nx](#) ([starpu_data_handle_t](#) handle)
- size_t [starpu_vector_get_elemsize](#) ([starpu_data_handle_t](#) handle)
- uintptr_t [starpu_vector_get_local_ptr](#) ([starpu_data_handle_t](#) handle)

Accessing Matrix Data Interfaces

- #define [STARPU_MATRIX_GET_PTR](#)(interface)
- #define [STARPU_MATRIX_GET_DEV_HANDLE](#)(interface)
- #define [STARPU_MATRIX_GET_OFFSET](#)(interface)
- #define [STARPU_MATRIX_GET_NX](#)(interface)
- #define [STARPU_MATRIX_GET_NY](#)(interface)
- #define [STARPU_MATRIX_GET_LD](#)(interface)
- #define [STARPU_MATRIX_GET_ELEMSIZE](#)(interface)
- uint32_t [starpu_matrix_get_nx](#) ([starpu_data_handle_t](#) handle)
- uint32_t [starpu_matrix_get_ny](#) ([starpu_data_handle_t](#) handle)
- uint32_t [starpu_matrix_get_local_ld](#) ([starpu_data_handle_t](#) handle)
- uintptr_t [starpu_matrix_get_local_ptr](#) ([starpu_data_handle_t](#) handle)
- size_t [starpu_matrix_get_elemsize](#) ([starpu_data_handle_t](#) handle)

Accessing Block Data Interfaces

- #define [STARPU_BLOCK_GET_PTR](#)(interface)
- #define [STARPU_BLOCK_GET_DEV_HANDLE](#)(interface)
- #define [STARPU_BLOCK_GET_OFFSET](#)(interface)
- #define [STARPU_BLOCK_GET_NX](#)(interface)
- #define [STARPU_BLOCK_GET_NY](#)(interface)
- #define [STARPU_BLOCK_GET_NZ](#)(interface)
- #define [STARPU_BLOCK_GET_LDY](#)(interface)
- #define [STARPU_BLOCK_GET_LDZ](#)(interface)
- #define [STARPU_BLOCK_GET_ELEMSIZE](#)(interface)
- [uint32_t starpu_block_get_nx](#) ([starpu_data_handle_t](#) handle)
- [uint32_t starpu_block_get_ny](#) ([starpu_data_handle_t](#) handle)
- [uint32_t starpu_block_get_nz](#) ([starpu_data_handle_t](#) handle)
- [uint32_t starpu_block_get_local_ldy](#) ([starpu_data_handle_t](#) handle)
- [uint32_t starpu_block_get_local_ldz](#) ([starpu_data_handle_t](#) handle)
- [uintptr_t starpu_block_get_local_ptr](#) ([starpu_data_handle_t](#) handle)
- [size_t starpu_block_get_elemsize](#) ([starpu_data_handle_t](#) handle)

Accessing BCSR Data Interfaces

- #define [STARPU_BCSR_GET_NNZ](#)(interface)
- #define [STARPU_BCSR_GET_NZVAL](#)(interface)
- #define [STARPU_BCSR_GET_NZVAL_DEV_HANDLE](#)(interface)
- #define [STARPU_BCSR_GET_COLIND](#)(interface)
- #define [STARPU_BCSR_GET_COLIND_DEV_HANDLE](#)(interface)
- #define [STARPU_BCSR_GET_ROWPTR](#)(interface)
- #define [STARPU_BCSR_GET_ROWPTR_DEV_HANDLE](#)(interface)
- #define [STARPU_BCSR_GET_OFFSET](#)
- [uint32_t starpu_bcsr_get_nnz](#) ([starpu_data_handle_t](#) handle)
- [uint32_t starpu_bcsr_get_nrow](#) ([starpu_data_handle_t](#) handle)
- [uint32_t starpu_bcsr_get_firstentry](#) ([starpu_data_handle_t](#) handle)
- [uintptr_t starpu_bcsr_get_local_nzval](#) ([starpu_data_handle_t](#) handle)
- [uint32_t * starpu_bcsr_get_local_colind](#) ([starpu_data_handle_t](#) handle)
- [uint32_t * starpu_bcsr_get_local_rowptr](#) ([starpu_data_handle_t](#) handle)
- [uint32_t starpu_bcsr_get_r](#) ([starpu_data_handle_t](#) handle)
- [uint32_t starpu_bcsr_get_c](#) ([starpu_data_handle_t](#) handle)
- [size_t starpu_bcsr_get_elemsize](#) ([starpu_data_handle_t](#) handle)

Accessing CSR Data Interfaces

- #define [STARPU_CSR_GET_NNZ](#)(interface)
- #define [STARPU_CSR_GET_NROW](#)(interface)
- #define [STARPU_CSR_GET_NZVAL](#)(interface)
- #define [STARPU_CSR_GET_NZVAL_DEV_HANDLE](#)(interface)
- #define [STARPU_CSR_GET_COLIND](#)(interface)
- #define [STARPU_CSR_GET_COLIND_DEV_HANDLE](#)(interface)
- #define [STARPU_CSR_GET_ROWPTR](#)(interface)
- #define [STARPU_CSR_GET_ROWPTR_DEV_HANDLE](#)(interface)
- #define [STARPU_CSR_GET_OFFSET](#)
- #define [STARPU_CSR_GET_FIRSTENTRY](#)(interface)
- #define [STARPU_CSR_GET_ELEMSIZE](#)(interface)
- [uint32_t starpu_csr_get_nnz](#) ([starpu_data_handle_t](#) handle)
- [uint32_t starpu_csr_get_nrow](#) ([starpu_data_handle_t](#) handle)
- [uint32_t starpu_csr_get_firstentry](#) ([starpu_data_handle_t](#) handle)
- [uintptr_t starpu_csr_get_local_nzval](#) ([starpu_data_handle_t](#) handle)
- [uint32_t * starpu_csr_get_local_colind](#) ([starpu_data_handle_t](#) handle)
- [uint32_t * starpu_csr_get_local_rowptr](#) ([starpu_data_handle_t](#) handle)
- [size_t starpu_csr_get_elemsize](#) ([starpu_data_handle_t](#) handle)

30.10 starpu_deprecated_api.h File Reference

Macros

- #define **starpu_permodel_history_based_expected_perf**

30.11 starpu_disk.h File Reference

```
#include <sys/types.h>
#include <starpu_config.h>
```

Data Structures

- struct [starpu_disk_ops](#)

Macros

- #define [STARPU_DISK_SIZE_MIN](#)

Functions

- void [starpu_disk_close](#) (unsigned node, void *obj, size_t size)
- void * [starpu_disk_open](#) (unsigned node, void *pos, size_t size)
- int [starpu_disk_register](#) (struct [starpu_disk_ops](#) *func, void *parameter, starpu_ssize_t size)

Variables

- struct [starpu_disk_ops](#) [starpu_disk_stdio_ops](#)
- struct [starpu_disk_ops](#) [starpu_disk_unistd_ops](#)
- struct [starpu_disk_ops](#) [starpu_disk_unistd_o_direct_ops](#)
- struct [starpu_disk_ops](#) [starpu_disk_leveldb_ops](#)
- int [starpu_disk_swap_node](#)

30.12 starpu_driver.h File Reference

```
#include <starpu_config.h>
#include <starpu_openccl.h>
```

Data Structures

- struct [starpu_driver](#)
- union [starpu_driver.id](#)

Functions

- int [starpu_driver_run](#) (struct [starpu_driver](#) *d)
- void [starpu_drivers_request_termination](#) (void)
- int [starpu_driver_init](#) (struct [starpu_driver](#) *d)
- int [starpu_driver_run_once](#) (struct [starpu_driver](#) *d)
- int [starpu_driver_deinit](#) (struct [starpu_driver](#) *d)

30.13 starpu_expert.h File Reference

```
#include <starpu.h>
```

Functions

- void [starpu_wake_all_blocked_workers](#) (void)
- int [starpu_progression_hook_register](#) (unsigned(*func)(void *arg), void *arg)
- void [starpu_progression_hook_deregister](#) (int hook_id)

30.14 starpu_fxt.h File Reference

```
#include <starpu_perfmodel.h>
```

Data Structures

- struct [starpu_fxt_codelet_event](#)
- struct [starpu_fxt_options](#)

Macros

- #define [STARPU_FXT_MAX_FILES](#)

Functions

- void [starpu_fxt_options_init](#) (struct [starpu_fxt_options](#) *options)
- void [starpu_fxt_generate_trace](#) (struct [starpu_fxt_options](#) *options)
- void [starpu_fxt_autostart_profiling](#) (int autostart)
- void [starpu_fxt_start_profiling](#) (void)
- void [starpu_fxt_stop_profiling](#) (void)
- void [starpu_fxt_write_data_trace](#) (char *filename_in)
- void [starpu_fxt_trace_user_event](#) (unsigned long code)
- void [starpu_fxt_trace_user_event_string](#) (const char *s)

30.15 starpu_hash.h File Reference

```
#include <stdint.h>
#include <stddef.h>
```

Functions

Defining Interface

Applications can provide their own interface as shown in [Defining A New Data Interface](#).

- `uint32_t starpu_hash_crc32c_be_n` (`const void *input`, `size_t n`, `uint32_t inputcrc`)
- `uint32_t starpu_hash_crc32c_be` (`uint32_t input`, `uint32_t inputcrc`)
- `uint32_t starpu_hash_crc32c_string` (`const char *str`, `uint32_t inputcrc`)

30.16 starpu_mic.h File Reference

```
#include <starpu_config.h>
```

Typedefs

- `typedef void * starpu_mic_func_symbol_t`

Functions

- `int starpu_mic_register_kernel` (`starpu_mic_func_symbol_t *symbol`, `const char *func_name`)
- `starpu_mic_kernel_t starpu_mic_get_kernel` (`starpu_mic_func_symbol_t symbol`)

30.17 starpu_opencl.h File Reference

```
#include <starpu_config.h>
#include <CL/cl.h>
#include <assert.h>
```

Data Structures

- `struct starpu_opencl_program`

Macros

- `#define CL_TARGET_OPENCL_VERSION`

Functions

Writing OpenCL kernels

- void [starpu_opengl_get_context](#) (int devid, cl_context *context)
- void [starpu_opengl_get_device](#) (int devid, cl_device_id *device)
- void [starpu_opengl_get_queue](#) (int devid, cl_command_queue *queue)
- void [starpu_opengl_get_current_context](#) (cl_context *context)
- void [starpu_opengl_get_current_queue](#) (cl_command_queue *queue)
- int [starpu_opengl_set_kernel_args](#) (cl_int *err, cl_kernel *kernel,...)

Compiling OpenCL kernels

Source codes for OpenCL kernels can be stored in a file or in a string. StarPU provides functions to build the program executable for each available OpenCL device as a `cl_program` object. This program executable can then be loaded within a specific queue as explained in the next section. These are only helpers, Applications can also fill a [starpu_opengl_program](#) array by hand for more advanced use (e.g. different programs on the different OpenCL devices, for relocation purpose for instance).

- void [starpu_opengl_load_program_source](#) (const char *source_file_name, char *located_file_name, char *located_dir_name, char *opengl_program_source)
- void [starpu_opengl_load_program_source_malloc](#) (const char *source_file_name, char **located_file_name, char **located_dir_name, char **opengl_program_source)
- int [starpu_opengl_compile_opengl_from_file](#) (const char *source_file_name, const char *build_options)
- int [starpu_opengl_compile_opengl_from_string](#) (const char *opengl_program_source, const char *file_name, const char *build_options)
- int [starpu_opengl_load_binary_opengl](#) (const char *kernel_id, struct [starpu_opengl_program](#) *opengl_programs)
- int [starpu_opengl_load_opengl_from_file](#) (const char *source_file_name, struct [starpu_opengl_program](#) *opengl_programs, const char *build_options)
- int [starpu_opengl_load_opengl_from_string](#) (const char *opengl_program_source, struct [starpu_opengl_program](#) *opengl_programs, const char *build_options)
- int [starpu_opengl_unload_opengl](#) (struct [starpu_opengl_program](#) *opengl_programs)

Loading OpenCL kernels

- int [starpu_opengl_load_kernel](#) (cl_kernel *kernel, cl_command_queue *queue, struct [starpu_opengl_program](#) *opengl_programs, const char *kernel_name, int devid)
- int [starpu_opengl_release_kernel](#) (cl_kernel kernel)

OpenCL statistics

- int [starpu_opengl_collect_stats](#) (cl_event event)

OpenCL utilities

- #define [STARPU_OPENGL_DISPLAY_ERROR](#)(status)
- #define [STARPU_OPENGL_REPORT_ERROR](#)(status)
- #define [STARPU_OPENGL_REPORT_ERROR_WITH_MSG](#)(msg, status)
- const char * [starpu_opengl_error_string](#) (cl_int status)
- void [starpu_opengl_display_error](#) (const char *func, const char *file, int line, const char *msg, cl_int status)
- static __starpu_inline void [starpu_opengl_report_error](#) (const char *func, const char *file, int line, const char *msg, cl_int status)
- cl_int [starpu_opengl_allocate_memory](#) (int devid, cl_mem *addr, size_t size, cl_mem_flags flags)
- cl_int [starpu_opengl_copy_ram_to_opengl](#) (void *ptr, unsigned src_node, cl_mem buffer, unsigned dst_node, size_t size, size_t offset, cl_event *event, int *ret)
- cl_int [starpu_opengl_copy_opengl_to_ram](#) (cl_mem buffer, unsigned src_node, void *ptr, unsigned dst_node, size_t size, size_t offset, cl_event *event, int *ret)
- cl_int [starpu_opengl_copy_opengl_to_opengl](#) (cl_mem src, unsigned src_node, size_t src_offset, cl_mem dst, unsigned dst_node, size_t dst_offset, size_t size, cl_event *event, int *ret)
- cl_int [starpu_opengl_copy_async_sync](#) (uintptr_t src, size_t src_offset, unsigned src_node, uintptr_t dst, size_t dst_offset, unsigned dst_node, size_t size, cl_event *event)

30.18 starpu_omp.h File Reference

```
#include <starpu_config.h>
```

Data Structures

- struct [starpu_omp_lock_t](#)
- struct [starpu_omp_nest_lock_t](#)
- struct [starpu_omp_parallel_region_attr](#)
- struct [starpu_omp_task_region_attr](#)

Macros

- `#define __STARPU_OMP_NOTHROW`

Enumerations

- enum [starpu_omp_sched_value](#) {
[starpu_omp_sched_undefined](#), [starpu_omp_sched_static](#), [starpu_omp_sched_dynamic](#), [starpu_omp_sched_guided](#),
[starpu_omp_sched_auto](#), [starpu_omp_sched_runtime](#) }
- enum [starpu_omp_proc_bind_value](#) {
[starpu_omp_proc_bind_undefined](#), [starpu_omp_proc_bind_false](#), [starpu_omp_proc_bind_true](#), [starpu_omp_proc_bind_master](#),
[starpu_omp_proc_bind_close](#), [starpu_omp_proc_bind_spread](#) }

Functions

- struct [starpu_arbiter](#) * [starpu_omp_get_default_arbiter](#) (void) __STARPU_OMP_NOTHROW

Initialisation

- int [starpu_omp_init](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_shutdown](#) (void) __STARPU_OMP_NOTHROW

Parallel

- void [starpu_omp_parallel_region](#) (const struct [starpu_omp_parallel_region_attr](#) *attr) __STARPU_OMP_NOTHROW
- void [starpu_omp_master](#) (void(*f)(void *arg), void *arg) __STARPU_OMP_NOTHROW
- int [starpu_omp_master_inline](#) (void) __STARPU_OMP_NOTHROW

Synchronization

- void [starpu_omp_barrier](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_critical](#) (void(*f)(void *arg), void *arg, const char *name) __STARPU_OMP_NOTHROW
- void [starpu_omp_critical_inline_begin](#) (const char *name) __STARPU_OMP_NOTHROW
- void [starpu_omp_critical_inline_end](#) (const char *name) __STARPU_OMP_NOTHROW

Worksharing

- void [starpu_omp_single](#) (void(*f)(void *arg), void *arg, int nowait) __STARPU_OMP_NOTHROW
- int [starpu_omp_single_inline](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_single_copyprivate](#) (void(*f)(void *arg, void *data, unsigned long long data_size), void *arg, void *data, unsigned long long data_size) __STARPU_OMP_NOTHROW
- void * [starpu_omp_single_copyprivate_inline_begin](#) (void *data) __STARPU_OMP_NOTHROW
- void [starpu_omp_single_copyprivate_inline_end](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_for](#) (void(*f)(unsigned long long _first_i, unsigned long long _nb_i, void *arg), void *arg, unsigned long long nb_iterations, unsigned long long chunk, int schedule, int ordered, int nowait) __STARPU_OMP_NOTHROW
- int [starpu_omp_for_inline_first](#) (unsigned long long nb_iterations, unsigned long long chunk, int schedule, int ordered, unsigned long long *_first_i, unsigned long long *_nb_i) __STARPU_OMP_NOTHROW
- int [starpu_omp_for_inline_next](#) (unsigned long long nb_iterations, unsigned long long chunk, int schedule, int ordered, unsigned long long *_first_i, unsigned long long *_nb_i) __STARPU_OMP_NOTHROW
- void [starpu_omp_for_alt](#) (void(*f)(unsigned long long _begin_i, unsigned long long _end_i, void *arg), void *arg, unsigned long long nb_iterations, unsigned long long chunk, int schedule, int ordered, int nowait) __STARPU_OMP_NOTHROW
- int [starpu_omp_for_inline_first_alt](#) (unsigned long long nb_iterations, unsigned long long chunk, int schedule, int ordered, unsigned long long *_begin_i, unsigned long long *_end_i) __STARPU_OMP_NOTHROW
- int [starpu_omp_for_inline_next_alt](#) (unsigned long long nb_iterations, unsigned long long chunk, int schedule, int ordered, unsigned long long *_begin_i, unsigned long long *_end_i) __STARPU_OMP_NOTHROW
- void [starpu_omp_ordered_inline_begin](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_ordered_inline_end](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_ordered](#) (void(*f)(void *arg), void *arg) __STARPU_OMP_NOTHROW
- void [starpu_omp_sections](#) (unsigned long long nb_sections, void(**section_f)(void *arg), void **section_arg, int nowait) __STARPU_OMP_NOTHROW
- void [starpu_omp_sections_combined](#) (unsigned long long nb_sections, void(*section_f)(unsigned long long section_num, void *arg), void *section_arg, int nowait) __STARPU_OMP_NOTHROW

Task

- void [starpu_omp_task_region](#) (const struct [starpu_omp_task_region_attr](#) *attr) __STARPU_OMP_NOTHROW
- void [starpu_omp_taskwait](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_taskgroup](#) (void(*f)(void *arg), void *arg) __STARPU_OMP_NOTHROW
- void [starpu_omp_taskgroup_inline_begin](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_taskgroup_inline_end](#) (void) __STARPU_OMP_NOTHROW

API

- void [starpu_omp_set_num_threads](#) (int threads) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_num_threads](#) () __STARPU_OMP_NOTHROW
- int [starpu_omp_get_thread_num](#) () __STARPU_OMP_NOTHROW
- int [starpu_omp_get_max_threads](#) () __STARPU_OMP_NOTHROW
- int [starpu_omp_get_num_procs](#) (void) __STARPU_OMP_NOTHROW
- int [starpu_omp_in_parallel](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_set_dynamic](#) (int dynamic_threads) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_dynamic](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_set_nested](#) (int nested) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_nested](#) (void) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_cancellation](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_set_schedule](#) (enum [starpu_omp_sched_value](#) kind, int modifier) __STARPU_OMP_NOTHROW
- void [starpu_omp_get_schedule](#) (enum [starpu_omp_sched_value](#) *kind, int *modifier) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_thread_limit](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_set_max_active_levels](#) (int max_levels) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_max_active_levels](#) (void) __STARPU_OMP_NOTHROW

- int [starpu_omp_get_level](#) (void) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_ancestor_thread_num](#) (int level) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_team_size](#) (int level) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_active_level](#) (void) __STARPU_OMP_NOTHROW
- int [starpu_omp_in_final](#) (void) __STARPU_OMP_NOTHROW
- enum [starpu_omp_proc_bind_value](#) [starpu_omp_get_proc_bind](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_set_default_device](#) (int device_num) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_default_device](#) (void) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_num_devices](#) (void) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_num_teams](#) (void) __STARPU_OMP_NOTHROW
- int [starpu_omp_get_team_num](#) (void) __STARPU_OMP_NOTHROW
- int [starpu_omp_is_initial_device](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_init_lock](#) ([starpu_omp_lock_t](#) *lock) __STARPU_OMP_NOTHROW
- void [starpu_omp_destroy_lock](#) ([starpu_omp_lock_t](#) *lock) __STARPU_OMP_NOTHROW
- void [starpu_omp_set_lock](#) ([starpu_omp_lock_t](#) *lock) __STARPU_OMP_NOTHROW
- void [starpu_omp_unset_lock](#) ([starpu_omp_lock_t](#) *lock) __STARPU_OMP_NOTHROW
- int [starpu_omp_test_lock](#) ([starpu_omp_lock_t](#) *lock) __STARPU_OMP_NOTHROW
- void [starpu_omp_init_nest_lock](#) ([starpu_omp_nest_lock_t](#) *lock) __STARPU_OMP_NOTHROW
- void [starpu_omp_destroy_nest_lock](#) ([starpu_omp_nest_lock_t](#) *lock) __STARPU_OMP_NOTHROW
- void [starpu_omp_set_nest_lock](#) ([starpu_omp_nest_lock_t](#) *lock) __STARPU_OMP_NOTHROW
- void [starpu_omp_unset_nest_lock](#) ([starpu_omp_nest_lock_t](#) *lock) __STARPU_OMP_NOTHROW
- int [starpu_omp_test_nest_lock](#) ([starpu_omp_nest_lock_t](#) *lock) __STARPU_OMP_NOTHROW
- void [starpu_omp_atomic_fallback_inline_begin](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_atomic_fallback_inline_end](#) (void) __STARPU_OMP_NOTHROW
- double [starpu_omp_get_wtime](#) (void) __STARPU_OMP_NOTHROW
- double [starpu_omp_get_wtick](#) (void) __STARPU_OMP_NOTHROW
- void [starpu_omp_vector_annotate](#) ([starpu_data_handle_t](#) handle, uint32_t slice_base) __STARPU_OMP_NOTHROW

30.19 starpu_perfmodel.h File Reference

```
#include <starpu.h>
#include <stdio.h>
#include <starpu_util.h>
#include <starpu_worker.h>
```

Data Structures

- struct [starpu_perfmodel_device](#)
- struct [starpu_perfmodel_arch](#)
- struct [starpu_perfmodel_history_entry](#)
- struct [starpu_perfmodel_history_list](#)
- struct [starpu_perfmodel_regression_model](#)
- struct [starpu_perfmodel_per_arch](#)
- struct [starpu_perfmodel](#)

Macros

- #define **STARPU_NARCH**
- #define **starpu_per_arch_perfmodel**

Typedefs

- typedef double(* **starpu_perfmodel_per_arch_cost_function**) (struct [starpu_task](#) *task, struct [starpu_perfmodel_arch](#) *arch, unsigned nimpl)
- typedef size_t(* **starpu_perfmodel_per_arch_size_base**) (struct [starpu_task](#) *task, struct [starpu_perfmodel_arch](#) *arch, unsigned nimpl)
- typedef struct _starpu_perfmodel_state * **starpu_perfmodel_state_t**

Enumerations

- enum [starpu_perfmodel_type](#) {
STARPU_PERFMODEL_INVALID, **STARPU_PER_ARCH**, **STARPU_COMMON**, **STARPU_HISTORY_BASED**,
STARPU_REGRESSION_BASED, **STARPU_NL_REGRESSION_BASED** }

Functions

- void [starpu_perfmodel_init](#) (struct [starpu_perfmodel](#) *model)
- int [starpu_perfmodel_load_file](#) (const char *filename, struct [starpu_perfmodel](#) *model)
- int [starpu_perfmodel_load_symbol](#) (const char *symbol, struct [starpu_perfmodel](#) *model)
- int [starpu_perfmodel_unload_model](#) (struct [starpu_perfmodel](#) *model)
- void **starpu_perfmodel_get_model_path** (const char *symbol, char *path, size_t maxlen)
- void [starpu_perfmodel_free_sampling_directories](#) (void)
- struct [starpu_perfmodel_arch](#) * [starpu_worker_get_perf_archtype](#) (int workerid, unsigned sched_ctx_id)
- int **starpu_perfmodel_get_narch_combs** ()
- int **starpu_perfmodel_arch_comb_add** (int ndevices, struct [starpu_perfmodel_device](#) *devices)
- int **starpu_perfmodel_arch_comb_get** (int ndevices, struct [starpu_perfmodel_device](#) *devices)
- struct [starpu_perfmodel_arch](#) * **starpu_perfmodel_arch_comb_fetch** (int comb)
- struct [starpu_perfmodel_per_arch](#) * **starpu_perfmodel_get_model_per_arch** (struct [starpu_perfmodel](#) *model, struct [starpu_perfmodel_arch](#) *arch, unsigned impl)
- struct [starpu_perfmodel_per_arch](#) * **starpu_perfmodel_get_model_per_devices** (struct [starpu_perfmodel](#) *model, int impl,...)
- int **starpu_perfmodel_set_per_devices_cost_function** (struct [starpu_perfmodel](#) *model, int impl, [starpu_perfmodel_per_arch_cost_function](#) func,...)
- int **starpu_perfmodel_set_per_devices_size_base** (struct [starpu_perfmodel](#) *model, int impl, [starpu_perfmodel_per_arch_size_base](#) func,...)
- void [starpu_perfmodel_debugfilepath](#) (struct [starpu_perfmodel](#) *model, struct [starpu_perfmodel_arch](#) *arch, char *path, size_t maxlen, unsigned nimpl)
- char * [starpu_perfmodel_get_archtype_name](#) (enum [starpu_worker_archtype](#) archtype)
- void [starpu_perfmodel_get_arch_name](#) (struct [starpu_perfmodel_arch](#) *arch, char *archname, size_t maxlen, unsigned nimpl)
- double [starpu_perfmodel_history_based_expected_perf](#) (struct [starpu_perfmodel](#) *model, struct [starpu_perfmodel_arch](#) *arch, uint32_t footprint)
- void [starpu_perfmodel_initialize](#) (void)
- int [starpu_perfmodel_list](#) (FILE *output)
- void [starpu_perfmodel_print](#) (struct [starpu_perfmodel](#) *model, struct [starpu_perfmodel_arch](#) *arch, unsigned nimpl, char *parameter, uint32_t *footprint, FILE *output)
- int [starpu_perfmodel_print_all](#) (struct [starpu_perfmodel](#) *model, char *arch, char *parameter, uint32_t *footprint, FILE *output)
- int [starpu_perfmodel_print_estimations](#) (struct [starpu_perfmodel](#) *model, uint32_t footprint, FILE *output)
- int **starpu_perfmodel_list_combs** (FILE *output, struct [starpu_perfmodel](#) *model)
- void [starpu_perfmodel_update_history](#) (struct [starpu_perfmodel](#) *model, struct [starpu_task](#) *task, struct [starpu_perfmodel_arch](#) *arch, unsigned cpuid, unsigned nimpl, double measured)
- void [starpu_perfmodel_directory](#) (FILE *output)

- void [starpu_bus_print_bandwidth](#) (FILE *f)
- void [starpu_bus_print_affinity](#) (FILE *f)
- void [starpu_bus_print_filenames](#) (FILE *f)
- double [starpu_transfer_bandwidth](#) (unsigned src_node, unsigned dst_node)
- double [starpu_transfer_latency](#) (unsigned src_node, unsigned dst_node)
- double [starpu_transfer_predict](#) (unsigned src_node, unsigned dst_node, size_t size)

30.20 starpu_profiling.h File Reference

```
#include <starpu.h>
#include <errno.h>
#include <time.h>
#include <starpu_util.h>
```

Data Structures

- struct [starpu_profiling_task_info](#)
- struct [starpu_profiling_worker_info](#)
- struct [starpu_profiling_bus_info](#)

Macros

- #define [STARPU_PROFILING_DISABLE](#)
- #define [STARPU_PROFILING_ENABLE](#)
- #define [STARPU_NS_PER_S](#)
- #define [starpu_timespec_cmp](#)(a, b, CMP)

Functions

- void [starpu_profiling_init](#) (void)
- void [starpu_profiling_set_id](#) (int new_id)
- int [starpu_profiling_status_set](#) (int status)
- int [starpu_profiling_status_get](#) (void)
- int [starpu_profiling_worker_get_info](#) (int workerid, struct [starpu_profiling_worker_info](#) *worker_info)
- int [starpu_bus_get_count](#) (void)
- int [starpu_bus_get_id](#) (int src, int dst)
- int [starpu_bus_get_src](#) (int busid)
- int [starpu_bus_get_dst](#) (int busid)
- int [starpu_bus_get_profiling_info](#) (int busid, struct [starpu_profiling_bus_info](#) *bus_info)
- static __starpu_inline void [starpu_timespec_clear](#) (struct timespec *tsp)
- static __starpu_inline void [starpu_timespec_add](#) (struct timespec *a, struct timespec *b, struct timespec *result)
- static __starpu_inline void [starpu_timespec_accumulate](#) (struct timespec *result, struct timespec *a)
- static __starpu_inline void [starpu_timespec_sub](#) (const struct timespec *a, const struct timespec *b, struct timespec *result)
- double [starpu_timing_timespec_delay_us](#) (struct timespec *start, struct timespec *end)
- double [starpu_timing_timespec_to_us](#) (struct timespec *ts)
- void [starpu_profiling_bus_helper_display_summary](#) (void)
- void [starpu_profiling_worker_helper_display_summary](#) (void)

30.21 starpu_rand.h File Reference

```
#include <stdlib.h>
#include <starpu_config.h>
```

Macros

- `#define starpu_seed(seed)`
- `#define starpu_srand48(seed)`
- `#define starpu_drand48()`
- `#define starpu_lrand48()`
- `#define starpu_erand48(xsubi)`
- `#define starpu_srand48_r(seed, buffer)`
- `#define starpu_erand48_r(xsubi, buffer, result)`

Typedefs

- `typedef int starpu_drand48_data`

30.22 starpu_scc.h File Reference

```
#include <starpu_config.h>
```

Typedefs

- `typedef void * starpu_scc_func_symbol_t`

Functions

- `int starpu_scc_register_kernel (starpu_scc_func_symbol_t *symbol, const char *func_name)`
- `starpu_scc_kernel_t starpu_scc_get_kernel (starpu_scc_func_symbol_t symbol)`

30.23 starpu_sched_ctx.h File Reference

```
#include <starpu.h>
```

Macros

- `#define STARPU_SCHED_CTX_HIERARCHY_LEVEL`
- `#define STARPU_SCHED_CTX_NESTED`
- `#define STARPU_SCHED_CTX_AWAKE_WORKERS`

Functions

- unsigned **starpu_sched_ctx_get_inheritor** (unsigned sched_ctx_id)
- unsigned **starpu_sched_ctx_get_hierarchy_level** (unsigned sched_ctx_id)
- unsigned **starpu_sched_ctx_contains_type_of_worker** (enum [starpu_worker_archtype](#) arch, unsigned sched_ctx_id)
- int **starpu_sched_get_min_priority** (void)
- int **starpu_sched_get_max_priority** (void)
- int **starpu_sched_set_min_priority** (int min_prio)
- int **starpu_sched_set_max_priority** (int max_prio)
- void **starpu_sched_ctx_set_priority** (int *workers, int nworkers, unsigned sched_ctx_id, unsigned priority)
- void **starpu_sched_ctx_set_priority_on_level** (int *workers_to_add, unsigned nworkers_to_add, unsigned sched_ctx, unsigned priority)
- unsigned **starpu_sched_ctx_get_priority** (int worker, unsigned sched_ctx_id)
- void **starpu_sched_ctx_get_available_cpuids** (unsigned sched_ctx_id, int **cpuids, int *ncpuids)
- void **starpu_sched_ctx_bind_current_thread_to_cpuid** (unsigned cpuid)
- int **starpu_sched_ctx_book_workers_for_task** (unsigned sched_ctx_id, int *workerids, int nworkers)
- void **starpu_sched_ctx_unbook_workers_for_task** (unsigned sched_ctx_id, int master)
- unsigned **starpu_sched_ctx_worker_is_master_for_child_ctx** (int workerid, unsigned sched_ctx_id)
- void **starpu_sched_ctx_revert_task_counters** (unsigned sched_ctx_id, double flops)
- void **starpu_sched_ctx_move_task_to_ctx** (struct [starpu_task](#) *task, unsigned sched_ctx)
- int **starpu_sched_ctx_get_worker_rank** (unsigned sched_ctx_id)

Scheduling Context Worker Collection

- struct [starpu_worker_collection](#) * **starpu_sched_ctx_create_worker_collection** (unsigned sched_ctx_id, enum [starpu_worker_collection_type](#) type) [STARPU_ATTRIBUTE_MALLOC](#)
- void **starpu_sched_ctx_delete_worker_collection** (unsigned sched_ctx_id)
- struct [starpu_worker_collection](#) * **starpu_sched_ctx_get_worker_collection** (unsigned sched_ctx_id)

Scheduling Context Link with Hypervisor

- void **starpu_sched_ctx_set_policy_data** (unsigned sched_ctx_id, void *policy_data)
- void * **starpu_sched_ctx_get_policy_data** (unsigned sched_ctx_id)
- void * **starpu_sched_ctx_exec_parallel_code** (void *(*func)(void *), void *param, unsigned sched_ctx_id)
- int **starpu_sched_ctx_get_nready_tasks** (unsigned sched_ctx_id)
- double **starpu_sched_ctx_get_nready_flops** (unsigned sched_ctx_id)
- void **starpu_sched_ctx_call_pushed_task_cb** (int workerid, unsigned sched_ctx_id)

Scheduling Contexts Basic API

- #define [STARPU_SCHED_CTX_POLICY_NAME](#)
- #define [STARPU_SCHED_CTX_POLICY_STRUCT](#)
- #define [STARPU_SCHED_CTX_POLICY_MIN_PRIO](#)
- #define [STARPU_SCHED_CTX_POLICY_MAX_PRIO](#)
- unsigned **starpu_sched_ctx_create** (int *workerids_ctx, int nworkers_ctx, const char *sched_ctx_name,...)
- unsigned **starpu_sched_ctx_create_inside_interval** (const char *policy_name, const char *sched_ctx_name, int min_ncpus, int max_ncpus, int min_ngpus, int max_ngpus, unsigned allow_overlap)
- void **starpu_sched_ctx_register_close_callback** (unsigned sched_ctx_id, void(*close_callback)(unsigned sched_ctx_id, void *args), void *args)
- void **starpu_sched_ctx_add_workers** (int *workerids_ctx, int nworkers_ctx, unsigned sched_ctx_id)
- void **starpu_sched_ctx_remove_workers** (int *workerids_ctx, int nworkers_ctx, unsigned sched_ctx_id)
- void **starpu_sched_ctx_display_workers** (unsigned sched_ctx_id, FILE *f)
- void **starpu_sched_ctx_delete** (unsigned sched_ctx_id)
- void **starpu_sched_ctx_set_inheritor** (unsigned sched_ctx_id, unsigned inheritor)

- void [starpu_sched_ctx_set_context](#) (unsigned *sched_ctx_id)
- unsigned [starpu_sched_ctx_get_context](#) (void)
- void [starpu_sched_ctx_stop_task_submission](#) (void)
- void [starpu_sched_ctx_finished_submit](#) (unsigned sched_ctx_id)
- unsigned [starpu_sched_ctx_get_workers_list](#) (unsigned sched_ctx_id, int **workerids)
- unsigned [starpu_sched_ctx_get_workers_list_raw](#) (unsigned sched_ctx_id, int **workerids)
- unsigned [starpu_sched_ctx_get_nworkers](#) (unsigned sched_ctx_id)
- unsigned [starpu_sched_ctx_get_nshared_workers](#) (unsigned sched_ctx_id, unsigned sched_ctx_id2)
- unsigned [starpu_sched_ctx_contains_worker](#) (int workerid, unsigned sched_ctx_id)
- unsigned [starpu_sched_ctx_worker_get_id](#) (unsigned sched_ctx_id)
- unsigned [starpu_sched_ctx_overlapping_ctxs_on_worker](#) (int workerid)

Scheduling Context Priorities

- #define [STARPU_MIN_PRIO](#)
- #define [STARPU_MAX_PRIO](#)
- #define [STARPU_DEFAULT_PRIO](#)
- int [starpu_sched_ctx_get_min_priority](#) (unsigned sched_ctx_id)
- int [starpu_sched_ctx_get_max_priority](#) (unsigned sched_ctx_id)
- int [starpu_sched_ctx_set_min_priority](#) (unsigned sched_ctx_id, int min_prio)
- int [starpu_sched_ctx_set_max_priority](#) (unsigned sched_ctx_id, int max_prio)
- int [starpu_sched_ctx_min_priority_is_set](#) (unsigned sched_ctx_id)
- int [starpu_sched_ctx_max_priority_is_set](#) (unsigned sched_ctx_id)

30.24 starpu_sched_ctx_hypervisor.h File Reference

Data Structures

- struct [starpu_sched_ctx_performance_counters](#)

Functions

- void [starpu_sched_ctx_update_start_resizing_sample](#) (unsigned sched_ctx_id, double start_sample)

Scheduling Context Link with Hypervisor

- void [starpu_sched_ctx_set_perf_counters](#) (unsigned sched_ctx_id, void *perf_counters)
- void [starpu_sched_ctx_notify_hypervisor_exists](#) (void)
- unsigned [starpu_sched_ctx_check_if_hypervisor_exists](#) (void)

30.25 starpu_scheduler.h File Reference

```
#include <starpu.h>
```

Data Structures

- struct [starpu_sched_policy](#)

Functions

- struct [starpu_sched_policy](#) ** [starpu_sched_get_predefined_policies](#) ()
- void [starpu_worker_get_sched_condition](#) (int workerid, [starpu_pthread_mutex_t](#) **sched_mutex, [starpu_pthread_cond_t](#) **sched_cond)
- unsigned long [starpu_task_get_job_id](#) (struct [starpu_task](#) *task)
- int [starpu_wake_worker](#) (int workerid)
- int [starpu_wakeup_worker](#) (int workerid, [starpu_pthread_cond_t](#) *cond, [starpu_pthread_mutex_t](#) *mutex)
- int [starpu_wake_worker_locked](#) (int workerid)
- int [starpu_wakeup_worker_locked](#) (int workerid, [starpu_pthread_cond_t](#) *cond, [starpu_pthread_mutex_t](#) *mutex)
- int [starpu_worker_can_execute_task](#) (unsigned workerid, struct [starpu_task](#) *task, unsigned nimpl)
- int [starpu_worker_can_execute_task_impl](#) (unsigned workerid, struct [starpu_task](#) *task, unsigned *impl_mask)
- int [starpu_worker_can_execute_task_first_impl](#) (unsigned workerid, struct [starpu_task](#) *task, unsigned *nimpl)
- int [starpu_push_local_task](#) (int workerid, struct [starpu_task](#) *task, int back)
- int [starpu_push_task_end](#) (struct [starpu_task](#) *task)
- int [starpu_combined_worker_assign_workerid](#) (int nworkers, int workerid_array[])
- int [starpu_combined_worker_get_description](#) (int workerid, int *worker_size, int **combined_workerid)
- int [starpu_combined_worker_can_execute_task](#) (unsigned workerid, struct [starpu_task](#) *task, unsigned nimpl)
- int [starpu_get_prefetch_flag](#) (void)
- int [starpu_prefetch_task_input_on_node](#) (struct [starpu_task](#) *task, unsigned node)
- int [starpu_idle_prefetch_task_input_on_node](#) (struct [starpu_task](#) *task, unsigned node)
- uint32_t [starpu_task_footprint](#) (struct [starpu_perfmodel](#) *model, struct [starpu_task](#) *task, struct [starpu_perfmodel_arch](#) *arch, unsigned nimpl)
- uint32_t [starpu_task_data_footprint](#) (struct [starpu_task](#) *task)
- double [starpu_task_expected_length](#) (struct [starpu_task](#) *task, struct [starpu_perfmodel_arch](#) *arch, unsigned nimpl)
- double [starpu_worker_get_relative_speedup](#) (struct [starpu_perfmodel_arch](#) *perf_arch)
- double [starpu_task_expected_data_transfer_time](#) (unsigned memory_node, struct [starpu_task](#) *task)
- double [starpu_data_expected_transfer_time](#) ([starpu_data_handle_t](#) handle, unsigned memory_node, enum [starpu_data_access_mode](#) mode)
- double [starpu_task_expected_energy](#) (struct [starpu_task](#) *task, struct [starpu_perfmodel_arch](#) *arch, unsigned nimpl)
- double [starpu_task_expected_conversion_time](#) (struct [starpu_task](#) *task, struct [starpu_perfmodel_arch](#) *arch, unsigned nimpl)
- double [starpu_task_bundle_expected_length](#) ([starpu_task_bundle_t](#) bundle, struct [starpu_perfmodel_arch](#) *arch, unsigned nimpl)
- double [starpu_task_bundle_expected_data_transfer_time](#) ([starpu_task_bundle_t](#) bundle, unsigned memory_node)
- double [starpu_task_bundle_expected_energy](#) ([starpu_task_bundle_t](#) bundle, struct [starpu_perfmodel_arch](#) *arch, unsigned nimpl)
- void [starpu_sched_ctx_worker_shares_tasks_lists](#) (int workerid, int sched_ctx_id)
- void [starpu_sched_task_break](#) (struct [starpu_task](#) *task)

30.26 starpu_sink.h File Reference

Functions

- void [starpu_sink_common_worker](#) (int argc, char **argv)

30.27 starpu_stdlib.h File Reference

```
#include <starpu.h>
```

Macros

- `#define STARPU_MALLOC_PINNED`
- `#define STARPU_MALLOC_COUNT`
- `#define STARPU_MALLOC_NORECLAIM`
- `#define STARPU_MEMORY_WAIT`
- `#define STARPU_MEMORY_OVERFLOW`
- `#define STARPU_MALLOC_SIMULATION_FOLDED`

Functions

- void `starpu_malloc_set_align` (size_t align)
- int `starpu_malloc` (void **A, size_t dim) STARPU_ATTRIBUTE_ALLOC_SIZE(2)
- int `starpu_free` (void *A)
- int `starpu_malloc_flags` (void **A, size_t dim, int flags) STARPU_ATTRIBUTE_ALLOC_SIZE(2)
- int `starpu_free_flags` (void *A, size_t dim, int flags)
- int `starpu_memory_pin` (void *addr, size_t size)
- int `starpu_memory_unpin` (void *addr, size_t size)
- starpu_ssize_t `starpu_memory_get_total` (unsigned node)
- starpu_ssize_t `starpu_memory_get_available` (unsigned node)
- void `starpu_memory_wait_available` (unsigned node, size_t size)
- int `starpu_memory_allocate` (unsigned node, size_t size, int flags)
- void `starpu_memory_deallocate` (unsigned node, size_t size)
- void `starpu_sleep` (float nb_sec)

30.28 starpu_task.h File Reference

```
#include <starpu.h>
#include <starpu_data.h>
#include <starpu_util.h>
#include <starpu_task_bundle.h>
#include <errno.h>
#include <assert.h>
#include <cuda.h>
```

Data Structures

- struct `starpu_codelet`
- struct `starpu_task`

Macros

- `#define STARPU_NOWHERE`
- `#define STARPU_CPU`
- `#define STARPU_CUDA`
- `#define STARPU_OPENCL`
- `#define STARPU_MIC`
- `#define STARPU_SCC`
- `#define STARPU_CODELET_SIMGRID_EXECUTE`
- `#define STARPU_CUDA_ASYNC`
- `#define STARPU_OPENCL_ASYNC`
- `#define STARPU_TASK_INVALID`
- `#define STARPU_MULTIPLE_CPU_IMPLEMENTATIONS`
- `#define STARPU_MULTIPLE_CUDA_IMPLEMENTATIONS`
- `#define STARPU_MULTIPLE_OPENCL_IMPLEMENTATIONS`
- `#define STARPU_VARIABLE_NBUFFERS`
- `#define STARPU_TASK_TYPE_NORMAL`
- `#define STARPU_TASK_TYPE_INTERNAL`
- `#define STARPU_TASK_TYPE_DATA_ACQUIRE`
- `#define STARPU_TASK_INITIALIZER`
- `#define STARPU_TASK_GET_NBUFFERS(task)`
- `#define STARPU_TASK_GET_HANDLE(task, i)`
- `#define STARPU_TASK_GET_HANDLES(task)`
- `#define STARPU_TASK_SET_HANDLE(task, handle, i)`
- `#define STARPU_CODELET_GET_MODE(codelet, i)`
- `#define STARPU_CODELET_SET_MODE(codelet, mode, i)`
- `#define STARPU_TASK_GET_MODE(task, i)`
- `#define STARPU_TASK_SET_MODE(task, mode, i)`
- `#define STARPU_CODELET_GET_NODE(codelet, i)`
- `#define STARPU_CODELET_SET_NODE(codelet, __node, i)`

Typedefs

- `typedef uint64_t starpu_tag_t`
- `typedef void(* starpu_cpu_func_t) (void **, void *)`
- `typedef void(* starpu_cuda_func_t) (void **, void *)`
- `typedef void(* starpu_opencl_func_t) (void **, void *)`
- `typedef void(* starpu_mic_kernel_t) (void **, void *)`
- `typedef void(* starpu_scc_kernel_t) (void **, void *)`
- `typedef starpu_mic_kernel_t(* starpu_mic_func_t) (void)`
- `typedef starpu_scc_kernel_t(* starpu_scc_func_t) (void)`

Enumerations

- `enum starpu_codelet_type { STARPU_SEQ, STARPU_SPMD, STARPU_FORKJOIN }`
- `enum starpu_task_status {`
`STARPU_TASK_INVALID, STARPU_TASK_INVALID, STARPU_TASK_BLOCKED, STARPU_TASK_READY,`
`STARPU_TASK_RUNNING, STARPU_TASK_FINISHED, STARPU_TASK_BLOCKED_ON_TAG, STARPU_TASK_BLOCKED_ON_TASK,`
`STARPU_TASK_BLOCKED_ON_DATA, STARPU_TASK_STOPPED }`

Functions

- void [starpu_tag_declare_deps](#) ([starpu_tag_t](#) id, unsigned ndeps,...)
- void [starpu_tag_declare_deps_array](#) ([starpu_tag_t](#) id, unsigned ndeps, [starpu_tag_t](#) *array)
- void [starpu_task_declare_deps_array](#) (struct [starpu_task](#) *task, unsigned ndeps, struct [starpu_task](#) *task_array[])
- int [starpu_task_get_task_succs](#) (struct [starpu_task](#) *task, unsigned ndeps, struct [starpu_task](#) *task_array[])
- int [starpu_task_get_task_scheduled_succs](#) (struct [starpu_task](#) *task, unsigned ndeps, struct [starpu_task](#) *task_array[])
- int [starpu_tag_wait](#) ([starpu_tag_t](#) id)
- int [starpu_tag_wait_array](#) (unsigned ntags, [starpu_tag_t](#) *id)
- void [starpu_tag_notify_from_apps](#) ([starpu_tag_t](#) id)
- void [starpu_tag_restart](#) ([starpu_tag_t](#) id)
- void [starpu_tag_remove](#) ([starpu_tag_t](#) id)
- void [starpu_task_init](#) (struct [starpu_task](#) *task)
- void [starpu_task_clean](#) (struct [starpu_task](#) *task)
- struct [starpu_task](#) * [starpu_task_create](#) (void) [STARPU_ATTRIBUTE_MALLOC](#)
- void [starpu_task_destroy](#) (struct [starpu_task](#) *task)
- int [starpu_task_submit](#) (struct [starpu_task](#) *task) [STARPU_WARN_UNUSED_RESULT](#)
- int [starpu_task_submit_to_ctx](#) (struct [starpu_task](#) *task, unsigned sched_ctx_id)
- int [starpu_task_finished](#) (struct [starpu_task](#) *task) [STARPU_WARN_UNUSED_RESULT](#)
- int [starpu_task_wait](#) (struct [starpu_task](#) *task) [STARPU_WARN_UNUSED_RESULT](#)
- int [starpu_task_wait_for_all](#) (void)
- int [starpu_task_wait_for_n_submitted](#) (unsigned n)
- int [starpu_task_wait_for_all_in_ctx](#) (unsigned sched_ctx_id)
- int [starpu_task_wait_for_n_submitted_in_ctx](#) (unsigned sched_ctx_id, unsigned n)
- int [starpu_task_wait_for_no_ready](#) (void)
- int [starpu_task_nready](#) (void)
- int [starpu_task_nsubmitted](#) (void)
- void [starpu_iteration_push](#) (unsigned long iteration)
- void [starpu_iteration_pop](#) (void)
- void [starpu_do_schedule](#) (void)
- void [starpu_codelet_init](#) (struct [starpu_codelet](#) *cl)
- void [starpu_codelet_display_stats](#) (struct [starpu_codelet](#) *cl)
- struct [starpu_task](#) * [starpu_task_get_current](#) (void)
- const char * [starpu_task_get_model_name](#) (struct [starpu_task](#) *task)
- const char * [starpu_task_get_name](#) (struct [starpu_task](#) *task)
- void [starpu_parallel_task_barrier_init](#) (struct [starpu_task](#) *task, int workerid)
- void [starpu_parallel_task_barrier_init_n](#) (struct [starpu_task](#) *task, int worker_size)
- struct [starpu_task](#) * [starpu_task_dup](#) (struct [starpu_task](#) *task)
- void [starpu_task_set_implementation](#) (struct [starpu_task](#) *task, unsigned impl)
- unsigned [starpu_task_get_implementation](#) (struct [starpu_task](#) *task)

30.28.1 Macro Definition Documentation

30.28.1.1 STARPU_CODELET_SIMGRID_EXECUTE

```
#define STARPU_CODELET_SIMGRID_EXECUTE
```

Value to be set in [starpu_codelet::flags](#) to execute the codelet functions even in simgrid mode.

30.28.1.2 STARPU_CUDA_ASYNC

```
#define STARPU_CUDA_ASYNC
```

Value to be set in [starpu_codelet::cuda_flags](#) to allow asynchronous CUDA kernel execution.

30.28.1.3 STARPU_OPENCL_ASYNC

```
#define STARPU_OPENCL_ASYNC
```

Value to be set in [starpu_codelet::opencl_flags](#) to allow asynchronous OpenCL kernel execution.

30.29 starpu_task_bundle.h File Reference

Typedefs

- typedef struct _starpu_task_bundle * [starpu_task_bundle_t](#)

Functions

- void [starpu_task_bundle_create](#) (starpu_task_bundle_t *bundle)
- int [starpu_task_bundle_insert](#) (starpu_task_bundle_t bundle, struct starpu_task *task)
- int [starpu_task_bundle_remove](#) (starpu_task_bundle_t bundle, struct starpu_task *task)
- void [starpu_task_bundle_close](#) (starpu_task_bundle_t bundle)

30.30 starpu_task_list.h File Reference

```
#include <starpu_task.h>
#include <starpu_util.h>
```

Data Structures

- struct [starpu_task_list](#)

Functions

- static STARPU_INLINE void [starpu_task_list_init](#) (struct starpu_task_list *list)
- static STARPU_INLINE void [starpu_task_list_push_front](#) (struct starpu_task_list *list, struct starpu_task *task)
- static STARPU_INLINE void [starpu_task_list_push_back](#) (struct starpu_task_list *list, struct starpu_task *task)
- static STARPU_INLINE struct starpu_task * [starpu_task_list_front](#) (struct starpu_task_list *list)
- static STARPU_INLINE struct starpu_task * [starpu_task_list_back](#) (struct starpu_task_list *list)
- static STARPU_INLINE int [starpu_task_list_empty](#) (struct starpu_task_list *list)
- static STARPU_INLINE void [starpu_task_list_erase](#) (struct starpu_task_list *list, struct starpu_task *task)
- static STARPU_INLINE struct starpu_task * [starpu_task_list_pop_front](#) (struct starpu_task_list *list)
- static STARPU_INLINE struct starpu_task * [starpu_task_list_pop_back](#) (struct starpu_task_list *list)
- static STARPU_INLINE struct starpu_task * [starpu_task_list_begin](#) (struct starpu_task_list *list)
- static STARPU_INLINE struct starpu_task * [starpu_task_list_end](#) (struct starpu_task_list *list [STARPU_ATTRIBUTE_UNUSED](#))
- static STARPU_INLINE struct starpu_task * [starpu_task_list_next](#) (struct starpu_task *task)
- static STARPU_INLINE int [starpu_task_list_ismember](#) (struct starpu_task_list *list, struct starpu_task *look)

30.31 starpu_task_util.h File Reference

```
#include <stdio.h>
#include <stdlib.h>
#include <string.h>
#include <assert.h>
#include <starpu.h>
```

Data Structures

- struct [starpu_codelet_pack_arg_data](#)

Macros

- #define **STARPU_MODE_SHIFT**
- #define [STARPU_VALUE](#)
- #define [STARPU_CALLBACK](#)
- #define [STARPU_CALLBACK_WITH_ARG](#)
- #define [STARPU_CALLBACK_ARG](#)
- #define [STARPU_PRIORITY](#)
- #define [STARPU_DATA_ARRAY](#)
- #define [STARPU_DATA_MODE_ARRAY](#)
- #define [STARPU_TAG](#)
- #define [STARPU_HYPERVISOR_TAG](#)
- #define [STARPU_FLOPS](#)
- #define [STARPU_SCHED_CTX](#)
- #define **STARPU_PROLOGUE_CALLBACK**
- #define **STARPU_PROLOGUE_CALLBACK_ARG**
- #define **STARPU_PROLOGUE_CALLBACK_POP**
- #define **STARPU_PROLOGUE_CALLBACK_POP_ARG**
- #define [STARPU_EXECUTE_ON_WORKER](#)
- #define [STARPU_TAG_ONLY](#)
- #define **STARPU_POSSIBLY_PARALLEL**
- #define [STARPU_WORKER_ORDER](#)
- #define [STARPU_NAME](#)
- #define [STARPU_CL_ARGS](#)
- #define [STARPU_TASK_COLOR](#)
- #define **STARPU_SHIFTED_MODE_MAX**

MPI Insert Task

- #define [STARPU_EXECUTE_ON_NODE](#)
- #define [STARPU_EXECUTE_ON_DATA](#)
- #define [STARPU_NODE_SELECTION_POLICY](#)

Functions

- void [starpu_create_sync_task](#) ([starpu_tag_t](#) sync_tag, unsigned ndeps, [starpu_tag_t](#) *deps, void(*callback)(void *), void *callback_arg)
- struct [starpu_task](#) * [starpu_task_build](#) (struct [starpu_codelet](#) *cl,...)
- int [starpu_task_insert](#) (struct [starpu_codelet](#) *cl,...)
- int [starpu_insert_task](#) (struct [starpu_codelet](#) *cl,...)
- void [starpu_task_insert_data_make_room](#) (struct [starpu_codelet](#) *cl, struct [starpu_task](#) *task, int *allocated_buffers, int current_buffer, int room)
- void [starpu_task_insert_data_process_arg](#) (struct [starpu_codelet](#) *cl, struct [starpu_task](#) *task, int *allocated_buffers, int *current_buffer, int arg_type, [starpu_data_handle_t](#) handle)
- void [starpu_task_insert_data_process_array_arg](#) (struct [starpu_codelet](#) *cl, struct [starpu_task](#) *task, int *allocated_buffers, int *current_buffer, int nb_handles, [starpu_data_handle_t](#) *handles)
- void [starpu_task_insert_data_process_mode_array_arg](#) (struct [starpu_codelet](#) *cl, struct [starpu_task](#) *task, int *allocated_buffers, int *current_buffer, int nb_descrs, struct [starpu_data_descr](#) *descrs)
- void [starpu_codelet_pack_args](#) (void **arg_buffer, size_t *arg_buffer_size,...)
- void [starpu_codelet_pack_arg_init](#) (struct [starpu_codelet_pack_arg_data](#) *state)
- void [starpu_codelet_pack_arg](#) (struct [starpu_codelet_pack_arg_data](#) *state, const void *ptr, size_t ptr_size)
- void [starpu_codelet_pack_arg_fini](#) (struct [starpu_codelet_pack_arg_data](#) *state, void **cl_arg, size_t *cl_arg_size)
- void [starpu_codelet_unpack_args](#) (void *cl_arg,...)
- void [starpu_codelet_unpack_args_and_copyleft](#) (void *cl_arg, void *buffer, size_t buffer_size,...)

30.31.1 Data Structure Documentation

30.31.1.1 struct [starpu_codelet_pack_arg_data](#)

Data Fields

char *	arg_buffer	
size_t	arg_buffer_size	
size_t	current_offset	
int	nargs	

30.32 [starpu_thread.h](#) File Reference

```
#include <starpu_config.h>
#include <starpu_util.h>
#include <xbt/synchro_core.h>
#include <msg/msg.h>
#include <stdint.h>
```

Data Structures

- struct [starpu_pthread_barrier_t](#)
- struct [starpu_pthread_spinlock_t](#)

Macros

- `#define starpu_thread_setname(name)`
- `#define STARPU_PTHREAD_MUTEX_INITIALIZER`
- `#define STARPU_PTHREAD_COND_INITIALIZER`
- `#define STARPU_PTHREAD_BARRIER_SERIAL_THREAD`

Typedefs

- `typedef msg_process_t starpu_thread_t`
- `typedef int starpu_thread_attr_t`
- `typedef xbt_mutex_t starpu_thread_mutex_t`
- `typedef int starpu_thread_mutexattr_t`
- `typedef int starpu_thread_key_t`
- `typedef xbt_cond_t starpu_thread_cond_t`
- `typedef int starpu_thread_condattr_t`
- `typedef xbt_mutex_t starpu_thread_rwlock_t`
- `typedef int starpu_thread_rwlockattr_t`
- `typedef int starpu_thread_barrierattr_t`

Functions

- `int starpu_thread_create_on (char *name, starpu_thread_t *thread, const starpu_thread_attr_t *attr, void *(*start_routine)(void *), void *arg, msg_host_t host)`
- `int starpu_thread_create (starpu_thread_t *thread, const starpu_thread_attr_t *attr, void *(*start_routine)(void *), void *arg)`
- `int starpu_thread_join (starpu_thread_t thread, void **retval)`
- `int starpu_thread_exit (void *retval) STARPU_ATTRIBUTE_NORETURN`
- `int starpu_thread_attr_init (starpu_thread_attr_t *attr)`
- `int starpu_thread_attr_destroy (starpu_thread_attr_t *attr)`
- `int starpu_thread_attr_setdetachstate (starpu_thread_attr_t *attr, int detachstate)`
- `int starpu_thread_mutex_init (starpu_thread_mutex_t *mutex, const starpu_thread_mutexattr_t *mutexattr)`
- `int starpu_thread_mutex_destroy (starpu_thread_mutex_t *mutex)`
- `int starpu_thread_mutex_lock (starpu_thread_mutex_t *mutex)`
- `int starpu_thread_mutex_unlock (starpu_thread_mutex_t *mutex)`
- `int starpu_thread_mutex_trylock (starpu_thread_mutex_t *mutex)`
- `int starpu_thread_mutexattr_gettype (const starpu_thread_mutexattr_t *attr, int *type)`
- `int starpu_thread_mutexattr_settype (starpu_thread_mutexattr_t *attr, int type)`
- `int starpu_thread_mutexattr_destroy (starpu_thread_mutexattr_t *attr)`
- `int starpu_thread_mutexattr_init (starpu_thread_mutexattr_t *attr)`
- `int starpu_thread_mutex_lock_sched (starpu_thread_mutex_t *mutex)`
- `int starpu_thread_mutex_unlock_sched (starpu_thread_mutex_t *mutex)`
- `int starpu_thread_mutex_trylock_sched (starpu_thread_mutex_t *mutex)`
- `void starpu_thread_mutex_check_sched (starpu_thread_mutex_t *mutex, char *file, int line)`
- `int starpu_thread_key_create (starpu_thread_key_t *key, void(*destr_function)(void *))`
- `int starpu_thread_key_delete (starpu_thread_key_t key)`
- `int starpu_thread_setspecific (starpu_thread_key_t key, const void *pointer)`
- `void * starpu_thread_getspecific (starpu_thread_key_t key)`
- `int starpu_thread_cond_init (starpu_thread_cond_t *cond, starpu_thread_condattr_t *cond_attr)`
- `int starpu_thread_cond_signal (starpu_thread_cond_t *cond)`
- `int starpu_thread_cond_broadcast (starpu_thread_cond_t *cond)`
- `int starpu_thread_cond_wait (starpu_thread_cond_t *cond, starpu_thread_mutex_t *mutex)`

- int [starpu_pthread_cond_timedwait](#) (starpu_pthread_cond_t *cond, starpu_pthread_mutex_t *mutex, const struct timespec *abstime)
- int [starpu_pthread_cond_destroy](#) (starpu_pthread_cond_t *cond)
- int [starpu_pthread_rwlock_init](#) (starpu_pthread_rwlock_t *rwlock, const starpu_pthread_rwlockattr_t *attr)
- int [starpu_pthread_rwlock_destroy](#) (starpu_pthread_rwlock_t *rwlock)
- int [starpu_pthread_rwlock_rdlock](#) (starpu_pthread_rwlock_t *rwlock)
- int [starpu_pthread_rwlock_tryrdlock](#) (starpu_pthread_rwlock_t *rwlock)
- int [starpu_pthread_rwlock_wrlock](#) (starpu_pthread_rwlock_t *rwlock)
- int [starpu_pthread_rwlock_trywrlock](#) (starpu_pthread_rwlock_t *rwlock)
- int [starpu_pthread_rwlock_unlock](#) (starpu_pthread_rwlock_t *rwlock)
- int [starpu_pthread_barrier_init](#) (starpu_pthread_barrier_t *barrier, const starpu_pthread_barrierattr_t *attr, unsigned count)
- int [starpu_pthread_barrier_destroy](#) (starpu_pthread_barrier_t *barrier)
- int [starpu_pthread_barrier_wait](#) (starpu_pthread_barrier_t *barrier)
- int [starpu_pthread_spin_init](#) (starpu_pthread_spinlock_t *lock, int pshared)
- int [starpu_pthread_spin_destroy](#) (starpu_pthread_spinlock_t *lock)
- int [starpu_pthread_spin_lock](#) (starpu_pthread_spinlock_t *lock)
- int [starpu_pthread_spin_trylock](#) (starpu_pthread_spinlock_t *lock)
- int [starpu_pthread_spin_unlock](#) (starpu_pthread_spinlock_t *lock)

30.32.1 Data Structure Documentation

30.32.1.1 struct starpu_pthread_barrier_t

Data Fields

starpu_pthread_mutex_t	mutex	
starpu_pthread_cond_t	cond	
starpu_pthread_cond_t	cond_destroy	
unsigned	count	
unsigned	done	
unsigned	busy	

30.32.1.2 struct starpu_pthread_spinlock_t

Data Fields

int	taken	
-----	-------	--

30.33 starpu_thread_util.h File Reference

```
#include <starpu_util.h>
#include <errno.h>
```

Macros

- #define [STARPU_PTHREAD_CREATE_ON](#)(name, thread, attr, routine, arg, where)

- `#define STARPU_PTHREAD_CREATE`(thread, attr, routine, arg)
- `#define STARPU_PTHREAD_MUTEX_INIT`(mutex, attr)
- `#define STARPU_PTHREAD_MUTEX_DESTROY`(mutex)
- `#define _STARPU_CHECK_NOT_SCHED_MUTEX`(mutex, file, line)
- `#define STARPU_PTHREAD_MUTEX_LOCK`(mutex)
- `#define STARPU_PTHREAD_MUTEX_LOCK_SCHED`(mutex)
- `#define STARPU_PTHREAD_MUTEX_TRYLOCK`(mutex)
- `#define STARPU_PTHREAD_MUTEX_TRYLOCK_SCHED`(mutex)
- `#define STARPU_PTHREAD_MUTEX_UNLOCK`(mutex)
- `#define STARPU_PTHREAD_MUTEX_UNLOCK_SCHED`(mutex)
- `#define STARPU_PTHREAD_KEY_CREATE`(key, destr)
- `#define STARPU_PTHREAD_KEY_DELETE`(key)
- `#define STARPU_PTHREAD_SETSPECIFIC`(key, ptr)
- `#define STARPU_PTHREAD_GETSPECIFIC`(key)
- `#define STARPU_PTHREAD_RWLOCK_INIT`(rwlock, attr)
- `#define STARPU_PTHREAD_RWLOCK_RDLOCK`(rwlock)
- `#define STARPU_PTHREAD_RWLOCK_TRYRDLOCK`(rwlock)
- `#define STARPU_PTHREAD_RWLOCK_WRLOCK`(rwlock)
- `#define STARPU_PTHREAD_RWLOCK_TRYWRLOCK`(rwlock)
- `#define STARPU_PTHREAD_RWLOCK_UNLOCK`(rwlock)
- `#define STARPU_PTHREAD_RWLOCK_DESTROY`(rwlock)
- `#define STARPU_PTHREAD_COND_INIT`(cond, attr)
- `#define STARPU_PTHREAD_COND_DESTROY`(cond)
- `#define STARPU_PTHREAD_COND_SIGNAL`(cond)
- `#define STARPU_PTHREAD_COND_BROADCAST`(cond)
- `#define STARPU_PTHREAD_COND_WAIT`(cond, mutex)
- `#define STARPU_PTHREAD_BARRIER_INIT`(barrier, attr, count)
- `#define STARPU_PTHREAD_BARRIER_DESTROY`(barrier)
- `#define STARPU_PTHREAD_BARRIER_WAIT`(barrier)

Functions

- static `STARPU_INLINE int _starpu_pthread_mutex_trylock` (starpu_pthread_mutex_t *mutex, char *file, int line)
- static `STARPU_INLINE int _starpu_pthread_mutex_trylock_sched` (starpu_pthread_mutex_t *mutex, char *file, int line)
- static `STARPU_INLINE int _starpu_pthread_rwlock_tryrdlock` (starpu_pthread_rwlock_t *rwlock, char *file, int line)
- static `STARPU_INLINE int _starpu_pthread_rwlock_trywrlock` (starpu_pthread_rwlock_t *rwlock, char *file, int line)

30.34 starpu_top.h File Reference

```
#include <starpu.h>
#include <stdlib.h>
#include <time.h>
```

Data Structures

- struct `starpu_top_data`
- struct `starpu_top_param`

Enumerations

- enum [starpu_top_data_type](#) { STARPU_TOP_DATA_BOOLEAN, STARPU_TOP_DATA_INTEGER, STARPU_TOP_DATA_FLOAT }
- enum [starpu_top_param_type](#) { STARPU_TOP_PARAM_BOOLEAN, STARPU_TOP_PARAM_INTEGER, STARPU_TOP_PARAM_FLOAT, STARPU_TOP_PARAM_ENUM }
- enum [starpu_top_message_type](#) { TOP_TYPE_GO, TOP_TYPE_SET, TOP_TYPE_CONTINUE, TOP_TYPE_ENABLE, TOP_TYPE_DISABLE, TOP_TYPE_DEBUG, TOP_TYPE_UNKNOW }

Functions

Functions to call before the initialisation

- struct [starpu_top_data](#) * [starpu_top_add_data_boolean](#) (const char *data_name, int active)
- struct [starpu_top_data](#) * [starpu_top_add_data_integer](#) (const char *data_name, int minimum_value, int maximum_value, int active)
- struct [starpu_top_data](#) * [starpu_top_add_data_float](#) (const char *data_name, double minimum_value, double maximum_value, int active)
- struct [starpu_top_param](#) * [starpu_top_register_parameter_boolean](#) (const char *param_name, int *parameter_field, void(*callback)(struct [starpu_top_param](#) *))
- struct [starpu_top_param](#) * [starpu_top_register_parameter_integer](#) (const char *param_name, int *parameter_field, int minimum_value, int maximum_value, void(*callback)(struct [starpu_top_param](#) *))
- struct [starpu_top_param](#) * [starpu_top_register_parameter_float](#) (const char *param_name, double *parameter_field, double minimum_value, double maximum_value, void(*callback)(struct [starpu_top_param](#) *))
- struct [starpu_top_param](#) * [starpu_top_register_parameter_enum](#) (const char *param_name, int *parameter_field, char **values, int nb_values, void(*callback)(struct [starpu_top_param](#) *))

Initialisation

- void [starpu_top_init_and_wait](#) (const char *server_name)

To call after initialisation

- void [starpu_top_update_parameter](#) (const struct [starpu_top_param](#) *param)
- void [starpu_top_update_data_boolean](#) (const struct [starpu_top_data](#) *data, int value)
- void [starpu_top_update_data_integer](#) (const struct [starpu_top_data](#) *data, int value)
- void [starpu_top_update_data_float](#) (const struct [starpu_top_data](#) *data, double value)
- void [starpu_top_task_prevision](#) (struct [starpu_task](#) *task, int devid, unsigned long long start, unsigned long long end)
- void [starpu_top_debug_log](#) (const char *message)
- void [starpu_top_debug_lock](#) (const char *message)

30.35 starpu_tree.h File Reference

Data Structures

- struct [starpu_tree](#)

Functions

- void [starpu_tree_reset_visited](#) (struct [starpu_tree](#) *tree, char *visited)
- void [starpu_tree_prepare_children](#) (unsigned arity, struct [starpu_tree](#) *father)
- void [starpu_tree_insert](#) (struct [starpu_tree](#) *tree, int id, int level, int is_pu, int arity, struct [starpu_tree](#) *father)
- struct [starpu_tree](#) * [starpu_tree_get](#) (struct [starpu_tree](#) *tree, int id)
- struct [starpu_tree](#) * [starpu_tree_get_neighbour](#) (struct [starpu_tree](#) *tree, struct [starpu_tree](#) *node, char *visited, char *present)
- void [starpu_tree_free](#) (struct [starpu_tree](#) *tree)

30.36 starpu_util.h File Reference

```
#include <stdio.h>
#include <stdlib.h>
#include <string.h>
#include <assert.h>
#include <starpu_config.h>
#include <starpu_task.h>
#include <sys/time.h>
```

Macros

- #define [STARPU_GNUC_PREREQ](#)(maj, min)
- #define [STARPU_UNLIKELY](#)(expr)
- #define [STARPU_LIKELY](#)(expr)
- #define [STARPU_ATTRIBUTE_UNUSED](#)
- #define [STARPU_ATTRIBUTE_NORETURN](#)
- #define [STARPU_ATTRIBUTE_INTERNAL](#)
- #define [STARPU_ATTRIBUTE_MALLOC](#)
- #define [STARPU_ATTRIBUTE_WARN_UNUSED_RESULT](#)
- #define [STARPU_ATTRIBUTE_PURE](#)
- #define [STARPU_ATTRIBUTE_ALIGNED](#)(size)
- #define [STARPU_ATTRIBUTE_FORMAT](#)(type, string, first)
- #define [STARPU_INLINE](#)
- #define [STARPU_ATTRIBUTE_CALLOC_SIZE](#)(num, size)
- #define [STARPU_ATTRIBUTE_ALLOC_SIZE](#)(size)
- #define [endif](#)
- #define [STARPU_WARN_UNUSED_RESULT](#)
- #define [STARPU_POISON_PTR](#)
- #define [STARPU_MIN](#)(a, b)
- #define [STARPU_MAX](#)(a, b)
- #define [STARPU_BACKTRACE_LENGTH](#)
- #define [STARPU_DUMP_BACKTRACE](#)()
- #define [STARPU_ASSERT](#)(x)
- #define [STARPU_ASSERT_MSG](#)(x, msg, ...)
- #define [STARPU_ASSERT_ACCESSIBLE](#)(ptr)
- #define [_starpu_abort](#)()
- #define [STARPU_ABORT](#)()
- #define [STARPU_ABORT_MSG](#)(msg, ...)
- #define [STARPU_CHECK_RETURN_VALUE](#)(err, message, ...)
- #define [STARPU_CHECK_RETURN_VALUE_IS](#)(err, value, message, ...)
- #define [STARPU_ATOMIC_SOMETHING](#)(name, expr)
- #define [STARPU_ATOMIC_SOMETHINGL](#)(name, expr)
- #define [STARPU_RMB](#)()
- #define [STARPU_WMB](#)()

Functions

- char * **starpu_getenv** (const char *str)
- static __starpu_inline int **starpu_get_env_number** (const char *str)
- static __starpu_inline int **starpu_get_env_number_default** (const char *str, int defval)
- static __starpu_inline float **starpu_get_env_float_default** (const char *str, float defval)
- void **starpu_execute_on_each_worker** (void(*func)(void *), void *arg, uint32_t where)
- void **starpu_execute_on_each_worker_ex** (void(*func)(void *), void *arg, uint32_t where, const char *name)
- void **starpu_execute_on_specific_workers** (void(*func)(void *), void *arg, unsigned num_workers, unsigned *workers, const char *name)
- int **starpu_data_cpy** (starpu_data_handle_t dst_handle, starpu_data_handle_t src_handle, int asynchronous, void(*callback_func)(void *), void *callback_arg)
- double **starpu_timing_now** (void)

Variables

- int **_starpu_silent**

30.37 starpu_worker.h File Reference

```
#include <stdlib.h>
#include <starpu_config.h>
#include <starpu_thread.h>
```

Data Structures

- struct **starpu_sched_ctx_iterator**
- struct **starpu_worker_collection**

Macros

- #define **starpu_worker_get_id_check**()

Enumerations

- enum **starpu_worker_archtype** {
 STARPU_CPU_WORKER, **STARPU_CUDA_WORKER**, **STARPU_OPENCL_WORKER**, **STARPU_MIC_↔**
 WORKER,
 STARPU_SCC_WORKER, **STARPU_ANY_WORKER** }
- enum **starpu_worker_collection_type** { **STARPU_WORKER_TREE**, **STARPU_WORKER_LIST** }

Functions

- unsigned [starpu_worker_get_count](#) (void)
- unsigned [starpu_combined_worker_get_count](#) (void)
- unsigned [starpu_worker_is_combined_worker](#) (int id)
- unsigned [starpu_cpu_worker_get_count](#) (void)
- unsigned [starpu_cuda_worker_get_count](#) (void)
- unsigned [starpu_opengl_worker_get_count](#) (void)
- unsigned [starpu_mic_worker_get_count](#) (void)
- unsigned [starpu_scc_worker_get_count](#) (void)
- unsigned [starpu_mic_device_get_count](#) (void)
- int [starpu_worker_get_id](#) (void)
- unsigned [_starpu_worker_get_id_check](#) (const char *f, int l)
- int [starpu_worker_get_bindid](#) (int workerid)
- int [starpu_combined_worker_get_id](#) (void)
- int [starpu_combined_worker_get_size](#) (void)
- int [starpu_combined_worker_get_rank](#) (void)
- enum [starpu_worker_archtype](#) [starpu_worker_get_type](#) (int id)
- int [starpu_worker_get_count_by_type](#) (enum [starpu_worker_archtype](#) type)
- int [starpu_worker_get_ids_by_type](#) (enum [starpu_worker_archtype](#) type, int *workerids, int maxsize)
- int [starpu_worker_get_by_type](#) (enum [starpu_worker_archtype](#) type, int num)
- int [starpu_worker_get_by_devid](#) (enum [starpu_worker_archtype](#) type, int devid)
- void [starpu_worker_get_name](#) (int id, char *dst, size_t maxlen)
- int [starpu_worker_get_devid](#) (int id)
- int [starpu_worker_get_mp_nodeid](#) (int id)
- struct [starpu_tree](#) * [starpu_workers_get_tree](#) (void)
- unsigned [starpu_worker_get_sched_ctx_list](#) (int worker, unsigned **sched_ctx)
- unsigned [starpu_worker_is_slave](#) (int workerid)
- char * [starpu_worker_get_type_as_string](#) (enum [starpu_worker_archtype](#) type)

Variables

- struct [starpu_worker_collection](#) [worker_list](#)
- struct [starpu_worker_collection](#) [worker_tree](#)

30.38 starpu_mpi.h File Reference

```
#include <starpu.h>
#include <mpi.h>
```

Macros

- #define [STARPU_MPI_NODE_SELECTION_CURRENT_POLICY](#)
- #define [STARPU_MPI_NODE_SELECTION_MOST_R_DATA](#)

Typedefs

- typedef void * **starpu_mpi_req**
- typedef int(* **starpu_mpi_select_node_policy_func_t**) (int me, int nb_nodes, struct [starpu_data_descr](#) *descr, int nb_data)
- typedef void(* **starpu_mpi_datatype_allocate_func_t**) ([starpu_data_handle_t](#), MPI_Datatype *)
- typedef void(* **starpu_mpi_datatype_free_func_t**) (MPI_Datatype *)

Functions

Initialisation

- int [starpu_mpi_init_comm](#) (int *argc, char ***argv, int initialize_mpi, MPI_Comm comm)
- int [starpu_mpi_init](#) (int *argc, char ***argv, int initialize_mpi)
- int [starpu_mpi_initialize](#) (void)
- int [starpu_mpi_initialize_extended](#) (int *rank, int *world_size)
- int [starpu_mpi_shutdown](#) (void)
- void [starpu_mpi_comm_amounts_retrieve](#) (size_t *comm_amounts)
- int [starpu_mpi_comm_size](#) (MPI_Comm comm, int *size)
- int [starpu_mpi_comm_rank](#) (MPI_Comm comm, int *rank)
- int [starpu_mpi_world_rank](#) (void)
- int [starpu_mpi_world_size](#) (void)

Collective Operations

- void [starpu_mpi_redux_data](#) (MPI_Comm comm, [starpu_data_handle_t](#) data_handle)
- int [starpu_mpi_scatter_detached](#) ([starpu_data_handle_t](#) *data_handles, int count, int root, MPI_Comm comm, void(*scallback)(void *), void *sarg, void(*rcallback)(void *), void *rarg)
- int [starpu_mpi_gather_detached](#) ([starpu_data_handle_t](#) *data_handles, int count, int root, MPI_Comm comm, void(*scallback)(void *), void *sarg, void(*rcallback)(void *), void *rarg)

Communication Cache

- void [starpu_mpi_cache_flush](#) (MPI_Comm comm, [starpu_data_handle_t](#) data_handle)
- void [starpu_mpi_cache_flush_all_data](#) (MPI_Comm comm)
- int [starpu_mpi_cached_receive](#) ([starpu_data_handle_t](#) data_handle)
- int [starpu_mpi_cached_send](#) ([starpu_data_handle_t](#) data_handle, int dest)
- int [starpu_mpi_cache_is_enabled](#) ()
- int [starpu_mpi_cache_set](#) (int enabled)

Node Selection Policy

- int [starpu_mpi_node_selection_register_policy](#) (starpu_mpi_select_node_policy_func_t policy_func)
- int [starpu_mpi_node_selection_unregister_policy](#) (int policy)
- int [starpu_mpi_node_selection_get_current_policy](#) ()
- int [starpu_mpi_node_selection_set_current_policy](#) (int policy)

Communication

- `#define STARPU_MPI_TAG_UB`
- `int starpu_mpi_isend (starpu_data_handle_t data_handle, starpu_mpi_req *req, int dest, int mpi_tag, MPI_Comm comm)`
- `int starpu_mpi_irecv (starpu_data_handle_t data_handle, starpu_mpi_req *req, int source, int mpi_tag, MPI_Comm comm)`
- `int starpu_mpi_send (starpu_data_handle_t data_handle, int dest, int mpi_tag, MPI_Comm comm)`
- `int starpu_mpi_recv (starpu_data_handle_t data_handle, int source, int mpi_tag, MPI_Comm comm, MPI_Status *status)`
- `int starpu_mpi_isend_detached (starpu_data_handle_t data_handle, int dest, int mpi_tag, MPI_Comm comm, void(*callback)(void *), void *arg)`
- `int starpu_mpi_irecv_detached (starpu_data_handle_t data_handle, int source, int mpi_tag, MPI_Comm comm, void(*callback)(void *), void *arg)`
- `int starpu_mpi_issend (starpu_data_handle_t data_handle, starpu_mpi_req *req, int dest, int mpi_tag, MPI_Comm comm)`
- `int starpu_mpi_issend_detached (starpu_data_handle_t data_handle, int dest, int mpi_tag, MPI_Comm comm, void(*callback)(void *), void *arg)`
- `int starpu_mpi_wait (starpu_mpi_req *req, MPI_Status *status)`
- `int starpu_mpi_test (starpu_mpi_req *req, int *flag, MPI_Status *status)`
- `int starpu_mpi_barrier (MPI_Comm comm)`
- `int starpu_mpi_irecv_detached_sequential_consistency (starpu_data_handle_t data_handle, int source, int mpi_tag, MPI_Comm comm, void(*callback)(void *), void *arg, int sequential_consistency)`
- `int starpu_mpi_isend_detached_unlock_tag (starpu_data_handle_t data_handle, int dest, int mpi_tag, MPI_Comm comm, starpu_tag_t tag)`
- `int starpu_mpi_irecv_detached_unlock_tag (starpu_data_handle_t data_handle, int source, int mpi_tag, MPI_Comm comm, starpu_tag_t tag)`
- `int starpu_mpi_isend_array_detached_unlock_tag (unsigned array_size, starpu_data_handle_t *data_handle, int *dest, int *mpi_tag, MPI_Comm *comm, starpu_tag_t tag)`
- `int starpu_mpi_irecv_array_detached_unlock_tag (unsigned array_size, starpu_data_handle_t *data_handle, int *source, int *mpi_tag, MPI_Comm *comm, starpu_tag_t tag)`
- `int starpu_mpi_get_communication_tag (void)`
- `void starpu_mpi_set_communication_tag (int tag)`
- `int starpu_mpi_wait_for_all (MPI_Comm comm)`
- `int starpu_mpi_datatype_register (starpu_data_handle_t handle, starpu_mpi_datatype_allocate_func_t allocate_datatype_func, starpu_mpi_datatype_free_func_t free_datatype_func)`
- `int starpu_mpi_datatype_unregister (starpu_data_handle_t handle)`
- `int starpu_mpi_comm_get_attr (MPI_Comm comm, int keyval, void *attribute_val, int *flag)`

MPI Insert Task

- `#define starpu_mpi_data_register(data_handle, tag, rank)`
- `#define STARPU_MPI_PER_NODE`
- `#define starpu_mpi_data_set_rank(handle, rank)`
- `#define starpu_data_set_rank`
- `#define starpu_data_set_tag`
- `#define starpu_data_get_rank`
- `#define starpu_data_get_tag`
- `struct starpu_task * starpu_mpi_task_build (MPI_Comm comm, struct starpu_codelet *codelet,...)`
- `int starpu_mpi_task_post_build (MPI_Comm comm, struct starpu_codelet *codelet,...)`
- `int starpu_mpi_task_insert (MPI_Comm comm, struct starpu_codelet *codelet,...)`
- `int starpu_mpi_insert_task (MPI_Comm comm, struct starpu_codelet *codelet,...)`
- `void starpu_mpi_get_data_on_node (MPI_Comm comm, starpu_data_handle_t data_handle, int node)`

- void [starpup_mpi_get_data_on_node_detached](#) (MPI_Comm comm, [starpup_data_handle_t](#) data_handle, int node, void(*callback)(void *), void *arg)
- void [starpup_mpi_get_data_on_all_nodes_detached](#) (MPI_Comm comm, [starpup_data_handle_t](#) data_handle)
- void [starpup_mpi_data_register_comm](#) ([starpup_data_handle_t](#) data_handle, int tag, int rank, MPI_Comm comm)
- void [starpup_mpi_data_set_rank_comm](#) ([starpup_data_handle_t](#) handle, int rank, MPI_Comm comm)
- void [starpup_mpi_data_set_tag](#) ([starpup_data_handle_t](#) handle, int tag)
- int [starpup_mpi_data_get_rank](#) ([starpup_data_handle_t](#) handle)
- int [starpup_mpi_data_get_tag](#) ([starpup_data_handle_t](#) handle)
- void [starpup_mpi_data_migrate](#) (MPI_Comm comm, [starpup_data_handle_t](#) handle, int new_rank)

30.39 starpufft.h File Reference

Typedefs

- typedef double _Complex **starpufft_complex**
- typedef struct starpufft_plan * **starpufft_plan**
- typedef float _Complex **starpufftf_complex**
- typedef struct starpufftf_plan * **starpufftf_plan**
- typedef long double _Complex **starpufftl_complex**
- typedef struct starpufftl_plan * **starpufftl_plan**

Functions

- starpufft_plan [starpufft_plan_dft_1d](#) (int n, int sign, unsigned flags)
- starpufft_plan [starpufft_plan_dft_2d](#) (int n, int m, int sign, unsigned flags)
- starpufft_plan **starpufft_plan_dft_r2c_1d** (int n, unsigned flags)
- starpufft_plan **starpufft_plan_dft_c2r_1d** (int n, unsigned flags)
- void * [starpufft_malloc](#) (size_t n)
- void [starpufft_free](#) (void *p)
- int [starpufft_execute](#) (starpufft_plan p, void *in, void *out)
- struct [starpup_task](#) * [starpufft_start](#) (starpufft_plan p, void *in, void *out)
- int [starpufft_execute_handle](#) (starpufft_plan p, [starpup_data_handle_t](#) in, [starpup_data_handle_t](#) out)
- struct [starpup_task](#) * [starpufft_start_handle](#) (starpufft_plan p, [starpup_data_handle_t](#) in, [starpup_data_handle_t](#) out)
- void [starpufft_cleanup](#) (starpufft_plan p)
- void [starpufft_destroy_plan](#) (starpufft_plan p)
- void **starpufft_startstats** (void)
- void **starpufft_stopstats** (void)
- void **starpufft_showstats** (FILE *out)
- starpufftf_plan **starpufftf_plan_dft_1d** (int n, int sign, unsigned flags)
- starpufftf_plan **starpufftf_plan_dft_2d** (int n, int m, int sign, unsigned flags)
- starpufftf_plan **starpufftf_plan_dft_r2c_1d** (int n, unsigned flags)
- starpufftf_plan **starpufftf_plan_dft_c2r_1d** (int n, unsigned flags)
- void * **starpufftf_malloc** (size_t n)
- void **starpufftf_free** (void *p)
- int **starpufftf_execute** (starpufftf_plan p, void *in, void *out)
- struct [starpup_task](#) * **starpufftf_start** (starpufftf_plan p, void *in, void *out)
- int **starpufftf_execute_handle** (starpufftf_plan p, [starpup_data_handle_t](#) in, [starpup_data_handle_t](#) out)
- struct [starpup_task](#) * **starpufftf_start_handle** (starpufftf_plan p, [starpup_data_handle_t](#) in, [starpup_data_handle_t](#) out)
- void **starpufftf_cleanup** (starpufftf_plan p)

- void **starpufftf_destroy_plan** (starpufftf_plan p)
- void **starpufftf_startstats** (void)
- void **starpufftf_stopstats** (void)
- void **starpufftf_showstats** (FILE *out)
- starpufftl_plan **starpufftl_plan_dft_1d** (int n, int sign, unsigned flags)
- starpufftl_plan **starpufftl_plan_dft_2d** (int n, int m, int sign, unsigned flags)
- starpufftl_plan **starpufftl_plan_dft_r2c_1d** (int n, unsigned flags)
- starpufftl_plan **starpufftl_plan_dft_c2r_1d** (int n, unsigned flags)
- void * **starpufftl_malloc** (size_t n)
- void **starpufftl_free** (void *p)
- int **starpufftl_execute** (starpufftl_plan p, void *in, void *out)
- struct [starpufftl_task](#) * **starpufftl_start** (starpufftl_plan p, void *in, void *out)
- int **starpufftl_execute_handle** (starpufftl_plan p, [starpufftl_data_handle_t](#) in, [starpufftl_data_handle_t](#) out)
- struct [starpufftl_task](#) * **starpufftl_start_handle** (starpufftl_plan p, [starpufftl_data_handle_t](#) in, [starpufftl_data_handle_t](#) out)
- void **starpufftl_cleanup** (starpufftl_plan p)
- void **starpufftl_destroy_plan** (starpufftl_plan p)
- void **starpufftl_startstats** (void)
- void **starpufftl_stopstats** (void)
- void **starpufftl_showstats** (FILE *out)

Variables

- int **starpufftl_last_plan_number**

30.40 sc_hypervisor.h File Reference

```
#include <starpufftl.h>
#include <starpufftl_sched_ctx_hypervisor.h>
#include <sc_hypervisor_config.h>
#include <sc_hypervisor_monitoring.h>
#include <math.h>
```

Data Structures

- struct [sc_hypervisor_policy](#)

Functions

- void * [sc_hypervisor_init](#) (struct [sc_hypervisor_policy](#) *policy)
- void [sc_hypervisor_shutdown](#) (void)
- void [sc_hypervisor_register_ctx](#) (unsigned sched_ctx, double total_flops)
- void [sc_hypervisor_unregister_ctx](#) (unsigned sched_ctx)
- void [sc_hypervisor_post_resize_request](#) (unsigned sched_ctx, int task_tag)
- void [sc_hypervisor_resize_ctxs](#) (unsigned *sched_ctxs, int nsched_ctxs, int *workers, int nworkers)
- void [sc_hypervisor_stop_resize](#) (unsigned sched_ctx)
- void [sc_hypervisor_start_resize](#) (unsigned sched_ctx)
- const char * [sc_hypervisor_get_policy](#) ()

- void [sc_hypervisor_add_workers_to_sched_ctx](#) (int *workers_to_add, unsigned nworkers_to_add, unsigned sched_ctx)
- void [sc_hypervisor_remove_workers_from_sched_ctx](#) (int *workers_to_remove, unsigned nworkers_to_remove, unsigned sched_ctx, unsigned now)
- void [sc_hypervisor_move_workers](#) (unsigned sender_sched_ctx, unsigned receiver_sched_ctx, int *workers_to_move, unsigned nworkers_to_move, unsigned now)
- void [sc_hypervisor_size_ctxs](#) (unsigned *sched_ctxs, int nsched_ctxs, int *workers, int nworkers)
- unsigned [sc_hypervisor_get_size_req](#) (unsigned **sched_ctxs, int *nsched_ctxs, int **workers, int *nworkers)
- void [sc_hypervisor_save_size_req](#) (unsigned *sched_ctxs, int nsched_ctxs, int *workers, int nworkers)
- void [sc_hypervisor_free_size_req](#) (void)
- unsigned [sc_hypervisor_can_resize](#) (unsigned sched_ctx)
- void [sc_hypervisor_set_type_of_task](#) (struct [starpu_codelet](#) *cl, unsigned sched_ctx, uint32_t footprint, size_t data_size)
- void [sc_hypervisor_update_diff_total_flops](#) (unsigned sched_ctx, double diff_total_flops)
- void [sc_hypervisor_update_diff_elapsed_flops](#) (unsigned sched_ctx, double diff_task_flops)
- void [sc_hypervisor_update_resize_interval](#) (unsigned *sched_ctxs, int nsched_ctxs, int max_nworkers)
- void [sc_hypervisor_get_ctxs_on_level](#) (unsigned **sched_ctxs, int *nsched_ctxs, unsigned hierarchy_level, unsigned father_sched_ctx_id)
- unsigned [sc_hypervisor_get_nhierarchy_levels](#) (void)
- void [sc_hypervisor_get_leaves](#) (unsigned *sched_ctxs, int nsched_ctxs, unsigned *leaves, int *nleaves)
- double [sc_hypervisor_get_nready_flops_of_all_sons_of_sched_ctx](#) (unsigned sched_ctx)
- void [sc_hypervisor_print_overhead](#) ()

Variables

- [starpu_pthread_mutex_t act_hypervisor_mutex](#)

30.41 sc_hypervisor_config.h File Reference

```
#include <sc_hypervisor.h>
```

Data Structures

- struct [sc_hypervisor_policy_config](#)

Macros

- #define [SC_HYPERVISOR_MAX_IDLE](#)
- #define [SC_HYPERVISOR_MIN_WORKING](#)
- #define [SC_HYPERVISOR_PRIORITY](#)
- #define [SC_HYPERVISOR_MIN_WORKERS](#)
- #define [SC_HYPERVISOR_MAX_WORKERS](#)
- #define [SC_HYPERVISOR_GRANULARITY](#)
- #define [SC_HYPERVISOR_FIXED_WORKERS](#)
- #define [SC_HYPERVISOR_MIN_TASKS](#)
- #define [SC_HYPERVISOR_NEW_WORKERS_MAX_IDLE](#)
- #define [SC_HYPERVISOR_TIME_TO_APPLY](#)
- #define [SC_HYPERVISOR_NULL](#)
- #define [SC_HYPERVISOR_ISPEED_W_SAMPLE](#)
- #define [SC_HYPERVISOR_ISPEED_CTX_SAMPLE](#)
- #define [SC_HYPERVISOR_TIME_SAMPLE](#)
- #define [MAX_IDLE_TIME](#)
- #define [MIN_WORKING_TIME](#)

Functions

- void `sc_hypervisor_set_config` (unsigned sched_ctx, void *config)
- struct `sc_hypervisor_policy_config` * `sc_hypervisor_get_config` (unsigned sched_ctx)
- void `sc_hypervisor_ctl` (unsigned sched_ctx,...)

30.42 `sc_hypervisor_lp.h` File Reference

```
#include <sc_hypervisor.h>
#include <starpu_config.h>
```

Functions

- double `sc_hypervisor_lp_get_nworkers_per_ctx` (int nsched_ctxs, int ntypes_of_workers, double res[nsched_ctxs][ntypes_of_workers], int total_nw[ntypes_of_workers], struct `types_of_workers` *tw, unsigned *in_sched_ctxs)
- double `sc_hypervisor_lp_get_tmax` (int nw, int *workers)
- void `sc_hypervisor_lp_round_double_to_int` (int ns, int nw, double res[ns][nw], int res_rounded[ns][nw])
- void `sc_hypervisor_lp_redistribute_resources_in_ctxs` (int ns, int nw, int res_rounded[ns][nw], double res[ns][nw], unsigned *sched_ctxs, struct `types_of_workers` *tw)
- void `sc_hypervisor_lp_distribute_resources_in_ctxs` (unsigned *sched_ctxs, int ns, int nw, int res_rounded[ns][nw], double res[ns][nw], int *workers, int nworkers, struct `types_of_workers` *tw)
- void `sc_hypervisor_lp_distribute_floating_no_resources_in_ctxs` (unsigned *sched_ctxs, int ns, int nw, double res[ns][nw], int *workers, int nworkers, struct `types_of_workers` *tw)
- void `sc_hypervisor_lp_place_resources_in_ctx` (int ns, int nw, double w_in_s[ns][nw], unsigned *sched_ctxs, int *workers, unsigned do_size, struct `types_of_workers` *tw)
- void `sc_hypervisor_lp_share_remaining_resources` (int ns, unsigned *sched_ctxs, int nworkers, int *workers)
- double `sc_hypervisor_lp_find_tmax` (double t1, double t2)
- unsigned `sc_hypervisor_lp_execute_dichotomy` (int ns, int nw, double w_in_s[ns][nw], unsigned solve_lp_integer, void *specific_data, double tmin, double tmax, double smallest_tmax, double(*lp_estimated_distrib_func)(int ns, int nw, double draft_w_in_s[ns][nw], unsigned is_integer, double tmax, void *specific_data))

30.43 `sc_hypervisor_monitoring.h` File Reference

```
#include <sc_hypervisor.h>
```

Data Structures

- struct `sc_hypervisor_resize_ack`
- struct `sc_hypervisor_wrapper`

Functions

- struct [sc_hypervisor_wrapper](#) * [sc_hypervisor_get_wrapper](#) (unsigned sched_ctx)
- unsigned * [sc_hypervisor_get_sched_ctxs](#) ()
- int [sc_hypervisor_get_nsched_ctxs](#) ()
- int [sc_hypervisor_get_nworkers_ctx](#) (unsigned sched_ctx, enum [starpu_worker_archtype](#) arch)
- double [sc_hypervisor_get_elapsed_flops_per_sched_ctx](#) (struct [sc_hypervisor_wrapper](#) *sc_w)
- double [sc_hypervisor_get_total_elapsed_flops_per_sched_ctx](#) (struct [sc_hypervisor_wrapper](#) *sc_w)
- double [sc_hypervisor_get_speed_per_worker_type](#) (struct [sc_hypervisor_wrapper](#) *sc_w, enum [starpu_worker_archtype](#) arch)
- double [sc_hypervisor_get_speed](#) (struct [sc_hypervisor_wrapper](#) *sc_w, enum [starpu_worker_archtype](#) arch)

30.44 sc_hypervisor_policy.h File Reference

```
#include <sc_hypervisor.h>
```

Data Structures

- struct [types_of_workers](#)
- struct [sc_hypervisor_policy_task_pool](#)

Macros

- #define [HYPERVISOR_REDIM_SAMPLE](#)
- #define [HYPERVISOR_START_REDIM_SAMPLE](#)
- #define [SC_NOTHING](#)
- #define [SC_IDLE](#)
- #define [SC_SPEED](#)

Functions

- void [sc_hypervisor_policy_add_task_to_pool](#) (struct [starpu_codelet](#) *cl, unsigned sched_ctx, uint32_t footprint, struct [sc_hypervisor_policy_task_pool](#) **task_pools, size_t data_size)
- void [sc_hypervisor_policy_remove_task_from_pool](#) (struct [starpu_task](#) *task, uint32_t footprint, struct [sc_hypervisor_policy_task_pool](#) **task_pools)
- struct [sc_hypervisor_policy_task_pool](#) * [sc_hypervisor_policy_clone_task_pool](#) (struct [sc_hypervisor_policy_task_pool](#) *tp)
- void [sc_hypervisor_get_tasks_times](#) (int nw, int nt, double times[nw][nt], int *workers, unsigned size_ctxs, struct [sc_hypervisor_policy_task_pool](#) *task_pools)
- unsigned [sc_hypervisor_find_lowest_prio_sched_ctx](#) (unsigned req_sched_ctx, int nworkers_to_move)
- int * [sc_hypervisor_get_idlest_workers](#) (unsigned sched_ctx, int *nworkers, enum [starpu_worker_archtype](#) arch)
- int * [sc_hypervisor_get_idlest_workers_in_list](#) (int *start, int *workers, int nall_workers, int *nworkers, enum [starpu_worker_archtype](#) arch)
- int [sc_hypervisor_get_movable_nworkers](#) (struct [sc_hypervisor_policy_config](#) *config, unsigned sched_ctx, enum [starpu_worker_archtype](#) arch)
- int [sc_hypervisor_compute_nworkers_to_move](#) (unsigned req_sched_ctx)

- unsigned `sc_hypervisor_policy_resize` (unsigned sender_sched_ctx, unsigned receiver_sched_ctx, unsigned force_resize, unsigned now)
- unsigned `sc_hypervisor_policy_resize_to_unknown_receiver` (unsigned sender_sched_ctx, unsigned now)
- double `sc_hypervisor_get_ctx_speed` (struct `sc_hypervisor_wrapper` *sc_w)
- double `sc_hypervisor_get_slowest_ctx_exec_time` (void)
- double `sc_hypervisor_get_fastest_ctx_exec_time` (void)
- double `sc_hypervisor_get_speed_per_worker` (struct `sc_hypervisor_wrapper` *sc_w, unsigned worker)
- double `sc_hypervisor_get_speed_per_worker_type` (struct `sc_hypervisor_wrapper` *sc_w, enum `starpu_worker_archtype` arch)
- double `sc_hypervisor_get_ref_speed_per_worker_type` (struct `sc_hypervisor_wrapper` *sc_w, enum `starpu_worker_archtype` arch)
- double `sc_hypervisor_get_avg_speed` (enum `starpu_worker_archtype` arch)
- void `sc_hypervisor_check_if_consider_max` (struct `types_of_workers` *tw)
- void `sc_hypervisor_group_workers_by_type` (struct `types_of_workers` *tw, int *total_nw)
- enum `starpu_worker_archtype` `sc_hypervisor_get_arch_for_index` (unsigned w, struct `types_of_workers` *tw)
- unsigned `sc_hypervisor_get_index_for_arch` (enum `starpu_worker_archtype` arch, struct `types_of_workers` *tw)
- unsigned `sc_hypervisor_criteria_fulfilled` (unsigned sched_ctx, int worker)
- unsigned `sc_hypervisor_check_idle` (unsigned sched_ctx, int worker)
- unsigned `sc_hypervisor_check_speed_gap_btw_ctxs` (unsigned *sched_ctxs, int nsched_ctxs, int *workers, int nworkers)
- unsigned `sc_hypervisor_check_speed_gap_btw_ctxs_on_level` (int level, int *workers_in, int nworkers_in, unsigned father_sched_ctx_id, unsigned **sched_ctxs, int *nsched_ctxs)
- unsigned `sc_hypervisor_get_resize_criteria` ()
- struct `types_of_workers` * `sc_hypervisor_get_types_of_workers` (int *workers, unsigned nworkers)

30.44.1 Data Structure Documentation

30.44.1.1 struct `types_of_workers`

Data Fields

unsigned	ncpus	
unsigned	ncuda	
unsigned	nw	

Chapter 31

Deprecated List

Global [starpu_codelet::cpu_func](#)

Optional field which has been made deprecated. One should use instead the field [starpu_codelet::cpu_funcs](#).

Global [starpu_codelet::cuda_func](#)

Optional field which has been made deprecated. One should use instead the [starpu_codelet::cuda_funcs](#) field.

Global [starpu_codelet::opencl_func](#)

Optional field which has been made deprecated. One should use instead the [starpu_codelet::opencl_funcs](#) field.

Global [starpu_data_free_pinned_if_possible](#)

Equivalent to [starpu_free\(\)](#). This macro is provided to avoid breaking old codes.

Global [starpu_data_malloc_pinned_if_possible](#)

Equivalent to [starpu_malloc\(\)](#). This macro is provided to avoid breaking old codes.

Global [starpu_mpi_initialize](#) (void)

This function has been made deprecated. One should use instead the function [starpu_mpi_init\(\)](#). This function does not call `MPI_Init()`, it should be called beforehand.

Global [starpu_mpi_initialize_extended](#) (int *rank, int *world_size)

This function has been made deprecated. One should use instead the function [starpu_mpi_init\(\)](#). MPI will be initialized by `starpumpi` by calling `MPI_Init_Thread(argc, argv, MPI_THREAD_SERIALIZED, ...)`.

Global [STARPU_MULTIPLE_CPU_IMPLEMENTATIONS](#)

Setting the field [starpu_codelet::cpu_func](#) with this macro indicates the codelet will have several implementations. The use of this macro is deprecated. One should always only define the field [starpu_codelet::cpu_funcs](#).

Global [STARPU_MULTIPLE_CUDA_IMPLEMENTATIONS](#)

Setting the field [starpu_codelet::cuda_func](#) with this macro indicates the codelet will have several implementations. The use of this macro is deprecated. One should always only define the field [starpu_codelet::cuda_funcs](#).

Global [STARPU_MULTIPLE_OPENCL_IMPLEMENTATIONS](#)

Setting the field [starpu_codelet::opencl_func](#) with this macro indicates the codelet will have several implementations. The use of this macro is deprecated. One should always only define the field [starpu_codelet::opencl_funcs](#).

Part VI

Appendix

Chapter 32

Full Source Code for the 'Scaling a Vector' Example

32.1 Main Application

```
/*
 * This example demonstrates how to use StarPU to scale an array by a factor.
 * It shows how to manipulate data with StarPU's data management library.
 * 1- how to declare a piece of data to StarPU (starpu_vector_data_register)
 * 2- how to describe which data are accessed by a task (task->handles[0])
 * 3- how a kernel can manipulate the data (buffers[0].vector.ptr)
 */
#include <starpu.h>

#define    NX    2048

extern void scal_cpu_func(void *buffers[], void *_args);
extern void scal_sse_func(void *buffers[], void *_args);
extern void scal_cuda_func(void *buffers[], void *_args);
extern void scal_opencil_func(void *buffers[], void *_args);

static struct starpu_codelet cl = {
    .where = STARPU_CPU | STARPU_CUDA | STARPU_OPENCL,
    /* CPU implementation of the codelet */
    .cpu_funcs = { scal_cpu_func, scal_sse_func },
    .cpu_funcs_name = { "scal_cpu_func", "scal_sse_func" },
#ifdef STARPU_USE_CUDA
    /* CUDA implementation of the codelet */
    .cuda_funcs = { scal_cuda_func },
#endif
#ifdef STARPU_USE_OPENCL
    /* OpenCL implementation of the codelet */
    .opencil_funcs = { scal_opencil_func },
#endif
    .nbuffers = 1,
    .modes = { STARPU_RW }
};

#ifdef STARPU_USE_OPENCL
struct starpu_opencil_program programs;
#endif

int main(int argc, char **argv)
{
    /* We consider a vector of float that is initialized just as any of C
     * data */
    float vector[NX];
    unsigned i;
    for (i = 0; i < NX; i++)
        vector[i] = 1.0f;

    fprintf(stderr, "BEFORE: First element was %f\n", vector[0]);

    /* Initialize StarPU with default configuration */
    starpu_init(NULL);

#ifdef STARPU_USE_OPENCL
    starpu_opencil_load_opencil_from_file(
        "examples/basic_examples/vector_scal_opencil_kernel.cl", &programs, NULL);
#endif
}
```

```

/* Tell StaPU to associate the "vector" vector with the "vector_handle"
 * identifier. When a task needs to access a piece of data, it should
 * refer to the handle that is associated to it.
 * In the case of the "vector" data interface:
 * - the first argument of the registration method is a pointer to the
 *   handle that should describe the data
 * - the second argument is the memory node where the data (ie. "vector")
 *   resides initially: STARPU_MAIN_RAM stands for an address in main memory, as
 *   opposed to an address on a GPU for instance.
 * - the third argument is the address of the vector in RAM
 * - the fourth argument is the number of elements in the vector
 * - the fifth argument is the size of each element.
 */
starpu_data_handle_t vector_handle;
starpu_vector_data_register(&vector_handle, STARPU_MAIN_RAM,
    (uintptr_t)vector,
    NX, sizeof(vector[0]));

float factor = 3.14;

/* create a synchronous task: any call to starpu_task_submit will block
 * until it is terminated */
struct starpu_task *task = starpu_task_create();
task->synchronous = 1;

task->cl = &cl;

/* the codelet manipulates one buffer in RW mode */
task->handles[0] = vector_handle;

/* an argument is passed to the codelet, beware that this is a
 * READ-ONLY buffer and that the codelet may be given a pointer to a
 * COPY of the argument */
task->cl_arg = &factor;
task->cl_arg_size = sizeof(factor);

/* execute the task on any eligible computational ressource */
starpu_task_submit(task);

/* StarPU does not need to manipulate the array anymore so we can stop
 * monitoring it */
starpu_data_unregister(vector_handle);

#ifdef STARPU_USE_OPENCL
    starpu_opencil_unload_opencil(&programs);
#endif

/* terminate StarPU, no task can be submitted after */
starpu_shutdown();

fprintf(stderr, "AFTER First element is %f\n", vector[0]);

return 0;
}

```

32.2 CPU Kernel

```

#include <starpu.h>
#include <xmmintrin.h>

/* This kernel takes a buffer and scales it by a constant factor */
void scal_cpu_func(void *buffers[], void *cl_arg)
{
    unsigned i;
    float *factor = cl_arg;

    /*
     * The "buffers" array matches the task->handles array: for instance
     * task->handles[0] is a handle that corresponds to a data with
     * vector "interface", so that the first entry of the array in the
     * codelet is a pointer to a structure describing such a vector (ie.
     * struct starpu_vector_interface *). Here, we therefore manipulate
     * the buffers[0] element as a vector: nx gives the number of elements
     * in the array, ptr gives the location of the array (that was possibly
     * migrated/replicated), and elemsize gives the size of each elements.
     */
    struct starpu_vector_interface *vector = buffers[0];

    /* length of the vector */
    unsigned n = STARPU_VECTOR_GET_NX(vector);

```

```

/* get a pointer to the local copy of the vector: note that we have to
 * cast it in (float *) since a vector could contain any type of
 * elements so that the .ptr field is actually a uintptr_t */
float *val = (float *)STARPU_VECTOR_GET_PTR(vector);

/* scale the vector */
for (i = 0; i < n; i++)
    val[i] *= *factor;
}

void scal_sse_func(void *buffers[], void *cl_arg)
{
    float *vector = (float *) STARPU_VECTOR_GET_PTR(buffers[0]);
    unsigned int n = STARPU_VECTOR_GET_NX(buffers[0]);
    unsigned int n_iterations = n/4;

    __m128 *VECTOR = (__m128*) vector;
    __m128 FACTOR STARPU_ATTRIBUTE_ALIGNED(16);
    float factor = *(float *) cl_arg;
    FACTOR = _mm_set1_ps(factor);

    unsigned int i;
    for (i = 0; i < n_iterations; i++)
        VECTOR[i] = _mm_mul_ps(FACTOR, VECTOR[i]);

    unsigned int remainder = n%4;
    if (remainder != 0)
    {
        unsigned int start = 4 * n_iterations;
        for (i = start; i < start+remainder; ++i)
        {
            vector[i] = factor * vector[i];
        }
    }
}

```

32.3 CUDA Kernel

```

#include <starpu.h>

static __global__ void vector_mult_cuda(unsigned n, float *val,
                                       float factor)
{
    unsigned i = blockIdx.x*blockDim.x + threadIdx.x;
    if (i < n)
        val[i] *= factor;
}

extern "C" void scal_cuda_func(void *buffers[], void *_args)
{
    float *factor = (float *)_args;

    /* length of the vector */
    unsigned n = STARPU_VECTOR_GET_NX(buffers[0]);
    /* local copy of the vector pointer */
    float *val = (float *)STARPU_VECTOR_GET_PTR(buffers[0]);
    unsigned threads_per_block = 64;
    unsigned nblocks = (n + threads_per_block-1) / threads_per_block;

    vector_mult_cuda<<<nblocks, threads_per_block, 0, starpu_cuda_get_local_stream()>>>
        (n, val, *factor);

    cudaStreamSynchronize(starpu_cuda_get_local_stream());
}

```

32.4 OpenCL Kernel

32.4.1 Invoking the Kernel

```

#include <starpu.h>

extern struct starpu_opencil_program programs;

void scal_opencil_func(void *buffers[], void *_args)

```

```

{
    float *factor = _args;
    int id, devid, err;
    cl_kernel kernel;
    cl_command_queue queue;
    cl_event event;

    /* length of the vector */
    unsigned n = STARPU_VECTOR_GET_NX(buffers[0]);
    /* OpenCL copy of the vector pointer */
    cl_mem val = (cl_mem)STARPU_VECTOR_GET_DEV_HANDLE(buffers[0]);

    { /* OpenCL specific code */
        id = starpu_worker_get_id();
        devid = starpu_worker_get_devid(id);

        err = starpu_openc1_load_kernel(&kernel, &queue,
                                       &programs,
                                       "vector_mult_openc1", /* Name of the codelet */
                                       devid);
        if (err != CL_SUCCESS) STARPU_OPENC1_REPORT_ERROR(err);

        err = clSetKernelArg(kernel, 0, sizeof(n), &n);
        err |= clSetKernelArg(kernel, 1, sizeof(val), &val);
        err |= clSetKernelArg(kernel, 2, sizeof(*factor), factor);
        if (err) STARPU_OPENC1_REPORT_ERROR(err);
    }

    { /* OpenCL specific code */
        size_t global=n;
        size_t local;
        size_t s;
        cl_device_id device;

        starpu_openc1_get_device(devid, &device);
        err = clGetKernelWorkGroupInfo (kernel, device, CL_KERNEL_WORK_GROUP_SIZE,
                                         sizeof(local), &local, &s);
        if (err != CL_SUCCESS) STARPU_OPENC1_REPORT_ERROR(err);
        if (local > global) local=global;

        err = clEnqueueNDRangeKernel(queue, kernel, 1, NULL, &global, &local, 0,
                                     NULL, &event);
        if (err != CL_SUCCESS) STARPU_OPENC1_REPORT_ERROR(err);
    }

    { /* OpenCL specific code */
        clFinish(queue);
        starpu_openc1_collect_stats(event);
        clReleaseEvent(event);

        starpu_openc1_release_kernel(kernel);
    }
}

```

32.4.2 Source of the Kernel

```

__kernel void vector_mult_openc1(int nx, __global float* val, float factor)
{
    const int i = get_global_id(0);
    if (i < nx) {
        val[i] *= factor;
    }
}

```

Chapter 33

GNU Free Documentation License

Version 1.3, 3 November 2008

Copyright

2000, 2001, 2002, 2007, 2008 Free Software Foundation, Inc. <http://fsf.org/>

Everyone is permitted to copy and distribute verbatim copies of this license document, but changing it is not allowed.

1. PREAMBLE

The purpose of this License is to make a manual, textbook, or other functional and useful document *free* in the sense of freedom: to assure everyone the effective freedom to copy and redistribute it, with or without modifying it, either commercially or noncommercially. Secondly, this License preserves for the author and publisher a way to get credit for their work, while not being considered responsible for modifications made by others.

This License is a kind of “copyleft”, which means that derivative works of the document must themselves be free in the same sense. It complements the GNU General Public License, which is a copyleft license designed for free software.

We have designed this License in order to use it for manuals for free software, because free software needs free documentation: a free program should come with manuals providing the same freedoms that the software does. But this License is not limited to software manuals; it can be used for any textual work, regardless of subject matter or whether it is published as a printed book. We recommend this License principally for works whose purpose is instruction or reference.

2. APPLICABILITY AND DEFINITIONS

This License applies to any manual or other work, in any medium, that contains a notice placed by the copyright holder saying it can be distributed under the terms of this License. Such a notice grants a world-wide, royalty-free license, unlimited in duration, to use that work under the conditions stated herein. The “Document”, below, refers to any such manual or work. Any member of the public is a licensee, and is addressed as “you”. You accept the license if you copy, modify or distribute the work in a way requiring permission under copyright law.

A “Modified Version” of the Document means any work containing the Document or a portion of it, either copied verbatim, or with modifications and/or translated into another language.

A “Secondary Section” is a named appendix or a front-matter section of the Document that deals exclusively with the relationship of the publishers or authors of the Document to the Document’s overall subject (or to related matters) and contains nothing that could fall directly within that overall subject. (Thus, if the Document is in part a textbook of mathematics, a Secondary Section may not explain any mathematics.) The relationship could be a matter of historical connection with the subject or with related matters, or of legal, commercial, philosophical, ethical or political position regarding them.

The “Invariant Sections” are certain Secondary Sections whose titles are designated, as being those of Invariant Sections, in the notice that says that the Document is released under this License. If a section does not fit the above definition of Secondary then it is not allowed to be designated as Invariant. The Document may contain zero Invariant Sections. If the Document does not identify any Invariant Sections then there are none.

The “Cover Texts” are certain short passages of text that are listed, as Front-Cover Texts or Back-Cover Texts, in the notice that says that the Document is released under this License. A Front-Cover Text may be at most 5 words, and a Back-Cover Text may be at most 25 words.

A “Transparent” copy of the Document means a machine-readable copy, represented in a format whose specification is available to the general public, that is suitable for revising the document straightforwardly with generic text editors or (for images composed of pixels) generic paint programs or (for drawings) some widely available drawing editor, and that is suitable for input to text formatters or for automatic translation to a variety of formats suitable for input to text formatters. A copy made in an otherwise Transparent file format whose markup, or absence of markup, has been arranged to thwart or discourage subsequent modification by readers is not Transparent. An image format is not Transparent if used for any substantial amount of text. A copy that is not “Transparent” is called “Opaque”.

Examples of suitable formats for Transparent copies include plain ASCII without markup, Texinfo input format, LaTeX input format, SGML or XML using a publicly available DTD, and standard-conforming simple HTML, PostScript or PDF designed for human modification. Examples of transparent image formats include PNG, XCF and JPG. Opaque formats include proprietary formats that can be read and edited only by proprietary word processors, SGML or XML for which the DTD and/or processing tools are not generally available, and the machine-generated HTML, PostScript or PDF produced by some word processors for output purposes only.

The “Title Page” means, for a printed book, the title page itself, plus such following pages as are needed to hold, legibly, the material this License requires to appear in the title page. For works in formats which do not have any title page as such, “Title Page” means the text near the most prominent appearance of the work's title, preceding the beginning of the body of the text.

The “publisher” means any person or entity that distributes copies of the Document to the public.

A section “Entitled XYZ” means a named subunit of the Document whose title either is precisely XYZ or contains XYZ in parentheses following text that translates XYZ in another language. (Here XYZ stands for a specific section name mentioned below, such as “Acknowledgements”, “Dedications”, “Endorsements”, or “History”.) To “Preserve the Title” of such a section when you modify the Document means that it remains a section “Entitled XYZ” according to this definition.

The Document may include Warranty Disclaimers next to the notice which states that this License applies to the Document. These Warranty Disclaimers are considered to be included by reference in this License, but only as regards disclaiming warranties: any other implication that these Warranty Disclaimers may have is void and has no effect on the meaning of this License.

3. VERBATIM COPYING

You may copy and distribute the Document in any medium, either commercially or noncommercially, provided that this License, the copyright notices, and the license notice saying this License applies to the Document are reproduced in all copies, and that you add no other conditions whatsoever to those of this License. You may not use technical measures to obstruct or control the reading or further copying of the copies you make or distribute. However, you may accept compensation in exchange for copies. If you distribute a large enough number of copies you must also follow the conditions in section 3.

You may also lend copies, under the same conditions stated above, and you may publicly display copies.

4. COPYING IN QUANTITY

If you publish printed copies (or copies in media that commonly have printed covers) of the Document, numbering more than 100, and the Document's license notice requires Cover Texts, you must enclose the copies in covers that carry, clearly and legibly, all these Cover Texts: Front-Cover Texts on the front cover, and Back-Cover Texts on the back cover. Both covers must also clearly and legibly identify you as the publisher of these copies. The front cover must present the full title with all words of the title equally prominent and visible. You may add other material on the covers in addition. Copying with changes limited to the covers, as long as they preserve the title of the Document and satisfy these conditions, can be treated as verbatim copying in other respects.

If the required texts for either cover are too voluminous to fit legibly, you should put the first ones listed (as many as fit reasonably) on the actual cover, and continue the rest onto adjacent pages.

If you publish or distribute Opaque copies of the Document numbering more than 100, you must either include a machine-readable Transparent copy along with each Opaque copy, or state in or with each Opaque copy a computer-network location from which the general network-using public has access to download using public-standard network protocols a complete Transparent copy of the Document, free of added material. If you use the latter option, you must take reasonably prudent steps, when you begin distribution of Opaque copies in quantity, to ensure that this Transparent copy will remain thus accessible at the stated location until at least one year after the last time you distribute an Opaque copy (directly or through your agents or retailers) of that edition to the public.

It is requested, but not required, that you contact the authors of the Document well before redistributing any large number of copies, to give them a chance to provide you with an updated version of the Document.

5. MODIFICATIONS

You may copy and distribute a Modified Version of the Document under the conditions of sections 2 and 3 above, provided that you release the Modified Version under precisely this License, with the Modified Version filling the role of the Document, thus licensing distribution and modification of the Modified Version to whoever possesses a copy of it. In addition, you must do these things in the Modified Version:

- (a) Use in the Title Page (and on the covers, if any) a title distinct from that of the Document, and from those of previous versions (which should, if there were any, be listed in the History section of the Document). You may use the same title as a previous version if the original publisher of that version gives permission.
- (b) List on the Title Page, as authors, one or more persons or entities responsible for authorship of the modifications in the Modified Version, together with at least five of the principal authors of the Document (all of its principal authors, if it has fewer than five), unless they release you from this requirement.
- (c) State on the Title page the name of the publisher of the Modified Version, as the publisher.
- (d) Preserve all the copyright notices of the Document.
- (e) Add an appropriate copyright notice for your modifications adjacent to the other copyright notices.
- (f) Include, immediately after the copyright notices, a license notice giving the public permission to use the Modified Version under the terms of this License, in the form shown in the Addendum below.
- (g) Preserve in that license notice the full lists of Invariant Sections and required Cover Texts given in the Document's license notice.
- (h) Include an unaltered copy of this License.
- (i) Preserve the section Entitled "History", Preserve its Title, and add to it an item stating at least the title, year, new authors, and publisher of the Modified Version as given on the Title Page. If there is no section Entitled "History" in the Document, create one stating the title, year, authors, and publisher of the Document as given on its Title Page, then add an item describing the Modified Version as stated in the previous sentence.
- (j) Preserve the network location, if any, given in the Document for public access to a Transparent copy of the Document, and likewise the network locations given in the Document for previous versions it was based on. These may be placed in the "History" section. You may omit a network location for a work that was published at least four years before the Document itself, or if the original publisher of the version it refers to gives permission.
- (k) For any section Entitled "Acknowledgements" or "Dedications", Preserve the Title of the section, and preserve in the section all the substance and tone of each of the contributor acknowledgements and/or dedications given therein.
- (l) Preserve all the Invariant Sections of the Document, unaltered in their text and in their titles. Section numbers or the equivalent are not considered part of the section titles.
- (m) Delete any section Entitled "Endorsements". Such a section may not be included in the Modified Version.
- (n) Do not retitle any existing section to be Entitled "Endorsements" or to conflict in title with any Invariant Section.
- (o) Preserve any Warranty Disclaimers.

If the Modified Version includes new front-matter sections or appendices that qualify as Secondary Sections and contain no material copied from the Document, you may at your option designate some or all of these sections as invariant. To do this, add their titles to the list of Invariant Sections in the Modified Version's license notice. These titles must be distinct from any other section titles.

You may add a section Entitled "Endorsements", provided it contains nothing but endorsements of your Modified Version by various parties—for example, statements of peer review or that the text has been approved by an organization as the authoritative definition of a standard.

You may add a passage of up to five words as a Front-Cover Text, and a passage of up to 25 words as a Back-Cover Text, to the end of the list of Cover Texts in the Modified Version. Only one passage of Front-Cover Text and one of Back-Cover Text may be added by (or through arrangements made by) any one entity. If the Document already includes a cover text for the same cover, previously added by you or by arrangement made by the same entity you are acting on behalf of, you may not add another; but you may replace the old one, on explicit permission from the previous publisher that added the old one.

The author(s) and publisher(s) of the Document do not by this License give permission to use their names for publicity for or to assert or imply endorsement of any Modified Version.

6. COMBINING DOCUMENTS

You may combine the Document with other documents released under this License, under the terms defined in section 4 above for modified versions, provided that you include in the combination all of the Invariant Sections of all of the original documents, unmodified, and list them all as Invariant Sections of your combined work in its license notice, and that you preserve all their Warranty Disclaimers.

The combined work need only contain one copy of this License, and multiple identical Invariant Sections may be replaced with a single copy. If there are multiple Invariant Sections with the same name but different contents, make the title of each such section unique by adding at the end of it, in parentheses, the name of the original author or publisher of that section if known, or else a unique number. Make the same adjustment to the section titles in the list of Invariant Sections in the license notice of the combined work.

In the combination, you must combine any sections Entitled "History" in the various original documents, forming one section Entitled "History"; likewise combine any sections Entitled "Acknowledgements", and any sections Entitled "Dedications". You must delete all sections Entitled "Endorsements."

7. COLLECTIONS OF DOCUMENTS

You may make a collection consisting of the Document and other documents released under this License, and replace the individual copies of this License in the various documents with a single copy that is included in the collection, provided that you follow the rules of this License for verbatim copying of each of the documents in all other respects.

You may extract a single document from such a collection, and distribute it individually under this License, provided you insert a copy of this License into the extracted document, and follow this License in all other respects regarding verbatim copying of that document.

8. AGGREGATION WITH INDEPENDENT WORKS

A compilation of the Document or its derivatives with other separate and independent documents or works, in or on a volume of a storage or distribution medium, is called an "aggregate" if the copyright resulting from the compilation is not used to limit the legal rights of the compilation's users beyond what the individual works permit. When the Document is included in an aggregate, this License does not apply to the other works in the aggregate which are not themselves derivative works of the Document.

If the Cover Text requirement of section 3 is applicable to these copies of the Document, then if the Document is less than one half of the entire aggregate, the Document's Cover Texts may be placed on covers that bracket the Document within the aggregate, or the electronic equivalent of covers if the Document is in electronic form. Otherwise they must appear on printed covers that bracket the whole aggregate.

9. TRANSLATION

Translation is considered a kind of modification, so you may distribute translations of the Document under the terms of section 4. Replacing Invariant Sections with translations requires special permission from their copyright holders, but you may include translations of some or all Invariant Sections in addition to the original versions of these Invariant Sections. You may include a translation of this License, and all the license notices in the Document, and any Warranty Disclaimers, provided that you also include the original English version

of this License and the original versions of those notices and disclaimers. In case of a disagreement between the translation and the original version of this License or a notice or disclaimer, the original version will prevail.

If a section in the Document is Entitled "Acknowledgements", "Dedications", or "History", the requirement (section 4) to Preserve its Title (section 1) will typically require changing the actual title.

10. TERMINATION

You may not copy, modify, sublicense, or distribute the Document except as expressly provided under this License. Any attempt otherwise to copy, modify, sublicense, or distribute it is void, and will automatically terminate your rights under this License.

However, if you cease all violation of this License, then your license from a particular copyright holder is reinstated (a) provisionally, unless and until the copyright holder explicitly and finally terminates your license, and (b) permanently, if the copyright holder fails to notify you of the violation by some reasonable means prior to 60 days after the cessation.

Moreover, your license from a particular copyright holder is reinstated permanently if the copyright holder notifies you of the violation by some reasonable means, this is the first time you have received notice of violation of this License (for any work) from that copyright holder, and you cure the violation prior to 30 days after your receipt of the notice.

Termination of your rights under this section does not terminate the licenses of parties who have received copies or rights from you under this License. If your rights have been terminated and not permanently reinstated, receipt of a copy of some or all of the same material does not give you any rights to use it.

11. FUTURE REVISIONS OF THIS LICENSE

The Free Software Foundation may publish new, revised versions of the GNU Free Documentation License from time to time. Such new versions will be similar in spirit to the present version, but may differ in detail to address new problems or concerns. See <http://www.gnu.org/copyleft/>.

Each version of the License is given a distinguishing version number. If the Document specifies that a particular numbered version of this License "or any later version" applies to it, you have the option of following the terms and conditions either of that specified version or of any later version that has been published (not as a draft) by the Free Software Foundation. If the Document does not specify a version number of this License, you may choose any version ever published (not as a draft) by the Free Software Foundation. If the Document specifies that a proxy can decide which future versions of this License can be used, that proxy's public statement of acceptance of a version permanently authorizes you to choose that version for the Document.

12. RELICENSING

"Massive Multiauthor Collaboration Site" (or "MMC Site") means any World Wide Web server that publishes copyrightable works and also provides prominent facilities for anybody to edit those works. A public wiki that anybody can edit is an example of such a server. A "Massive Multiauthor Collaboration" (or "MMC") contained in the site means any set of copyrightable works thus published on the MMC site.

"CC-BY-SA" means the Creative Commons Attribution-Share Alike 3.0 license published by Creative Commons Corporation, a not-for-profit corporation with a principal place of business in San Francisco, California, as well as future copyleft versions of that license published by that same organization.

"Incorporate" means to publish or republish a Document, in whole or in part, as part of another Document.

An MMC is "eligible for relicensing" if it is licensed under this License, and if all works that were first published under this License somewhere other than this MMC, and subsequently incorporated in whole or in part into the MMC, (1) had no cover texts or invariant sections, and (2) were thus incorporated prior to November 1, 2008.

The operator of an MMC Site may republish an MMC contained in the site under CC-BY-SA on the same site at any time before August 1, 2009, provided the MMC is eligible for relicensing.

33.1 ADDENDUM: How to use this License for your documents

To use this License in a document you have written, include a copy of the License in the document and put the following copyright and license notices just after the title page:

Copyright (C) *year your name*. Permission is granted to copy, distribute and/or modify this document under the terms of the GNU Free Documentation License, Version 1.3 or any later version published by the Free Software Foundation; with no Invariant Sections, no Front-Cover Texts, and no Back-Cover Texts. A copy of the license is included in the section entitled "GNU Free Documentation License".

If you have Invariant Sections, Front-Cover Texts and Back-Cover Texts, replace the "with...Texts." line with this:

with the Invariant Sections being *list their titles*, with the Front-Cover Texts being *list*, and with the Back-Cover Texts being *list*.

If you have Invariant Sections without Cover Texts, or some other combination of the three, merge those two alternatives to suit the situation.

If your document contains nontrivial examples of program code, we recommend releasing these examples in parallel under your choice of free software license, such as the GNU General Public License, to permit their use in free software.

Part VII

Index

Index

`__configure__ --disable-asynchronous-copy, 174`
`__configure__ --disable-asynchronous-cuda-copy, 174`
`__configure__ --disable-asynchronous-mic-copy, 174`
`__configure__ --disable-asynchronous-opencl-copy, 174`
`__configure__ --disable-build-doc, 173`
`__configure__ --disable-build-examples, 176`
`__configure__ --disable-build-tests, 176`
`__configure__ --disable-cpu, 174`
`__configure__ --disable-cuda, 174`
`__configure__ --disable-cuda-memcpy-peer, 174`
`__configure__ --disable-fortran, 175`
`__configure__ --disable-gcc-extensions, 175`
`__configure__ --disable-glpk, 176`
`__configure__ --disable-icc, 173`
`__configure__ --disable-opencl, 174`
`__configure__ --disable-socl, 175`
`__configure__ --disable-starpu-top, 175`
`__configure__ --disable-starpuftt, 176`
`__configure__ --enable-allocation-cache, 175`
`__configure__ --enable-blas-lib, 175`
`__configure__ --enable-blocking-drivers, 174`
`__configure__ --enable-calibration-heuristic, 176`
`__configure__ --enable-coverage, 173`
`__configure__ --enable-debug, 173`
`__configure__ --enable-fast, 173`
`__configure__ --enable-fxt-lock, 175`
`__configure__ --enable-leveldb, 175`
`__configure__ --enable-long-check, 173`
`__configure__ --enable-max-sched-ctxs, 174`
`__configure__ --enable-maxbuffers, 175`
`__configure__ --enable-maxcpus, 174`
`__configure__ --enable-maxcudadev, 174`
`__configure__ --enable-maximplementations, 174`
`__configure__ --enable-maxmicthreads, 174`
`__configure__ --enable-maxnodes, 174`
`__configure__ --enable-maxopencldev, 174`
`__configure__ --enable-memory-stats, 176`
`__configure__ --enable-model-debug, 175`
`__configure__ --enable-mpi-progression-hook, 175`
`__configure__ --enable-mpi-verbose, 175`
`__configure__ --enable-new-check, 173`
`__configure__ --enable-opencl-simulator, 174`
`__configure__ --enable-opengl-render, 175`
`__configure__ --enable-openmp, 175`
`__configure__ --enable-perf-debug, 175`
`__configure__ --enable-quick-check, 173`
`__configure__ --enable-sc-hypervisor, 176`
`__configure__ --enable-simgrid, 176`
`__configure__ --enable-spinlock-check, 173`
`__configure__ --enable-starpuftt-examples, 176`
`__configure__ --enable-stats, 175`
`__configure__ --enable-verbose, 173`
`__configure__ --mic-host, 175`
`__configure__ --with-atlas-dir, 176`
`__configure__ --with-coi-dir, 175`
`__configure__ --with-cuda-dir, 174`
`__configure__ --with-cuda-include-dir, 174`
`__configure__ --with-cuda-lib-dir, 174`
`__configure__ --with-fxt, 176`
`__configure__ --with-goto-dir, 176`
`__configure__ --with-hwloc, 173`
`__configure__ --with-mkl-cflags, 176`
`__configure__ --with-mkl-ldflags, 176`
`__configure__ --with-mpicc, 175`
`__configure__ --with-opencl-dir, 174`
`__configure__ --with-opencl-include-dir, 174`
`__configure__ --with-opencl-lib-dir, 174`
`__configure__ --with-perf-model-dir, 176`
`__configure__ --with-simgrid-dir, 176`
`__configure__ --with-simgrid-include-dir, 176`
`__configure__ --with-simgrid-lib-dir, 176`
`__configure__ --with-smpirun, 176`
`__configure__ --without-hwloc, 173`
`env__ OCL_ICD_VENDORS, 168`
`env__ SC_HYPERVISOR_LAZY_RESIZE, 172`
`env__ SC_HYPERVISOR_MAX_SPEED_GAP, 172`
`env__ SC_HYPERVISOR_POLICY, 172`
`env__ SC_HYPERVISOR_SAMPLE_CRITERIA, 172`
`env__ SC_HYPERVISOR_START_RESIZE, 172`
`env__ SC_HYPERVISOR_STOP_PRINT, 172`
`env__ SC_HYPERVISOR_TRIGGER_RESIZE, 172`
`env__ SOCL_OCL_LIB_OPENCL, 168`
`env__ STARPU_BUS_CALIBRATE, 167`
`env__ STARPU_BUS_STATS, 171`
`env__ STARPU_CALIBRATE, 167`
`env__ STARPU_CALIBRATE_MINIMUM, 167`
`env__ STARPU_COMM_STATS, 168`
`env__ STARPU_CUDA_PIPELINE, 165`
`env__ STARPU_DISABLE_ASYNCCHRONOUS_COPY, 167`
`env__ STARPU_DISABLE_ASYNCCHRONOUS_CUDA_COPY, 167`
`env__ STARPU_DISABLE_ASYNCCHRONOUS_MIC_COPY, 167`
`env__ STARPU_DISABLE_ASYNCCHRONOUS_OPENCL_COPY, 167`
`env__ STARPU_DISABLE_KERNELS, 171`
`env__ STARPU_DISABLE_PINNING, 167`

- `__env__STARPU_DISK_SWAP`, 170
- `__env__STARPU_DISK_SWAP_BACKEND`, 170
- `__env__STARPU_DISK_SWAP_SIZE`, 170
- `__env__STARPU_ENABLE_CUDA_GPU_GPU_DIR`↔
ECT, 167
- `__env__STARPU_FXT_PREFIX`, 169
- `__env__STARPU_FXT_TRACE`, 169
- `__env__STARPU_GENERATE_TRACE`, 170
- `__env__STARPU_GLOBAL_ARBITER`, 171
- `__env__STARPU_HISTORY_MAX_ERROR`, 171
- `__env__STARPU_HOME`, 169
- `__env__STARPU_HOSTNAME`, 169
- `__env__STARPU_IDLE_FILE`, 171
- `__env__STARPU_IDLE_POWER`, 168
- `__env__STARPU_IDLE_TIME`, 171
- `__env__STARPU_LIMIT_CPU_MEM`, 170
- `__env__STARPU_LIMIT_CUDA_MEM`, 170
- `__env__STARPU_LIMIT_CUDA_devid_MEM`, 169
- `__env__STARPU_LIMIT_MAX_SUBMITTED_TASKS`,
170
- `__env__STARPU_LIMIT_MIN_SUBMITTED_TASKS`,
170
- `__env__STARPU_LIMIT_OPENCL_MEM`, 170
- `__env__STARPU_LIMIT_OPENCL_devid_MEM`, 170
- `__env__STARPU_LOGFILENAME`, 169
- `__env__STARPU_MALLOC_SIMULATION_FOLD`, 169
- `__env__STARPU_MAX_MEMORY_USE`, 170
- `__env__STARPU_MAX_PRIO`, 167
- `__env__STARPU_MAX_WORKERSIZE`, 166
- `__env__STARPU_MEMORY_STATS`, 170
- `__env__STARPU_MIC_PROGRAM_PATH`, 167
- `__env__STARPU_MIC_SINK_PROGRAM_NAME`, 167
- `__env__STARPU_MIC_SINK_PROGRAM_PATH`, 167
- `__env__STARPU_MINIMUM_AVAILABLE_MEM`, 170
- `__env__STARPU_MINIMUM_CLEAN_BUFFERS`, 170
- `__env__STARPU_MIN_PRIO`, 167
- `__env__STARPU_MIN_WORKERSIZE`, 166
- `__env__STARPU_MPI_CACHE`, 168
- `__env__STARPU_MPI_CACHE_STATS`, 168
- `__env__STARPU_MPI_COMM`, 168
- `__env__STARPU_MPI_FAKE_RANK`, 168
- `__env__STARPU_MPI_FAKE_SIZE`, 168
- `__env__STARPU_NCPU`, 165
- `__env__STARPU_NCPUS`, 165
- `__env__STARPU_NCUDA`, 165
- `__env__STARPU_NMIC`, 166
- `__env__STARPU_NMICTHREADS`, 166
- `__env__STARPU_NOPENCL`, 165
- `__env__STARPU_NSCC`, 166
- `__env__STARPU_NWORKER_PER_CUDA`, 165
- `__env__STARPU_OPENCL_ONLY_ON_CPUS`, 165
- `__env__STARPU_OPENCL_ON_CPUS`, 165
- `__env__STARPU_OPENCL_PIPELINE`, 165
- `__env__STARPU_OPENCL_PROGRAM_DIR`, 169
- `__env__STARPU_PATH`, 169
- `__env__STARPU_PCI_FLAT`, 168
- `__env__STARPU_PERF_MODEL_DIR`, 169
- `__env__STARPU_PERF_MODEL_HOMOGENEOU`↔
S_CPU, 169
- `__env__STARPU_PERF_MODEL_HOMOGENEOU`↔
S_CUDA, 169
- `__env__STARPU_PERF_MODEL_HOMOGENEOU`↔
S_MIC, 169
- `__env__STARPU_PERF_MODEL_HOMOGENEOU`↔
S_OPENCL, 169
- `__env__STARPU_PERF_MODEL_HOMOGENEOU`↔
S_SCC, 169
- `__env__STARPU_PREFETCH`, 168
- `__env__STARPU_PROFILING`, 168
- `__env__STARPU_RAND_SEED`, 171
- `__env__STARPU_SCHED`, 167
- `__env__STARPU_SCHED_ALPHA`, 168
- `__env__STARPU_SCHED_BETA`, 168
- `__env__STARPU_SCHED_GAMMA`, 168
- `__env__STARPU_SILENT`, 169
- `__env__STARPU_SIMGRID_CUDA_MALLOC_COST`,
168
- `__env__STARPU_SIMGRID_CUDA_QUEUE_COST`,
168
- `__env__STARPU_SIMGRID_QUEUE_MALLOC_CO`↔
ST, 168
- `__env__STARPU_SINGLE_COMBINED_WORKER`,
166
- `__env__STARPU_STATS`, 171
- `__env__STARPU_SYNTHESIZE_ARITY_COMBINE`↔
D_WORKER, 167
- `__env__STARPU_TARGET_AVAILABLE_MEM`, 170
- `__env__STARPU_TARGET_CLEAN_BUFFERS`, 170
- `__env__STARPU_TASK_BREAK_ON_EXEC`, 171
- `__env__STARPU_TASK_BREAK_ON_POP`, 171
- `__env__STARPU_TASK_BREAK_ON_PUSH`, 171
- `__env__STARPU_TASK_BREAK_ON_SCHED`, 171
- `__env__STARPU_TRACE_BUFFER_SIZE`, 170
- `__env__STARPU_WATCHDOG_CRASH`, 171
- `__env__STARPU_WATCHDOG_DELAY`, 171
- `__env__STARPU_WATCHDOG_TIMEOUT`, 171
- `__env__STARPU_WORKERS_CPUID`, 166
- `__env__STARPU_WORKERS_CUDAID`, 166
- `__env__STARPU_WORKERS_MICID`, 166
- `__env__STARPU_WORKERS_NOBIND`, 166
- `__env__STARPU_WORKERS_OPENCLID`, 166
- `__env__STARPU_WORKERS_SCCID`, 166
- `__env__STARPU_WORKER_STATS`, 171
- `__env__STARPU_WORKER_TREE`, 166
- add
 - starpu_worker_collection, 216
- add_child
 - starpu_sched_component, 465
- add_parent
 - starpu_sched_component, 465
- add_workers
 - starpu_sched_policy, 440
- alloc
 - starpu_disk_ops, 283
- allocate_data_on_node

- starpu_data_interface_ops, 238
- any_to_any
 - starpu_data_copy_methods, 244
- arch_cost_function
 - starpu_perfmodel, 328
- async_full_read
 - starpu_disk_ops, 284
- async_full_write
 - starpu_disk_ops, 284
- async_read
 - starpu_disk_ops, 284
- async_write
 - starpu_disk_ops, 284
- bandwidth
 - starpu_disk_ops, 283
- Bitmap, 210
 - starpu_bitmap_and_get, 212
 - starpu_bitmap_cardinal, 212
 - starpu_bitmap_create, 211
 - starpu_bitmap_destroy, 211
 - starpu_bitmap_first, 213
 - starpu_bitmap_get, 212
 - starpu_bitmap_has_next, 213
 - starpu_bitmap_last, 213
 - starpu_bitmap_next, 213
 - starpu_bitmap_or, 212
 - starpu_bitmap_set, 211
 - starpu_bitmap_unset, 211
 - starpu_bitmap_unset_all, 212
 - starpu_bitmap_unset_and, 212
- bundle
 - starpu_task, 303
- CUDA Extensions, 342
 - STARPU_CUBLAS_REPORT_ERROR, 343
 - STARPU_CUDA_REPORT_ERROR, 343
 - STARPU_MAXCUDADEVs, 343
 - STARPU_USE_CUDA, 343
 - starpu_cublas_init, 345
 - starpu_cublas_report_error, 345
 - starpu_cublas_shutdown, 345
 - starpu_cuda_copy_async_sync, 344
 - starpu_cuda_get_device_properties, 344
 - starpu_cuda_get_local_stream, 344
 - starpu_cuda_report_error, 344
 - starpu_cuda_set_device, 344
- callback
 - starpu_top_param, 421
- callback_arg
 - starpu_task, 299
- callback_arg_free
 - starpu_task, 300
- callback_func
 - starpu_task, 299
- can_copy
 - starpu_data_copy_methods, 241
- can_execute
 - starpu_codelet, 292
- can_pull
 - starpu_sched_component, 466
- can_push
 - starpu_sched_component, 466
- children
 - starpu_sched_component, 465
- cl
 - starpu_task, 298
- cl_arg
 - starpu_task, 299
- cl_arg_free
 - starpu_task, 300
- cl_arg_size
 - starpu_task, 299
- close
 - starpu_disk_ops, 283
- Codelet And Tasks, 289
 - STARPU_CODELET_GET_MODE, 307
 - STARPU_CODELET_GET_NODE, 307
 - STARPU_CODELET_SET_MODE, 307
 - STARPU_CODELET_SET_NODE, 308
 - STARPU_CPU, 304
 - STARPU_CUDA, 304
 - STARPU_MAIN_RAM, 305
 - STARPU_MIC, 305
 - STARPU_MULTIPLE_CPU_IMPLEMENTATIONS, 305
 - STARPU_MULTIPLE_CUDA_IMPLEMENTATIONS, 305
 - STARPU_MULTIPLE_OPENCL_IMPLEMENTATIONS, 305
 - STARPU_NMAXBUFS, 306
 - STARPU_NOWHERE, 304
 - STARPU_OPENCL, 304
 - STARPU_SCC, 305
 - STARPU_TASK_GET_HANDLE, 306
 - STARPU_TASK_GET_MODE, 307
 - STARPU_TASK_GET_NBUFFERS, 306
 - STARPU_TASK_INITIALIZER, 306
 - STARPU_TASK_INVALID, 308
 - STARPU_TASK_SET_HANDLE, 306
 - STARPU_TASK_SET_MODE, 307
 - STARPU_VARIABLE_NBUFFERS, 306
 - starpu_codelet_display_stats, 313
 - starpu_codelet_init, 310
 - starpu_codelet_type, 309
 - starpu_cpu_func_t, 308
 - starpu_create_sync_task, 314
 - starpu_cuda_func_t, 308
 - starpu_iteration_pop, 314
 - starpu_iteration_push, 314
 - starpu_mic_func_t, 308
 - starpu_mic_kernel_t, 309
 - starpu_opencl_func_t, 308
 - starpu_scc_func_t, 309
 - starpu_scc_kernel_t, 309
 - starpu_task_clean, 311
 - starpu_task_create, 310

- starpu_task_destroy, [311](#)
 - starpu_task_dup, [310](#)
 - starpu_task_get_current, [313](#)
 - starpu_task_get_implementation, [314](#)
 - starpu_task_get_model_name, [313](#)
 - starpu_task_get_name, [313](#)
 - starpu_task_init, [310](#)
 - starpu_task_nready, [312](#)
 - starpu_task_nsubmitted, [312](#)
 - starpu_task_set_implementation, [313](#)
 - starpu_task_status, [309](#)
 - starpu_task_submit, [311](#)
 - starpu_task_submit_to_ctx, [311](#)
 - starpu_task_wait, [311](#)
 - starpu_task_wait_for_all, [312](#)
 - starpu_task_wait_for_all_in_ctx, [312](#)
 - starpu_task_wait_for_n_submitted, [312](#)
 - starpu_task_wait_for_n_submitted_in_ctx, [312](#)
 - starpu_task_wait_for_no_ready, [313](#)
- color
 - starpu_codelet, [296](#)
 - starpu_task, [303](#)
- compare
 - starpu_data_interface_ops, [239](#)
- copy
 - starpu_disk_ops, [284](#)
- copy_methods
 - starpu_data_interface_ops, [238](#)
- cost_function
 - starpu_perfmodel, [328](#)
- cpu_func
 - starpu_codelet, [292](#)
- cpu_funcs
 - starpu_codelet, [293](#)
- cpu_funcs_name
 - starpu_codelet, [294](#)
- cuda_flags
 - starpu_codelet, [293](#)
- cuda_func
 - starpu_codelet, [292](#)
- cuda_funcs
 - starpu_codelet, [293](#)
- cuda_to_cuda
 - starpu_data_copy_methods, [242](#)
- cuda_to_cuda_async
 - starpu_data_copy_methods, [243](#)
- cuda_to_opengl
 - starpu_data_copy_methods, [242](#)
- cuda_to_ram
 - starpu_data_copy_methods, [242](#)
- cuda_to_ram_async
 - starpu_data_copy_methods, [243](#)
- custom
 - sc_hypervisor_policy, [455](#)
- data
 - starpu_sched_component, [464](#)
- Data Interfaces, [233](#)
- STARPU_BCSR_GET_COLIND_DEV_HANDLE, [252](#)
- STARPU_BCSR_GET_COLIND, [252](#)
- STARPU_BCSR_GET_NNZ, [251](#)
- STARPU_BCSR_GET_NZVAL_DEV_HANDLE, [251](#)
- STARPU_BCSR_GET_NZVAL, [251](#)
- STARPU_BCSR_GET_OFFSET, [252](#)
- STARPU_BCSR_GET_ROWPTR_DEV_HANDLE, [252](#)
- STARPU_BCSR_GET_ROWPTR, [252](#)
- STARPU_BLOCK_GET_DEV_HANDLE, [250](#)
- STARPU_BLOCK_GET_ELEMSIZE, [251](#)
- STARPU_BLOCK_GET_LDY, [251](#)
- STARPU_BLOCK_GET_LDZ, [251](#)
- STARPU_BLOCK_GET_NX, [250](#)
- STARPU_BLOCK_GET_NY, [250](#)
- STARPU_BLOCK_GET_NZ, [251](#)
- STARPU_BLOCK_GET_OFFSET, [250](#)
- STARPU_BLOCK_GET_PTR, [250](#)
- STARPU_COO_GET_COLUMNS_DEV_HANDLE, [254](#)
- STARPU_COO_GET_COLUMNS, [254](#)
- STARPU_COO_GET_ELEMSIZE, [255](#)
- STARPU_COO_GET_NVALUES, [255](#)
- STARPU_COO_GET_NX, [255](#)
- STARPU_COO_GET_NY, [255](#)
- STARPU_COO_GET_OFFSET, [255](#)
- STARPU_COO_GET_ROWS_DEV_HANDLE, [254](#)
- STARPU_COO_GET_ROWS, [254](#)
- STARPU_COO_GET_VALUES_DEV_HANDLE, [255](#)
- STARPU_COO_GET_VALUES, [255](#)
- STARPU_CSR_GET_COLIND_DEV_HANDLE, [253](#)
- STARPU_CSR_GET_COLIND, [253](#)
- STARPU_CSR_GET_ELEMSIZE, [254](#)
- STARPU_CSR_GET_FIRSTENTRY, [254](#)
- STARPU_CSR_GET_NNZ, [252](#)
- STARPU_CSR_GET_NROW, [253](#)
- STARPU_CSR_GET_NZVAL_DEV_HANDLE, [253](#)
- STARPU_CSR_GET_NZVAL, [253](#)
- STARPU_CSR_GET_OFFSET, [254](#)
- STARPU_CSR_GET_ROWPTR_DEV_HANDLE, [253](#)
- STARPU_CSR_GET_ROWPTR, [253](#)
- STARPU_MATRIX_GET_DEV_HANDLE, [249](#)
- STARPU_MATRIX_GET_ELEMSIZE, [250](#)
- STARPU_MATRIX_GET_LD, [250](#)
- STARPU_MATRIX_GET_NX, [249](#)
- STARPU_MATRIX_GET_NY, [249](#)
- STARPU_MATRIX_GET_OFFSET, [249](#)
- STARPU_MATRIX_GET_PTR, [249](#)
- STARPU_VARIABLE_GET_DEV_HANDLE, [247](#)
- STARPU_VARIABLE_GET_ELEMSIZE, [247](#)
- STARPU_VARIABLE_GET_OFFSET, [248](#)
- STARPU_VARIABLE_GET_PTR, [247](#)

- STARPU_VECTOR_GET_DEV_HANDLE, 248
- STARPU_VECTOR_GET_ELEMSIZE, 248
- STARPU_VECTOR_GET_NX, 248
- STARPU_VECTOR_GET_OFFSET, 248
- STARPU_VECTOR_GET_PTR, 248
- STARPU_VECTOR_GET_SLICE_BASE, 249
- starpu_bcsr_data_register, 259
- starpu_bcsr_get_c, 266
- starpu_bcsr_get_elemsize, 266
- starpu_bcsr_get_firstentry, 265
- starpu_bcsr_get_local_colind, 265
- starpu_bcsr_get_local_nzval, 265
- starpu_bcsr_get_local_rowptr, 265
- starpu_bcsr_get_nnz, 265
- starpu_bcsr_get_nrow, 265
- starpu_bcsr_get_r, 266
- starpu_block_data_register, 258
- starpu_block_get_elemsize, 265
- starpu_block_get_local_ldy, 264
- starpu_block_get_local_ldz, 264
- starpu_block_get_local_ptr, 264
- starpu_block_get_nx, 264
- starpu_block_get_ny, 264
- starpu_block_get_nz, 264
- starpu_block_ptr_register, 259
- starpu_coo_data_register, 261
- starpu_csr_data_register, 260
- starpu_csr_get_elemsize, 267
- starpu_csr_get_firstentry, 266
- starpu_csr_get_local_colind, 267
- starpu_csr_get_local_nzval, 266
- starpu_csr_get_local_rowptr, 267
- starpu_csr_get_nnz, 266
- starpu_csr_get_nrow, 266
- starpu_data_get_interface_id, 262
- starpu_data_get_interface_on_node, 261
- starpu_data_get_local_ptr, 261
- starpu_data_get_size, 262
- starpu_data_handle_to_pointer, 261
- starpu_data_interface_get_next_id, 269
- starpu_data_interface_id, 256
- starpu_data_pack, 262
- starpu_data_pointer_is_inside, 261
- starpu_data_unpack, 262
- starpu_free_on_node, 268
- starpu_free_on_node_flags, 267
- starpu_hash_crc32c_be, 268
- starpu_hash_crc32c_be_n, 268
- starpu_hash_crc32c_string, 269
- starpu_interface_copy, 268
- starpu_malloc_on_node, 267
- starpu_malloc_on_node_flags, 267
- starpu_malloc_on_node_set_default_flags, 268
- starpu_matrix_data_register, 258
- starpu_matrix_get_elemsize, 264
- starpu_matrix_get_local_id, 263
- starpu_matrix_get_local_ptr, 263
- starpu_matrix_get_nx, 263
- starpu_matrix_get_ny, 263
- starpu_matrix_ptr_register, 258
- starpu_variable_data_register, 256
- starpu_variable_get_elemsize, 262
- starpu_variable_get_local_ptr, 262
- starpu_variable_ptr_register, 257
- starpu_vector_data_register, 257
- starpu_vector_get_elemsize, 263
- starpu_vector_get_local_ptr, 263
- starpu_vector_get_nx, 263
- starpu_vector_ptr_register, 257
- starpu_void_data_register, 256
- Data Management, 221
 - STARPU_ACQUIRE_ALL_NODES, 223
 - STARPU_ACQUIRE_NO_NODE, 223
 - STARPU_DATA_ACQUIRE_CB, 223
 - starpu_arbiter_create, 232
 - starpu_arbiter_destroy, 233
 - starpu_arbiter_t, 224
 - starpu_data_access_mode, 224
 - starpu_data_acquire, 230
 - starpu_data_acquire_cb, 230
 - starpu_data_acquire_cb_sequential_consistency, 230
 - starpu_data_acquire_on_node, 231
 - starpu_data_acquire_on_node_cb, 231
 - starpu_data_acquire_on_node_cb_sequential_↔ consistency, 231
 - starpu_data_acquire_on_node_cb_sequential_↔ consistency_sync_jobids, 231
 - starpu_data_acquire_on_node_try, 232
 - starpu_data_acquire_try, 230
 - starpu_data_advise_as_important, 229
 - starpu_data_assign_arbiter, 232
 - starpu_data_fetch_on_node, 227
 - starpu_data_get_interface_ops, 229
 - starpu_data_get_user_data, 229
 - starpu_data_handle_t, 224
 - starpu_data_idle_prefetch_on_node, 228
 - starpu_data_invalidate, 226
 - starpu_data_invalidate_submit, 226
 - starpu_data_lookup, 228
 - starpu_data_prefetch_on_node, 227
 - starpu_data_ptr_register, 225
 - starpu_data_query_status, 228
 - starpu_data_register, 225
 - starpu_data_register_same, 225
 - starpu_data_release, 232
 - starpu_data_release_on_node, 232
 - starpu_data_request_allocation, 228
 - starpu_data_set_coordinates, 227
 - starpu_data_set_coordinates_array, 227
 - starpu_data_set_name, 227
 - starpu_data_set_reduction_methods, 229
 - starpu_data_set_user_data, 229
 - starpu_data_set_wt_mask, 226
 - starpu_data_unregister, 226
 - starpu_data_unregister_no_coherency, 226

- starpu_data_unregister_submit, 226
 - starpu_data_wont_use, 228
- Data Partition, 269
 - starpu_bcsr_filter_canonical_block, 281
 - starpu_block_filter_block, 279
 - starpu_block_filter_block_shadow, 279
 - starpu_block_filter_depth_block, 280
 - starpu_block_filter_depth_block_shadow, 280
 - starpu_block_filter_vertical_block, 280
 - starpu_block_filter_vertical_block_shadow, 280
 - starpu_csr_filter_vertical_block, 281
 - starpu_data_get_child, 274
 - starpu_data_get_nb_children, 273
 - starpu_data_get_sub_data, 274
 - starpu_data_map_filters, 274
 - starpu_data_partition, 273
 - starpu_data_partition_clean, 277
 - starpu_data_partition_plan, 275
 - starpu_data_partition_readonly_submit, 275
 - starpu_data_partition_readwrite_upgrade_submit, 276
 - starpu_data_partition_submit, 275
 - starpu_data_unpartition, 273
 - starpu_data_unpartition_readonly_submit, 276
 - starpu_data_unpartition_submit, 276
 - starpu_data_vget_sub_data, 274
 - starpu_data_vmap_filters, 274
 - starpu_matrix_filter_block, 278
 - starpu_matrix_filter_block_shadow, 278
 - starpu_matrix_filter_vertical_block, 279
 - starpu_matrix_filter_vertical_block_shadow, 279
 - starpu_vector_filter_block, 277
 - starpu_vector_filter_block_shadow, 277
 - starpu_vector_filter_divide_in_2, 278
 - starpu_vector_filter_list, 278
 - starpu_vector_filter_list_long, 277
- deinit
 - starpu_worker_collection, 216
- deinit_data
 - starpu_sched_component, 466
- deinit_sched
 - starpu_sched_policy, 439
- describe
 - starpu_data_interface_ops, 239
- destroy
 - starpu_task, 301
- detach
 - starpu_task, 301
- display
 - starpu_data_interface_ops, 239
- do_schedule
 - starpu_sched_policy, 440
- dontcache
 - starpu_data_interface_ops, 239
- double_max_value
 - starpu_top_param, 422
- double_min_value
 - starpu_top_param, 422
- dyn_handles
 - starpu_task, 298
- dyn_interfaces
 - starpu_task, 299
- dyn_modes
 - starpu_codelet, 295
 - starpu_task, 299
- dyn_nodes
 - starpu_codelet, 295
- end_ctx
 - sc_hypervisor_policy, 456
- energy_model
 - starpu_codelet, 295
- enum_values
 - starpu_top_param, 421
- estimated_end
 - starpu_sched_component, 466
- estimated_load
 - starpu_sched_component, 466
- execute_on_a_specific_worker
 - starpu_task, 301
- Expert Mode, 418
 - starpu_progression_hook_deregister, 418
 - starpu_progression_hook_register, 418
 - starpu_wake_all_blocked_workers, 418
- Explicit Dependencies, 321
 - starpu_tag_declare_deps, 322
 - starpu_tag_declare_deps_array, 323
 - starpu_tag_notify_from_apps, 324
 - starpu_tag_remove, 324
 - starpu_tag_restart, 324
 - starpu_tag_t, 321
 - starpu_tag_wait, 323
 - starpu_tag_wait_array, 323
 - starpu_task_declare_deps_array, 322
 - starpu_task_get_task_scheduled_succs, 322
 - starpu_task_get_task_succs, 322
- FFT Support, 391
 - starpufft_cleanup, 393
 - starpufft_destroy_plan, 393
 - starpufft_execute, 392
 - starpufft_execute_handle, 393
 - starpufft_free, 391
 - starpufft_malloc, 391
 - starpufft_plan_dft_1d, 392
 - starpufft_plan_dft_2d, 392
 - starpufft_start, 392
 - starpufft_start_handle, 392
- filter_arg
 - starpu_data_filter, 272
- filter_arg_ptr
 - starpu_data_filter, 273
- filter_func
 - starpu_data_filter, 272
- flags
 - starpu_codelet, 296
- flops

- starpu_task, 303
- footprint
 - starpu_data_interface_ops, 238
 - starpu_perfmodel, 328
- free
 - starpu_disk_ops, 283
- free_data_on_node
 - starpu_data_interface_ops, 238
- free_request
 - starpu_disk_ops, 285
- full_read
 - starpu_disk_ops, 283
- full_write
 - starpu_disk_ops, 284
- FxT Support, 388
 - starpu_fxt_autostart_profiling, 390
 - starpu_fxt_generate_trace, 390
 - starpu_fxt_options_init, 390
 - starpu_fxt_start_profiling, 390
 - starpu_fxt_stop_profiling, 390
 - starpu_fxt_trace_user_event, 390
 - starpu_fxt_trace_user_event_string, 391
 - starpu_fxt_write_data_trace, 390
- get_child_ops
 - starpu_data_filter, 272
- get_mf_ops
 - starpu_data_interface_ops, 239
- get_nchildren
 - starpu_data_filter, 272
- get_next
 - starpu_worker_collection, 215
- get_size
 - starpu_data_interface_ops, 238
- handle_idle_cycle
 - sc_hypervisor_policy, 455
- handle_idle_end
 - sc_hypervisor_policy, 455
- handle_poped_task
 - sc_hypervisor_policy, 455
- handle_post_exec_hook
 - sc_hypervisor_policy, 455
- handle_pushed_task
 - sc_hypervisor_policy, 455
- handle_submitted_job
 - sc_hypervisor_policy, 456
- handle_to_pointer
 - starpu_data_interface_ops, 238
- handles
 - starpu_task, 298
- has_next
 - starpu_worker_collection, 215
- hypervisor_tag
 - starpu_task, 303
- id
 - starpu_top_param, 421
- Implicit Data Dependencies, 324
 - starpu_data_get_default_sequential_consistency↔_flag, 325
 - starpu_data_get_sequential_consistency_flag, 325
 - starpu_data_set_default_sequential_consistency↔_flag, 325
 - starpu_data_set_sequential_consistency_flag, 325
- init
 - starpu_worker_collection, 216
- init_iterator
 - starpu_worker_collection, 216
- init_sched
 - starpu_sched_policy, 439
- Initialization and Termination, 180
 - starpu_asynchronous_copy_disabled, 187
 - starpu_asynchronous_cuda_copy_disabled, 187
 - starpu_asynchronous_mic_copy_disabled, 187
 - starpu_asynchronous_opencl_copy_disabled, 187
 - starpu_conf_init, 186
 - starpu_init, 186
 - starpu_initialize, 186
 - starpu_pause, 187
 - starpu_resume, 187
 - starpu_shutdown, 186
 - starpu_topology_print, 188
- Insert_Task, 315
 - STARPU_CALLBACK_ARG, 316
 - STARPU_CALLBACK_WITH_ARG, 316
 - STARPU_CALLBACK, 316
 - STARPU_CL_ARGS, 315
 - STARPU_DATA_ARRAY, 316
 - STARPU_DATA_MODE_ARRAY, 316
 - STARPU_EXECUTE_ON_WORKER, 316
 - STARPU_FLOPS, 317
 - STARPU_NAME, 317
 - STARPU_PRIORITY, 316
 - STARPU_SCHED_CTX, 317
 - STARPU_TAG_ONLY, 317
 - STARPU_TASK_COLOR, 317
 - STARPU_TAG, 317
 - STARPU_VALUE, 315
 - STARPU_WORKER_ORDER, 317
 - starpu_codelet_pack_arg_fini, 320
 - starpu_codelet_pack_arg_init, 320
 - starpu_codelet_pack_args, 319
 - starpu_codelet_unpack_args, 320
 - starpu_codelet_unpack_args_and_copyleft, 320
 - starpu_insert_task, 318
 - starpu_task_build, 320
 - starpu_task_insert, 318
 - starpu_task_insert_data_make_room, 318
 - starpu_task_insert_data_process_arg, 319
 - starpu_task_insert_data_process_array_arg, 319
 - starpu_task_insert_data_process_mode_array↔_arg, 319
- int_max_value
 - starpu_top_param, 421
- int_min_value
 - starpu_top_param, 421

- interface_size
 - starpu_data_interface_ops, 239
- interfaceid
 - starpu_data_interface_ops, 239
- interfaces
 - starpu_task, 298
- is_init
 - starpu_perfmodel, 329
- is_loaded
 - starpu_perfmodel, 328
- is_multiformat
 - starpu_data_interface_ops, 239
- MIC Extensions, 383
 - STARPU_MAXMICDEVS, 384
 - STARPU_USE_MIC, 384
 - starpu_mic_func_symbol_t, 384
 - starpu_mic_get_kernel, 384
 - starpu_mic_register_kernel, 384
- MPI Support, 393
 - STARPU_EXECUTE_ON_DATA, 397
 - STARPU_EXECUTE_ON_NODE, 397
 - STARPU_MPI_PER_NODE, 397
 - STARPU_MPI_TAG_UB, 396
 - STARPU_NODE_SELECTION_POLICY, 397
 - STARPU_USE_MPI, 395
 - starpu_data_get_rank, 396
 - starpu_data_get_tag, 397
 - starpu_data_set_rank, 396
 - starpu_data_set_tag, 396
 - starpu_mpi_barrier, 402
 - starpu_mpi_cache_flush, 405
 - starpu_mpi_cache_flush_all_data, 405
 - starpu_mpi_cache_is_enabled, 404
 - starpu_mpi_cache_set, 404
 - starpu_mpi_cached_receive, 405
 - starpu_mpi_cached_send, 405
 - starpu_mpi_comm_amounts_retrieve, 398
 - starpu_mpi_comm_get_attr, 404
 - starpu_mpi_comm_rank, 399
 - starpu_mpi_comm_size, 399
 - starpu_mpi_data_get_rank, 406
 - starpu_mpi_data_get_tag, 406
 - starpu_mpi_data_migrate, 406
 - starpu_mpi_data_register, 396
 - starpu_mpi_data_register_comm, 405
 - starpu_mpi_data_set_rank, 396
 - starpu_mpi_data_set_rank_comm, 406
 - starpu_mpi_data_set_tag, 405
 - starpu_mpi_datatype_register, 404
 - starpu_mpi_datatype_unregister, 404
 - starpu_mpi_gather_detached, 410
 - starpu_mpi_get_communication_tag, 403
 - starpu_mpi_get_data_on_all_nodes_detached, 408
 - starpu_mpi_get_data_on_node, 408
 - starpu_mpi_get_data_on_node_detached, 408
 - starpu_mpi_init, 398
 - starpu_mpi_init_comm, 397
 - starpu_mpi_initialize, 398
 - starpu_mpi_initialize_extended, 398
 - starpu_mpi_insert_task, 406
 - starpu_mpi_irecv, 400
 - starpu_mpi_irecv_array_detached_unlock_tag, 403
 - starpu_mpi_irecv_detached, 400
 - starpu_mpi_irecv_detached_sequential_consistency, 401
 - starpu_mpi_irecv_detached_unlock_tag, 403
 - starpu_mpi_isend, 400
 - starpu_mpi_isend_array_detached_unlock_tag, 403
 - starpu_mpi_isend_detached, 400
 - starpu_mpi_isend_detached_unlock_tag, 402
 - starpu_mpi_issend, 401
 - starpu_mpi_issend_detached, 401
 - starpu_mpi_node_selection_get_current_policy, 408
 - starpu_mpi_node_selection_register_policy, 409
 - starpu_mpi_node_selection_set_current_policy, 408
 - starpu_mpi_node_selection_unregister_policy, 409
 - starpu_mpi_recv, 399
 - starpu_mpi_redux_data, 409
 - starpu_mpi_scatter_detached, 409
 - starpu_mpi_send, 399
 - starpu_mpi_set_communication_tag, 404
 - starpu_mpi_shutdown, 398
 - starpu_mpi_task_build, 407
 - starpu_mpi_task_insert, 407
 - starpu_mpi_task_post_build, 407
 - starpu_mpi_test, 402
 - starpu_mpi_wait, 402
 - starpu_mpi_wait_for_all, 402
 - starpu_mpi_world_rank, 399
 - starpu_mpi_world_size, 399
- magic
 - starpu_task, 302
- max_parallelism
 - starpu_codelet, 292
- mf_skip
 - starpu_task, 301
- mic_funcs
 - starpu_codelet, 294
- mic_to_ram
 - starpu_data_copy_methods, 242
- mic_to_ram_async
 - starpu_data_copy_methods, 244
- Miscellaneous Helpers, 386
 - starpu_data_cpy, 387
 - starpu_execute_on_each_worker, 387
 - starpu_execute_on_each_worker_ex, 387
 - starpu_execute_on_specific_workers, 387
 - starpu_timing_now, 388
- model
 - starpu_codelet, 295

modes

starpu_codelet, 294
starpu_task, 298

Modularized Scheduler Interface, 461

STARPU_SCHED_COMPONENT_IS_HOMOG↔
ENEIOUS, 468

STARPU_SCHED_COMPONENT_IS_SINGLE↔
MEMORY_NODE, 469

starpu_sched_component_can_execute_task, 471

starpu_sched_component_composed_component↔
_create, 477

starpu_sched_component_composed_recipe_add,
476

starpu_sched_component_composed_recipe↔
create, 476

starpu_sched_component_composed_recipe↔
create_singleton, 476

starpu_sched_component_composed_recipe↔
destroy, 476

starpu_sched_component_connect, 470

starpu_sched_component_create, 471

starpu_sched_component_destroy, 471

starpu_sched_component_destroy_rec, 471

starpu_sched_component_estimated_end↔
average, 473

starpu_sched_component_estimated_end_min,
473

starpu_sched_component_estimated_load, 473

starpu_sched_component_execute_preds, 471

starpu_sched_component_fifo_create, 473

starpu_sched_component_heft_create, 475

starpu_sched_component_is_combined_worker,
472

starpu_sched_component_is_eager, 475

starpu_sched_component_is_eager_calibration,
475

starpu_sched_component_is_fifo, 474

starpu_sched_component_is_heft, 475

starpu_sched_component_is_mct, 475

starpu_sched_component_is_perfmodel_select,
476

starpu_sched_component_is_prio, 474

starpu_sched_component_is_random, 474

starpu_sched_component_is_simple_worker, 472

starpu_sched_component_is_work_stealing, 474

starpu_sched_component_is_worker, 472

starpu_sched_component_make_scheduler, 477

starpu_sched_component_mct_create, 475

starpu_sched_component_perfmodel_select↔
create, 476

starpu_sched_component_prio_create, 474

starpu_sched_component_properties, 469

starpu_sched_component_pull_task, 477

starpu_sched_component_push_task, 477

starpu_sched_component_transfer_length, 472

starpu_sched_component_worker_get, 472

starpu_sched_component_worker_get_workerid,
472

starpu_sched_component_worker_post_exec↔
hook, 473

starpu_sched_component_worker_pre_exec↔
hook, 473

starpu_sched_tree_add_workers, 470

starpu_sched_tree_create, 469

starpu_sched_tree_destroy, 469

starpu_sched_tree_pop_task, 470

starpu_sched_tree_push_task, 470

starpu_sched_tree_remove_workers, 470

starpu_sched_tree_update_workers, 469

starpu_sched_tree_update_workers_in_ctx, 470

starpu_sched_tree_work_stealing_push_task, 474

Multiformat Data Interface, 287

STARPU_MULTIFORMAT_GET_CPU_PTR, 288

STARPU_MULTIFORMAT_GET_CUDA_PTR,
288

STARPU_MULTIFORMAT_GET_MIC_PTR, 288

STARPU_MULTIFORMAT_GET_NX, 288

STARPU_MULTIFORMAT_GET_OPENCL_PTR,
288

starpu_multiformat_data_register, 289

name

sc_hypervisor_policy, 455

starpu_codelet, 296

starpu_data_interface_ops, 240

starpu_task, 298

starpu_top_param, 421

nb_values

starpu_top_param, 421

nbuffers

starpu_codelet, 294

starpu_task, 298

nchildren

starpu_data_filter, 272

starpu_sched_component, 465

next

starpu_task, 304

starpu_top_param, 422

nodes

starpu_codelet, 295

notify_change_workers

starpu_sched_component, 467

notify_delete_context

starpu_sched_ctx_performance_counters, 429

notify_idle_cycle

starpu_sched_ctx_performance_counters, 428

notify_poped_task

starpu_sched_ctx_performance_counters, 428

notify_post_exec_task

starpu_sched_ctx_performance_counters, 429

notify_pushed_task

starpu_sched_ctx_performance_counters, 429

notify_submitted_job

starpu_sched_ctx_performance_counters, 429

nparents

starpu_sched_component, 465

nworkers

- starpu_worker_collection, [215](#)
- obj
 - starpu_sched_component, [467](#)
- open
 - starpu_disk_ops, [283](#)
- OpenCL Extensions, [345](#)
 - STARPU_MAXOPENCLDEVS, [347](#)
 - STARPU_OPENCL_DATADIR, [347](#)
 - STARPU_OPENCL_DISPLAY_ERROR, [348](#)
 - STARPU_OPENCL_REPORT_ERROR_WITH_↔MSG, [348](#)
 - STARPU_OPENCL_REPORT_ERROR, [348](#)
 - STARPU_USE_OPENCL, [347](#)
 - starpu_opengl_allocate_memory, [352](#)
 - starpu_opengl_collect_stats, [351](#)
 - starpu_opengl_compile_opengl_from_file, [350](#)
 - starpu_opengl_compile_opengl_from_string, [351](#)
 - starpu_opengl_copy_async_sync, [353](#)
 - starpu_opengl_copy_opengl_to_opengl, [353](#)
 - starpu_opengl_copy_opengl_to_ram, [353](#)
 - starpu_opengl_copy_ram_to_opengl, [352](#)
 - starpu_opengl_display_error, [352](#)
 - starpu_opengl_error_string, [352](#)
 - starpu_opengl_get_context, [348](#)
 - starpu_opengl_get_current_context, [349](#)
 - starpu_opengl_get_current_queue, [349](#)
 - starpu_opengl_get_device, [348](#)
 - starpu_opengl_get_queue, [349](#)
 - starpu_opengl_load_binary_opengl, [351](#)
 - starpu_opengl_load_kernel, [351](#)
 - starpu_opengl_load_opengl_from_file, [349](#)
 - starpu_opengl_load_opengl_from_string, [350](#)
 - starpu_opengl_load_program_source, [350](#)
 - starpu_opengl_load_program_source_malloc, [350](#)
 - starpu_opengl_release_kernel, [351](#)
 - starpu_opengl_report_error, [352](#)
 - starpu_opengl_set_kernel_args, [349](#)
 - starpu_opengl_unload_opengl, [350](#)
- OpenMP Runtime Support, [354](#)
 - STARPU_OPENMP, [359](#)
 - starpu_omp_atomic_fallback_inline_begin, [381](#)
 - starpu_omp_atomic_fallback_inline_end, [382](#)
 - starpu_omp_barrier, [361](#)
 - starpu_omp_critical, [361](#)
 - starpu_omp_critical_inline_begin, [361](#)
 - starpu_omp_critical_inline_end, [361](#)
 - starpu_omp_destroy_lock, [378](#)
 - starpu_omp_destroy_nest_lock, [380](#)
 - starpu_omp_for, [363](#)
 - starpu_omp_for_alt, [364](#)
 - starpu_omp_for_inline_first, [363](#)
 - starpu_omp_for_inline_first_alt, [365](#)
 - starpu_omp_for_inline_next, [364](#)
 - starpu_omp_for_inline_next_alt, [365](#)
 - starpu_omp_get_active_level, [375](#)
 - starpu_omp_get_ancestor_thread_num, [374](#)
 - starpu_omp_get_cancellation, [372](#)
 - starpu_omp_get_default_device, [376](#)
 - starpu_omp_get_dynamic, [371](#)
 - starpu_omp_get_level, [374](#)
 - starpu_omp_get_max_active_levels, [374](#)
 - starpu_omp_get_max_threads, [370](#)
 - starpu_omp_get_nested, [372](#)
 - starpu_omp_get_num_devices, [377](#)
 - starpu_omp_get_num_procs, [370](#)
 - starpu_omp_get_num_teams, [377](#)
 - starpu_omp_get_num_threads, [369](#)
 - starpu_omp_get_proc_bind, [376](#)
 - starpu_omp_get_schedule, [373](#)
 - starpu_omp_get_team_num, [377](#)
 - starpu_omp_get_team_size, [375](#)
 - starpu_omp_get_thread_limit, [373](#)
 - starpu_omp_get_thread_num, [369](#)
 - starpu_omp_get_wtick, [382](#)
 - starpu_omp_get_wtime, [382](#)
 - starpu_omp_in_final, [375](#)
 - starpu_omp_in_parallel, [370](#)
 - starpu_omp_init, [360](#)
 - starpu_omp_init_lock, [378](#)
 - starpu_omp_init_nest_lock, [380](#)
 - starpu_omp_is_initial_device, [378](#)
 - starpu_omp_master, [360](#)
 - starpu_omp_master_inline, [360](#)
 - starpu_omp_ordered, [366](#)
 - starpu_omp_ordered_inline_begin, [366](#)
 - starpu_omp_ordered_inline_end, [366](#)
 - starpu_omp_parallel_region, [360](#)
 - starpu_omp_proc_bind_value, [359](#)
 - starpu_omp_sched_value, [359](#)
 - starpu_omp_sections, [366](#)
 - starpu_omp_sections_combined, [367](#)
 - starpu_omp_set_default_device, [376](#)
 - starpu_omp_set_dynamic, [371](#)
 - starpu_omp_set_lock, [379](#)
 - starpu_omp_set_max_active_levels, [373](#)
 - starpu_omp_set_nest_lock, [380](#)
 - starpu_omp_set_nested, [371](#)
 - starpu_omp_set_num_threads, [369](#)
 - starpu_omp_set_schedule, [372](#)
 - starpu_omp_shutdown, [360](#)
 - starpu_omp_single, [362](#)
 - starpu_omp_single_copyprivate, [362](#)
 - starpu_omp_single_copyprivate_inline_begin, [362](#)
 - starpu_omp_single_copyprivate_inline_end, [363](#)
 - starpu_omp_single_inline, [362](#)
 - starpu_omp_task_region, [367](#)
 - starpu_omp_taskgroup, [368](#)
 - starpu_omp_taskgroup_inline_begin, [368](#)
 - starpu_omp_taskgroup_inline_end, [368](#)
 - starpu_omp_taskwait, [367](#)
 - starpu_omp_test_lock, [379](#)
 - starpu_omp_test_nest_lock, [381](#)
 - starpu_omp_unset_lock, [379](#)
 - starpu_omp_unset_nest_lock, [381](#)
 - starpu_omp_vector_annotate, [383](#)
- opengl_flags

- starpu_codelet, 293
- openccl_func
 - starpu_codelet, 292
- openccl_funcs
 - starpu_codelet, 293
- openccl_to_cuda
 - starpu_data_copy_methods, 242
- openccl_to_openccl
 - starpu_data_copy_methods, 242
- openccl_to_openccl_async
 - starpu_data_copy_methods, 244
- openccl_to_ram
 - starpu_data_copy_methods, 242
- openccl_to_ram_async
 - starpu_data_copy_methods, 244
- Out Of Core, 281
 - STARPU_DISK_SIZE_MIN, 285
 - starpu_disk_close, 285
 - starpu_disk_leveldb_ops, 286
 - starpu_disk_open, 285
 - starpu_disk_register, 285
 - starpu_disk_stdio_ops, 286
 - starpu_disk_swap_node, 286
 - starpu_disk_unistd_o_direct_ops, 286
 - starpu_disk_unistd_ops, 286
- pack_data
 - starpu_data_interface_ops, 240
- Parallel Tasks, 415
 - starpu_combined_worker_assign_workerid, 416
 - starpu_combined_worker_can_execute_task, 416
 - starpu_combined_worker_get_count, 415
 - starpu_combined_worker_get_description, 416
 - starpu_combined_worker_get_id, 416
 - starpu_combined_worker_get_rank, 415
 - starpu_combined_worker_get_size, 415
 - starpu_parallel_task_barrier_init, 416
 - starpu_parallel_task_barrier_init_n, 416
- parents
 - starpu_sched_component, 465
- per_worker_stats
 - starpu_codelet, 296
- Performance Model, 326
 - starpu_bus_print_affinity, 334
 - starpu_bus_print_bandwidth, 333
 - starpu_bus_print_filenames, 334
 - starpu_perfmodel_debugfilepath, 332
 - starpu_perfmodel_directory, 333
 - starpu_perfmodel_free_sampling_directories, 331
 - starpu_perfmodel_get_arch_name, 332
 - starpu_perfmodel_get_archtype_name, 332
 - starpu_perfmodel_history_based_expected_perf, 335
 - starpu_perfmodel_init, 331
 - starpu_perfmodel_initialize, 332
 - starpu_perfmodel_list, 333
 - starpu_perfmodel_load_file, 331
 - starpu_perfmodel_load_symbol, 331
 - starpu_perfmodel_print, 333
 - starpu_perfmodel_print_all, 333
 - starpu_perfmodel_print_estimations, 333
 - starpu_perfmodel_type, 330
 - starpu_perfmodel_unload_model, 332
 - starpu_perfmodel_update_history, 334
 - starpu_transfer_bandwidth, 334
 - starpu_transfer_latency, 334
 - starpu_transfer_predict, 334
 - starpu_worker_get_perf_archtype, 332
- plug
 - starpu_disk_ops, 282
- pointer_is_inside
 - starpu_data_interface_ops, 238
- policy_description
 - starpu_sched_policy, 440
- policy_name
 - starpu_sched_policy, 440
- pop_every_task
 - starpu_sched_policy, 439
- pop_task
 - starpu_sched_policy, 439
- post_exec_hook
 - starpu_sched_policy, 440
- pre_exec_hook
 - starpu_sched_policy, 440
- predicted
 - starpu_task, 303
- predicted_transfer
 - starpu_task, 303
- prev
 - starpu_task, 304
- priority
 - starpu_task, 302
- Profiling, 335
 - STARPU_PROFILING_DISABLE, 338
 - STARPU_PROFILING_ENABLE, 338
 - starpu_bus_get_count, 339
 - starpu_bus_get_dst, 340
 - starpu_bus_get_id, 339
 - starpu_bus_get_profiling_info, 339
 - starpu_bus_get_src, 339
 - starpu_data_display_memory_stats, 340
 - starpu_profiling_bus_helper_display_summary, 340
 - starpu_profiling_init, 338
 - starpu_profiling_set_id, 339
 - starpu_profiling_status_get, 338
 - starpu_profiling_status_set, 338
 - starpu_profiling_worker_get_info, 339
 - starpu_profiling_worker_helper_display_summary, 340
 - starpu_timing_timespec_delay_us, 340
 - starpu_timing_timespec_to_us, 340
- profiling_info
 - starpu_task, 303
- prologue_callback_arg
 - starpu_task, 300
- prologue_callback_arg_free

- starpu_task, [300](#)
- prologue_callback_func
 - starpu_task, [300](#)
- properties
 - starpu_sched_component, [467](#)
- pull_task
 - starpu_sched_component, [466](#)
- push_task
 - starpu_sched_component, [466](#)
 - starpu_sched_policy, [439](#)
- push_task_notify
 - starpu_sched_policy, [439](#)
- ram_to_cuda
 - starpu_data_copy_methods, [241](#)
- ram_to_cuda_async
 - starpu_data_copy_methods, [243](#)
- ram_to_mic
 - starpu_data_copy_methods, [241](#)
- ram_to_mic_async
 - starpu_data_copy_methods, [244](#)
- ram_to_opencl
 - starpu_data_copy_methods, [241](#)
- ram_to_opencl_async
 - starpu_data_copy_methods, [244](#)
- ram_to_ram
 - starpu_data_copy_methods, [241](#)
- read
 - starpu_disk_ops, [283](#)
- regenerate
 - starpu_task, [301](#)
- register_data_handle
 - starpu_data_interface_ops, [237](#)
- remove
 - starpu_worker_collection, [216](#)
- remove_child
 - starpu_sched_component, [465](#)
- remove_parent
 - starpu_sched_component, [465](#)
- remove_workers
 - starpu_sched_policy, [440](#)
- resize_ctxs
 - sc_hypervisor_policy, [455](#)
- Running Drivers, [417](#)
 - starpu_driver_deinit, [417](#)
 - starpu_driver_init, [417](#)
 - starpu_driver_run, [417](#)
 - starpu_driver_run_once, [417](#)
 - starpu_drivers_request_termination, [418](#)
- SC_HYPERVISOR_FIXED_WORKERS
 - Scheduling Context Hypervisor - Regular usage, [449](#)
- SC_HYPERVISOR_GRANULARITY
 - Scheduling Context Hypervisor - Regular usage, [449](#)
- SC_HYPERVISOR_ISPEED_CTX_SAMPLE
 - Scheduling Context Hypervisor - Regular usage, [450](#)
- SC_HYPERVISOR_ISPEED_W_SAMPLE
 - Scheduling Context Hypervisor - Regular usage, [450](#)
- SC_HYPERVISOR_MAX_IDLE
 - Scheduling Context Hypervisor - Regular usage, [448](#)
- SC_HYPERVISOR_MAX_WORKERS
 - Scheduling Context Hypervisor - Regular usage, [449](#)
- SC_HYPERVISOR_MIN_TASKS
 - Scheduling Context Hypervisor - Regular usage, [449](#)
- SC_HYPERVISOR_MIN_WORKERS
 - Scheduling Context Hypervisor - Regular usage, [449](#)
- SC_HYPERVISOR_NEW_WORKERS_MAX_IDLE
 - Scheduling Context Hypervisor - Regular usage, [450](#)
- SC_HYPERVISOR_NULL
 - Scheduling Context Hypervisor - Regular usage, [450](#)
- SC_HYPERVISOR_PRIORITY
 - Scheduling Context Hypervisor - Regular usage, [449](#)
- SC_HYPERVISOR_TIME_TO_APPLY
 - Scheduling Context Hypervisor - Regular usage, [450](#)
- SCC Extensions, [385](#)
 - STARPU_MAXSCCDEVS, [385](#)
 - STARPU_USE_SCC, [385](#)
 - starpu_scc_func_symbol_t, [386](#)
 - starpu_scc_get_kernel, [386](#)
 - starpu_scc_register_kernel, [386](#)
- STARPU_ABORT_MSG
 - Toolbox, [196](#)
- STARPU_ABORT
 - Toolbox, [196](#)
- STARPU_ACQUIRE_ALL_NODES
 - Data Management, [223](#)
- STARPU_ACQUIRE_NO_NODE
 - Data Management, [223](#)
- STARPU_ASSERT_MSG
 - Toolbox, [196](#)
- STARPU_ASSERT
 - Toolbox, [196](#)
- STARPU_ATTRIBUTE_ALIGNED
 - Toolbox, [195](#)
- STARPU_ATTRIBUTE_INTERNAL
 - Toolbox, [194](#)
- STARPU_ATTRIBUTE_MALLOC
 - Toolbox, [194](#)
- STARPU_ATTRIBUTE_PURE
 - Toolbox, [195](#)
- STARPU_ATTRIBUTE_UNUSED
 - Toolbox, [194](#)
- STARPU_ATTRIBUTE_WARN_UNUSED_RESULT
 - Toolbox, [195](#)
- STARPU_BCSR_GET_COLIND_DEV_HANDLE

- Data Interfaces, [252](#)
- STARPU_BCSR_GET_COLIND
 - Data Interfaces, [252](#)
- STARPU_BCSR_GET_NNZ
 - Data Interfaces, [251](#)
- STARPU_BCSR_GET_NZVAL_DEV_HANDLE
 - Data Interfaces, [251](#)
- STARPU_BCSR_GET_NZVAL
 - Data Interfaces, [251](#)
- STARPU_BCSR_GET_OFFSET
 - Data Interfaces, [252](#)
- STARPU_BCSR_GET_ROWPTR_DEV_HANDLE
 - Data Interfaces, [252](#)
- STARPU_BCSR_GET_ROWPTR
 - Data Interfaces, [252](#)
- STARPU_BLOCK_GET_DEV_HANDLE
 - Data Interfaces, [250](#)
- STARPU_BLOCK_GET_ELEMSIZE
 - Data Interfaces, [251](#)
- STARPU_BLOCK_GET_LDY
 - Data Interfaces, [251](#)
- STARPU_BLOCK_GET_LDZ
 - Data Interfaces, [251](#)
- STARPU_BLOCK_GET_NX
 - Data Interfaces, [250](#)
- STARPU_BLOCK_GET_NY
 - Data Interfaces, [250](#)
- STARPU_BLOCK_GET_NZ
 - Data Interfaces, [251](#)
- STARPU_BLOCK_GET_OFFSET
 - Data Interfaces, [250](#)
- STARPU_BLOCK_GET_PTR
 - Data Interfaces, [250](#)
- STARPU_CALLBACK_ARG
 - Insert_Task, [316](#)
- STARPU_CALLBACK_WITH_ARG
 - Insert_Task, [316](#)
- STARPU_CALLBACK
 - Insert_Task, [316](#)
- STARPU_CHECK_RETURN_VALUE_IS
 - Toolbox, [196](#)
- STARPU_CHECK_RETURN_VALUE
 - Toolbox, [196](#)
- STARPU_CL_ARGS
 - Insert_Task, [315](#)
- STARPU_CODELET_GET_MODE
 - Codelet And Tasks, [307](#)
- STARPU_CODELET_GET_NODE
 - Codelet And Tasks, [307](#)
- STARPU_CODELET_SET_MODE
 - Codelet And Tasks, [307](#)
- STARPU_CODELET_SET_NODE
 - Codelet And Tasks, [308](#)
- STARPU_CODELET_SIMGRID_EXECUTE
 - starpu_task.h, [509](#)
- STARPU_COO_GET_COLUMNS_DEV_HANDLE
 - Data Interfaces, [254](#)
- STARPU_COO_GET_COLUMNS
 - Data Interfaces, [254](#)
- STARPU_COO_GET_ELEMSIZE
 - Data Interfaces, [255](#)
- STARPU_COO_GET_NVALUES
 - Data Interfaces, [255](#)
- STARPU_COO_GET_NX
 - Data Interfaces, [255](#)
- STARPU_COO_GET_NY
 - Data Interfaces, [255](#)
- STARPU_COO_GET_OFFSET
 - Data Interfaces, [255](#)
- STARPU_COO_GET_ROWS_DEV_HANDLE
 - Data Interfaces, [254](#)
- STARPU_COO_GET_ROWS
 - Data Interfaces, [254](#)
- STARPU_COO_GET_VALUES_DEV_HANDLE
 - Data Interfaces, [255](#)
- STARPU_COO_GET_VALUES
 - Data Interfaces, [255](#)
- STARPU_CPU
 - Codelet And Tasks, [304](#)
- STARPU_CSR_GET_COLIND_DEV_HANDLE
 - Data Interfaces, [253](#)
- STARPU_CSR_GET_COLIND
 - Data Interfaces, [253](#)
- STARPU_CSR_GET_ELEMSIZE
 - Data Interfaces, [254](#)
- STARPU_CSR_GET_FIRSTENTRY
 - Data Interfaces, [254](#)
- STARPU_CSR_GET_NNZ
 - Data Interfaces, [252](#)
- STARPU_CSR_GET_NROW
 - Data Interfaces, [253](#)
- STARPU_CSR_GET_NZVAL_DEV_HANDLE
 - Data Interfaces, [253](#)
- STARPU_CSR_GET_NZVAL
 - Data Interfaces, [253](#)
- STARPU_CSR_GET_OFFSET
 - Data Interfaces, [254](#)
- STARPU_CSR_GET_ROWPTR_DEV_HANDLE
 - Data Interfaces, [253](#)
- STARPU_CSR_GET_ROWPTR
 - Data Interfaces, [253](#)
- STARPU_CUBLAS_REPORT_ERROR
 - CUDA Extensions, [343](#)
- STARPU_CUDA_ASYNC
 - starpu_task.h, [509](#)
- STARPU_CUDA_REPORT_ERROR
 - CUDA Extensions, [343](#)
- STARPU_CUDA
 - Codelet And Tasks, [304](#)
- STARPU_DATA_ACQUIRE_CB
 - Data Management, [223](#)
- STARPU_DATA_ARRAY
 - Insert_Task, [316](#)
- STARPU_DATA_MODE_ARRAY
 - Insert_Task, [316](#)
- STARPU_DEFAULT_PRIO

- Scheduling Contexts, [430](#)
- STARPU_DISK_SIZE_MIN
 - Out Of Core, [285](#)
- STARPU_EXECUTE_ON_DATA
 - MPI Support, [397](#)
- STARPU_EXECUTE_ON_NODE
 - MPI Support, [397](#)
- STARPU_EXECUTE_ON_WORKER
 - Insert_Task, [316](#)
- STARPU_FLOPS
 - Insert_Task, [317](#)
- STARPU_GNUC_PREREQ
 - Toolbox, [194](#)
- STARPU_HYPERVERSOR_TAG
 - Scheduling Context Hypervisor - Building a new re-sizing policy, [458](#)
- STARPU_LIKELY
 - Toolbox, [194](#)
- STARPU_MAIN_RAM
 - Codelet And Tasks, [305](#)
- STARPU_MAJOR_VERSION
 - Versioning, [179](#)
- STARPU_MALLOC_COUNT
 - Standard Memory Library, [189](#)
- STARPU_MALLOC_NORECLAIM
 - Standard Memory Library, [189](#)
- STARPU_MALLOC_PINNED
 - Standard Memory Library, [189](#)
- STARPU_MALLOC_SIMULATION_FOLDED
 - Standard Memory Library, [189](#)
- STARPU_MATRIX_GET_DEV_HANDLE
 - Data Interfaces, [249](#)
- STARPU_MATRIX_GET_ELEMSIZE
 - Data Interfaces, [250](#)
- STARPU_MATRIX_GET_LD
 - Data Interfaces, [250](#)
- STARPU_MATRIX_GET_NX
 - Data Interfaces, [249](#)
- STARPU_MATRIX_GET_NY
 - Data Interfaces, [249](#)
- STARPU_MATRIX_GET_OFFSET
 - Data Interfaces, [249](#)
- STARPU_MATRIX_GET_PTR
 - Data Interfaces, [249](#)
- STARPU_MAX_PRIO
 - Scheduling Contexts, [430](#)
- STARPU_MAXCPUS
 - Workers' Properties, [217](#)
- STARPU_MAXCUDADEVES
 - CUDA Extensions, [343](#)
- STARPU_MAXIMPLEMENTATIONS
 - Scheduling Policy, [441](#)
- STARPU_MAXMICDEVES
 - MIC Extensions, [384](#)
- STARPU_MAXNODES
 - Workers' Properties, [217](#)
- STARPU_MAXOPENCLDEVES
 - OpenCL Extensions, [347](#)
- STARPU_MAXSCCDEVES
 - SCC Extensions, [385](#)
- STARPU_MAX
 - Toolbox, [195](#)
- STARPU_MEMORY_OVERFLOW
 - Standard Memory Library, [190](#)
- STARPU_MEMORY_WAIT
 - Standard Memory Library, [190](#)
- STARPU_MIN_PRIO
 - Scheduling Contexts, [430](#)
- STARPU_MINOR_VERSION
 - Versioning, [179](#)
- STARPU_MIC
 - Codelet And Tasks, [305](#)
- STARPU_MIN
 - Toolbox, [195](#)
- STARPU_MPI_PER_NODE
 - MPI Support, [397](#)
- STARPU_MPI_TAG_UB
 - MPI Support, [396](#)
- STARPU_MULTIFORMAT_GET_CPU_PTR
 - Multiformat Data Interface, [288](#)
- STARPU_MULTIFORMAT_GET_CUDA_PTR
 - Multiformat Data Interface, [288](#)
- STARPU_MULTIFORMAT_GET_MIC_PTR
 - Multiformat Data Interface, [288](#)
- STARPU_MULTIFORMAT_GET_NX
 - Multiformat Data Interface, [288](#)
- STARPU_MULTIFORMAT_GET_OPENCL_PTR
 - Multiformat Data Interface, [288](#)
- STARPU_MULTIPLE_CPU_IMPLEMENTATIONS
 - Codelet And Tasks, [305](#)
- STARPU_MULTIPLE_CUDA_IMPLEMENTATIONS
 - Codelet And Tasks, [305](#)
- STARPU_MULTIPLE_OPENCL_IMPLEMENTATIONS
 - Codelet And Tasks, [305](#)
- STARPU_NAME
 - Insert_Task, [317](#)
- STARPU_NMAX_SCHED_CTXS
 - Scheduling Policy, [441](#)
- STARPU_NMAXBUFS
 - Codelet And Tasks, [306](#)
- STARPU_NMAXWORKERS
 - Workers' Properties, [217](#)
- STARPU_NODE_SELECTION_POLICY
 - MPI Support, [397](#)
- STARPU_NOWHERE
 - Codelet And Tasks, [304](#)
- STARPU_OPENCL_ASYNC
 - starpu_task.h, [510](#)
- STARPU_OPENCL_DATADIR
 - OpenCL Extensions, [347](#)
- STARPU_OPENCL_DISPLAY_ERROR
 - OpenCL Extensions, [348](#)
- STARPU_OPENCL_REPORT_ERROR_WITH_MSG
 - OpenCL Extensions, [348](#)
- STARPU_OPENCL_REPORT_ERROR
 - OpenCL Extensions, [348](#)

- STARPU_OPENCL
 - Codelet And Tasks, [304](#)
- STARPU_OPENMP
 - OpenMP Runtime Support, [359](#)
- STARPU_POISON_PTR
 - Toolbox, [195](#)
- STARPU_PRIORITY
 - Insert_Task, [316](#)
- STARPU_PROFILING_DISABLE
 - Profiling, [338](#)
- STARPU_PROFILING_ENABLE
 - Profiling, [338](#)
- STARPU_PTHREAD_BARRIER_DESTROY
 - Threads, [202](#)
- STARPU_PTHREAD_BARRIER_INIT
 - Threads, [202](#)
- STARPU_PTHREAD_BARRIER_WAIT
 - Threads, [203](#)
- STARPU_PTHREAD_COND_BROADCAST
 - Threads, [202](#)
- STARPU_PTHREAD_COND_DESTROY
 - Threads, [202](#)
- STARPU_PTHREAD_COND_INITIALIZER
 - Threads, [203](#)
- STARPU_PTHREAD_COND_INIT
 - Threads, [201](#)
- STARPU_PTHREAD_COND_SIGNAL
 - Threads, [202](#)
- STARPU_PTHREAD_COND_WAIT
 - Threads, [202](#)
- STARPU_PTHREAD_CREATE_ON
 - Threads, [199](#)
- STARPU_PTHREAD_CREATE
 - Threads, [199](#)
- STARPU_PTHREAD_GETSPECIFIC
 - Threads, [201](#)
- STARPU_PTHREAD_KEY_CREATE
 - Threads, [200](#)
- STARPU_PTHREAD_KEY_DELETE
 - Threads, [200](#)
- STARPU_PTHREAD_MUTEX_DESTROY
 - Threads, [200](#)
- STARPU_PTHREAD_MUTEX_INITIALIZER
 - Threads, [203](#)
- STARPU_PTHREAD_MUTEX_INIT
 - Threads, [199](#)
- STARPU_PTHREAD_MUTEX_LOCK
 - Threads, [200](#)
- STARPU_PTHREAD_MUTEX_UNLOCK
 - Threads, [200](#)
- STARPU_PTHREAD_RWLOCK_DESTROY
 - Threads, [201](#)
- STARPU_PTHREAD_RWLOCK_INIT
 - Threads, [201](#)
- STARPU_PTHREAD_RWLOCK_RDLOCK
 - Threads, [201](#)
- STARPU_PTHREAD_RWLOCK_UNLOCK
 - Threads, [201](#)
- STARPU_PTHREAD_RWLOCK_WRLOCK
 - Threads, [201](#)
- STARPU_PTHREAD_SETSPECIFIC
 - Threads, [200](#)
- STARPU_RELEASE_VERSION
 - Versioning, [179](#)
- STARPU_RMB
 - Toolbox, [197](#)
- STARPU_SCHED_COMPONENT_IS_HOMOGENEOUS
 - Modularized Scheduler Interface, [468](#)
- STARPU_SCHED_COMPONENT_IS_SINGLE_MEMORY_NODE
 - Modularized Scheduler Interface, [469](#)
- STARPU_SCHED_CTX_POLICY_MAX_PRIORITY
 - Scheduling Contexts, [430](#)
- STARPU_SCHED_CTX_POLICY_MIN_PRIORITY
 - Scheduling Contexts, [429](#)
- STARPU_SCHED_CTX_POLICY_NAME
 - Scheduling Contexts, [429](#)
- STARPU_SCHED_CTX_POLICY_STRUCT
 - Scheduling Contexts, [429](#)
- STARPU_SCHED_CTX
 - Insert_Task, [317](#)
- STARPU_SCC
 - Codelet And Tasks, [305](#)
- STARPU_TAG_ONLY
 - Insert_Task, [317](#)
- STARPU_TASK_COLOR
 - Insert_Task, [317](#)
- STARPU_TASK_GET_HANDLE
 - Codelet And Tasks, [306](#)
- STARPU_TASK_GET_MODE
 - Codelet And Tasks, [307](#)
- STARPU_TASK_GET_NBUFFERS
 - Codelet And Tasks, [306](#)
- STARPU_TASK_INITIALIZER
 - Codelet And Tasks, [306](#)
- STARPU_TASK_INVALID
 - Codelet And Tasks, [308](#)
- STARPU_TASK_SET_HANDLE
 - Codelet And Tasks, [306](#)
- STARPU_TASK_SET_MODE
 - Codelet And Tasks, [307](#)
- STARPU_TAG
 - Insert_Task, [317](#)
- STARPU_UNLIKELY
 - Toolbox, [194](#)
- STARPU_USE_CUDA
 - CUDA Extensions, [343](#)
- STARPU_USE_MIC
 - MIC Extensions, [384](#)
- STARPU_USE_MPI
 - MPI Support, [395](#)
- STARPU_USE_OPENCL
 - OpenCL Extensions, [347](#)
- STARPU_USE_SCC
 - SCC Extensions, [385](#)

- STARPU_VALUE
 - Insert_Task, [315](#)
- STARPU_VARIABLE_GET_DEV_HANDLE
 - Data Interfaces, [247](#)
- STARPU_VARIABLE_GET_ELEMSIZE
 - Data Interfaces, [247](#)
- STARPU_VARIABLE_GET_OFFSET
 - Data Interfaces, [248](#)
- STARPU_VARIABLE_GET_PTR
 - Data Interfaces, [247](#)
- STARPU_VARIABLE_NBUFFERS
 - Codelet And Tasks, [306](#)
- STARPU_VECTOR_GET_DEV_HANDLE
 - Data Interfaces, [248](#)
- STARPU_VECTOR_GET_ELEMSIZE
 - Data Interfaces, [248](#)
- STARPU_VECTOR_GET_NX
 - Data Interfaces, [248](#)
- STARPU_VECTOR_GET_OFFSET
 - Data Interfaces, [248](#)
- STARPU_VECTOR_GET_PTR
 - Data Interfaces, [248](#)
- STARPU_VECTOR_GET_SLICE_BASE
 - Data Interfaces, [249](#)
- STARPU_WARN_UNUSED_RESULT
 - Toolbox, [195](#)
- STARPU_WMB
 - Toolbox, [197](#)
- STARPU_WORKER_ORDER
 - Insert_Task, [317](#)
- sc_hypervisor.h, [523](#)
- sc_hypervisor_add_workers_to_sched_ctx
 - Scheduling Context Hypervisor - Regular usage, [452](#)
- sc_hypervisor_can_resize
 - Scheduling Context Hypervisor - Building a new re-sizing policy, [459](#)
- sc_hypervisor_config.h, [524](#)
- sc_hypervisor_ctl
 - Scheduling Context Hypervisor - Regular usage, [453](#)
- sc_hypervisor_free_size_req
 - Scheduling Context Hypervisor - Building a new re-sizing policy, [459](#)
- sc_hypervisor_get_config
 - Scheduling Context Hypervisor - Building a new re-sizing policy, [460](#)
- sc_hypervisor_get_elapsed_flops_per_sched_ctx
 - Scheduling Context Hypervisor - Building a new re-sizing policy, [460](#)
- sc_hypervisor_get_nsched_ctxs
 - Scheduling Context Hypervisor - Building a new re-sizing policy, [460](#)
- sc_hypervisor_get_policy
 - Scheduling Context Hypervisor - Regular usage, [452](#)
- sc_hypervisor_get_sched_ctxs
 - Scheduling Context Hypervisor - Building a new re-sizing policy, [460](#)
- sc_hypervisor_get_size_req
 - Scheduling Context Hypervisor - Building a new re-sizing policy, [459](#)
- sc_hypervisor_get_wrapper
 - Scheduling Context Hypervisor - Building a new re-sizing policy, [460](#)
- sc_hypervisor_init
 - Scheduling Context Hypervisor - Regular usage, [450](#)
- sc_hypervisor_ip.h, [525](#)
- sc_hypervisor_monitoring.h, [525](#)
- sc_hypervisor_move_workers
 - Scheduling Context Hypervisor - Regular usage, [452](#)
- sc_hypervisor_policy, [454](#)
 - custom, [455](#)
 - end_ctx, [456](#)
 - handle_idle_cycle, [455](#)
 - handle_idle_end, [455](#)
 - handle_poped_task, [455](#)
 - handle_post_exec_hook, [455](#)
 - handle_pushed_task, [455](#)
 - handle_submitted_job, [456](#)
 - name, [455](#)
 - resize_ctxs, [455](#)
 - size_ctxs, [455](#)
- sc_hypervisor_policy.h, [526](#)
- sc_hypervisor_policy_config, [456](#)
- sc_hypervisor_policy_task_pool, [458](#)
- sc_hypervisor_post_resize_request
 - Scheduling Context Hypervisor - Building a new re-sizing policy, [459](#)
- sc_hypervisor_register_ctx
 - Scheduling Context Hypervisor - Regular usage, [451](#)
- sc_hypervisor_remove_workers_from_sched_ctx
 - Scheduling Context Hypervisor - Regular usage, [452](#)
- sc_hypervisor_resize_ack, [458](#)
- sc_hypervisor_resize_ctxs
 - Scheduling Context Hypervisor - Regular usage, [451](#)
- sc_hypervisor_save_size_req
 - Scheduling Context Hypervisor - Building a new re-sizing policy, [459](#)
- sc_hypervisor_set_config
 - Scheduling Context Hypervisor - Building a new re-sizing policy, [460](#)
- sc_hypervisor_set_type_of_task
 - Scheduling Context Hypervisor - Regular usage, [453](#)
- sc_hypervisor_shutdown
 - Scheduling Context Hypervisor - Regular usage, [451](#)
- sc_hypervisor_size_ctxs

- Scheduling Context Hypervisor - Regular usage, 452
- sc_hypervisor_start_resize
 - Scheduling Context Hypervisor - Regular usage, 452
- sc_hypervisor_stop_resize
 - Scheduling Context Hypervisor - Regular usage, 451
- sc_hypervisor_unregister_ctx
 - Scheduling Context Hypervisor - Regular usage, 451
- sc_hypervisor_update_diff_elapsed_flops
 - Scheduling Context Hypervisor - Regular usage, 453
- sc_hypervisor_update_diff_total_flops
 - Scheduling Context Hypervisor - Regular usage, 453
- sc_hypervisor_wrapper, 456
- scc_funcs
 - starpu_codelet, 294
- scc_sink_to_sink
 - starpu_data_copy_methods, 243
- scc_sink_to_src
 - starpu_data_copy_methods, 243
- scc_src_to_sink
 - starpu_data_copy_methods, 243
- sched_ctx
 - starpu_task, 303
- scheduled
 - starpu_task, 302
- Scheduling Context Hypervisor - Building a new resizing policy, 454
 - STARPU_HYPERVISOR_TAG, 458
 - sc_hypervisor_can_resize, 459
 - sc_hypervisor_free_size_req, 459
 - sc_hypervisor_get_config, 460
 - sc_hypervisor_get_elapsed_flops_per_sched_ctx, 460
 - sc_hypervisor_get_nsched_ctxs, 460
 - sc_hypervisor_get_sched_ctxs, 460
 - sc_hypervisor_get_size_req, 459
 - sc_hypervisor_get_wrapper, 460
 - sc_hypervisor_post_resize_request, 459
 - sc_hypervisor_save_size_req, 459
 - sc_hypervisor_set_config, 460
- Scheduling Context Hypervisor - Regular usage, 448
 - SC_HYPERVISOR_FIXED_WORKERS, 449
 - SC_HYPERVISOR_GRANULARITY, 449
 - SC_HYPERVISOR_ISPEED_CTX_SAMPLE, 450
 - SC_HYPERVISOR_ISPEED_W_SAMPLE, 450
 - SC_HYPERVISOR_MAX_IDLE, 448
 - SC_HYPERVISOR_MAX_WORKERS, 449
 - SC_HYPERVISOR_MIN_TASKS, 449
 - SC_HYPERVISOR_MIN_WORKERS, 449
 - SC_HYPERVISOR_NEW_WORKERS_MAX_ID↵LE, 450
 - SC_HYPERVISOR_NULL, 450
 - SC_HYPERVISOR_PRIORITY, 449
 - SC_HYPERVISOR_TIME_TO_APPLY, 450
 - sc_hypervisor_add_workers_to_sched_ctx, 452
 - sc_hypervisor_ctl, 453
 - sc_hypervisor_get_policy, 452
 - sc_hypervisor_init, 450
 - sc_hypervisor_move_workers, 452
 - sc_hypervisor_register_ctx, 451
 - sc_hypervisor_remove_workers_from_sched_ctx, 452
 - sc_hypervisor_resize_ctxs, 451
 - sc_hypervisor_set_type_of_task, 453
 - sc_hypervisor_shutdown, 451
 - sc_hypervisor_size_ctxs, 452
 - sc_hypervisor_start_resize, 452
 - sc_hypervisor_stop_resize, 451
 - sc_hypervisor_unregister_ctx, 451
 - sc_hypervisor_update_diff_elapsed_flops, 453
 - sc_hypervisor_update_diff_total_flops, 453
- Scheduling Contexts, 426
 - STARPU_DEFAULT_PRIO, 430
 - STARPU_MAX_PRIO, 430
 - STARPU_MIN_PRIO, 430
 - STARPU_SCHED_CTX_POLICY_MAX_PRIO, 430
 - STARPU_SCHED_CTX_POLICY_MIN_PRIO, 429
 - STARPU_SCHED_CTX_POLICY_NAME, 429
 - STARPU_SCHED_CTX_POLICY_STRUCT, 429
 - starpu_sched_ctx_add_workers, 431
 - starpu_sched_ctx_call_pushed_task_cb, 435
 - starpu_sched_ctx_check_if_hypervisor_exists, 436
 - starpu_sched_ctx_contains_worker, 433
 - starpu_sched_ctx_create, 430
 - starpu_sched_ctx_create_inside_interval, 430
 - starpu_sched_ctx_create_worker_collection, 435
 - starpu_sched_ctx_delete, 431
 - starpu_sched_ctx_delete_worker_collection, 435
 - starpu_sched_ctx_display_workers, 431
 - starpu_sched_ctx_exec_parallel_code, 436
 - starpu_sched_ctx_finished_submit, 432
 - starpu_sched_ctx_get_context, 432
 - starpu_sched_ctx_get_max_priority, 434
 - starpu_sched_ctx_get_min_priority, 434
 - starpu_sched_ctx_get_nready_flops, 436
 - starpu_sched_ctx_get_nready_tasks, 436
 - starpu_sched_ctx_get_nshared_workers, 433
 - starpu_sched_ctx_get_nworkers, 433
 - starpu_sched_ctx_get_policy_data, 436
 - starpu_sched_ctx_get_worker_collection, 435
 - starpu_sched_ctx_get_workers_list, 432
 - starpu_sched_ctx_get_workers_list_raw, 433
 - starpu_sched_ctx_max_priority_is_set, 434
 - starpu_sched_ctx_min_priority_is_set, 434
 - starpu_sched_ctx_notify_hypervisor_exists, 435
 - starpu_sched_ctx_overlapping_ctxs_on_worker, 433
 - starpu_sched_ctx_register_close_callback, 431
 - starpu_sched_ctx_remove_workers, 431
 - starpu_sched_ctx_set_context, 432

- starpu_sched_ctx_set_inheritor, 432
- starpu_sched_ctx_set_max_priority, 434
- starpu_sched_ctx_set_min_priority, 434
- starpu_sched_ctx_set_perf_counters, 435
- starpu_sched_ctx_set_policy_data, 436
- starpu_sched_ctx_stop_task_submission, 432
- starpu_sched_ctx_worker_get_id, 433
- Scheduling Policy, 437
 - STARPU_MAXIMPLEMENTATIONS, 441
 - STARPU_NMAX_SCHED_CTXS, 441
 - starpu_data_expected_transfer_time, 444
 - starpu_get_prefetch_flag, 444
 - starpu_idle_prefetch_task_input_on_node, 445
 - starpu_prefetch_task_input_on_node, 445
 - starpu_push_local_task, 442
 - starpu_push_task_end, 442
 - starpu_sched_ctx_worker_shares_tasks_lists, 445
 - starpu_sched_get_max_priority, 442
 - starpu_sched_get_min_priority, 442
 - starpu_sched_get_predefined_policies, 441
 - starpu_sched_set_max_priority, 442
 - starpu_sched_set_min_priority, 441
 - starpu_task_data_footprint, 443
 - starpu_task_expected_conversion_time, 444
 - starpu_task_expected_data_transfer_time, 444
 - starpu_task_expected_energy, 444
 - starpu_task_expected_length, 443
 - starpu_task_footprint, 443
 - starpu_wake_worker, 441
 - starpu_worker_can_execute_task, 442
 - starpu_worker_can_execute_task_first_impl, 443
 - starpu_worker_can_execute_task_impl, 443
 - starpu_worker_get_relative_speedup, 444
 - starpu_worker_get_sched_condition, 441
- sequential_consistency
 - starpu_task, 301
- size_base
 - starpu_perfmodel, 328
- size_ctxs
 - sc_hypervisor_policy, 455
- specific_nodes
 - starpu_codelet, 295
- Standard Memory Library, 188
 - STARPU_MALLOC_COUNT, 189
 - STARPU_MALLOC_NORECLAIM, 189
 - STARPU_MALLOC_PINNED, 189
 - STARPU_MALLOC_SIMULATION_FOLDED, 189
 - STARPU_MEMORY_OVERFLOW, 190
 - STARPU_MEMORY_WAIT, 190
 - starpu_data_free_pinned_if_possible, 189
 - starpu_data_malloc_pinned_if_possible, 188
 - starpu_free, 191
 - starpu_free_flags, 191
 - starpu_malloc, 190
 - starpu_malloc_flags, 190
 - starpu_malloc_set_align, 190
 - starpu_memory_allocate, 192
 - starpu_memory_deallocate, 192
 - starpu_memory_get_available, 192
 - starpu_memory_get_total, 191
 - starpu_memory_pin, 191
 - starpu_memory_unpin, 191
 - starpu_memory_wait_available, 193
- StarPU-Top Interface, 419
 - starpu_top_add_data_boolean, 423
 - starpu_top_add_data_float, 423
 - starpu_top_add_data_integer, 423
 - starpu_top_data_type, 422
 - starpu_top_debug_lock, 426
 - starpu_top_debug_log, 426
 - starpu_top_init_and_wait, 425
 - starpu_top_message_type, 423
 - starpu_top_param_type, 422
 - starpu_top_register_parameter_boolean, 424
 - starpu_top_register_parameter_enum, 424
 - starpu_top_register_parameter_float, 424
 - starpu_top_register_parameter_integer, 424
 - starpu_top_task_prevision, 425
 - starpu_top_update_data_boolean, 425
 - starpu_top_update_data_float, 425
 - starpu_top_update_data_integer, 425
 - starpu_top_update_parameter, 425
- starpu.h, 481
- starpu_arbiter_create
 - Data Management, 232
- starpu_arbiter_destroy
 - Data Management, 233
- starpu_arbiter_t
 - Data Management, 224
- starpu_asynchronous_copy_disabled
 - Initialization and Termination, 187
- starpu_asynchronous_cuda_copy_disabled
 - Initialization and Termination, 187
- starpu_asynchronous_mic_copy_disabled
 - Initialization and Termination, 187
- starpu_asynchronous_openccl_copy_disabled
 - Initialization and Termination, 187
- starpu_bcsr_data_register
 - Data Interfaces, 259
- starpu_bcsr_filter_canonical_block
 - Data Partition, 281
- starpu_bcsr_get_c
 - Data Interfaces, 266
- starpu_bcsr_get_elemsize
 - Data Interfaces, 266
- starpu_bcsr_get_firstentry
 - Data Interfaces, 265
- starpu_bcsr_get_local_colind
 - Data Interfaces, 265
- starpu_bcsr_get_local_nzval
 - Data Interfaces, 265
- starpu_bcsr_get_local_rowptr
 - Data Interfaces, 265
- starpu_bcsr_get_nnz
 - Data Interfaces, 265
- starpu_bcsr_get_nrow

- Data Interfaces, 265
- starpu_bcsr_get_r
 - Data Interfaces, 266
- starpu_bcsr_interface, 246
- starpu_bitmap.h, 482
- starpu_bitmap_and_get
 - Bitmap, 212
- starpu_bitmap_cardinal
 - Bitmap, 212
- starpu_bitmap_create
 - Bitmap, 211
- starpu_bitmap_destroy
 - Bitmap, 211
- starpu_bitmap_first
 - Bitmap, 213
- starpu_bitmap_get
 - Bitmap, 212
- starpu_bitmap_has_next
 - Bitmap, 213
- starpu_bitmap_last
 - Bitmap, 213
- starpu_bitmap_next
 - Bitmap, 213
- starpu_bitmap_or
 - Bitmap, 212
- starpu_bitmap_set
 - Bitmap, 211
- starpu_bitmap_unset
 - Bitmap, 211
- starpu_bitmap_unset_all
 - Bitmap, 212
- starpu_bitmap_unset_and
 - Bitmap, 212
- starpu_block_data_register
 - Data Interfaces, 258
- starpu_block_filter_block
 - Data Partition, 279
- starpu_block_filter_block_shadow
 - Data Partition, 279
- starpu_block_filter_depth_block
 - Data Partition, 280
- starpu_block_filter_depth_block_shadow
 - Data Partition, 280
- starpu_block_filter_vertical_block
 - Data Partition, 280
- starpu_block_filter_vertical_block_shadow
 - Data Partition, 280
- starpu_block_get_elemsize
 - Data Interfaces, 265
- starpu_block_get_local_ldy
 - Data Interfaces, 264
- starpu_block_get_local_ldz
 - Data Interfaces, 264
- starpu_block_get_local_ptr
 - Data Interfaces, 264
- starpu_block_get_nx
 - Data Interfaces, 264
- starpu_block_get_ny
 - Data Interfaces, 264
- starpu_block_get_nz
 - Data Interfaces, 264
- starpu_block_interface, 246
- starpu_block_ptr_register
 - Data Interfaces, 259
- starpu_bound.h, 482
- starpu_bound_compute
 - Theoretical Lower Bound on Execution Time, 342
- starpu_bound_print
 - Theoretical Lower Bound on Execution Time, 342
- starpu_bound_print_dot
 - Theoretical Lower Bound on Execution Time, 341
- starpu_bound_print_lp
 - Theoretical Lower Bound on Execution Time, 342
- starpu_bound_print_mps
 - Theoretical Lower Bound on Execution Time, 342
- starpu_bound_start
 - Theoretical Lower Bound on Execution Time, 341
- starpu_bound_stop
 - Theoretical Lower Bound on Execution Time, 341
- starpu_bus_get_count
 - Profiling, 339
- starpu_bus_get_dst
 - Profiling, 340
- starpu_bus_get_id
 - Profiling, 339
- starpu_bus_get_profiling_info
 - Profiling, 339
- starpu_bus_get_src
 - Profiling, 339
- starpu_bus_print_affinity
 - Performance Model, 334
- starpu_bus_print_bandwidth
 - Performance Model, 333
- starpu_bus_print_filenames
 - Performance Model, 334
- starpu_codelet, 291
 - can_execute, 292
 - color, 296
 - cpu_func, 292
 - cpu_funcs, 293
 - cpu_funcs_name, 294
 - cuda_flags, 293
 - cuda_func, 292
 - cuda_funcs, 293
 - dyn_modes, 295
 - dyn_nodes, 295
 - energy_model, 295
 - flags, 296
 - max_parallelism, 292
 - mic_funcs, 294
 - model, 295
 - modes, 294
 - name, 296
 - nbuffers, 294
 - nodes, 295
 - opencl_flags, 293

- opencl_func, 292
 - opencl_funcs, 293
 - per_worker_stats, 296
 - scc_funcs, 294
 - specific_nodes, 295
 - type, 292
 - where, 292
- starpu_codelet_display_stats
 - Codelet And Tasks, 313
- starpu_codelet_init
 - Codelet And Tasks, 310
- starpu_codelet_pack_arg_data, 512
- starpu_codelet_pack_arg_fini
 - Insert_Task, 320
- starpu_codelet_pack_arg_init
 - Insert_Task, 320
- starpu_codelet_pack_args
 - Insert_Task, 319
- starpu_codelet_type
 - Codelet And Tasks, 309
- starpu_codelet_unpack_args
 - Insert_Task, 320
- starpu_codelet_unpack_args_and_copyleft
 - Insert_Task, 320
- starpu_combined_worker_assign_workerid
 - Parallel Tasks, 416
- starpu_combined_worker_can_execute_task
 - Parallel Tasks, 416
- starpu_combined_worker_get_count
 - Parallel Tasks, 415
- starpu_combined_worker_get_description
 - Parallel Tasks, 416
- starpu_combined_worker_get_id
 - Parallel Tasks, 416
- starpu_combined_worker_get_rank
 - Parallel Tasks, 415
- starpu_combined_worker_get_size
 - Parallel Tasks, 415
- starpu_conf, 181
- starpu_conf_init
 - Initialization and Termination, 186
- starpu_config.h, 483
- starpu_coo_data_register
 - Data Interfaces, 261
- starpu_coo_interface, 247
- starpu_cpu_func_t
 - Codelet And Tasks, 308
- starpu_cpu_worker_get_count
 - Workers' Properties, 218
- starpu_create_sync_task
 - Codelet And Tasks, 314
- starpu_csr_data_register
 - Data Interfaces, 260
- starpu_csr_filter_vertical_block
 - Data Partition, 281
- starpu_csr_get_elemsize
 - Data Interfaces, 267
- starpu_csr_get_firstentry
 - Data Interfaces, 266
- starpu_csr_get_local_colind
 - Data Interfaces, 267
- starpu_csr_get_local_nzval
 - Data Interfaces, 266
- starpu_csr_get_local_rowptr
 - Data Interfaces, 267
- starpu_csr_get_nnz
 - Data Interfaces, 266
- starpu_csr_get_nrow
 - Data Interfaces, 266
- starpu_csr_interface, 247
- starpu_cublas.h, 485
- starpu_cublas_init
 - CUDA Extensions, 345
- starpu_cublas_report_error
 - CUDA Extensions, 345
- starpu_cublas_shutdown
 - CUDA Extensions, 345
- starpu_cuda.h, 485
- starpu_cuda_copy_async_sync
 - CUDA Extensions, 344
- starpu_cuda_func_t
 - Codelet And Tasks, 308
- starpu_cuda_get_device_properties
 - CUDA Extensions, 344
- starpu_cuda_get_local_stream
 - CUDA Extensions, 344
- starpu_cuda_report_error
 - CUDA Extensions, 344
- starpu_cuda_set_device
 - CUDA Extensions, 344
- starpu_cuda_worker_get_count
 - Workers' Properties, 219
- starpu_data.h, 485
- starpu_data_access_mode
 - Data Management, 224
- starpu_data_acquire
 - Data Management, 230
- starpu_data_acquire_cb
 - Data Management, 230
- starpu_data_acquire_cb_sequential_consistency
 - Data Management, 230
- starpu_data_acquire_on_node
 - Data Management, 231
- starpu_data_acquire_on_node_cb
 - Data Management, 231
- starpu_data_acquire_on_node_cb_sequential_↔consistency
 - Data Management, 231
- starpu_data_acquire_on_node_cb_sequential_↔consistency_sync_jobids
 - Data Management, 231
- starpu_data_acquire_on_node_try
 - Data Management, 232
- starpu_data_acquire_try
 - Data Management, 230
- starpu_data_advise_as_important

- Data Management, [229](#)
- starpu_data_assign_arbiter
 - Data Management, [232](#)
- starpu_data_copy_methods, [240](#)
 - any_to_any, [244](#)
 - can_copy, [241](#)
 - cuda_to_cuda, [242](#)
 - cuda_to_cuda_async, [243](#)
 - cuda_to_opencil, [242](#)
 - cuda_to_ram, [242](#)
 - cuda_to_ram_async, [243](#)
 - mic_to_ram, [242](#)
 - mic_to_ram_async, [244](#)
 - opencil_to_cuda, [242](#)
 - opencil_to_opencil, [242](#)
 - opencil_to_opencil_async, [244](#)
 - opencil_to_ram, [242](#)
 - opencil_to_ram_async, [244](#)
 - ram_to_cuda, [241](#)
 - ram_to_cuda_async, [243](#)
 - ram_to_mic, [241](#)
 - ram_to_mic_async, [244](#)
 - ram_to_opencil, [241](#)
 - ram_to_opencil_async, [244](#)
 - ram_to_ram, [241](#)
 - scc_sink_to_sink, [243](#)
 - scc_sink_to_src, [243](#)
 - scc_src_to_sink, [243](#)
- starpu_data_cpy
 - Miscellaneous Helpers, [387](#)
- starpu_data_descr, [296](#)
- starpu_data_display_memory_stats
 - Profiling, [340](#)
- starpu_data_expected_transfer_time
 - Scheduling Policy, [444](#)
- starpu_data_fetch_on_node
 - Data Management, [227](#)
- starpu_data_filter, [271](#)
 - filter_arg, [272](#)
 - filter_arg_ptr, [273](#)
 - filter_func, [272](#)
 - get_child_ops, [272](#)
 - get_nchildren, [272](#)
 - nchildren, [272](#)
- starpu_data_filters.h, [487](#)
- starpu_data_free_pinned_if_possible
 - Standard Memory Library, [189](#)
- starpu_data_get_child
 - Data Partition, [274](#)
- starpu_data_get_default_sequential_consistency_flag
 - Implicit Data Dependencies, [325](#)
- starpu_data_get_interface_id
 - Data Interfaces, [262](#)
- starpu_data_get_interface_on_node
 - Data Interfaces, [261](#)
- starpu_data_get_interface_ops
 - Data Management, [229](#)
- starpu_data_get_local_ptr
 - Data Interfaces, [261](#)
- starpu_data_get_nb_children
 - Data Partition, [273](#)
- starpu_data_get_rank
 - MPI Support, [396](#)
- starpu_data_get_sequential_consistency_flag
 - Implicit Data Dependencies, [325](#)
- starpu_data_get_size
 - Data Interfaces, [262](#)
- starpu_data_get_sub_data
 - Data Partition, [274](#)
- starpu_data_get_tag
 - MPI Support, [397](#)
- starpu_data_get_user_data
 - Data Management, [229](#)
- starpu_data_handle_t
 - Data Management, [224](#)
- starpu_data_handle_to_pointer
 - Data Interfaces, [261](#)
- starpu_data_idle_prefetch_on_node
 - Data Management, [228](#)
- starpu_data_interface_get_next_id
 - Data Interfaces, [269](#)
- starpu_data_interface_id
 - Data Interfaces, [256](#)
- starpu_data_interface_ops, [237](#)
 - allocate_data_on_node, [238](#)
 - compare, [239](#)
 - copy_methods, [238](#)
 - describe, [239](#)
 - display, [239](#)
 - dontcache, [239](#)
 - footprint, [238](#)
 - free_data_on_node, [238](#)
 - get_mf_ops, [239](#)
 - get_size, [238](#)
 - handle_to_pointer, [238](#)
 - interface_size, [239](#)
 - interfaceid, [239](#)
 - is_multiformat, [239](#)
 - name, [240](#)
 - pack_data, [240](#)
 - pointer_is_inside, [238](#)
 - register_data_handle, [237](#)
 - unpack_data, [240](#)
- starpu_data_interfaces.h, [489](#)
- starpu_data_invalidate
 - Data Management, [226](#)
- starpu_data_invalidate_submit
 - Data Management, [226](#)
- starpu_data_lookup
 - Data Management, [228](#)
- starpu_data_malloc_pinned_if_possible
 - Standard Memory Library, [188](#)
- starpu_data_map_filters
 - Data Partition, [274](#)
- starpu_data_pack
 - Data Interfaces, [262](#)

- starpu_data_partition
 - Data Partition, [273](#)
- starpu_data_partition_clean
 - Data Partition, [277](#)
- starpu_data_partition_plan
 - Data Partition, [275](#)
- starpu_data_partition_readonly_submit
 - Data Partition, [275](#)
- starpu_data_partition_readwrite_upgrade_submit
 - Data Partition, [276](#)
- starpu_data_partition_submit
 - Data Partition, [275](#)
- starpu_data_pointer_is_inside
 - Data Interfaces, [261](#)
- starpu_data_prefetch_on_node
 - Data Management, [227](#)
- starpu_data_ptr_register
 - Data Management, [225](#)
- starpu_data_query_status
 - Data Management, [228](#)
- starpu_data_register
 - Data Management, [225](#)
- starpu_data_register_same
 - Data Management, [225](#)
- starpu_data_release
 - Data Management, [232](#)
- starpu_data_release_on_node
 - Data Management, [232](#)
- starpu_data_request_allocation
 - Data Management, [228](#)
- starpu_data_set_coordinates
 - Data Management, [227](#)
- starpu_data_set_coordinates_array
 - Data Management, [227](#)
- starpu_data_set_default_sequential_consistency_flag
 - Implicit Data Dependencies, [325](#)
- starpu_data_set_name
 - Data Management, [227](#)
- starpu_data_set_rank
 - MPI Support, [396](#)
- starpu_data_set_reduction_methods
 - Data Management, [229](#)
- starpu_data_set_sequential_consistency_flag
 - Implicit Data Dependencies, [325](#)
- starpu_data_set_tag
 - MPI Support, [396](#)
- starpu_data_set_user_data
 - Data Management, [229](#)
- starpu_data_set_wt_mask
 - Data Management, [226](#)
- starpu_data_unpack
 - Data Interfaces, [262](#)
- starpu_data_unpartition
 - Data Partition, [273](#)
- starpu_data_unpartition_readonly_submit
 - Data Partition, [276](#)
- starpu_data_unpartition_submit
 - Data Partition, [276](#)
- starpu_data_unregister
 - Data Management, [226](#)
- starpu_data_unregister_no_coherency
 - Data Management, [226](#)
- starpu_data_unregister_submit
 - Data Management, [226](#)
- starpu_data_vget_sub_data
 - Data Partition, [274](#)
- starpu_data_vmap_filters
 - Data Partition, [274](#)
- starpu_data_wont_use
 - Data Management, [228](#)
- starpu_deprecated_api.h, [494](#)
- starpu_disk.h, [494](#)
- starpu_disk_close
 - Out Of Core, [285](#)
- starpu_disk_leveldb_ops
 - Out Of Core, [286](#)
- starpu_disk_open
 - Out Of Core, [285](#)
- starpu_disk_ops, [282](#)
 - alloc, [283](#)
 - async_full_read, [284](#)
 - async_full_write, [284](#)
 - async_read, [284](#)
 - async_write, [284](#)
 - bandwidth, [283](#)
 - close, [283](#)
 - copy, [284](#)
 - free, [283](#)
 - free_request, [285](#)
 - full_read, [283](#)
 - full_write, [284](#)
 - open, [283](#)
 - plug, [282](#)
 - read, [283](#)
 - test_request, [284](#)
 - unplug, [282](#)
 - wait_request, [284](#)
 - write, [283](#)
- starpu_disk_register
 - Out Of Core, [285](#)
- starpu_disk_stdio_ops
 - Out Of Core, [286](#)
- starpu_disk_swap_node
 - Out Of Core, [286](#)
- starpu_disk_unistd_o_direct_ops
 - Out Of Core, [286](#)
- starpu_disk_unistd_ops
 - Out Of Core, [286](#)
- starpu_driver, [180](#)
- starpu_driver.h, [494](#)
- starpu_driver.id, [181](#)
- starpu_driver_deinit
 - Running Drivers, [417](#)
- starpu_driver_init
 - Running Drivers, [417](#)
- starpu_driver_run

- Running Drivers, [417](#)
- starpu_driver_run_once
 - Running Drivers, [417](#)
- starpu_drivers_request_termination
 - Running Drivers, [418](#)
- starpu_execute_on_each_worker
 - Miscellaneous Helpers, [387](#)
- starpu_execute_on_each_worker_ex
 - Miscellaneous Helpers, [387](#)
- starpu_execute_on_specific_workers
 - Miscellaneous Helpers, [387](#)
- starpu_expert.h, [495](#)
- starpu_free
 - Standard Memory Library, [191](#)
- starpu_free_flags
 - Standard Memory Library, [191](#)
- starpu_free_on_node
 - Data Interfaces, [268](#)
- starpu_free_on_node_flags
 - Data Interfaces, [267](#)
- starpu_fxt.h, [495](#)
- starpu_fxt_autostart_profiling
 - FxT Support, [390](#)
- starpu_fxt_codelet_event, [388](#)
- starpu_fxt_generate_trace
 - FxT Support, [390](#)
- starpu_fxt_options, [389](#)
- starpu_fxt_options_init
 - FxT Support, [390](#)
- starpu_fxt_start_profiling
 - FxT Support, [390](#)
- starpu_fxt_stop_profiling
 - FxT Support, [390](#)
- starpu_fxt_trace_user_event
 - FxT Support, [390](#)
- starpu_fxt_trace_user_event_string
 - FxT Support, [391](#)
- starpu_fxt_write_data_trace
 - FxT Support, [390](#)
- starpu_get_env_number
 - Toolbox, [197](#)
- starpu_get_prefetch_flag
 - Scheduling Policy, [444](#)
- starpu_get_version
 - Versioning, [180](#)
- starpu_hash.h, [496](#)
- starpu_hash_crc32c_be
 - Data Interfaces, [268](#)
- starpu_hash_crc32c_be_n
 - Data Interfaces, [268](#)
- starpu_hash_crc32c_string
 - Data Interfaces, [269](#)
- starpu_idle_prefetch_task_input_on_node
 - Scheduling Policy, [445](#)
- starpu_init
 - Initialization and Termination, [186](#)
- starpu_initialize
 - Initialization and Termination, [186](#)
- starpu_insert_task
 - Insert_Task, [318](#)
- starpu_interface_copy
 - Data Interfaces, [268](#)
- starpu_iteration_pop
 - Codelet And Tasks, [314](#)
- starpu_iteration_push
 - Codelet And Tasks, [314](#)
- starpu_malloc
 - Standard Memory Library, [190](#)
- starpu_malloc_flags
 - Standard Memory Library, [190](#)
- starpu_malloc_on_node
 - Data Interfaces, [267](#)
- starpu_malloc_on_node_flags
 - Data Interfaces, [267](#)
- starpu_malloc_on_node_set_default_flags
 - Data Interfaces, [268](#)
- starpu_malloc_set_align
 - Standard Memory Library, [190](#)
- starpu_matrix_data_register
 - Data Interfaces, [258](#)
- starpu_matrix_filter_block
 - Data Partition, [278](#)
- starpu_matrix_filter_block_shadow
 - Data Partition, [278](#)
- starpu_matrix_filter_vertical_block
 - Data Partition, [279](#)
- starpu_matrix_filter_vertical_block_shadow
 - Data Partition, [279](#)
- starpu_matrix_get_elemsize
 - Data Interfaces, [264](#)
- starpu_matrix_get_local_id
 - Data Interfaces, [263](#)
- starpu_matrix_get_local_ptr
 - Data Interfaces, [263](#)
- starpu_matrix_get_nx
 - Data Interfaces, [263](#)
- starpu_matrix_get_ny
 - Data Interfaces, [263](#)
- starpu_matrix_interface, [245](#)
- starpu_matrix_ptr_register
 - Data Interfaces, [258](#)
- starpu_memory_allocate
 - Standard Memory Library, [192](#)
- starpu_memory_deallocate
 - Standard Memory Library, [192](#)
- starpu_memory_get_available
 - Standard Memory Library, [192](#)
- starpu_memory_get_total
 - Standard Memory Library, [191](#)
- starpu_memory_pin
 - Standard Memory Library, [191](#)
- starpu_memory_unpin
 - Standard Memory Library, [191](#)
- starpu_memory_wait_available
 - Standard Memory Library, [193](#)
- starpu_mic.h, [496](#)

- starpu_mic_device_get_count
 - Workers' Properties, [219](#)
- starpu_mic_func_symbol_t
 - MIC Extensions, [384](#)
- starpu_mic_func_t
 - Codelet And Tasks, [308](#)
- starpu_mic_get_kernel
 - MIC Extensions, [384](#)
- starpu_mic_kernel_t
 - Codelet And Tasks, [309](#)
- starpu_mic_register_kernel
 - MIC Extensions, [384](#)
- starpu_mic_worker_get_count
 - Workers' Properties, [219](#)
- starpu_mpi.h, [519](#)
- starpu_mpi_barrier
 - MPI Support, [402](#)
- starpu_mpi_cache_flush
 - MPI Support, [405](#)
- starpu_mpi_cache_flush_all_data
 - MPI Support, [405](#)
- starpu_mpi_cache_is_enabled
 - MPI Support, [404](#)
- starpu_mpi_cache_set
 - MPI Support, [404](#)
- starpu_mpi_cached_receive
 - MPI Support, [405](#)
- starpu_mpi_cached_send
 - MPI Support, [405](#)
- starpu_mpi_comm_amounts_retrieve
 - MPI Support, [398](#)
- starpu_mpi_comm_get_attr
 - MPI Support, [404](#)
- starpu_mpi_comm_rank
 - MPI Support, [399](#)
- starpu_mpi_comm_size
 - MPI Support, [399](#)
- starpu_mpi_data_get_rank
 - MPI Support, [406](#)
- starpu_mpi_data_get_tag
 - MPI Support, [406](#)
- starpu_mpi_data_migrate
 - MPI Support, [406](#)
- starpu_mpi_data_register
 - MPI Support, [396](#)
- starpu_mpi_data_register_comm
 - MPI Support, [405](#)
- starpu_mpi_data_set_rank
 - MPI Support, [396](#)
- starpu_mpi_data_set_rank_comm
 - MPI Support, [406](#)
- starpu_mpi_data_set_tag
 - MPI Support, [405](#)
- starpu_mpi_datatype_register
 - MPI Support, [404](#)
- starpu_mpi_datatype_unregister
 - MPI Support, [404](#)
- starpu_mpi_gather_detached
 - MPI Support, [410](#)
- starpu_mpi_get_communication_tag
 - MPI Support, [403](#)
- starpu_mpi_get_data_on_all_nodes_detached
 - MPI Support, [408](#)
- starpu_mpi_get_data_on_node
 - MPI Support, [408](#)
- starpu_mpi_get_data_on_node_detached
 - MPI Support, [408](#)
- starpu_mpi_init
 - MPI Support, [398](#)
- starpu_mpi_init_comm
 - MPI Support, [397](#)
- starpu_mpi_initialize
 - MPI Support, [398](#)
- starpu_mpi_initialize_extended
 - MPI Support, [398](#)
- starpu_mpi_insert_task
 - MPI Support, [406](#)
- starpu_mpi_irecv
 - MPI Support, [400](#)
- starpu_mpi_irecv_array_detached_unlock_tag
 - MPI Support, [403](#)
- starpu_mpi_irecv_detached
 - MPI Support, [400](#)
- starpu_mpi_irecv_detached_sequential_consistency
 - MPI Support, [401](#)
- starpu_mpi_irecv_detached_unlock_tag
 - MPI Support, [403](#)
- starpu_mpi_isend
 - MPI Support, [400](#)
- starpu_mpi_isend_array_detached_unlock_tag
 - MPI Support, [403](#)
- starpu_mpi_isend_detached
 - MPI Support, [400](#)
- starpu_mpi_isend_detached_unlock_tag
 - MPI Support, [402](#)
- starpu_mpi_issend
 - MPI Support, [401](#)
- starpu_mpi_issend_detached
 - MPI Support, [401](#)
- starpu_mpi_node_selection_get_current_policy
 - MPI Support, [408](#)
- starpu_mpi_node_selection_register_policy
 - MPI Support, [409](#)
- starpu_mpi_node_selection_set_current_policy
 - MPI Support, [408](#)
- starpu_mpi_node_selection_unregister_policy
 - MPI Support, [409](#)
- starpu_mpi_rcv
 - MPI Support, [399](#)
- starpu_mpi_redux_data
 - MPI Support, [409](#)
- starpu_mpi_scatter_detached
 - MPI Support, [409](#)
- starpu_mpi_send
 - MPI Support, [399](#)
- starpu_mpi_set_communication_tag

- MPI Support, [404](#)
- starpu_mpi_shutdown
 - MPI Support, [398](#)
- starpu_mpi_task_build
 - MPI Support, [407](#)
- starpu_mpi_task_insert
 - MPI Support, [407](#)
- starpu_mpi_task_post_build
 - MPI Support, [407](#)
- starpu_mpi_test
 - MPI Support, [402](#)
- starpu_mpi_wait
 - MPI Support, [402](#)
- starpu_mpi_wait_for_all
 - MPI Support, [402](#)
- starpu_mpi_world_rank
 - MPI Support, [399](#)
- starpu_mpi_world_size
 - MPI Support, [399](#)
- starpu_multiformat_data_interface_ops, [287](#)
- starpu_multiformat_data_register
 - Multiformat Data Interface, [289](#)
- starpu_multiformat_interface, [287](#)
- starpu_node_get_kind
 - Workers' Properties, [221](#)
- starpu_node_kind
 - Workers' Properties, [217](#)
- starpu_omp_atomic_fallback_inline_begin
 - OpenMP Runtime Support, [381](#)
- starpu_omp_atomic_fallback_inline_end
 - OpenMP Runtime Support, [382](#)
- starpu_omp_barrier
 - OpenMP Runtime Support, [361](#)
- starpu_omp_critical
 - OpenMP Runtime Support, [361](#)
- starpu_omp_critical_inline_begin
 - OpenMP Runtime Support, [361](#)
- starpu_omp_critical_inline_end
 - OpenMP Runtime Support, [361](#)
- starpu_omp_destroy_lock
 - OpenMP Runtime Support, [378](#)
- starpu_omp_destroy_nest_lock
 - OpenMP Runtime Support, [380](#)
- starpu_omp_for
 - OpenMP Runtime Support, [363](#)
- starpu_omp_for_alt
 - OpenMP Runtime Support, [364](#)
- starpu_omp_for_inline_first
 - OpenMP Runtime Support, [363](#)
- starpu_omp_for_inline_first_alt
 - OpenMP Runtime Support, [365](#)
- starpu_omp_for_inline_next
 - OpenMP Runtime Support, [364](#)
- starpu_omp_for_inline_next_alt
 - OpenMP Runtime Support, [365](#)
- starpu_omp_get_active_level
 - OpenMP Runtime Support, [375](#)
- starpu_omp_get_ancestor_thread_num
 - OpenMP Runtime Support, [374](#)
- starpu_omp_get_cancellation
 - OpenMP Runtime Support, [372](#)
- starpu_omp_get_default_device
 - OpenMP Runtime Support, [376](#)
- starpu_omp_get_dynamic
 - OpenMP Runtime Support, [371](#)
- starpu_omp_get_level
 - OpenMP Runtime Support, [374](#)
- starpu_omp_get_max_active_levels
 - OpenMP Runtime Support, [374](#)
- starpu_omp_get_max_threads
 - OpenMP Runtime Support, [370](#)
- starpu_omp_get_nested
 - OpenMP Runtime Support, [372](#)
- starpu_omp_get_num_devices
 - OpenMP Runtime Support, [377](#)
- starpu_omp_get_num_procs
 - OpenMP Runtime Support, [370](#)
- starpu_omp_get_num_teams
 - OpenMP Runtime Support, [377](#)
- starpu_omp_get_num_threads
 - OpenMP Runtime Support, [369](#)
- starpu_omp_get_proc_bind
 - OpenMP Runtime Support, [376](#)
- starpu_omp_get_schedule
 - OpenMP Runtime Support, [373](#)
- starpu_omp_get_team_num
 - OpenMP Runtime Support, [377](#)
- starpu_omp_get_team_size
 - OpenMP Runtime Support, [375](#)
- starpu_omp_get_thread_limit
 - OpenMP Runtime Support, [373](#)
- starpu_omp_get_thread_num
 - OpenMP Runtime Support, [369](#)
- starpu_omp_get_wtick
 - OpenMP Runtime Support, [382](#)
- starpu_omp_get_wtime
 - OpenMP Runtime Support, [382](#)
- starpu_omp_in_final
 - OpenMP Runtime Support, [375](#)
- starpu_omp_in_parallel
 - OpenMP Runtime Support, [370](#)
- starpu_omp_init
 - OpenMP Runtime Support, [360](#)
- starpu_omp_init_lock
 - OpenMP Runtime Support, [378](#)
- starpu_omp_init_nest_lock
 - OpenMP Runtime Support, [380](#)
- starpu_omp_is_initial_device
 - OpenMP Runtime Support, [378](#)
- starpu_omp_lock_t, [357](#)
- starpu_omp_master
 - OpenMP Runtime Support, [360](#)
- starpu_omp_master_inline
 - OpenMP Runtime Support, [360](#)
- starpu_omp_nest_lock_t, [357](#)
- starpu_omp_ordered

- OpenMP Runtime Support, [366](#)
- starpu_omp_ordered_inline_begin
 - OpenMP Runtime Support, [366](#)
- starpu_omp_ordered_inline_end
 - OpenMP Runtime Support, [366](#)
- starpu_omp_parallel_region
 - OpenMP Runtime Support, [360](#)
- starpu_omp_parallel_region_attr, [357](#)
- starpu_omp_proc_bind_value
 - OpenMP Runtime Support, [359](#)
- starpu_omp_sched_value
 - OpenMP Runtime Support, [359](#)
- starpu_omp_sections
 - OpenMP Runtime Support, [366](#)
- starpu_omp_sections_combined
 - OpenMP Runtime Support, [367](#)
- starpu_omp_set_default_device
 - OpenMP Runtime Support, [376](#)
- starpu_omp_set_dynamic
 - OpenMP Runtime Support, [371](#)
- starpu_omp_set_lock
 - OpenMP Runtime Support, [379](#)
- starpu_omp_set_max_active_levels
 - OpenMP Runtime Support, [373](#)
- starpu_omp_set_nest_lock
 - OpenMP Runtime Support, [380](#)
- starpu_omp_set_nested
 - OpenMP Runtime Support, [371](#)
- starpu_omp_set_num_threads
 - OpenMP Runtime Support, [369](#)
- starpu_omp_set_schedule
 - OpenMP Runtime Support, [372](#)
- starpu_omp_shutdown
 - OpenMP Runtime Support, [360](#)
- starpu_omp_single
 - OpenMP Runtime Support, [362](#)
- starpu_omp_single_copyprivate
 - OpenMP Runtime Support, [362](#)
- starpu_omp_single_copyprivate_inline_begin
 - OpenMP Runtime Support, [362](#)
- starpu_omp_single_copyprivate_inline_end
 - OpenMP Runtime Support, [363](#)
- starpu_omp_single_inline
 - OpenMP Runtime Support, [362](#)
- starpu_omp_task_region
 - OpenMP Runtime Support, [367](#)
- starpu_omp_task_region_attr, [358](#)
- starpu_omp_taskgroup
 - OpenMP Runtime Support, [368](#)
- starpu_omp_taskgroup_inline_begin
 - OpenMP Runtime Support, [368](#)
- starpu_omp_taskgroup_inline_end
 - OpenMP Runtime Support, [368](#)
- starpu_omp_taskwait
 - OpenMP Runtime Support, [367](#)
- starpu_omp_test_lock
 - OpenMP Runtime Support, [379](#)
- starpu_omp_test_nest_lock
 - OpenMP Runtime Support, [381](#)
- starpu_omp_unset_lock
 - OpenMP Runtime Support, [379](#)
- starpu_omp_unset_nest_lock
 - OpenMP Runtime Support, [381](#)
- starpu_omp_vector_annotate
 - OpenMP Runtime Support, [383](#)
- starpu_opencl.h, [496](#)
- starpu_opencl_allocate_memory
 - OpenCL Extensions, [352](#)
- starpu_opencl_collect_stats
 - OpenCL Extensions, [351](#)
- starpu_opencl_compile_opencl_from_file
 - OpenCL Extensions, [350](#)
- starpu_opencl_compile_opencl_from_string
 - OpenCL Extensions, [351](#)
- starpu_opencl_copy_async_sync
 - OpenCL Extensions, [353](#)
- starpu_opencl_copy_opencl_to_opencl
 - OpenCL Extensions, [353](#)
- starpu_opencl_copy_opencl_to_ram
 - OpenCL Extensions, [353](#)
- starpu_opencl_copy_ram_to_opencl
 - OpenCL Extensions, [352](#)
- starpu_opencl_display_error
 - OpenCL Extensions, [352](#)
- starpu_opencl_error_string
 - OpenCL Extensions, [352](#)
- starpu_opencl_func_t
 - Codelet And Tasks, [308](#)
- starpu_opencl_get_context
 - OpenCL Extensions, [348](#)
- starpu_opencl_get_current_context
 - OpenCL Extensions, [349](#)
- starpu_opencl_get_current_queue
 - OpenCL Extensions, [349](#)
- starpu_opencl_get_device
 - OpenCL Extensions, [348](#)
- starpu_opencl_get_queue
 - OpenCL Extensions, [349](#)
- starpu_opencl_load_binary_opencl
 - OpenCL Extensions, [351](#)
- starpu_opencl_load_kernel
 - OpenCL Extensions, [351](#)
- starpu_opencl_load_opencl_from_file
 - OpenCL Extensions, [349](#)
- starpu_opencl_load_opencl_from_string
 - OpenCL Extensions, [350](#)
- starpu_opencl_load_program_source
 - OpenCL Extensions, [350](#)
- starpu_opencl_load_program_source_malloc
 - OpenCL Extensions, [350](#)
- starpu_opencl_program, [347](#)
- starpu_opencl_release_kernel
 - OpenCL Extensions, [351](#)
- starpu_opencl_report_error
 - OpenCL Extensions, [352](#)
- starpu_opencl_set_kernel_args

- OpenCL Extensions, [349](#)
- starpu_opengl_unload_opengl
 - OpenCL Extensions, [350](#)
- starpu_opengl_worker_get_count
 - Workers' Properties, [219](#)
- starpu_openmp.h, [498](#)
- starpu_parallel_task_barrier_init
 - Parallel Tasks, [416](#)
- starpu_parallel_task_barrier_init_n
 - Parallel Tasks, [416](#)
- starpu_pause
 - Initialization and Termination, [187](#)
- starpu_perfmodel, [327](#)
 - arch_cost_function, [328](#)
 - cost_function, [328](#)
 - footprint, [328](#)
 - is_init, [329](#)
 - is_loaded, [328](#)
 - size_base, [328](#)
 - symbol, [328](#)
 - type, [327](#)
- starpu_perfmodel.h, [500](#)
- starpu_perfmodel_arch, [327](#)
- starpu_perfmodel_debugfilepath
 - Performance Model, [332](#)
- starpu_perfmodel_device, [327](#)
- starpu_perfmodel_directory
 - Performance Model, [333](#)
- starpu_perfmodel_free_sampling_directories
 - Performance Model, [331](#)
- starpu_perfmodel_get_arch_name
 - Performance Model, [332](#)
- starpu_perfmodel_get_archtype_name
 - Performance Model, [332](#)
- starpu_perfmodel_history_based_expected_perf
 - Performance Model, [335](#)
- starpu_perfmodel_history_entry, [330](#)
- starpu_perfmodel_history_list, [330](#)
- starpu_perfmodel_init
 - Performance Model, [331](#)
- starpu_perfmodel_initialize
 - Performance Model, [332](#)
- starpu_perfmodel_list
 - Performance Model, [333](#)
- starpu_perfmodel_load_file
 - Performance Model, [331](#)
- starpu_perfmodel_load_symbol
 - Performance Model, [331](#)
- starpu_perfmodel_per_arch, [329](#)
- starpu_perfmodel_print
 - Performance Model, [333](#)
- starpu_perfmodel_print_all
 - Performance Model, [333](#)
- starpu_perfmodel_print_estimations
 - Performance Model, [333](#)
- starpu_perfmodel_regression_model, [329](#)
- starpu_perfmodel_type
 - Performance Model, [330](#)
- starpu_perfmodel_unload_model
 - Performance Model, [332](#)
- starpu_perfmodel_update_history
 - Performance Model, [334](#)
- starpu_prefetch_task_input_on_node
 - Scheduling Policy, [445](#)
- starpu_private
 - starpu_task, [304](#)
- starpu_profiling.h, [502](#)
- starpu_profiling_bus_helper_display_summary
 - Profiling, [340](#)
- starpu_profiling_bus_info, [337](#)
- starpu_profiling_init
 - Profiling, [338](#)
- starpu_profiling_set_id
 - Profiling, [339](#)
- starpu_profiling_status_get
 - Profiling, [338](#)
- starpu_profiling_status_set
 - Profiling, [338](#)
- starpu_profiling_task_info, [336](#)
- starpu_profiling_worker_get_info
 - Profiling, [339](#)
- starpu_profiling_worker_helper_display_summary
 - Profiling, [340](#)
- starpu_profiling_worker_info, [337](#)
- starpu_progression_hook_deregister
 - Expert Mode, [418](#)
- starpu_progression_hook_register
 - Expert Mode, [418](#)
- starpu_pthread_attr_destroy
 - Threads, [204](#)
- starpu_pthread_attr_init
 - Threads, [204](#)
- starpu_pthread_attr_setdetachstate
 - Threads, [204](#)
- starpu_pthread_barrier_destroy
 - Threads, [209](#)
- starpu_pthread_barrier_init
 - Threads, [209](#)
- starpu_pthread_barrier_t, [514](#)
- starpu_pthread_barrier_wait
 - Threads, [209](#)
- starpu_pthread_cond_broadcast
 - Threads, [207](#)
- starpu_pthread_cond_destroy
 - Threads, [208](#)
- starpu_pthread_cond_init
 - Threads, [207](#)
- starpu_pthread_cond_signal
 - Threads, [207](#)
- starpu_pthread_cond_timedwait
 - Threads, [207](#)
- starpu_pthread_cond_wait
 - Threads, [207](#)
- starpu_pthread_create
 - Threads, [203](#)
- starpu_pthread_exit

- Threads, [203](#)
- starpu_pthread_getspecific
 - Threads, [206](#)
- starpu_pthread_join
 - Threads, [203](#)
- starpu_pthread_key_create
 - Threads, [206](#)
- starpu_pthread_key_delete
 - Threads, [206](#)
- starpu_pthread_mutex_destroy
 - Threads, [204](#)
- starpu_pthread_mutex_init
 - Threads, [204](#)
- starpu_pthread_mutex_lock
 - Threads, [205](#)
- starpu_pthread_mutex_trylock
 - Threads, [205](#)
- starpu_pthread_mutex_unlock
 - Threads, [205](#)
- starpu_pthread_mutexattr_destroy
 - Threads, [206](#)
- starpu_pthread_mutexattr_gettype
 - Threads, [205](#)
- starpu_pthread_mutexattr_init
 - Threads, [206](#)
- starpu_pthread_mutexattr_settype
 - Threads, [205](#)
- starpu_pthread_rwlock_destroy
 - Threads, [208](#)
- starpu_pthread_rwlock_init
 - Threads, [208](#)
- starpu_pthread_rwlock_rdlock
 - Threads, [208](#)
- starpu_pthread_rwlock_tryrdlock
 - Threads, [208](#)
- starpu_pthread_rwlock_trywrlock
 - Threads, [209](#)
- starpu_pthread_rwlock_unlock
 - Threads, [209](#)
- starpu_pthread_rwlock_wrlock
 - Threads, [208](#)
- starpu_pthread_setspecific
 - Threads, [206](#)
- starpu_pthread_spin_destroy
 - Threads, [210](#)
- starpu_pthread_spin_init
 - Threads, [209](#)
- starpu_pthread_spin_lock
 - Threads, [210](#)
- starpu_pthread_spin_trylock
 - Threads, [210](#)
- starpu_pthread_spin_unlock
 - Threads, [210](#)
- starpu_pthread_spinlock_t, [514](#)
- starpu_push_local_task
 - Scheduling Policy, [442](#)
- starpu_push_task_end
 - Scheduling Policy, [442](#)
- starpu_rand.h, [503](#)
- starpu_resume
 - Initialization and Termination, [187](#)
- starpu_scc.h, [503](#)
- starpu_scc_func_symbol_t
 - SCC Extensions, [386](#)
- starpu_scc_func_t
 - Codelet And Tasks, [309](#)
- starpu_scc_get_kernel
 - SCC Extensions, [386](#)
- starpu_scc_kernel_t
 - Codelet And Tasks, [309](#)
- starpu_scc_register_kernel
 - SCC Extensions, [386](#)
- starpu_scc_worker_get_count
 - Workers' Properties, [219](#)
- starpu_sched_component, [463](#)
 - add_child, [465](#)
 - add_parent, [465](#)
 - can_pull, [466](#)
 - can_push, [466](#)
 - children, [465](#)
 - data, [464](#)
 - deinit_data, [466](#)
 - estimated_end, [466](#)
 - estimated_load, [466](#)
 - nchildren, [465](#)
 - notify_change_workers, [467](#)
 - nparents, [465](#)
 - obj, [467](#)
 - parents, [465](#)
 - properties, [467](#)
 - pull_task, [466](#)
 - push_task, [466](#)
 - remove_child, [465](#)
 - remove_parent, [465](#)
 - tree, [464](#)
 - workers, [464](#)
 - workers_in_ctx, [464](#)
- starpu_sched_component_can_execute_task
 - Modularized Scheduler Interface, [471](#)
- starpu_sched_component_composed_component_↔
 - create
 - Modularized Scheduler Interface, [477](#)
- starpu_sched_component_composed_recipe, [468](#)
- starpu_sched_component_composed_recipe_add
 - Modularized Scheduler Interface, [476](#)
- starpu_sched_component_composed_recipe_create
 - Modularized Scheduler Interface, [476](#)
- starpu_sched_component_composed_recipe_create↔
 - _singleton
 - Modularized Scheduler Interface, [476](#)
- starpu_sched_component_composed_recipe_destroy
 - Modularized Scheduler Interface, [476](#)
- starpu_sched_component_connect
 - Modularized Scheduler Interface, [470](#)
- starpu_sched_component_create
 - Modularized Scheduler Interface, [471](#)

- starpu_sched_component_destroy
 - Modularized Scheduler Interface, [471](#)
- starpu_sched_component_destroy_rec
 - Modularized Scheduler Interface, [471](#)
- starpu_sched_component_estimated_end_average
 - Modularized Scheduler Interface, [473](#)
- starpu_sched_component_estimated_end_min
 - Modularized Scheduler Interface, [473](#)
- starpu_sched_component_estimated_load
 - Modularized Scheduler Interface, [473](#)
- starpu_sched_component_execute_preds
 - Modularized Scheduler Interface, [471](#)
- starpu_sched_component_fifo_create
 - Modularized Scheduler Interface, [473](#)
- starpu_sched_component_fifo_data, [467](#)
- starpu_sched_component_heft_create
 - Modularized Scheduler Interface, [475](#)
- starpu_sched_component_is_combined_worker
 - Modularized Scheduler Interface, [472](#)
- starpu_sched_component_is_eager
 - Modularized Scheduler Interface, [475](#)
- starpu_sched_component_is_eager_calibration
 - Modularized Scheduler Interface, [475](#)
- starpu_sched_component_is_fifo
 - Modularized Scheduler Interface, [474](#)
- starpu_sched_component_is_heft
 - Modularized Scheduler Interface, [475](#)
- starpu_sched_component_is_mct
 - Modularized Scheduler Interface, [475](#)
- starpu_sched_component_is_perfmodel_select
 - Modularized Scheduler Interface, [476](#)
- starpu_sched_component_is_prio
 - Modularized Scheduler Interface, [474](#)
- starpu_sched_component_is_random
 - Modularized Scheduler Interface, [474](#)
- starpu_sched_component_is_simple_worker
 - Modularized Scheduler Interface, [472](#)
- starpu_sched_component_is_work_stealing
 - Modularized Scheduler Interface, [474](#)
- starpu_sched_component_is_worker
 - Modularized Scheduler Interface, [472](#)
- starpu_sched_component_make_scheduler
 - Modularized Scheduler Interface, [477](#)
- starpu_sched_component_mct_create
 - Modularized Scheduler Interface, [475](#)
- starpu_sched_component_mct_data, [468](#)
- starpu_sched_component_perfmodel_select_create
 - Modularized Scheduler Interface, [476](#)
- starpu_sched_component_perfmodel_select_data, [468](#)
- starpu_sched_component_prio_create
 - Modularized Scheduler Interface, [474](#)
- starpu_sched_component_prio_data, [468](#)
- starpu_sched_component_properties
 - Modularized Scheduler Interface, [469](#)
- starpu_sched_component_pull_task
 - Modularized Scheduler Interface, [477](#)
- starpu_sched_component_push_task
 - Modularized Scheduler Interface, [477](#)
- starpu_sched_component_specs, [468](#)
- starpu_sched_component_transfer_length
 - Modularized Scheduler Interface, [472](#)
- starpu_sched_component_worker_get
 - Modularized Scheduler Interface, [472](#)
- starpu_sched_component_worker_get_workerid
 - Modularized Scheduler Interface, [472](#)
- starpu_sched_component_worker_post_exec_hook
 - Modularized Scheduler Interface, [473](#)
- starpu_sched_component_worker_pre_exec_hook
 - Modularized Scheduler Interface, [473](#)
- starpu_sched_ctx.h, [503](#)
- starpu_sched_ctx_add_workers
 - Scheduling Contexts, [431](#)
- starpu_sched_ctx_call_pushed_task_cb
 - Scheduling Contexts, [435](#)
- starpu_sched_ctx_check_if_hypervisor_exists
 - Scheduling Contexts, [436](#)
- starpu_sched_ctx_contains_worker
 - Scheduling Contexts, [433](#)
- starpu_sched_ctx_create
 - Scheduling Contexts, [430](#)
- starpu_sched_ctx_create_inside_interval
 - Scheduling Contexts, [430](#)
- starpu_sched_ctx_create_worker_collection
 - Scheduling Contexts, [435](#)
- starpu_sched_ctx_delete
 - Scheduling Contexts, [431](#)
- starpu_sched_ctx_delete_worker_collection
 - Scheduling Contexts, [435](#)
- starpu_sched_ctx_display_workers
 - Scheduling Contexts, [431](#)
- starpu_sched_ctx_exec_parallel_code
 - Scheduling Contexts, [436](#)
- starpu_sched_ctx_finished_submit
 - Scheduling Contexts, [432](#)
- starpu_sched_ctx_get_context
 - Scheduling Contexts, [432](#)
- starpu_sched_ctx_get_max_priority
 - Scheduling Contexts, [434](#)
- starpu_sched_ctx_get_min_priority
 - Scheduling Contexts, [434](#)
- starpu_sched_ctx_get_nready_flops
 - Scheduling Contexts, [436](#)
- starpu_sched_ctx_get_nready_tasks
 - Scheduling Contexts, [436](#)
- starpu_sched_ctx_get_nshared_workers
 - Scheduling Contexts, [433](#)
- starpu_sched_ctx_get_nworkers
 - Scheduling Contexts, [433](#)
- starpu_sched_ctx_get_policy_data
 - Scheduling Contexts, [436](#)
- starpu_sched_ctx_get_worker_collection
 - Scheduling Contexts, [435](#)
- starpu_sched_ctx_get_workers_list
 - Scheduling Contexts, [432](#)
- starpu_sched_ctx_get_workers_list_raw
 - Scheduling Contexts, [433](#)

- starpu_sched_ctx_hypervisor.h, 505
- starpu_sched_ctx_iterator, 216
- starpu_sched_ctx_max_priority_is_set
 - Scheduling Contexts, 434
- starpu_sched_ctx_min_priority_is_set
 - Scheduling Contexts, 434
- starpu_sched_ctx_notify_hypervisor_exists
 - Scheduling Contexts, 435
- starpu_sched_ctx_overlapping_ctxs_on_worker
 - Scheduling Contexts, 433
- starpu_sched_ctx_performance_counters, 428
 - notify_delete_context, 429
 - notify_idle_cycle, 428
 - notify_poped_task, 428
 - notify_post_exec_task, 429
 - notify_pushed_task, 429
 - notify_submitted_job, 429
- starpu_sched_ctx_register_close_callback
 - Scheduling Contexts, 431
- starpu_sched_ctx_remove_workers
 - Scheduling Contexts, 431
- starpu_sched_ctx_set_context
 - Scheduling Contexts, 432
- starpu_sched_ctx_set_inheritor
 - Scheduling Contexts, 432
- starpu_sched_ctx_set_max_priority
 - Scheduling Contexts, 434
- starpu_sched_ctx_set_min_priority
 - Scheduling Contexts, 434
- starpu_sched_ctx_set_perf_counters
 - Scheduling Contexts, 435
- starpu_sched_ctx_set_policy_data
 - Scheduling Contexts, 436
- starpu_sched_ctx_stop_task_submission
 - Scheduling Contexts, 432
- starpu_sched_ctx_worker_get_id
 - Scheduling Contexts, 433
- starpu_sched_ctx_worker_shares_tasks_lists
 - Scheduling Policy, 445
- starpu_sched_get_max_priority
 - Scheduling Policy, 442
- starpu_sched_get_min_priority
 - Scheduling Policy, 442
- starpu_sched_get_predefined_policies
 - Scheduling Policy, 441
- starpu_sched_policy, 438
 - add_workers, 440
 - deinit_sched, 439
 - do_schedule, 440
 - init_sched, 439
 - policy_description, 440
 - policy_name, 440
 - pop_every_task, 439
 - pop_task, 439
 - post_exec_hook, 440
 - pre_exec_hook, 440
 - push_task, 439
 - push_task_notify, 439
 - remove_workers, 440
 - submit_hook, 439
- starpu_sched_set_max_priority
 - Scheduling Policy, 442
- starpu_sched_set_min_priority
 - Scheduling Policy, 441
- starpu_sched_tree, 467
- starpu_sched_tree_add_workers
 - Modularized Scheduler Interface, 470
- starpu_sched_tree_create
 - Modularized Scheduler Interface, 469
- starpu_sched_tree_destroy
 - Modularized Scheduler Interface, 469
- starpu_sched_tree_pop_task
 - Modularized Scheduler Interface, 470
- starpu_sched_tree_push_task
 - Modularized Scheduler Interface, 470
- starpu_sched_tree_remove_workers
 - Modularized Scheduler Interface, 470
- starpu_sched_tree_update_workers
 - Modularized Scheduler Interface, 469
- starpu_sched_tree_update_workers_in_ctx
 - Modularized Scheduler Interface, 470
- starpu_sched_tree_work_stealing_push_task
 - Modularized Scheduler Interface, 474
- starpu_scheduler.h, 505
- starpu_shutdown
 - Initialization and Termination, 186
- starpu_sink.h, 506
- starpu_sleep
 - Threads, 210
- starpu_stdlib.h, 507
- starpu_tag_declare_deps
 - Explicit Dependencies, 322
- starpu_tag_declare_deps_array
 - Explicit Dependencies, 323
- starpu_tag_notify_from_apps
 - Explicit Dependencies, 324
- starpu_tag_remove
 - Explicit Dependencies, 324
- starpu_tag_restart
 - Explicit Dependencies, 324
- starpu_tag_t
 - Explicit Dependencies, 321
- starpu_tag_wait
 - Explicit Dependencies, 323
- starpu_tag_wait_array
 - Explicit Dependencies, 323
- starpu_task, 296
 - bundle, 303
 - callback_arg, 299
 - callback_arg_free, 300
 - callback_func, 299
 - cl, 298
 - cl_arg, 299
 - cl_arg_free, 300
 - cl_arg_size, 299
 - color, 303

- destroy, [301](#)
- detach, [301](#)
- dyn_handles, [298](#)
- dyn_interfaces, [299](#)
- dyn_modes, [299](#)
- execute_on_a_specific_worker, [301](#)
- flops, [303](#)
- handles, [298](#)
- hypervisor_tag, [303](#)
- interfaces, [298](#)
- magic, [302](#)
- mf_skip, [301](#)
- modes, [298](#)
- name, [298](#)
- nbuffers, [298](#)
- next, [304](#)
- predicted, [303](#)
- predicted_transfer, [303](#)
- prev, [304](#)
- priority, [302](#)
- profiling_info, [303](#)
- prologue_callback_arg, [300](#)
- prologue_callback_arg_free, [300](#)
- prologue_callback_func, [300](#)
- regenerate, [301](#)
- sched_ctx, [303](#)
- scheduled, [302](#)
- sequential_consistency, [301](#)
- starpu_private, [304](#)
- status, [302](#)
- synchronous, [301](#)
- tag_id, [300](#)
- type, [302](#)
- use_tag, [300](#)
- workerid, [302](#)
- workerorder, [302](#)
- starpu_task.h, [507](#)
 - STARPU_CODELET_SIMGRID_EXECUTE, [509](#)
 - STARPU_CUDA_ASYNC, [509](#)
 - STARPU_OPENCL_ASYNC, [510](#)
- starpu_task_build
 - Insert_Task, [320](#)
- starpu_task_bundle.h, [510](#)
- starpu_task_bundle_close
 - Task Bundles, [411](#)
- starpu_task_bundle_create
 - Task Bundles, [411](#)
- starpu_task_bundle_expected_data_transfer_time
 - Task Bundles, [412](#)
- starpu_task_bundle_expected_energy
 - Task Bundles, [412](#)
- starpu_task_bundle_expected_length
 - Task Bundles, [412](#)
- starpu_task_bundle_insert
 - Task Bundles, [411](#)
- starpu_task_bundle_remove
 - Task Bundles, [411](#)
- starpu_task_bundle_t
 - Task Bundles, [411](#)
- starpu_task_clean
 - Codelet And Tasks, [311](#)
- starpu_task_create
 - Codelet And Tasks, [310](#)
- starpu_task_data_footprint
 - Scheduling Policy, [443](#)
- starpu_task_declare_deps_array
 - Explicit Dependencies, [322](#)
- starpu_task_destroy
 - Codelet And Tasks, [311](#)
- starpu_task_dup
 - Codelet And Tasks, [310](#)
- starpu_task_expected_conversion_time
 - Scheduling Policy, [444](#)
- starpu_task_expected_data_transfer_time
 - Scheduling Policy, [444](#)
- starpu_task_expected_energy
 - Scheduling Policy, [444](#)
- starpu_task_expected_length
 - Scheduling Policy, [443](#)
- starpu_task_footprint
 - Scheduling Policy, [443](#)
- starpu_task_get_current
 - Codelet And Tasks, [313](#)
- starpu_task_get_implementation
 - Codelet And Tasks, [314](#)
- starpu_task_get_model_name
 - Codelet And Tasks, [313](#)
- starpu_task_get_name
 - Codelet And Tasks, [313](#)
- starpu_task_get_task_scheduled_succs
 - Explicit Dependencies, [322](#)
- starpu_task_get_task_succs
 - Explicit Dependencies, [322](#)
- starpu_task_init
 - Codelet And Tasks, [310](#)
- starpu_task_insert
 - Insert_Task, [318](#)
- starpu_task_insert_data_make_room
 - Insert_Task, [318](#)
- starpu_task_insert_data_process_arg
 - Insert_Task, [319](#)
- starpu_task_insert_data_process_array_arg
 - Insert_Task, [319](#)
- starpu_task_insert_data_process_mode_array_arg
 - Insert_Task, [319](#)
- starpu_task_list, [413](#)
- starpu_task_list.h, [510](#)
- starpu_task_list_back
 - Task Lists, [413](#)
- starpu_task_list_begin
 - Task Lists, [414](#)
- starpu_task_list_empty
 - Task Lists, [414](#)
- starpu_task_list_erase
 - Task Lists, [414](#)
- starpu_task_list_front

- Task Lists, [413](#)
- starpu_task_list_init
 - Task Lists, [413](#)
- starpu_task_list_ismember
 - Task Lists, [414](#)
- starpu_task_list_next
 - Task Lists, [414](#)
- starpu_task_list_pop_back
 - Task Lists, [414](#)
- starpu_task_list_pop_front
 - Task Lists, [414](#)
- starpu_task_list_push_back
 - Task Lists, [413](#)
- starpu_task_list_push_front
 - Task Lists, [413](#)
- starpu_task_nready
 - Codelet And Tasks, [312](#)
- starpu_task_nsubmitted
 - Codelet And Tasks, [312](#)
- starpu_task_set_implementation
 - Codelet And Tasks, [313](#)
- starpu_task_status
 - Codelet And Tasks, [309](#)
- starpu_task_submit
 - Codelet And Tasks, [311](#)
- starpu_task_submit_to_ctx
 - Codelet And Tasks, [311](#)
- starpu_task_util.h, [511](#)
- starpu_task_wait
 - Codelet And Tasks, [311](#)
- starpu_task_wait_for_all
 - Codelet And Tasks, [312](#)
- starpu_task_wait_for_all_in_ctx
 - Codelet And Tasks, [312](#)
- starpu_task_wait_for_n_submitted
 - Codelet And Tasks, [312](#)
- starpu_task_wait_for_n_submitted_in_ctx
 - Codelet And Tasks, [312](#)
- starpu_task_wait_for_no_ready
 - Codelet And Tasks, [313](#)
- starpu_thread.h, [512](#)
- starpu_thread_util.h, [514](#)
- starpu_timing_now
 - Miscellaneous Helpers, [388](#)
- starpu_timing_timespec_delay_us
 - Profiling, [340](#)
- starpu_timing_timespec_to_us
 - Profiling, [340](#)
- starpu_top.h, [515](#)
- starpu_top_add_data_boolean
 - StarPU-Top Interface, [423](#)
- starpu_top_add_data_float
 - StarPU-Top Interface, [423](#)
- starpu_top_add_data_integer
 - StarPU-Top Interface, [423](#)
- starpu_top_data, [420](#)
- starpu_top_data_type
 - StarPU-Top Interface, [422](#)
- starpu_top_debug_lock
 - StarPU-Top Interface, [426](#)
- starpu_top_debug_log
 - StarPU-Top Interface, [426](#)
- starpu_top_init_and_wait
 - StarPU-Top Interface, [425](#)
- starpu_top_message_type
 - StarPU-Top Interface, [423](#)
- starpu_top_param, [420](#)
 - callback, [421](#)
 - double_max_value, [422](#)
 - double_min_value, [422](#)
 - enum_values, [421](#)
 - id, [421](#)
 - int_max_value, [421](#)
 - int_min_value, [421](#)
 - name, [421](#)
 - nb_values, [421](#)
 - next, [422](#)
 - type, [421](#)
 - value, [421](#)
- starpu_top_param_type
 - StarPU-Top Interface, [422](#)
- starpu_top_register_parameter_boolean
 - StarPU-Top Interface, [424](#)
- starpu_top_register_parameter_enum
 - StarPU-Top Interface, [424](#)
- starpu_top_register_parameter_float
 - StarPU-Top Interface, [424](#)
- starpu_top_register_parameter_integer
 - StarPU-Top Interface, [424](#)
- starpu_top_task_prevision
 - StarPU-Top Interface, [425](#)
- starpu_top_update_data_boolean
 - StarPU-Top Interface, [425](#)
- starpu_top_update_data_float
 - StarPU-Top Interface, [425](#)
- starpu_top_update_data_integer
 - StarPU-Top Interface, [425](#)
- starpu_top_update_parameter
 - StarPU-Top Interface, [425](#)
- starpu_topology_print
 - Initialization and Termination, [188](#)
- starpu_transfer_bandwidth
 - Performance Model, [334](#)
- starpu_transfer_latency
 - Performance Model, [334](#)
- starpu_transfer_predict
 - Performance Model, [334](#)
- starpu_tree, [446](#)
- starpu_tree.h, [516](#)
- starpu_tree_free
 - Tree, [447](#)
- starpu_tree_get
 - Tree, [447](#)
- starpu_tree_get_neighbour
 - Tree, [447](#)
- starpu_tree_insert

- Tree, [447](#)
- starpu_tree_reset_visited
 - Tree, [447](#)
- starpu_util.h, [517](#)
- starpu_variable_data_register
 - Data Interfaces, [256](#)
- starpu_variable_get_elemsize
 - Data Interfaces, [262](#)
- starpu_variable_get_local_ptr
 - Data Interfaces, [262](#)
- starpu_variable_interface, [245](#)
- starpu_variable_ptr_register
 - Data Interfaces, [257](#)
- starpu_vector_data_register
 - Data Interfaces, [257](#)
- starpu_vector_filter_block
 - Data Partition, [277](#)
- starpu_vector_filter_block_shadow
 - Data Partition, [277](#)
- starpu_vector_filter_divide_in_2
 - Data Partition, [278](#)
- starpu_vector_filter_list
 - Data Partition, [278](#)
- starpu_vector_filter_list_long
 - Data Partition, [277](#)
- starpu_vector_get_elemsize
 - Data Interfaces, [263](#)
- starpu_vector_get_local_ptr
 - Data Interfaces, [263](#)
- starpu_vector_get_nx
 - Data Interfaces, [263](#)
- starpu_vector_interface, [245](#)
- starpu_vector_ptr_register
 - Data Interfaces, [257](#)
- starpu_void_data_register
 - Data Interfaces, [256](#)
- starpu_wake_all_blocked_workers
 - Expert Mode, [418](#)
- starpu_wake_worker
 - Scheduling Policy, [441](#)
- starpu_worker.h, [518](#)
- starpu_worker_archtype
 - Workers' Properties, [218](#)
- starpu_worker_can_execute_task
 - Scheduling Policy, [442](#)
- starpu_worker_can_execute_task_first_impl
 - Scheduling Policy, [443](#)
- starpu_worker_can_execute_task_impl
 - Scheduling Policy, [443](#)
- starpu_worker_collection, [214](#)
 - add, [216](#)
 - deinit, [216](#)
 - get_next, [215](#)
 - has_next, [215](#)
 - init, [216](#)
 - init_iterator, [216](#)
 - nworkers, [215](#)
 - remove, [216](#)
 - type, [215](#)
 - workerids, [215](#)
- starpu_worker_collection_type
 - Workers' Properties, [218](#)
- starpu_worker_get_by_devid
 - Workers' Properties, [220](#)
- starpu_worker_get_by_type
 - Workers' Properties, [220](#)
- starpu_worker_get_count
 - Workers' Properties, [218](#)
- starpu_worker_get_count_by_type
 - Workers' Properties, [218](#)
- starpu_worker_get_devid
 - Workers' Properties, [220](#)
- starpu_worker_get_id
 - Workers' Properties, [219](#)
- starpu_worker_get_id_check
 - Workers' Properties, [217](#)
- starpu_worker_get_ids_by_type
 - Workers' Properties, [220](#)
- starpu_worker_get_memory_node
 - Workers' Properties, [221](#)
- starpu_worker_get_name
 - Workers' Properties, [221](#)
- starpu_worker_get_perf_archtype
 - Performance Model, [332](#)
- starpu_worker_get_relative_speedup
 - Scheduling Policy, [444](#)
- starpu_worker_get_sched_condition
 - Scheduling Policy, [441](#)
- starpu_worker_get_type
 - Workers' Properties, [220](#)
- starpu_worker_get_type_as_string
 - Workers' Properties, [221](#)
- starpufft.h, [522](#)
- starpufft_cleanup
 - FFT Support, [393](#)
- starpufft_destroy_plan
 - FFT Support, [393](#)
- starpufft_execute
 - FFT Support, [392](#)
- starpufft_execute_handle
 - FFT Support, [393](#)
- starpufft_free
 - FFT Support, [391](#)
- starpufft_malloc
 - FFT Support, [391](#)
- starpufft_plan_dft_1d
 - FFT Support, [392](#)
- starpufft_plan_dft_2d
 - FFT Support, [392](#)
- starpufft_start
 - FFT Support, [392](#)
- starpufft_start_handle
 - FFT Support, [392](#)
- status
 - starpu_task, [302](#)
- submit_hook

- starpu_sched_policy, [439](#)
- symbol
 - starpu_perfmodel, [328](#)
- synchronous
 - starpu_task, [301](#)
- tag_id
 - starpu_task, [300](#)
- Task Bundles, [410](#)
 - starpu_task_bundle_close, [411](#)
 - starpu_task_bundle_create, [411](#)
 - starpu_task_bundle_expected_data_transfer_time, [412](#)
 - starpu_task_bundle_expected_energy, [412](#)
 - starpu_task_bundle_expected_length, [412](#)
 - starpu_task_bundle_insert, [411](#)
 - starpu_task_bundle_remove, [411](#)
 - starpu_task_bundle_t, [411](#)
- Task Lists, [412](#)
 - starpu_task_list_back, [413](#)
 - starpu_task_list_begin, [414](#)
 - starpu_task_list_empty, [414](#)
 - starpu_task_list_erase, [414](#)
 - starpu_task_list_front, [413](#)
 - starpu_task_list_init, [413](#)
 - starpu_task_list_ismember, [414](#)
 - starpu_task_list_next, [414](#)
 - starpu_task_list_pop_back, [414](#)
 - starpu_task_list_pop_front, [414](#)
 - starpu_task_list_push_back, [413](#)
 - starpu_task_list_push_front, [413](#)
- test_request
 - starpu_disk_ops, [284](#)
- Theoretical Lower Bound on Execution Time, [341](#)
 - starpu_bound_compute, [342](#)
 - starpu_bound_print, [342](#)
 - starpu_bound_print_dot, [341](#)
 - starpu_bound_print_lp, [342](#)
 - starpu_bound_print_mps, [342](#)
 - starpu_bound_start, [341](#)
 - starpu_bound_stop, [341](#)
- Threads, [197](#)
 - STARPU_PTHREAD_BARRIER_DESTROY, [202](#)
 - STARPU_PTHREAD_BARRIER_INIT, [202](#)
 - STARPU_PTHREAD_BARRIER_WAIT, [203](#)
 - STARPU_PTHREAD_COND_BROADCAST, [202](#)
 - STARPU_PTHREAD_COND_DESTROY, [202](#)
 - STARPU_PTHREAD_COND_INITIALIZER, [203](#)
 - STARPU_PTHREAD_COND_INIT, [201](#)
 - STARPU_PTHREAD_COND_SIGNAL, [202](#)
 - STARPU_PTHREAD_COND_WAIT, [202](#)
 - STARPU_PTHREAD_CREATE_ON, [199](#)
 - STARPU_PTHREAD_CREATE, [199](#)
 - STARPU_PTHREAD_GETSPECIFIC, [201](#)
 - STARPU_PTHREAD_KEY_CREATE, [200](#)
 - STARPU_PTHREAD_KEY_DELETE, [200](#)
 - STARPU_PTHREAD_MUTEX_DESTROY, [200](#)
 - STARPU_PTHREAD_MUTEX_INITIALIZER, [203](#)
 - STARPU_PTHREAD_MUTEX_INIT, [199](#)
 - STARPU_PTHREAD_MUTEX_LOCK, [200](#)
 - STARPU_PTHREAD_MUTEX_UNLOCK, [200](#)
 - STARPU_PTHREAD_RWLOCK_DESTROY, [201](#)
 - STARPU_PTHREAD_RWLOCK_INIT, [201](#)
 - STARPU_PTHREAD_RWLOCK_RDLOCK, [201](#)
 - STARPU_PTHREAD_RWLOCK_UNLOCK, [201](#)
 - STARPU_PTHREAD_RWLOCK_WRLOCK, [201](#)
 - STARPU_PTHREAD_SETSPECIFIC, [200](#)
 - starpu_pthread_attr_destroy, [204](#)
 - starpu_pthread_attr_init, [204](#)
 - starpu_pthread_attr_setdetachstate, [204](#)
 - starpu_pthread_barrier_destroy, [209](#)
 - starpu_pthread_barrier_init, [209](#)
 - starpu_pthread_barrier_wait, [209](#)
 - starpu_pthread_cond_broadcast, [207](#)
 - starpu_pthread_cond_destroy, [208](#)
 - starpu_pthread_cond_init, [207](#)
 - starpu_pthread_cond_signal, [207](#)
 - starpu_pthread_cond_timedwait, [207](#)
 - starpu_pthread_cond_wait, [207](#)
 - starpu_pthread_create, [203](#)
 - starpu_pthread_exit, [203](#)
 - starpu_pthread_getspecific, [206](#)
 - starpu_pthread_join, [203](#)
 - starpu_pthread_key_create, [206](#)
 - starpu_pthread_key_delete, [206](#)
 - starpu_pthread_mutex_destroy, [204](#)
 - starpu_pthread_mutex_init, [204](#)
 - starpu_pthread_mutex_lock, [205](#)
 - starpu_pthread_mutex_trylock, [205](#)
 - starpu_pthread_mutex_unlock, [205](#)
 - starpu_pthread_mutexattr_destroy, [206](#)
 - starpu_pthread_mutexattr_gettype, [205](#)
 - starpu_pthread_mutexattr_init, [206](#)
 - starpu_pthread_mutexattr_settype, [205](#)
 - starpu_pthread_rwlock_destroy, [208](#)
 - starpu_pthread_rwlock_init, [208](#)
 - starpu_pthread_rwlock_rdlock, [208](#)
 - starpu_pthread_rwlock_tryrdlock, [208](#)
 - starpu_pthread_rwlock_trywrlock, [209](#)
 - starpu_pthread_rwlock_unlock, [209](#)
 - starpu_pthread_rwlock_wrlock, [208](#)
 - starpu_pthread_setspecific, [206](#)
 - starpu_pthread_spin_destroy, [210](#)
 - starpu_pthread_spin_init, [209](#)
 - starpu_pthread_spin_lock, [210](#)
 - starpu_pthread_spin_trylock, [210](#)
 - starpu_pthread_spin_unlock, [210](#)
 - starpu_sleep, [210](#)
- Toolbox, [193](#)
 - STARPU_ABORT_MSG, [196](#)
 - STARPU_ABORT, [196](#)
 - STARPU_ASSERT_MSG, [196](#)
 - STARPU_ASSERT, [196](#)
 - STARPU_ATTRIBUTE_ALIGNED, [195](#)
 - STARPU_ATTRIBUTE_INTERNAL, [194](#)
 - STARPU_ATTRIBUTE_MALLOC, [194](#)
 - STARPU_ATTRIBUTE_PURE, [195](#)

- STARPU_ATTRIBUTE_UNUSED, [194](#)
- STARPU_ATTRIBUTE_WARN_UNUSED_RESULT, [195](#)
- STARPU_CHECK_RETURN_VALUE_IS, [196](#)
- STARPU_CHECK_RETURN_VALUE, [196](#)
- STARPU_GNUC_PREREQ, [194](#)
- STARPU_LIKELY, [194](#)
- STARPU_MAX, [195](#)
- STARPU_MIN, [195](#)
- STARPU_POISON_PTR, [195](#)
- STARPU_RMB, [197](#)
- STARPU_UNLIKELY, [194](#)
- STARPU_WARN_UNUSED_RESULT, [195](#)
- STARPU_WMB, [197](#)
- starpu_get_env_number, [197](#)
- Tree, [445](#)
 - starpu_tree_free, [447](#)
 - starpu_tree_get, [447](#)
 - starpu_tree_get_neighbour, [447](#)
 - starpu_tree_insert, [447](#)
 - starpu_tree_reset_visited, [447](#)
- tree
 - starpu_sched_component, [464](#)
- type
 - starpu_codelet, [292](#)
 - starpu_perfmodel, [327](#)
 - starpu_task, [302](#)
 - starpu_top_param, [421](#)
 - starpu_worker_collection, [215](#)
- types_of_workers, [527](#)
- unpack_data
 - starpu_data_interface_ops, [240](#)
- unplug
 - starpu_disk_ops, [282](#)
- use_tag
 - starpu_task, [300](#)
- value
 - starpu_top_param, [421](#)
- Versioning, [179](#)
 - STARPU_MAJOR_VERSION, [179](#)
 - STARPU_MINOR_VERSION, [179](#)
 - STARPU_RELEASE_VERSION, [179](#)
 - starpu_get_version, [180](#)
- wait_request
 - starpu_disk_ops, [284](#)
- where
 - starpu_codelet, [292](#)
- workerid
 - starpu_task, [302](#)
- workerids
 - starpu_worker_collection, [215](#)
- workerorder
 - starpu_task, [302](#)
- workers
 - starpu_sched_component, [464](#)
- workers_in_ctx
 - starpu_sched_component, [464](#)
- Workers' Properties, [213](#)
 - STARPU_MAXCPUS, [217](#)
 - STARPU_MAXNODES, [217](#)
 - STARPU_NMAXWORKERS, [217](#)
 - starpu_cpu_worker_get_count, [218](#)
 - starpu_cuda_worker_get_count, [219](#)
 - starpu_mic_device_get_count, [219](#)
 - starpu_mic_worker_get_count, [219](#)
 - starpu_node_get_kind, [221](#)
 - starpu_node_kind, [217](#)
 - starpu_opencl_worker_get_count, [219](#)
 - starpu_scc_worker_get_count, [219](#)
 - starpu_worker_archtype, [218](#)
 - starpu_worker_collection_type, [218](#)
 - starpu_worker_get_by_devid, [220](#)
 - starpu_worker_get_by_type, [220](#)
 - starpu_worker_get_count, [218](#)
 - starpu_worker_get_count_by_type, [218](#)
 - starpu_worker_get_devid, [220](#)
 - starpu_worker_get_id, [219](#)
 - starpu_worker_get_id_check, [217](#)
 - starpu_worker_get_ids_by_type, [220](#)
 - starpu_worker_get_memory_node, [221](#)
 - starpu_worker_get_name, [221](#)
 - starpu_worker_get_type, [220](#)
 - starpu_worker_get_type_as_string, [221](#)
- write
 - starpu_disk_ops, [283](#)